SED-R-296
Excerpted Portions of SS-29 Well File
I.19-06-016
ALJs: Hecht/Poirier
Date Serviced: May 7, 2021

SS #29

AC_CPUC_0117951

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Cyn. WELL NAME SS-29 CONTRACTOR N/A RIG No. _____

RIG DAYS N/A. MWO# _____ / TOTAL COST ESTIMATE $ _____

RIG DATE 11-27-91 GWO# _____ / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR JD Woods DAILY COST $ 6,768

CUMULATIVE COST $ 414,464

CASING: OD _____ in. LINER OD _____ in.
DEPTH _____ ft. TOP _____ ft.
BOTTOM _____ ft.

BRIEF DESCRIPTION OF ACTIVITIES

LATC Ticket For SS-29

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL

AC_CPUC_0117952

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS 29 Date 11/20/91 Initials JPN

Daily Base Costs

Rig $ N/A /hour x _____ hours = $ _____ /day
Extra Labor ..... $ _____ /day
Rig Supervisor ..... $ _____ /day
BOPE Rental ..... $ _____ /day
Drillpipe Rental ..... $ _____ /day Subtotal $ _____

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$
Shaffer	4137	S,07	MT	46	702.25
Shaffer, additional To repair BOPE	36262	S07	MI	43	70
ATC	12218	R06	MI	46	5,705
John Thomas	39590	T03	ZZ	46	120
John Thomas,	38747	T03	ZZ	44	171
		LATE CHARGES			

Daily Total $ 6,768
Previous Total $ 407,696
Cumulative Total $ 414,464

Work Categories

PR Pre-rig work, well kill
MI Move in - rig up, install & test BOPE
CO Initial/final clean out
DD Drilling
LR Leak repair - cmt. sqz., casing patch
FF Fishing
PB Plugback, redrill
ST Stimulation - acid wash, reperforating
GP Gravel pack
IT Isolation test - noise log, WSO test
WW Wellhead work
CI Run casing/inner-string/liner
TP Run tbg. & prod. equip.
AA Abandonment
RR Rig repairs
SB Stand-by
MO Rig down - move out
PO Post-rig work
ZZ Miscellaneous

Functional Indexes

10 Tubular goods
11 Tubing accessories, packers
12 Wellhead equip. & svcs.
13 Gravel pack equip. & svcs.
14 Casing accessories
20 Bits
21 Fluids
22 Cement, acid, sand, chemicals & pumping svcs.
23 Nitrogen and coil tubing svcs.
24 Filtering and solids control
30 Service tools
31 Fishing tools & svcs.
32 Hole openers, mills, junk subs, reamers, stabilizers
33 Coring, dynadrills & directional svcs.
35 Piano wire equip. & svcs.
40 Open & cased hole logging
41 Other Wireline svcs.
42 Production logging
43 Hydrotest, torque, tong svcs., thread washing
44 Trucking, hauling, cranes & hot shots
45 Vacuum trucking, disposal charges
46 Tank rental, misc. rentals
47 Site preparation
60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Cyn WELL NAME SS-29 CONTRACTOR N/A. RIG No. _____

RIG DAYS N/A. MWO# 99412. / TOTAL COST ESTIMATE $ _____

RIG DATE 11-7-91 GWO# _____ / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR JDW DAILY COST $ 7476

CUMULATIVE COST $ 415,172.

CASING: OD _____ in. LINER OD _____ in.
DEPTH _____ ft. TOP _____ ft.
BOTTOM _____ ft.

BRIEF DESCRIPTION OF ACTIVITIES

Late Ticket For SS-29.

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL

SOUTHERN CALIFORNIA GAS COMPANY

AC_CPUC_0117954

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS-29. Date 11/7/ Initials JDW.

Daily Base Costs

Rig $ N/A. /hour x _____ hours = $ _____ /day
Extra Labor ..... $ _____ /day
Rig Supervisor ..... $ _____ /day
BOPE Rental ..... $ _____ /day
Drillpipe Rental ..... $ _____ /day Subtotal $ _____

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$
Hydro-Test	59616	H10	TP	43	1,050.
John Thomas.	38855	J03	ZZ	46	240
John Thomas.	38745	J03.	ZZ	44	260
DesAutelle & Son.	10459	D—	MO	45	1,174.
Venviro Tek	26392	V14	MO	45	584
DesAutelle & Son	10482	D—	MO	45	254
Venviro Tek	26377.	V14	MO	45	979
DesAutelle & Son	10483	D—	MO	45	635.
Venviro Tek	26384	V14	MO	45	979.
DesAutelle & Son	10493	D—	MO	47	750
DesAutelle & Son,	10458.	D—	MO	45	571

Daily Total $ 7,476
Previous Total $ 407,696
Cumulative Total $ 415,172.

Work Categories

PR Pre-rig work, well kill
MI Move in - rig up, install & test BOPE
Initial/final clean out
ning
epair - cmt. sqz., casing
drill
id wash,
IT Isolation test - noise log, WSO test
WW Wellhead work
CI Run casing/inner-string/liner
TP Run tbg. & prod. equip.
AA Abandonment
RR Rig repairs
SB Stand-by
MO Rig down - move out
PO Post-rig work
ZZ Miscellaneous

Functional Indexes

10 Tubular goods
11 Tubing accessories, packers
12 Wellhead equip. & svcs.
13 Gravel pack equip. & svcs.
14 Casing accessories
20 Bits
21 Fluids
22 Cement, acid, sand, chemicals & pumping svcs.
23 Nitrogen and coil tubing svcs.
24 Filtering and solids control
30 Service tools
31 Fishing tools & svcs.
32 Hole openers, mills, junk subs, reamers, stabilizers
33 Coring, dynadrills & directional svcs.
35 Piano wire equip. & svcs.
40 Open & cased hole logging
41 Other Wireline svcs.
42 Production logging
43 Hydrotest, torque, tong svcs., thread washing
44 Trucking, hauling, cranes & hot shots
45 Vacuum trucking, disposal charges
46 Tank rental, misc. rentals
47 Site preparation
60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Cyn. WELL NAME SS-29 CONTRACTOR CPS RIG No. D-7

RIG DAYS 41 MWO# 99412 / TOTAL COST ESTIMATE $

RIG DATE 11-6-91 GWO# / TOTAL COST ESTIMATE $

RIG SUPERVISOR JD Woods DAILY COST $ 20,350

CASING: OD 7" in. DEPTH 8180 ft. LINER OD 5" in. TOP 8075 ft. BOTTOM 9077 ft. CUMULATIVE COST $ 407,696

<Release Rig 11-6-91 AT 8:00 pm.

BRIEF DESCRIPTION OF ACTIVITIES

Finished Run Tubing. Latch-in To otis packer. pulled 20,000# wt over. space out with 8000# wt on packer. Test seals and packer. 1500 psi (ok) Loadout Hydrotest. Removed BOP and Load. installed xmas Tree Test to 5000 psi (ok) with Santa Paula wireline run in open otis "XD" sliding sleeve. Loadout S.P.W. Line. Change Fluid over To 2% KCL water. 340 BBLS. Double inhib. <11-7-91> Loadout Rig

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	7:00	1	6	Open well W/0 psi Hydro Test 2nd IN well
7:00	8:00	1	6	Hydro Test IN well
8:00	9:00	1	6	" " " "
9:00	10:00	1	6	" " " " - Rig down Hydro Test
10:00	11:00	1	21	Land Into Packer - Space Out - Pull 20,000 over - 6,000 down
11:00	12:00	1	21	Land Into Donut - Run In Packing studs - Install Back Press Valve
12:00	1:00	1	14	nipple down stack
1:00	2:00	1	14	nipple down stack

DRILLER Jimeau

FOOTAGE FROM	FOOTAGE TO	DR-D RM-R CORE-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL-S PAR-P COM-C
				Release Rig, 8:00 pm		11-6-91						

DEVIATION RECORD	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	3:00	1	14	nipple down stack
3:00	4:00	1	14	nipple up Production Tree
4:00	5:00	1	15	Test Production Tree To 5500 psi
5:00	6:00	1	11	Rig up Archer Reed. Open sliding sleeve-Rig down W/L
6:00	7:00	1	5	change over well Thru sleeve AT 7966'.
7:00	8:00	1	5	change over well - secure well load Release Rig

DRILLER

LLING REPORT FORM

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS-29 (#) Date 11/6/91 Initials JDW.

Daily Base Costs

Rig $ 240 /hour x 14 hours =	$ 3,360	/day
Extra Labor 7 X 25 . 3 MEN EXTRA 11 HOURS	$ 1,000	/day
Rig Supervisor	$ 425	/day
BOPE Rental	$ 600	/day
Drillpipe Rental	$	/day
	Subtotal $	5,385

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$ 5,385
SANTA PAULA wireline	0019	—	TP	41	603
ASSOCIATED SERV.	4190	A07	WW	12	390
RTC.	2343.	R06	TP	44	479.
RTC.	2342	R06	TP	44	1,392.
OTIS.	419259	008	TP	11	7,136
RTC.	12205	R06	ZZ	60	714
D&S INC.	10354	D—	ZZ	46	324
D&S INC VAC TRUCK	10241	D—	ST	45	666
VENVIROTEK.	26292	V14	ST	45	790
VENVIROTEK,	26293	V14	ST	45	790
D&S Trucking	10240	D—	ST	45	698.
D&S Trucking,	10455	D—	CO	45	698
D&S Trucking, H	10453	D—	CO	45	285

Daily Total	$ 20,350
Previous Total	$ 387,346
Cumulative Total	$ 407,696

Work Categories

- PR Pre-rig work, well kill
- MI Move in - rig up, install & test BOPE
- CO Initial/final clean out
- DD Drilling
- LR Leak repair - cmt. sqz., casing patch
- FF Fishing
- PB Plugback, redrill
- ST Stimulation - acid wash, reperforating
- GP Gravel pack
- IT Isolation test - noise log, WSO test
- WW Wellhead work
- CI Run casing/inner-string/liner
- TP Run tbg. & prod. equip.
- AA Abandonment
- RR Rig repairs
- SB Stand-by
- MO Rig down - move out
- PO Post-rig work
- ZZ Miscellaneous

Functional Indexes

- 10 Tubular goods
- 11 Tubing accessories, packers
- 12 Wellhead equip. & svcs.
- 13 Gravel pack equip. & svcs.
- 14 Casing accessories
- 20 Bits
- 21 Fluids
- 22 Cement, acid, sand, chemicals & pumping svcs.
- 23 Nitrogen and coil tubing svcs.
- 24 Filtering and solids control
- 30 Service tools
- 31 Fishing tools & svcs.
- 32 Hole openers, mills, junk subs, reamers, stabilizers
- 33 Coring, dynadrills & directional svcs.
- 35 Piano wire equip. & svcs.
- 40 Open & cased hole logging
- 41 Other Wireline svcs.
- 42 Production logging
- 43 Hydrotest, torque, tong svcs., thread washing
- 44 Trucking, hauling, cranes & hot shots
- 45 Vacuum trucking, disposal charges
- 46 Tank rental, misc. rentals
- 47 Site preparation
- 60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Cyn. WELL NAME SS-29 CONTRACTOR CPS RIG No. D-7

RIG DAYS 40 MWO# 99412. / TOTAL COST ESTIMATE $

RIG DATE 11-5-91 GWO# / TOTAL COST ESTIMATE $

RIG SUPERVISOR J D Woods. DAILY COST $ 4,005

CASING: OD 7" in. DEPTH 8180' ft. LINER OD 5" in. TOP 8075 ft. BOTTOM 9077. ft. CUMULATIVE COST $ 387,346.

BRIEF DESCRIPTION OF ACTIVITIES

Finished picking up Tubing, Latch in packer Pull 20,000# WT. over. Set 10,000# WT on packer. Test packer and seal AT 1500psi. (OK) Change 3 1/8" VALVE on Tubing head INSTALL New stud and packing For. Tubing Hanger. Test To 1500psi. (OK) Pull out made up Production Equip. Hydro Test. in To 4,000 PSI. Kill String, See well.

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	7:00	1	6	Open Well with 0 PSI - Fill Well W/65 BBLS. Pick up 2 7/8 TBG
7:00	9:00	1	6	Pick up Tubing
9:00	9:00	1	6	Pick up 2 7/8 Tubing - Found PKR AT 8038 TBG measurement
9:00	10:00	1	21	Land Test Seals W/ 20,000 over & 10,000 down - Test To 1500 PSI
10:00	11:00	1	22	Change out 3" Valve on BOTTOM OF Well Head
11:00	12:00	1	22	Change out 5 Packing Studs on Donut Landing Flange
12:00	1:00	1	6	Pull out Well
1:00	2:00	1	6	Pull out Well

DRILLER Junior

FOOTAGE FROM	FOOTAGE TO	DR-D RM-R CORE-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL-S PAR-P COM-C

DEVIATION RECORD	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
3:00	3:00	1	6	Pull out Well - Lay down Test Seals
3:00	4:00	1	6	SOLID Test Seals - NO-GO - Sliding sleeve, G.L.M 4000 psi - Rig up Hydro-Test
4:00	5:00	1	6	Test TBG IN Well
5:00	6:00	1	6	Test TBG IN Well - 54 stds IN - Secure Well

DRILLER

LLING REPORT FORM

AC_CPUC_0117958

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS-29 # Date 11/5/91 Initials JDW

Daily Base Costs

Rig $ 240 /hour x 12 hours =	$ 2,880	/day
Extra Labor 4 x 25	$ 100	/day
Rig Supervisor	$ 425	/day
BOPE Rental	$ 600	/day
Drillpipe Rental	$	/day
	Subtotal $	4,005

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$ 4,005

Daily Total	$ 4,005
Previous Total	$ 383,341
Cumulative Total	$ 387,346

Work Categories

- PR Pre-rig work, well kill
- MI Move in - rig up, install & test BOPE
- CO Initial/final clean out
- DD Drilling
- LR Leak repair - cmt. sqz., casing patch
- FF Fishing
- PB Plugback, redrill
- ST Stimulation - acid wash, reperforating
- GP Gravel pack
- IT Isolation test - noise log, WSO test
- WW Wellhead work
- CI Run casing/inner-string/liner
- TP Run tbg. & prod. equip.
- AA Abandonment
- RR Rig repairs
- SB Stand-by
- MO Rig down - move out
- PO Post-rig work
- ZZ Miscellaneous

Functional Indexes

- 10 Tubular goods
- 11 Tubing accessories, packers
- 12 Wellhead equip. & svcs.
- 13 Gravel pack equip. & svcs.
- 14 Casing accessories
- 20 Bits
- 21 Fluids
- 22 Cement, acid, sand, chemicals & pumping svcs.
- 23 Nitrogen and coil tubing svcs.
- 24 Filtering and solids control
- 30 Service tools
- 31 Fishing tools & svcs.
- 32 Hole openers, mills, junk subs, reamers, stabilizers
- 33 Coring, dynadrills & directional svcs.
- 35 Piano wire equip. & svcs.
- 40 Open & cased hole logging
- 41 Other Wireline svcs.
- 42 Production logging
- 43 Hydrotest, torque, tong svcs., thread washing
- 44 Trucking, hauling, cranes & hot shots
- 45 Vacuum trucking, disposal charges
- 46 Tank rental, misc. rentals
- 47 Site preparation
- 60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Cyn. WELL NAME SS 29 CONTRACTOR CPS RIG No. D-7

RIG DAYS 39 MWO# 99442 / TOTAL COST ESTIMATE $

RIG DATE 11-4-91 GWO# / TOTAL COST ESTIMATE $

RIG SUPERVISOR JD Woods. DAILY COST $ 15,388.

CUMULATIVE COST $ 383,341

CASING: OD 7" in. DEPTH 8180. ft. LINER OD 5" in. TOP 8075' ft. BOTTOM 9077' ft.

BRIEF DESCRIPTION OF ACTIVITIES

Pulled out Rig up H.L.S. made up otis "BWB" 7" packer Ran in set AT 8030'. POH. Loadout H.L.S. made up otis Test Seal measure in picking up 2 7/8" 8rd. Tubing.

(Had BOP Drill with crew. 44 sec)

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS Held B.O.P. drill 44 secs Dan
6:00	7:00	1	6	Open well w/ B.O.P. - Fill well w/ 84 BBLS - Run 25 JTS 2 7/8
7:00	8:00	1	6	Run out well
8:00	9:00	1	6	Run out well
9:00	10:00	1	21	R/S up shooting Flange - R/S up Halliburton Logging service
10:00	11:00	1	11	Run 7" Packer with Halliburton Logging service
11:00	12:00	1	11	" " " " " "
12:00	1:00	1	11	Set 7" Packer @ 8030
1:00	2:00	1	11	Run 7" Packer

DRILLER Jimenez

FOOTAGE FROM	TO	DR-D RM-R CORE-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL-S PAR-P COM-C

DEVIATION RECORD	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	3:00	1	11	Rig down H.L.S. - Install Picture nipple
3:00	4:00	1	6	Make up OTIS 3.25 SEAL ASSY - Run in well with 2 7/8 TBG
4:00	5:00	1	6	Run in well with 2 7/8 TBG
5:00	6:00	1	6	Run in well 197 JTS - Secure well

DRILLER

LLING REPORT FORM

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS-29 Date 11/4/91 Initials JDW.

Daily Base Costs

Rig $ 2.40 /hour x 12. hours =	$ 2,880	/day
Extra Labor 6 x 25 2 men x 12	$ 870	/day
Rig Supervisor	$ 425	/day
BOPE Rental	$ 600	/day
Drillpipe Rental	$	/day
	Subtotal $	4775

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$ 4775
H.L.S.	68379	H22	TP	41	2,388.
Sinclair mud	2437	S-33	CO	21	1,343.
B.S.T.	8645	B24	TP	11	1,606.
SHAFFER	25085	S07	WW	12.	3,574
SHAFFER	24837	S07.	TP	10	1,702.

Daily Total	$ 15,388.
Previous Total	$ 367,953
Cumulative Total	$ 383,341.

Work Categories

- PR Pre-rig work, well kill
- MI Move in - rig up, install & test BOPE
- CO Initial/final clean out
- DD Drilling
- LR Leak repair - cmt. sqz., casing patch
- FF Fishing
- PB Plugback, redrill
- ST Stimulation - acid wash, reperforating
- GP Gravel pack
- IT Isolation test - noise log, WSO test
- WW Wellhead work
- CI Run casing/inner-string/liner
- TP Run tbg. & prod. equip.
- AA Abandonment
- RR Rig repairs
- SB Stand-by
- MO Rig down - move out
- PO Post-rig work
- ZZ Miscellaneous

Functional Indexes

- 10 Tubular goods
- 11 Tubing accessories, packers
- 12 Wellhead equip. & svcs.
- 13 Gravel pack equip. & svcs.
- 14 Casing accessories
- 20 Bits
- 21 Fluids
- 22 Cement, acid, sand, chemicals & pumping svcs.
- 23 Nitrogen and coil tubing svcs.
- 24 Filtering and solids control
- 30 Service tools
- 31 Fishing tools & svcs.
- 32 Hole openers, mills, junk subs, reamers, stabilizers
- 33 Coring, dynadrills & directional svcs.
- 35 Piano wire equip. & svcs.
- 40 Open & cased hole logging
- 41 Other Wireline svcs.
- 42 Production logging
- 43 Hydrotest, torque, tong svcs., thread washing
- 44 Trucking, hauling, cranes & hot shots
- 45 Vacuum trucking, disposal charges
- 46 Tank rental, misc. rentals
- 47 Site preparation
- 60 Miscellaneous

STANDARD SESNON #30 - ALISO CANYON
TOUR SHEETS

AC_CPUC_0117962

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Canyon WELL NAME 5530 CONTRACTOR Late Charge RIG No. _____

RIG DAYS _____ MWO# _____ / TOTAL COST ESTIMATE $ _____

RIG DATE 5-16-89 GWO# _____ / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR Bradbury DAILY COST $ 180

CUMULATIVE COST $ _____

CASING: OD _____ in. LINER OD _____ in.
DEPTH _____ ft. TOP _____ ft.
BOTTOM _____ ft.

BRIEF DESCRIPTION OF ACTIVITIES

Washed well Head & Collar down after Move Out,

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL

SOUTHERN CALIFORNIA GAS COMPANY

AC_CPUC_0117963

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well 5530 Date 5/16/89 Initials EG

Daily Base Costs

Rig $ _____ /hour x _____ hours = $ _____ /day
Extra Labor ..... $ _____ /day
Rig Supervisor ..... $ _____ /day
BOPE Rental ..... $ _____ /day
Drillpipe Rental ..... $ _____ /day Subtotal $ _____

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$
Advanced Pressure Washing	602	A32 XXX	MO	60	180 ✓

Daily Total $ 180 ✓
Previous Total $ _____
Cumulative Total $ _____

Work Categories

- PR Pre-rig work, well kill
- MI Move in - rig up, install & test BOPE
- CO Initial/final clean out
- DD Drilling
- LR Leak repair - cmt. sqz., casing patch
- FF Fishing
- PB Plugback, redrill
- ST Stimulation - acid wash, reperforating
- GP Gravel pack
- IT Isolation test - noise log, WSO test
- WW Wellhead work
- CI Run casing/inner-string/liner
- TP Run tbg. & prod. equip.
- AA Abandonment
- RR Rig repairs
- SB Stand-by
- MO Rig down - move out
- PO Post-rig work
- ZZ Miscellaneous

Functional Indexes

- 10 Tubular goods
- 11 Tubing accessories, packers
- 12 Wellhead equip. & svcs.
- 13 Gravel pack equip. & svcs.
- 14 Casing accessories
- 20 Bits
- 21 Fluids
- 22 Cement, acid, sand, chemicals & pumping svcs.
- 23 Nitrogen and coil tubing svcs.
- 24 Filtering and solids control
- 30 Service tools
- 31 Fishing tools & svcs.
- 32 Hole openers, mills, junk subs, reamers, stabilizers
- 33 Coring, dynadrills & directional svcs.
- 35 Piano wire equip. & svcs.
- 40 Open & cased hole logging
- 41 Other Wireline svcs.
- 42 Production logging
- 43 Hydrotest, torque, tong svcs., thread washing
- 44 Trucking, hauling, cranes & hot shots
- 45 Vacuum trucking, disposal charges
- 46 Tank rental, misc. rentals
- 47 Site preparation
- 60 Miscellaneous

Marilyn FYI

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Cyn WELL NAME SS-30 CONTRACTOR _____ RIG No. _____

RIG DAYS Late MWO# 99934 / TOTAL COST ESTIMATE $ _____

RIG DATE 4-20-89 GWO# _____ / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR W.L. KillebRew DAILY COST $ 986

CUMULATIVE COST $ 47,681

CASING: OD _____ in. LINER OD _____ in.
DEPTH _____ ft. TOP _____ ft.
BOTTOM _____ ft.

BRIEF DESCRIPTION OF ACTIVITIES
Late Ticket

MUD PROPERTIES								
MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL

AC_CPUC_0117965

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS # 30 Date 4 / 20 / 89 Initials W.L.K.

Daily Base Costs

Rig $ _____ /hour x _____ hours = $ _____ /day
Extra Labor ..... $ _____ /day
Rig Supervisor ..... Late Ticket ..... $ _____ /day
BOPE Rental ..... $ _____ /day
Drillpipe Rental ..... $ _____ /day Subtotal $ _____

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$
Kristie	2003	K07	CO	45	480
Venvirotek	5707	V14	CO	45	506

Daily Total $ 986
Previous Total $ 46,695
Cumulative Total $ 47,681

Work Categories

PR Pre-rig work, well kill
MI Move in - rig up, install & test BOPE
[illegible]nitial/final clean out
[illegible]rilling
[illegible]ak repair - cmt. sqz., casing
[illegible]tch
[illegible]shing
[illegible]ugback, redrill
[illegible]mulation - acid wash, perforating
GP [illegible]vel pack
IT Isolation test - noise log, WSO test
WW Wellhead work
CI Run casing/inner-string/liner
TP Run tbg. & prod. equip.
AA Abandonment
RR Rig repairs
SB Stand-by
MO Rig down - move out
PO Post-rig work
ZZ Miscellaneous

Functional Indexes

10 Tubular goods
11 Tubing accessories, packers
12 Wellhead equip. & svcs.
13 Gravel pack equip. & svcs.
14 Casing accessories
20 Bits
21 Fluids
22 Cement, acid, sand, chemicals & pumping svcs.
23 Nitrogen and coil tubing svcs.
24 Filtering and solids control
30 Service tools
31 Fishing tools & svcs.
32 Hole openers, mills, junk subs, reamers, stabilizers
33 Coring, dynadrills & directional svcs.
35 Piano wire equip. & svcs.
40 Open & cased hole logging
41 Other Wireline svcs.
42 Production logging
43 Hydrotest, torque, tong svcs., thread washing
44 Trucking, hauling, cranes & hot shots
45 Vacuum trucking, disposal charges
46 Tank rental, misc. rentals
47 Site preparation
60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD ALISO CNY WELL NAME SS #30 CONTRACTOR _____ RIG No. _____

RIG DAYS LATE MWO# 99934 / TOTAL COST ESTIMATE $ _____

RIG DATE 3-7-89 GWO# _____ / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR W. L. KILLEBREW DAILY COST $ 374

CUMULATIVE COST $ 46695

CASING: OD _____ in. LINER OD _____ in.
DEPTH _____ ft. TOP _____ ft.
BOTTOM _____ ft.

BRIEF DESCRIPTION OF ACTIVITIES
LATE CHARGE

MUD PROPERTIES								
MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL

SOUTHERN CALIFORNIA GAS COMPANY

AC_CPUC_0117967

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS#30 Date 3 / 7 / 89 Initials WLK

Daily Base Costs

Rig $ _____ /hour x _____ hours = $ _____ /day
Extra Labor ..... $ _____ /day
Rig Supervisor ... LATE CHARGE ..... $ _____ /day
BOPE Rental ..... $ _____ /day
Drillpipe Rental ..... $ _____ /day Subtotal $ _____

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$
So. CA. GAS CO	36684	S 11	TP	11	374 ✓

Daily Total $ 374 ✓
Previous Total $ 46321
Cumulative Total $ 46695 ✓

Work Categories

PR Pre-rig work, well kill
MI Move in - rig up, install & test BOPE
CO Initial/final clean out
DD Drilling
LR Leak repair - cmt. sqz., casing patch
FF Fishing
PB Plugback, redrill
ST Stimulation - acid wash, reperforating
GP Gravel pack
IT Isolation test - noise log, WSO test
WW Wellhead work
CI Run casing/inner-string/liner
TP Run tbg. & prod. equip.
AA Abandonment
RR Rig repairs
SB Stand-by
MO Rig down - move out
PO Post-rig work
ZZ Miscellaneous

Functional Indexes

10 Tubular goods
11 Tubing accessories, packers
12 Wellhead equip. & svcs.
13 Gravel pack equip. & svcs.
14 Casing accessories
20 Bits
21 Fluids
22 Cement, acid, sand, chemicals & pumping svcs.
23 Nitrogen and coil tubing svcs.
24 Filtering and solids control
30 Service tools
31 Fishing tools & svcs.
32 Hole openers, mills, junk subs, reamers, stabilizers
33 Coring, dynadrills & directional svcs.
35 Piano wire equip. & svcs.
40 Open & cased hole logging
41 Other Wireline svcs.
42 Production logging
43 Hydrotest, torque, tong svcs., thread washing
44 Trucking, hauling, cranes & hot shots
45 Vacuum trucking, disposal charges
46 Tank rental, misc. rentals
47 Site preparation
60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Canyon WELL NAME SS 30 CONTRACTOR N/A RIG No. _____

RIG DAYS N/A MWO# 99934 / TOTAL COST ESTIMATE $ _____

RIG DATE 3-3-89 GWO# _____ / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR J.D. Woods DAILY COST $ 140

CASING: OD _____ in. LINER OD _____ in. CUMULATIVE COST $ 46,321

DEPTH _____ ft. TOP _____ ft.

BOTTOM _____ ft.

BRIEF DESCRIPTION OF ACTIVITIES

Late Ticket For SS #30

For cutting up tubing for lab samples.

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL

SOUTHERN CALIFORNIA GAS COMPANY

AC_CPUC_0117969

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS-#30 Date 3/3/89 Initials JDW

Daily Base Costs

Rig $ N/A /hour x _____ hours = $ _____ /day
Extra Labor ..... $ _____ /day
Rig Supervisor ..... $ _____ /day
BOPE Rental ..... $ _____ /day
Drillpipe Rental ..... $ _____ /day Subtotal $ _____

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$
RTC.	3412.	R06.	ZZ	60	140.

Daily Total $ 140
Previous Total $ 46,181
Cumulative Total $ 46,321

Work Categories

PR Pre-rig work, well kill
MI Move in - rig up, install & test BOPE
CO Initial/final clean out
DD Drilling
LR Leak repair - cmt. sqz., casing patch
FF Fishing
PB Plugback, redrill
ST Stimulation - acid wash, reperforating
GP Gravel pack
IT Isolation test - noise log, WSO test
WW Wellhead work
CI Run casing/inner-string/liner
TP Run tbg. & prod. equip.
AA Abandonment
RR Rig repairs
SB Stand-by
MO Rig down - move out
PO Post-rig work
ZZ Miscellaneous

Functional Indexes

10 Tubular goods
11 Tubing accessories, packers
12 Wellhead equip. & svcs.
13 Gravel pack equip. & svcs.
14 Casing accessories
20 Bits
21 Fluids
22 Cement, acid, sand, chemicals & pumping svcs.
23 Nitrogen and coil tubing svcs.
24 Filtering and solids control
30 Service tools
31 Fishing tools & svcs.
32 Hole openers, mills, junk subs, reamers, stabilizers
33 Coring, dynadrills & directional svcs.
35 Piano wire equip. & svcs.
40 Open & cased hole logging
41 Other Wireline svcs.
42 Production logging
43 Hydrotest, torque, tong svcs., thread washing
44 Trucking, hauling, cranes & hot shots
45 Vacuum trucking, disposal charges
46 Tank rental, misc. rentals
47 Site preparation
60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Cyn WELL NAME SS #30 CONTRACTOR _____ RIG No. _____

RIG DAYS Late charge MWO# 99934 / TOTAL COST ESTIMATE $ _____

RIG DATE 2-14-89 GWO# _____ / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR W. L. Killebrew DAILY COST $ 2300

CASING: OD _____ in. LINER OD _____ in. CUMULATIVE COST $ 46,181

DEPTH _____ ft. TOP _____ ft.

BOTTOM _____ ft.

BRIEF DESCRIPTION OF ACTIVITIES

LATE CHARGE

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL

AC_CPUC_0117971

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS #30 Late CHARGE Date 2/14/89 Initials WLK

Daily Base Costs

Rig $ _____ /hour x _____ hours = $ _____ /day
Extra Labor ..... $ _____ /day
Rig Supervisor ..... $ _____ /day
BOPE Rental ..... $ _____ /day
Drillpipe Rental ..... $ _____ /day Subtotal $ _____

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$
So. CA. GAS Co.	36681	511.	WW.	12.	2300 ✓

Daily Total $ 2300 ✓
Previous Total $ 43881
Cumulative Total $ 46181 ✓

Work Categories

PR Pre-rig work, well kill
MI Move in - rig up, install & test BOPE
CO Initial/final clean out
DD Drilling
LR Leak repair - cmt. sqz., casing patch
FF Fishing
PB Plugback, redrill
ST Stimulation - acid wash, reperforating
GP Gravel pack
IT Isolation test - noise log, WSO test
WW Wellhead work
CI Run casing/inner-string/liner
TP Run tbg. & prod. equip.
AA Abandonment
RR Rig repairs
SB Stand-by
MO Rig down - move out
PO Post-rig work
ZZ Miscellaneous

Functional Indexes

10 Tubular goods
11 Tubing accessories, packers
12 Wellhead equip. & svcs.
13 Gravel pack equip. & svcs.
14 Casing accessories
20 Bits
21 Fluids
22 Cement, acid, sand, chemicals & pumping svcs.
23 Nitrogen and coil tubing svcs.
24 Filtering and solids control
30 Service tools
31 Fishing tools & svcs.
32 Hole openers, mills, junk subs, reamers, stabilizers
33 Coring, dynadrills & directional svcs.
35 Piano wire equip. & svcs.
40 Open & cased hole logging
41 Other Wireline svcs.
42 Production logging
43 Hydrotest, torque, tong svcs., thread washing
44 Trucking, hauling, cranes & hot shots
45 Vacuum trucking, disposal charges
46 Tank rental, misc. rentals
47 Site preparation
60 Miscellaneous

Corrected

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Cyn. WELL NAME SS-30 CONTRACTOR _____ RIG No. _____

RIG DAYS Late MWO# _____ / TOTAL COST ESTIMATE $_____

RIG DATE 2-7-89 GWO# _____ / TOTAL COST ESTIMATE $_____

RIG SUPERVISOR W.L. Killebrew DAILY COST $ 1659

CASING: OD _____ in. LINER OD _____ in. CUMULATIVE COST $ 43881

DEPTH _____ ft. TOP _____ ft.

BOTTOM _____ ft.

BRIEF DESCRIPTION OF ACTIVITIES

Late Charge

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL

AC_CPUC_0117973

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS #30 Date 2/7/89 Initials WLK

Daily Base Costs

Rig $ _____ /hour x _____ hours = $ _____ /day
Extra Labor ..... $ _____ /day
Rig Supervisor ..... $ _____ /day
BOPE Rental ..... $ _____ /day
Drillpipe Rental ..... $ _____ /day Subtotal $ _____

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$
RTC	42-425.	R06.	TP.	44.	422 ✓
RTC	42-1266.	R06.	TP.	44.	298 ✓
RTC	1889.	R06.	ZZ.	44.	99 ✓
Kristie	1950.	K07.	CO.	45.	540 ✓
Kristie	1952.	K07.	CO.	45.	300 ✓

Daily Total $ 1659 ✓
Previous Total $ 42,222
Cumulative Total $ 43,881 ✓

Work Categories

PR Pre-rig work, well kill
MI Move in - rig up, install & test BOPE
CO Initial/final clean out
DD Drilling
LR Leak repair - cmt. sqz., casing patch
FF Fishing
PB Plugback, redrill
ST Stimulation - acid wash, reperforating
GP Gravel pack
IT Isolation test - noise log, WSO test
WW Wellhead work
CI Run casing/inner-string/liner
TP Run tbg. & prod. equip.
AA Abandonment
RR Rig repairs
SB Stand-by
MO Rig down - move out
PO Post-rig work
ZZ Miscellaneous

Functional Indexes

10 Tubular goods
11 Tubing accessories, packers
12 Wellhead equip. & svcs.
13 Gravel pack equip. & svcs.
14 Casing accessories
20 Bits
21 Fluids
22 Cement, acid, sand, chemicals & pumping svcs.
23 Nitrogen and coil tubing svcs.
24 Filtering and solids control
30 Service tools
31 Fishing tools & svcs.
32 Hole openers, mills, junk subs, reamers, stabilizers
33 Coring, dynadrills & directional svcs.
35 Piano wire equip. & svcs.
40 Open & cased hole logging
41 Other Wireline svcs.
42 Production logging
43 Hydrotest, torque, tong svcs., thread washing
44 Trucking, hauling, cranes & hot shots
45 Vacuum trucking, disposal charges
46 Tank rental, misc. rentals
47 Site preparation
60 Miscellaneous

Corrected

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Cyn WELL NAME SS # 30 CONTRACTOR CPS RIG No. 72

RIG DAYS 6

RIG DATE 2-3-89

RIG SUPERVISOR JD woods

MWO# 99934 / TOTAL COST ESTIMATE $ 35,000

GWO# _____ / TOTAL COST ESTIMATE $ 24,993

DAILY COST $ 25,163

CUMULATIVE COST $ 42,392. 222.

CASING: OD 7" in. DEPTH 9248' ft.

LINER OD _____ in. TOP _____ ft. BOTTOM _____ ft.

BRIEF DESCRIPTION OF ACTIVITIES

Finished Hydro Testing Tubing in well. Space out Change Fluid in well over To 2% KCL WATER. 340 BBLS. Land Tubing with 49,000 on Donut, 5000 down on packer, Removed B.O.P. & Instal. XMAS Tree. Test 3000 PSI, Release Rig 5:00 pm. Tear out Rig.

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %
2% KCL.			63 T.F.					

OPERATIONS SEQUENCE & DETAIL

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
600	700	1	6	BLED WELL @ PSI OPEN WELL INSTALL TEST TOOLS IN Tbg & TEST to 4000 PSI SER. EQUIPMENT
700	800	1	6	RIW HYDROTEST 2 7/8" Tbg 4000 PSI
800	900	1	6	RIW HYDROTEST 2 7/8 Tbg 4000 PSI
900	1000	1	6	RIW HYDROTEST 2 7/8" Tbg 4000 PSI TEST PUP'S & DOUGHNUT
1000	1100	1/2 - 1/2	6	RIG DOWN HYDROTEST Rig up To CHANGE WELL OVER TO K.C.L
1100	1200	1	5	CHANGE WELL OVER TO 2% K.C.L WATER.
1200	100	1/2 1/2	5 21	CHANGE WELL OVER TO 2% KCL WATER. LATCH ON PKR pull 18,000# OVER. LAND ON DOUGHNUT
100	200	1/2 1/2	21 14	SCREW IN DOUGHNUT SCREW INSTALL B.P NIPPLE DOWN B.O.P DRILLER W. Jones

FOOTAGE FROM	TO	DR-D RM-R CORE-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SCI-S PACKER-P COMP-C
				Release Rig 5: PM.								
				2-3-89								

DEVIATION RECORD	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
200	300	1	14	Nipple Down BOP & SET OUT
300	400	1	14	INSTALL XMAS TREE & flange up
400	500	1	E	TEST XMAS TREE TO 3000 PSI REMOVE B.P SHUT WELL IN
500	600	1	22	READY Rig for move
600	700	1	22	READY Rig for move

DRILLER W. Jones

AC_CPUC_0117975

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS- 30 Date 2/3/89 Initials JDW

Daily Base Costs

Rig $ 200 /hour x 11 hours = $ 2200 /day
~~Extra~~ Labor 100 X 2 ..... $ 200 /day
Rig Supervisor ..... $ 550 /day
BOPE Rental ..... $ 400 /day
Drillpipe Rental ..... $ ____ /day Subtotal $ 3356

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—	TP	01	$ 3350. ✓
SHAFFER	23125 23126	S07.	WW.	12.	3,094. ✓
SHAFFER.	23120.	S07.	TP.	10.	739 ✓
Hydro-Test.	46827.	#10.	TP.	43.	~~2,150~~ 1980
Associated.	001439.	A07.	WW.	12.	330. ✓
SOCAL GAS CO.	397734.	S-11.	TP.	10.	15,500 ✓

Daily Total $ ~~25,163~~ 24,993
Previous Total $ 17,229
Cumulative Total $ ~~42,392~~ 42,222

Work Categories

PR Pre-rig work, well kill
MI Move in - rig up, install & test BOPE
CO Initial/final clean out
DD Drilling
LR Leak repair - cmt. sqz., casing patch
FF Fishing
PB Plugback, redrill
ST Stimulation - acid wash, reperforating
GP Gravel pack
IT Isolation test - noise log, WSO test
WW Wellhead work
CI Run casing/inner-string/liner
TP Run tbg. & prod. equip.
AA Abandonment
RR Rig repairs
SB Stand-by
MO Rig down - move out
PO Post-rig work
ZZ Miscellaneous

Functional Indexes

10 Tubular goods
11 Tubing accessories, packers
12 Wellhead equip. & svcs.
13 Gravel pack equip. & svcs.
14 Casing accessories
20 Bits
21 Fluids
22 Cement, acid, sand, chemicals & pumping svcs.
23 Nitrogen and coil tubing svcs.
24 Filtering and solids control
30 Service tools
31 Fishing tools & svcs.
32 Hole openers, mills, junk subs, reamers, stabilizers
33 Coring, dynadrills & directional svcs.
35 Piano wire equip. & svcs.
40 Open & cased hole logging
41 Other Wireline svcs.
42 Production logging
43 Hydrotest, torque, tong svcs., thread washing
44 Trucking, hauling, cranes & hot shots
45 Vacuum trucking, disposal charges
46 Tank rental, misc. rentals
47 Site preparation
60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Cyn. WELL NAME SS #30 CONTRACTOR CPS RIG No. 72

RIG [illegible] 5

MWO# 99934 / TOTAL COST ESTIMATE $ 35,000

RIG DATE 2-2-89

GWO# _____ / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR JD Woods

DAILY COST $ 3350

CUMULATIVE COST $ 17,229

CASING: OD 7" in. DEPTH 9248' ft. LINER OD _____ in. TOP _____ ft. BOTTOM _____ ft.

BRIEF DESCRIPTION OF ACTIVITIES

Fill well # 6 BBLS. Finished picking up Tubing CKS latch on pkr 20,000# over set 10,000# on packer. Test 30 minutes with 1500 psi. (OK) measure out of well. made up production equipment. Hydro Testing in well to 4000 psi. Sec well.

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %
Polymer.			63.					

OPERATIONS SEQUENCE & DETAIL

DAY TOUR

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
600	700	1	6	BLED WELL Ø PSI OPEN WELL fill hole TOOK 46 BBLS HAUL IN 2 7/8 Tbg
700	800	1	6	HAUL IN 2 7/8" Tbg & PICK up
800	900	1	6	pick up 2 7/8" Tbg LATCH ON PKR Pull 20,000# OVER 20 MIN
900	1000	½-½	E/6	TEST PKR & CSG to 1500 PSI USING HydroTEST CHART RELEASE
1000	1100	1	6	POW MEASURE OUT
1100	1200	1	6	POW MEASURE OUT
1200	100	1	6	POW MEASURE OUT
100	200	1	6	POW MEASURE OUT

DRILLER W. Jones

FOOTAGE FROM	TO	DR..D RM--R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000's	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SCL..S PUMP..P ACTUAL..A COMP..C

DEVIATION RECORD	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

EVENING TOUR

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
200	300	1	6	POW MEASURE OUT BREAK off LATCH 2 SEALS
300	400	1	6	made up Prod EQUIPMENT & TEST 4000 PSI RIW TEST 2 7/8
400	500	1	6	RIW HydroTEST 2 7/8 Tbg 4000 PSI
500	600	1	6	RIW HydroTEST 2 7/8 Tbg 4000 PSI Rig DOWN
				HydroTEST tools SHUT IN WELL with PIPE &
				HYDRIL BALL VALVE

DRILLER W. Jones

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS-#30 Date 2/2/89 Initials JDW

Daily Base Costs

Rig $ 200 /hour x 12 hours =	$ 2400	/day
Extra Labor	$	/day
Rig Supervisor	$ 550	/day
BOPE Rental	$ 400	/day
Drillpipe Rental	$	/day
	Subtotal $	3350

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$ 3,350

Daily Total	$ 3350
Previous Total	$ 13,879
Cumulative Total	$ 17,229

Work Categories

- PR Pre-rig work, well kill
- MI Move in - rig up, install & test BOPE
- CO Initial/final clean out
- DD Drilling
- LR Leak repair - cmt. sqz., casing patch
- FF Fishing
- PB Plugback, redrill
- ST Stimulation - acid wash, reperforating
- GP Gravel pack
- IT Isolation test - noise log, WSO test
- WW Wellhead work
- CI Run casing/inner-string/liner
- TP Run tbg. & prod. equip.
- AA Abandonment
- RR Rig repairs
- SB Stand-by
- MO Rig down - move out
- PO Post-rig work
- ZZ Miscellaneous

Functional Indexes

- 10 Tubular goods
- 11 Tubing accessories, packers
- 12 Wellhead equip. & svcs.
- 13 Gravel pack equip. & svcs.
- 14 Casing accessories
- 20 Bits
- 21 Fluids
- 22 Cement, acid, sand, chemicals & pumping svcs.
- 23 Nitrogen and coil tubing svcs.
- 24 Filtering and solids control
- 30 Service tools
- 31 Fishing tools & svcs.
- 32 Hole openers, mills, junk subs, reamers, stabilizers
- 33 Coring, dynadrills & directional svcs.
- 35 Piano wire equip. & svcs.
- 40 Open & cased hole logging
- 41 Other Wireline svcs.
- 42 Production logging
- 43 Hydrotest, torque, tong svcs., thread washing
- 44 Trucking, hauling, cranes & hot shots
- 45 Vacuum trucking, disposal charges
- 46 Tank rental, misc. rentals
- 47 Site preparation
- 60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Cyn WELL NAME 55-30 CONTRACTOR CPS RIG No. 72
RIG DAYS 4 MWO# 99934 / TOTAL COST ESTIMATE $ 35,000
RIG DATE 2-1-89 GWO# _____ / TOTAL COST ESTIMATE $ _____
RIG SUPERVISOR J D Woods DAILY COST $ 4883
CASING: OD 7" in. LINER OD _____ in. CUMULATIVE COST $ 13,879
DEPTH 9248 ft. TOP _____ ft.
BOTTOM _____ ft.

BRIEF DESCRIPTION OF ACTIVITIES

Fill well 39 BBLS, Repair Rig. 1 hours. Finished pulling out LAY down product Equipment, made up TEST SEAL Run in Hydro TEST Tubing To 3000 PST, TEAR OUT Hydro TEST LAY down TOTAL of 56 Joints BAD. picked up 27 Joints 2⅞ N 80 Tubing Secure well

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %
Polymer.			63					

ELAPSED TIME (HR) | OPERATIONS SEQUENCE & DETAIL

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS SERVICE EQUIPMENT
6:00	7:00	1	5	OPEN Well @ P.S.I & Filled Took 54 bbls & Mixed 87 bbls Poly
7:00	8:00	1	6	P.O.W
8:00	9:00	1	6	P.O.W & LAYED down Prod
9:00	10:00	1	21	LOAD out Prod EQUIPMENT
10:00	11:00	1	6	Rig up Hydo TEST & Made up TEST Seals & No 60 & TESTING Hole
11:00	12:00	1	6	TEST IN Hole @ 5000 P.S.I
12:00	1:00	1	6	R.I.W TESTING
1:00	2:00	1	6	" " "

DRILLER K. K. Jones

FOOTAGE FROM	FOOTAGE TO	DR-D RM-R CORE-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 100's	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SCL-S PART-P COMP-C
(NOTE LAYED down) 56 JTS BAD TBG												

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	3:00	1	6	TESTING TBG @ 5,000 P.S.I
3:00	4:00	1	6	" " " & LAYED down Hydo TEST TOOLS
4:00	5:00	1	6	LAYED down 56 JTS BAD TBG & Picked up 27 JTS NEW TBG
5:00	6:00	1	6	LOAD out BAD TBG & Closed Well in w/ Pipe Rams & BLS & Ball Valve
6:00	7:00			

DRILLER K. K. Jones

AC_CPUC_0117979

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS-30 Date 2/1/89 Initials JPW

Daily Base Costs

Rig $ 200 /hour x 12 hours = $ 2400 /day
2 – Extra Labor ... 5.0 ... X ... 12 ... $ 600 /day
Rig Supervisor ... $ 550 /day
BOPE Rental ... $ 400 /day
Drillpipe Rental ... $ _____ /day
Subtotal $ 3950

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	–	–		01	$ 3950
OTIS	911703	009	TP	11	219
BAKER	337-66918	836	TP	11	714

Daily Total $ 4,883
Previous Total $ 8,996
Cumulative Total $ 13,879

Work Categories

PR Pre-rig work, well kill
MI Move in - rig up, install & test BOPE
CO Initial/final clean out
DD Drilling
LR Leak repair - cmt. sqz., casing patch
FF Fishing
PB Plugback, redrill
ST Stimulation - acid wash, reperforating
GP Gravel pack
IT Isolation test - noise log, WSO test
WW Wellhead work
CI Run casing/inner-string/liner
TP Run tbg. & prod. equip.
AA Abandonment
RR Rig repairs
SB Stand-by
MO Rig down - move out
PO Post-rig work
ZZ Miscellaneous

Functional Indexes

10 Tubular goods
11 Tubing accessories, packers
12 Wellhead equip. & svcs.
13 Gravel pack equip. & svcs.
14 Casing accessories
20 Bits
21 Fluids
22 Cement, acid, sand, chemicals & pumping svcs.
23 Nitrogen and coil tubing svcs.
24 Filtering and solids control
30 Service tools
31 Fishing tools & svcs.
32 Hole openers, mills, junk subs, reamers, stabilizers
33 Coring, dynadrills & directional svcs.
35 Piano wire equip. & svcs.
40 Open & cased hole logging
41 Other Wireline svcs.
42 Production logging
43 Hydrotest, torque, tong svcs, thread washing
44 Trucking, hauling, cranes, shot shots
45 Vacuum trucking, disposal charges
46 Tank rental, misc. rentals
47 Site preparation
60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Cyn. WELL NAME SS - 30 CONTRACTOR CPS RIG No. 72

RIG DAYS 3 MWO# 99934 / TOTAL COST ESTIMATE $ 35000

RIG DATE 1-31-89 GWO# _____ / TOTAL COST ESTIMATE $ /

RIG SUPERVISOR J.D. Woods DAILY COST $ 3,600

CASING: OD 7" in. DEPTH 9248' ft. LINER OD _____ in. TOP _____ ft. BOTTOM _____ ft.

CUMULATIVE COST $ ~~9,946~~ - 750 = 8996

BRIEF DESCRIPTION OF ACTIVITIES

Rig up working floor. Rig up and fill well 130 BBLS, circulate bottom up. work and turn tubing to release from packer pulling out of well. Found 6 joints full of hole between 900' and 2250' pipe is soft, some is flat above pin end from tongs, Pulled to kill string. Sec well,

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS Service Equipment
6:00	7:00	1	21	Rigged up Work Floor
7:00	8:00	1	21	" " "
8:00	9:00	1	21	" " "
9:00	10:00	1	5	Open Well @ P.S.I & Rig To Circ
10:00	11:00	1	5	Pumped 128 bbls & broke Circ
11:00	12:00	1	5	Circ Well
12:00	1:00	1/2	5-6	Circ Well & Att To Release From Packer
1:00	2:00	1	6	Att To Release From Packer

DRILLER H. K. Jones

FOOTAGE FROM	TO	DR-D RM-R CORE-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 100:=	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SCL-S PAPER-P COM-C

DEVIATION RECORD	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	3:00	1	6	Released & P.O.W laying down JTS W/ Pin Holes
3:00	4:00	1	6	P.O.W laying down JTS W/ Pin Holes
4:00	5:00	1	6	P.O.W To 3049'
5:00	6:00	1	6	P.O.W & Closed Well in w/ Pipe Rams Bag & Ball Valve
6:00	7:00			

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS-#30 Date 1/31/89 Initials JDW

Daily Base Costs

Rig $ 200 /hour x 12 hours = $ 2400 /day
Extra Labor ..... $ _____ /day
Rig Supervisor ..... $ 550 /day
BOPE Rental ..... $ 650 /day
Drillpipe Rental ..... $ _____ /day Subtotal $ 3600

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$ 3600

Daily Total $ 3600
Previous Total $ 6,146
Cumulative Total $ 9746
- 750
8,996

Work Categories

PR Pre-rig work, well kill
MI Move in - rig up, install & test BOPE
CO Initial/final clean out
DD Drilling
LR Leak repair - cmt. sqz., casing patch
FF Fishing
PB Plugback, redrill
ST Stimulation - acid wash, reperforating
GP Gravel pack
IT Isolation test - noise log, WSO test
WW Wellhead work
CI Run casing/inner-string/liner
TP Run tbg. & prod. equip.
AA Abandonment
RR Rig repairs
SB Stand-by
MO Rig down - move out
PO Post-rig work
ZZ Miscellaneous

Functional Indexes

10 Tubular goods
11 Tubing accessories, packers
12 Wellhead equip. & svcs.
13 Gravel pack equip. & svcs.
14 Casing accessories
20 Bits
21 Fluids
22 Cement, acid, sand, chemicals & pumping svcs.
23 Nitrogen and coil tubing svcs.
24 Filtering and solids control
30 Service tools
31 Fishing tools & svcs.
32 Hole openers, mills, junk subs, reamers, stabilizers
33 Coring, dynadrills & directional svcs.
35 Piano wire equip. & svcs.
40 Open & cased hole logging
41 Other Wireline svcs.
42 Production logging
43 Hydrotest, torque, tong svcs, thread washing
44 Trucking, hauling, cranes & hot shots
45 Vacuum trucking, disposal charges
46 Tank rental, misc. rentals
47 Site preparation
60 Miscellaneous

Corrected

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Canyon WELL NAME SS # 30 CONTRACTOR CPS RIG No. 72

RIG DAYS 2 MWO# 99934 / TOTAL COST ESTIMATE $ 35,000

RIG DATE 1-30-89 GWO# _____ / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR J.D. Woods DAILY COST $ 4046

CASING: OD 7" in. DEPTH 9248 ft. LINER OD _____ in. TOP _____ ft. BOTTOM _____ ft.

CUMULATIVE COST $ 5396

BRIEF DESCRIPTION OF ACTIVITIES

Rig up M-72 on SS 30. Removed X-MAS Tree, installed Shaffer, 7 1/16" x 5000 psi B.O.P.E.. Test Blind Rams, 2 7/8 pipe rams, and choke manifold to 3000 psi. Test Hydril bag to 2,300 psi. Sec well. Steve Mulqueen with Dog. Wave test.

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

RECORD

DAY TOUR

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
600	700	1	1	Rigged up Equipment
700	800	1	1	" " "
800	900	1	1	" " "
900	1000	1	1	" " "
1000	1100	1	1	" " "
1100	1200	1	1	Raised Rig & Tied down
1200	100	1	1	" " "
100	200	1	14	Remove Tree

DRILLER H.K. Jones

FOOTAGE FROM	TO	DR-D RM-R CORE-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 100's	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL-S PAR-P CON-C

DEVIATION RECORD	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

EVENING TOUR

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
200	300	1	14	Nipple up B.O.P.E
300	400	1	14	" " "
400	500	1/2 1/2	14-15	Nipple up & Rig up Hydo Test & Test Blind Rams & 300
500	600	1	15	(20 Mins OK) Test Pipe Rams 3000 P.S.I 20 Mins OK) & Test K
				2300 P.S.I 20 Mins & Closed Well IN w/ Pipe Rams
				Bag & Ball Valve

DRILLER H. Jones

DRILLING REPORT FORM

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well STANDARD SESNON 30 Date 1/30/89 Initials J.D.W.

Daily Base Costs

Rig $ 200 /hour x 5 hours = $ 1000 /day
Extra Labor ...100...x...7 ..... $ 700 /day
Rig Supervisor ..... $ 550 /day
BOPE Rental ..... $ 650 /day
Drillpipe Rental ..... $ ____ /day Subtotal $ 2900

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—	MI	01	$ 2,900
H&H Oil Tool (Rig Move)	27286.	H03	MI.	44.	506
RTC. (Rig Move)	42-1264.	R061	MI.	44.	298
Hydro Test,	46636.	H10	MI.	43.	342
				Daily Total	$ 4046
				Previous Total	$ 1350
				Cumulative Total	$ 5396

Work Categories

PR Pre-rig work, well kill
MI Move in - rig up, install & test BOPE
CO Initial/final clean out
DD Drilling
LR Leak repair - cmt. sqz., casing patch
FF Fishing
PB Plugback, redrill
ST Stimulation - acid wash, reperforating
GP Gravel pack
IT Isolation test - noise log, WSO test
WW Wellhead work
CI Run casing/inner-string/liner
TP Run tbg. & prod. equip.
AA Abandonment
RR Rig repairs
SB Stand-by
MO Rig down - move out
PO Post-rig work
ZZ Miscellaneous

Functional Indexes

10 Tubular goods
11 Tubing accessories, packers
12 Wellhead equip. & svcs.
13 Gravel pack equip. & svcs.
14 Casing accessories
20 Bits
21 Fluids
22 Cement, acid, sand, chemicals & pumping svcs.
23 Nitrogen and coil tubing svcs.
24 Filtering and solids control
30 Service tools
31 Fishing tools & svcs.
32 Hole openers, mills, junk subs, reamers, stabilizers
33 Coring, dynadrills & directional svcs.
35 Piano wire equip. & svcs.
40 Open & cased hole logging
41 Other Wireline svcs.
42 Production logging
43 Hydrotest, torque, tong svcs., thread washing
44 Trucking, hauling, cranes & hot shots
45 Vacuum trucking, disposal charges
46 Tank rental, misc. rentals
47 Site preparation
60 Miscellaneous

Corrected

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Cyn WELL NAME SS #30 CONTRACTOR CPS RIG No. 72

RIG DAYS 1 MWO# 99934 / TOTAL COST ESTIMATE $ 35000

RIG DATE 1-28-89 GWO# _____ / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR W.L. Killebrew DAILY COST $ 1350

CASING: OD 7" in. LINER OD _____ in. CUMULATIVE COST $ 1350

DEPTH 9248 ft. TOP _____ ft.

BOTTOM _____ ft.

BRIEF DESCRIPTION OF ACTIVITIES

Load Rig - moved from Porter 32 to Standard Seymont #30

Rigging up

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

DEVIATION RECORD	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
700	800	1		Load out Equipment & Move Equipment To S.S.30
800	900	1		" " " "
900	1000	1		" " " "
1000	1100			" " " "
1100	1200			Rig up
1200	100			" "
100	200			" "
200	300			" "

DRILLER H.K. JONES

FOOTAGE FROM	TO	DR.-D RM.-R CORE-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000's	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PAR.-P COMP.-C

DEVIATION RECORD	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
				DRILLER

LING REPORT FORM

AC_CPUC_0117985

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well Standard Session #30 Date 1/28/89 Initials WZK

Daily Base Costs

Rig $ _____ /hour x _____ hours =	$ _____	/day
Extra Labor 32 HRS X 25.00	$ 800 ✓	/day
Rig Supervisor	$ 550	/day
BOPE Rental	$ _____	/day
Drillpipe Rental	$ _____	/day
	Subtotal $	1350 ✓

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—	MI	01	$ 1350

Daily Total	$	1350 ✓
Previous Total	$	—
Cumulative Total	$	1350 ✓

Work Categories

- PR Pre-rig work, well kill
- MI Move in - rig up, install & test BOPE
- CO Initial/final clean out
- DD Drilling
- LR Leak repair - cmt. sqz., casing patch
- FF Fishing
- PB Plugback, redrill
- ST Stimulation - acid wash, reperforating
- GP Gravel pack
- IT Isolation test - noise log, WSO test
- WW Wellhead work
- CI Run casing/inner-string/liner
- TP Run tbg. & prod. equip.
- AA Abandonment
- RR Rig repairs
- SB Stand-by
- MO Rig down - move out
- PO Post-rig work
- ZZ Miscellaneous

Functional Indexes

- 10 Tubular goods
- 11 Tubing accessories, packers
- 12 Wellhead equip. & svcs.
- 13 Gravel pack equip. & svcs.
- 14 Casing accessories
- 20 Bits
- 21 Fluids
- 22 Cement, acid, sand, chemicals & pumping svcs.
- 23 Nitrogen and coil tubing svcs.
- 24 Filtering and solids control
- 30 Service tools
- 31 Fishing tools & svcs.
- 32 Hole openers, mills, junk subs, reamers, stabilizers
- 33 Coring, dynadrills & directional svcs.
- 35 Piano wire equip. & svcs.
- 40 Open & cased hole logging
- 41 Other Wireline svcs.
- 42 Production logging
- 43 Hydrotest, torque, tong svcs., thread washing
- 44 Trucking, hauling, cranes & hot shots
- 45 Vacuum trucking, disposal charges
- 46 Tank rental, misc. rentals
- 47 Site preparation
- 60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Cyn. WELL NAME SS#30 CONTRACTOR CPS RIG No. 72

RIG DAYS 1 MWO# 99933 / TOTAL COST ESTIMATE $ 40,000

RIG DATE 1-27-89 GWO# _____ / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR W.L.K./Eb Rew DAILY COST $ 750

CASING: OD 7" in. LINER OD _____ in. CUMULATIVE COST $ 750

DEPTH 9248' ft. TOP _____ ft.

BOTTOM _____ ft.

BRIEF DESCRIPTION OF ACTIVITIES

Lower DERRICK - TEARING DOWN

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

DEVIATION RECORD	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
4:00	5:00	1	14	TEST TREE TO 5000 P.S.I & Rig DOWN Rig
5:00	6:00	1	14	TEST TREE & CLOSED WELL IN @ TREE Rig DOWN
				DRILLER

FOOTAGE FROM	TO	DR..D RM..R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 100's	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL..S PAR..P COM..C

DEVIATION RECORD	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
				DRILLER

AC_CPUC_0117987

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well GS #30 Date 1/27/89 Initials W.L.K.

Daily Base Costs

Rig $ _____ /hour x _____ hours = $ _____ /day
Extra Labor ... 8 hrs ... 25.00 ... $ 200 /day
Rig Supervisor ... $ 550 /day
BOPE Rental ... $ _____ /day
Drillpipe Rental ... $ _____ /day Subtotal $ 750

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$ 750

Daily Total $ 750
Previous Total $ 0
Cumulative Total $ 750

Work Categories

PR Pre-rig work, well kill
MI Move in - rig up, install & test BOPE
CO Initial/final clean out
DD Drilling
LR Leak repair - cmt. sqz., casing patch
FF Fishing
PB Plugback, redrill
ST Stimulation - acid wash, reperforating
GP Gravel pack
IT Isolation test - noise log, WSO test
WW Wellhead work
CI Run casing/inner-string/liner
TP Run tbg. & prod. equip.
AA Abandonment
RR Rig repairs
SB Stand-by
MO Rig down - move out
PO Post-rig work
ZZ Miscellaneous

Functional Indexes

10 Tubular goods
11 Tubing accessories, packers
12 Wellhead equip. & svcs.
13 Gravel pack equip. & svcs.
14 Casing accessories
20 Bits
21 Fluids
22 Cement, acid, sand, chemicals & pumping svcs.
23 Nitrogen and coil tubing svcs.
24 Filtering and solids control
30 Service tools
31 Fishing tools & svcs.
32 Hole openers, mills, junk subs, reamers, stabilizers
33 Coring, dynadrills & directional svcs.
35 Piano wire equip. & svcs.
40 Open & cased hole logging
41 Other Wireline svcs.
42 Production logging
43 Hydrotest, torque, tong svcs. thread washing
44 Trucking, hauling, cranes & shots
45 Vacuum trucking, disposal charges
46 Tank rental, misc. rentals
47 Site preparation
60 Miscellaneous

Date: 2/3/89 Field: ALISO CANYON Well: SS 30

Rig: M-72 Tool Pusher: [signature] (signature) Company Representative: (signature)

TOUR CHECKS

Morning Volume to Fill Hole (bbls) 0 Formation Pressure (psig) 1600 Were any DOG inspections required? YES X NO

Accumulator Pressure (psig) 3100 Mud gradient (psi/ft)=[(#/ft^3)/144] .4375 If "Yes", reason(s) for inspection(s)

Emergency Supply Pressure (psig) 2000 TVD of zone (ft) 7563 Inspector's Name:

Manifold Pressure (psig) 1800 Hydrostatic Pressure (psig) 3308 Was the inspection waived? YES NO If n

Annular Preventer Pressure (psig) 1100 did the inspector sign tour sheet? YES NO

Accumulator Fluid Level (ft/in) 2/2 Overbalance (psig) 1708

Check of remote visual indicator(s) ✓ (✓ = OK, X = problem)

TRIP CHECKS

No. Stands Pulled	Trip No.	Vol. to Fill Hole (bbls)	No. Stands Run	Trip No.	Time for Hole to Stabilize (secs)
			10	1	0
			10	1	0
			10	1	0
			10	1	0
			10	1	0
			10	1	0
			10	1	0
			10	1	0
			5	1	0

MUD PROPERTIES

Mud Type KCL

Funnel Viscosity sec.

Water Loss cc

Density #/cu.ft.

Yield Pt. #/100 sq.ft.

pH

Solids %

Suspended Solids %

Comments: CHANGEOVER FROM POLYMER TO KCL

Were the following actuated during the trip?

Pipe Rams -- Yes ✓ No / Annular Preventer -- Yes ✓ No / Kelly Cocks -- Yes No ✓

Blind Rams -- Yes No ✓ / Adjustable Choke -- Yes ✓ No / Safety Ball Valve -- Yes ✓ No

Are low rate circulating pressure (LRCP) and pump strokes recorded on tour sheet? YES

REW
11-21-86

Date: 2/2/89 Field: ALISO CANYON Well: STANDARD SESNON # 30

Rig: M-72 Tool Pusher: _____ (signature) Company Representative: J Dawards (signature)

TOUR CHECKS

Morning Volume to Fill Hole (bbls) 46 Formation Pressure (psig) 1600 Were any DOG inspections required? YES___ NO✓

Accumulator Pressure (psig) 3000 Mud gradient (psi/ft)=[(#/ft^3)/144] .4375 If "Yes", reason(s) for inspection(s) _____

Emergency Supply Pressure (psig) 2200 TVD of zone (ft) 7563 Inspector's Name: _____

Manifold Pressure (psig) 1600 Hydrostatic Pressure (psig) 3308 Was the inspection waived? YES___ NO___ If n

Annular Preventer Pressure (psig) 1200 did the inspector sign tour sheet? YES___ NO

Accumulator Fluid Level (ft/in) 2/3 Overbalance (psig) 1708

Check of remote visual indicator(s) ✓ (✓ = OK, X = problem)

TRIP CHECKS

No.Stands Pulled	Trip No.	Vol. to Fill Hole (bbls)	No.Stands Run	Trip No.	Time for Hole to Stabilize (secs)
10	1	1.0	10	2	0
10	1	1.0	10	2	0
10	1	1.0	10	2	0
10	1	1.0	10	2	0
10	1	1.0	10	2	0
10	1	1.0	5	2	0
10	1	1.0			
10	1	1.0			
10	1	1.0			
10	1	1.0			
10	1	1.0			
10	1	1.0			
10	1	1.0			
10	1	1.0			
1	1	.1			

MUD PROPERTIES

Mud Type POLYMER

Funnel Viscosity 47 sec.

Water Loss _____ cc

Density 63 #/cu.ft.

Yield Pt. _____ #/100 sq.ft.

pH _____

Solids _____ %

Suspended Solids _____ %

Comments: _____

Were the following actuated during the trip?

Pipe Rams -- Yes ✓ No ___ / Annular Preventer -- Yes ✓ No ___ / Kelly Cocks -- Yes ___ No ✓

Blind Rams -- Yes ✓ No ___ / Adjustable Choke -- Yes ✓ No ___ / Safety Ball Valve -- Yes ✓ No ___

Are low rate circulating pressure (LRCP) and pump strokes recorded on tour sheet? YES

REW
11-21-86

Date: 2/1/89 Field: Aliso Well: SS-#30

Rig: M-72 Tool Pusher: Dave (signature) Company Representative: J. D. Woods (signature)

TOUR CHECKS

Morning Volume to Fill Hole (bbls) 59 Formation Pressure (psig) 1600 Were any DOG inspections required? YES___ NO___

Accumulator Pressure (psig) 2950 Mud gradient (psi/ft)=[(#/ft^3)/144] .435 If "Yes", reason(s) for inspection(s)_____

Emergency Supply Pressure (psig) 1950 TVD of zone (ft) 8854 Inspector's Name:_____

Manifold Pressure (psig) 1600 Hydrostatic Pressure (psig) 3888 Was the inspection waived? YES___ NO___ If n

Annular Preventer Pressure (psig) 1000 did the inspector sign tour sheet? YES___ NO

Accumulator Fluid Level (ft/in) 2' 1/4" Overbalance (psig) 2288

Check of remote visual indicator(s)_____ (✓ = OK, X = problem)

TRIP CHECKS

No. Stands Pulled	Trip No.	Vol. to Fill Hole (bbls)	No. Stands Run	Trip No.	Time for Hole to Stabilize (secs)
			10	1	0
			10	1	0
			10	1	0
Pulled	3049'	& laid	10	1	0
down	bad	joints	10	1	0
			10	1	0
			10	1	0
			10	1	0
			10	1	0
			10	1	0
			10	1	0
			10	1	0
			10	1	0
			10	1	0
			10	1	0
			10	1	0

MUD PROPERTIES

Mud Type Poly

Funnel Viscosity 50 sec.

Water Loss_____ cc

Density 6.3 #/cu.ft.

Yield Pt._____ #/100 sq.ft.

pH_____

Solids_____ %

Suspended Solids_____ %

Comments:_____

Were the following actuated during the trip?

Pipe Rams -- Yes ✓ No___ / Annular Preventer -- Yes ✓ No___ / Kelly Cocks -- Yes___ No ✓

Blind Rams -- Yes ✓ No___ / Adjustable Choke -- Yes ✓ No___ / Safety Ball Valve -- Yes ✓ No___

Are low rate circulating pressure (LRCP) and pump strokes recorded on tour sheet? yes

REW
11-21-86

AC_CPUC_0117991

Date: 1/31/89 Field: Aliso Well: S-S-#30

Rig: M-72 Tool Pusher: Dayton (signature) Company Representative: J.D. Woods (signature)

TOUR CHECKS

Morning Volume to Fill Hole (bbls) 0 Formation Pressure (psig) 1600 Were any DOG inspections required? YES___ NO

Accumulator Pressure (psig) 3000 Mud gradient (psi/ft)=[(#/ft^3)/144] .4375 If "Yes", reason(s) for inspection(s)

Emergency Supply Pressure (psig) 1950 TVD of zone (ft) 8884 Inspector's Name:

Manifold Pressure (psig) 1300 Hydrostatic Pressure (psig) 3888 Was the inspection waived? YES ✓ NO___ If n

Annular Preventer Pressure (psig) 1100 did the inspector sign tour sheet? YES___ NO

Accumulator Fluid Level (ft/in) 2'10 Overbalance (psig) 2288

Check of remote visual indicator(s) ✓ (✓ = OK, X = problem)

TRIP CHECKS

No. Stands Pulled	Trip No.	Vol. to Fill Hole (bbls)	No. Stands Run	Trip No.	Time for Hole to Stabilize (secs)
10	1	1.4			
10	1	1.4			
10	1	1.4			
10	1	1.4			
10	1	1.4			
10	1	1.4			
10	1	1.4			
10	1	1.4			
8	1	1.1			

MUD PROPERTIES

Mud Type PHP

Funnel Viscosity 45 sec.

Water Loss cc

Density 63 #/cu.ft.

Yield Pt. #/100 sq.ft.

pH

Solids %

Suspended Solids %

Comments:

Were the following actuated during the trip?

Pipe Rams -- Yes ✓ No___ / Annular Preventer -- Yes ✓ No___ / Kelly Cocks -- Yes___ No ✓ No Kelly Used

Blind Rams -- Yes___ No ✓ / Adjustable Choke -- Yes ✓ No___ / Safety Ball Valve -- Yes ✓ No___

Are low rate circulating pressure (LRCP) and pump strokes recorded on tour sheet? YES

REW
11-21-86

AC_CPUC_0117992

No. 153716

DAILY DRILLING REPORT — REPORT NO. 7

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CANYON	SS#30	7-7350	2-3-89

OPERATOR	CONTRACTOR	RIG NO.
SOUTHERN CALIF GAS CO.	CALIF PROD SERVICE	M-72

SIGNATURE OF OPERATOR'S REPRESENTATIVE: J.D. Wanke

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: L Dayton

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
41	O.P.I	500 AWS	4"X6"

FIELD OR DIST.: ALISO CANYON — COUNTY: L.A. — STATE: CALIF

LAST CASING TUBING OR LINER	SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT
	11 3/4"		42 47#				2500'
	7"		23 26 29#		PERFS 8884' TO 9240'		9240'
					BAKER model "D" PKR AT 8840'		

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED
1"	8	

FT. CUT OFF: — PRESENT LENGTH:

TON MI. OR TRIPS SINCE LAST CUT:

CUMULATIVE TON MI. OR TRIPS:

TIME DISTRIBUTION – HOURS

CODE NO.	OPERATION	MORN.	DAY	EVE.
1.	RIG UP AND TEAR DOWN			
2.	DRILL ACTUAL			
3.	REAMING			
4.	CORING			
5.	CONDITION MUD & CIRCULATE		2	
6.	TRIPS		4½	
7.	LUBRICATE RIG			
8.	REPAIR RIG			
9.	CUT OFF DRILLING LINE			
10.	DEVIATION SURVEY			
11.	WIRE LINE LOGS			
12.	RUN CASING & CEMENT			
13.	WAIT ON CEMENT			
14.	NIPPLE UP B.O.P.		2½	
15.	TEST B.O.P.			
16.	DRILL STEM TEST			
17.	PLUG BACK			
18.	SQUEEZE CEMENT			
19.	FISHING			
20.	DIR. WORK			
21.	OTHER Ready Rig		1	
22.			2	
23.				
COMPLETION	A. PERF'R'T'N			
	B. TBG TRIPS			
	C. TREATING			
	D. SWABBING			
	E. TESTING		1	
	F. ADDIT'N'L			
	G.			
TOTALS			13	

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

DRILLING ASSEMBLY (At end of tour)

NO.		FT.
	BIT	FT.
	STB RMR OD	FT.
	D.C. ID OD	FT.
	STB RMR OD	FT.
	D.C. ID OD	FT.
	STB RMR OD	FT.
	STANDS DP	FT.
	SINGLES DP	FT.
	KELLY DOWN	FT.
	TOTAL	FT.
	WT. OF STRING	LBS.

BIT RECORD

BIT NO. / SIZE / IADC CODE / MFG. / TYPE / SER. NO. / JETS 1/32" / TFA in² / DEPTH OUT / DEPTH IN / TOTAL FTG. / TOTAL HRS.

DULL: CUT. STRUC. I O D L B G O R

GPM/PUMP-PSI

MUD RECORD

TIME / WEIGHT / PRESSURE GRADIENT / VISC.-SEC. / PV/YP / GELS. / WL -CC'S. / pH / SOLIDS %

MUD & CHEMICALS ADDED: TYPE / AMT. / TYPE / AMT.

MORNING TOUR / DAY TOUR / EVENING TOUR

FOOTAGE / FORMATION (SHOW CORE RECORD)

FROM	TO	DR..D RM..R CORE..C	CORE NO.	FORMATION (SHOW CORE RECORD)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL. PARAL-P COMPL'D C

DEVIATION RECORD: DEPTH / DEV. / DIRECTION (×3)

MORNING TOUR

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
				CUMULATIVE FLUID LOSS IN WELL = 287 BBLS
				STORAGE TANKS VOLUME #1 = 21 BBLS KCL WATER
				#2 = 334 BBLS POLYMER
				CIRC PIT VOLUME = 12 BBLS
				TOTAL SURFACE VOLUME = 367 BBLS
				KILL SPEED 3 Bpm 115 spm 250 pSI Depth 8764'

DRILLER

DAY TOUR

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
600	700	1	6	BLED WELL @ 75I OPEN WELL INSTALL TEST TOOLS IN Tbg & TEST TO 4000PSI SER. EQUIPMENT
700	800	1	6	RIW HYDROTEST 2⅞" Tbg 4000 PSI
800	900	1	6	RIW HYDROTEST 2⅞ Tbg 4000 PSI
900	1000	1	6	RIW HYDROTEST 2⅞" Tbg 4000 PSI TEST PUPS & DOUGHNUT
1000	1100	½-½	6	RIG DOWN HYDROTEST RIG UP TO CHANGE WELL OVER TO K.C.L
1100	1200	1	5	CHANGE WELL OVER TO 2% K.C.L WATER.
1200	100	½ ½	5 21	CHANGE WELL OVER TO 2% KCL WATER. LATCH ON PKR pull 18,000# OVER. LAND ON DOUGHNUT
100	200	½ ½	21 14	SCREW IN DOUGHNUT SCREW INSTALL B.P NIPPLE DOWN B.O.P

DRILLER W. Jones

EVENING TOUR

Release Rig 5:PM. 2-3-89

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
200	300	1	14	NIPPLE DOWN BOPE SET OUT
300	400	1	14	INSTALL XMAS TREE & FLANGE UP
400	500	1	E	TEST XMAS TREE TO 3000 PSI REMOVE B.P SHUT WELL IN
500	600	1	22	READY RIG FOR MOVE
600	700	1	22	READY RIG FOR MOVE

DRILLER W. Jones

DRILLING CREW PAYROLL DATA

DATE 2-3-89

WELL NAME & NO. STANDARD SESNON #30 7-7350

COMPANY SOUTHERN CALIF GAS CO.

TOOL PUSHER Dayton RIG NO. M-72

MORNING TOUR — P.M. — A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE		" " NOTE LAND ON DOUGHNUT with 8,000# ON PACKER		

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 6:00 A.M. 7:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	013 31	W. JONES	13	2
DRKMAN	025 56	T. BLEDSOE	13	3
MTRMAN	023 60	W. KENNEDY	13	7
FIREMAN	026 18	J. OLIVARES	13	7
FLRMAN				
FLRMAN				
FLRMAN		Rig & CREW	11	
TRAINEE		LABOR ONLY	2	

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR — P.M. — P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

6AM – 5PM Rig & Crew 11 HRS

5PM – 7PM Crew Only 2 HRS

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

FORM 3T-5 PRINTED IN U.S.A. APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED No. 153716

AC_CPUC_0117993

No. 153715

DAILY DRILLING REPORT — REPORT NO. 6

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CANYON	S.S #30	7-7350	2-2-89

OPERATOR	CONTRACTOR	RIG NO.
SOUTHERN CALIF GAS CO.	CALIF PROD SERVICE	M-72

SIGNATURE OF OPERATOR'S REPRESENTATIVE: J.D Woods

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: L Dayton

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
41	O.P.I	500 AWS	4"x6"

FIELD OR DIST.	COUNTY	STATE
ALISO	L.A	CALIF

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT
11 3/4"		42# 47#				2500'
7"		23 26 29#	Perf's	8884' to 9240'		9240'
	BAKER PACKER Model "D" @ 8840'					

WIRE LINE RECORD — REEL NO.

SIZE 1" | NO. LINES 8 | FT. SLIPPED

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION — HOURS

CODE NO.	OPERATION	MORN.	DAY	EVE.
1.	RIG UP AND TEAR DOWN			
2.	DRILL ACTUAL			
3.	REAMING			
4.	CORING			
5.	CONDITION MUD & CIRCULATE			
6.	TRIPS		11½	
7.	LUBRICATE RIG			
8.	REPAIR RIG			
9.	CUT OFF DRILLING LINE			
10.	DEVIATION SURVEY			
11.	WIRE LINE LOGS			
12.	RUN CASING & CEMENT			
13.	WAIT ON CEMENT			
14.	NIPPLE UP B.O.P.			
15.	TEST B.O.P.			
16.	DRILL STEM TEST			
17.	PLUG BACK			
18.	SQUEEZE CEMENT			
19.	FISHING			
20.	DIR. WORK			
21.				
22.				
23.				
COMPLETION	A. PERF'R'T'N			
	B. TBG TRIPS			
	C. TREATING			
	D. SWABBING			
	E. TESTING			1/2
	F. ADDIT'N'L			
	G.			
TOTALS				12

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.	
HRS. W/OPR. D.P.	
HRS. WO/D.P.	
HRS. STANDBY	
TOTAL DAY WORK	
NO. OF DAYS FROM SPUD	
CUMULATIVE ROTATING HRS.	
TOTAL MUD COST	

DRILLING ASSEMBLY (At end of tour) — DAY TOUR

NO.		FT.
	BIT	
	STB RMR OD	
	D.C. ID OD	
	STB RMR OD	
	D.C. ID OD	
	STB RMR OD	
	STANDS DP	
	SINGLES DP	
	KELLY DOWN	
	TOTAL	
	WT. OF STRING	LBS.

BIT RECORD — DAY TOUR

BIT NO. | SIZE | IADC CODE | MFG. | TYPE | SER. NO. | JETS 1/32" /TFA in² | DEPTH OUT | DEPTH IN | TOTAL FTG. | TOTAL HRS.

DULL: CUT. STRUC. I O D L; B G O R

GPM/PUMP-PSI

MUD RECORD — DAY TOUR

TIME | WEIGHT | PRESSURE GRADIENT | VISC.-SEC. | PV/YP | GELS. | WL -CC'S. | pH | SOLIDS %

MUD & CHEMICALS ADDED: TYPE | AMT. | TYPE | AMT.

MORNING TOUR

FOOTAGE — DAY TOUR

FROM	TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PARL.-P COMP.-C

DEVIATION RECORD: DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION

TIME LOG — DAY TOUR

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
				CUMULATIVE FLUID LOSS IN WELL = 287 BBLS
				STORAGE TANKS VOLUME #1 = 0 BBLS
				#2 = 264 BBLS K.C.L
				CIRC PIT VOLUME = 18 BBLS
				TOTAL SURFACE VOLUME = 282 BBLS
				KILL SPEED 3BBLS PER MIN 250 PSI DEPTH 8764'

DRILLER

DRILLING ASSEMBLY (At end of tour) — DAY TOUR

NO.		FT.
	BIT	
	STB RMR OD	
	D.C. ID OD	
	STB RMR OD	
	D.C. ID OD	
	STB RMR OD	
	STANDS DP	
	SINGLES DP	
	KELLY DOWN	
	TOTAL	
	WT. OF STRING	LBS.

BIT RECORD — DAY TOUR

BIT NO. | SIZE | IADC CODE | MFG. | TYPE | SER. NO. | JETS 1/32" /TFA in² | DEPTH OUT | DEPTH IN | TOTAL FTG. | TOTAL HRS.

DULL: CUT. STRUC. I O D L; B G O R

GPM/PUMP-PSI

MUD RECORD — DAY TOUR

TIME | WEIGHT | PRESSURE GRADIENT | VISC.-SEC. | PV/YP | GELS. | WL -CC'S. | pH | SOLIDS %

MUD & CHEMICALS ADDED: TYPE | AMT. | TYPE | AMT.

DAY TOUR

FOOTAGE — DAY TOUR

FROM	TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PARL.-P COMP.-C

DEVIATION RECORD: DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION

TIME LOG — DAY TOUR

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
600	700	1	6	BLED WELL @ PSI OPEN WELL FILL HOLE TOOK 44 BBLS HAUL IN 2⅞ Tbg
700	800	1	6	HAUL IN 2⅞" Tbg & PICK UP
800	900	1	6	PICK UP 2⅞" Tbg LATCH ON PKR Pull 20,000# OVER 20 MIN
900	1000	½-½	E/6	TEST PKR & CSG to 1500 PSI using HydroTest CHART RELEASE S/PKR
1000	1100	1	6	POW MEASURE OUT
1100	1200	1	6	POW MEASURE OUT
1200	100	1	6	POW MEASURE OUT
100	200	1	6	POW MEASURE OUT

DRILLER W. Jones

DRILLING ASSEMBLY (At end of tour) — EVENING TOUR

NO.		FT.
	BIT	
	STB RMR OD	
	D.C. ID OD	
	STB RMR OD	
	D.C. ID OD	
	STB RMR OD	
55	STANDS DP Tbg	3504' FT.
	SINGLES DP	FT.
	KELLY DOWN	FT.
	TOTAL	FT.
	WT. OF STRING	LBS.

BIT RECORD — EVENING TOUR

BIT NO. | SIZE | IADC CODE | MFG. | TYPE | SER. NO. | JETS 1/32" /TFA in² | DEPTH OUT | DEPTH IN | TOTAL FTG. | TOTAL HRS.

DULL: CUT. STRUC. I O D L; B G O R

GPM/PUMP-PSI

MUD RECORD — EVENING TOUR

TIME | WEIGHT | PRESSURE GRADIENT | VISC.-SEC. | PV/YP | GELS. | WL -CC'S. | pH | SOLIDS %

MUD & CHEMICALS ADDED: TYPE | AMT. | TYPE | AMT.

EVENING TOUR

FOOTAGE — EVENING TOUR

FROM	TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PARL.-P COMP.-C

DEVIATION RECORD: DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION

TIME LOG — EVENING TOUR

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
200	300	1	6	POW MEASURE OUT BREAK off HATCH 2 SEALS
300	400	1	6	made up Prod EQUIPMENT & TEST 4000 PSI RIW TEST 2⅞ Tbg
400	500	1	6	RIW HydroTest 2⅞ Tbg 4000 PSI
500	600	1	6	RIW HydroTest 2⅞ Tbg 4000 PSI Rig Down Hydrotest tools Shut in well with PIPE RAMS Hydril Ball VALVE

DRILLER W. Jones

DRILLING CREW PAYROLL DATA

DATE 2-2-89

WELL NAME & NO. STANDARD SESNON #30 7-7350

COMPANY SOUTHERN CALIF GAS CO

TOOL PUSHER Dayton RIG NO. M-72

MORNING TOUR ____ P.M. ____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	Held 30 min. Safety Meeting			
DRKMAN	with Crew			
MTRMAN	C.P.S. Safety Director			
FIREMAN	Wayne Dean			
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 6:00 A.M. 6:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	013 31	W. JONES	12	2
DRKMAN	025 56	T. BLEDSOE	12	3
MTRMAN	015 88	H.W JONES	12	7
FIREMAN	025 18	J. OLIVARES	12	7
FLRMAN				
FLRMAN		Rig & CREW	12	
FLRMAN		NO ACC		
TRAINEE				

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR ____ P.M. ____ P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN		Rig & Crew 12 hrs		
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

AC_CPUC_0117994

No. 153714

DAILY DRILLING REPORT — REPORT NO. 5

LEASE	WELL NO.	API WELL NUMBER	DATE
Aliso Canyon	S.S. 30#	7-7350	2-1-89

OPERATOR	CONTRACTOR	RIG NO.
Southern Calif Gas Co	Calif Prod Service	M-72#

SIGNATURE OF OPERATOR'S REPRESENTATIVE: J.D. Woods

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J Dayton

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
41	O.P.I	500 AWS	4x6"

FIELD OR DIST. Aliso | COUNTY L.A | STATE Calif

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT
11 3/4		42 47				2500
7"		23 26 29	Perfs	8884' TO 9240'		9240'
Baker Packer Model "D" @ 8840'						

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED
1"	8	

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION — HOURS

CODE NO. — OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE		1	
6. TRIPS		10	
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. OTHER		1	
22.			
23.			
COMPLETION A. PERF'R'T'N			
B. TBG TRIPS			
C. TREATING			
D. SWABBING			
E. TESTING			
F. ADDIT'N'L			
G.			
TOTALS		12	

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

DRILLING ASSEMBLY (At end of tour)

NO.		
	BIT	FT.
	STB RMR OD	FT.
	D.C. ID OD	FT.
	STB RMR OD	FT.
	D.C. ID OD	FT.
	STB RMR OD	FT.
	STANDS DP	FT.
	SINGLES DP	FT.
	KELLY DOWN	FT.
	TOTAL	FT.
	WT. OF STRING	LBS.

BIT RECORD

BIT NO.	
SIZE	
IADC CODE	
MFG.	
TYPE	
SER. NO.	
JETS 1/32" /TFA in²	
DEPTH OUT	
DEPTH IN	
TOTAL FTG.	
TOTAL HRS.	
DULL CUT. STRUC. I O D L B G O R	
GPM/PUMP-PSI	

MUD RECORD

TIME			
WEIGHT			
PRESSURE GRADIENT			
VISC.-SEC.			
PV/YP	/	/	/
GELS.	/	/	/
WL -CC'S.			
pH			
SOLIDS %			

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

MORNING TOUR

FOOTAGE / FORMATION

FROM	TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PAR.EL.-P COMP.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS		
				Cumulative Fluid lost in well	241	bbls
				Storage Tanks Vol No# 1	0	bbls
				No# 2	264	bbls
				Circ Pit Vol	64	bbls
				Total Surface Vol	328	bbls
				Kill Speed @ 36bbl P.M. @ 115 SPM @ 250 P.S.I. @ 8764'		

DRILLER H.K. Jones

DRILLING ASSEMBLY (At end of tour)

NO.		
	BIT	FT.
	STB RMR OD	FT.
	D.C. ID OD	FT.
	STB RMR OD	FT.
	D.C. ID OD	FT.
	STB RMR OD	FT.
	STANDS DP	FT.
	SINGLES DP	FT.
	KELLY DOWN	FT.
	TOTAL	FT.
	WT. OF STRING	LBS.

BIT RECORD

BIT NO.	
SIZE	
IADC CODE	
MFG.	
TYPE	
SER. NO.	
JETS 1/32" /TFA in²	
DEPTH OUT	
DEPTH IN	
TOTAL FTG.	
TOTAL HRS.	
DULL CUT. STRUC. I O D L B G O R	
GPM/PUMP-PSI	

MUD RECORD

TIME			
WEIGHT			
PRESSURE GRADIENT			
VISC.-SEC.			
PV/YP	/	/	/
GELS.	/	/	/
WL -CC'S.			
pH			
SOLIDS %			

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

DAY TOUR

FOOTAGE / FORMATION

FROM	TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PAR.EL.-P COMP.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	7:00	1	5	Service Equipment OPEN Well @ P.S.I. & Filled Tank 596bbls & Mixed 876bbls Poly
7:00	8:00	1	6	P.O.W
8:00	9:00	1	6	P.O.W & Layed down Prod
9:00	10:00	1	21	Load out Prod Equipment
10:00	11:00	1	6	Rig up Hydo Test & Made up Test Seals & No/Go & Testing Hole
11:00	12:00	1	6	Test in Hole @ 5000 P.S.I.
12:00	1:00	1	6	R.I.W Testing
1:00	2:00	1	6	" " "

DRILLER H.K. Jones

EVENING TOUR

FOOTAGE / FORMATION

FROM	TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PAR.EL.-P COMP.-C
(NOTE Layed down) 56 JTS Bad TBG												

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	3:00	1	6	Testing TBG @ 5,000 P.S.I.
3:00	4:00	1	6	" " " & Layed down Hydo Test Tools
4:00	5:00	1	6	Layed down 56 JTS Bad TBG & Picked up 27 JTS New TBG
5:00	6:00	1	6	Load out Bad TBG & Moved Well in w/ Pipe Rams & Rig & Ball Valve
6:00	7:00			

DRILLER H.K. Jones

DRILLING CREW PAYROLL DATA

7-7350

DATE 2-1-89

WELL NAME & NO. Standard Sesnon# 30

COMPANY Southern Calif Gas Co

TOOL PUSHER Dayton RIG NO. M-72#

MORNING TOUR ____ P.M. ____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 6:00 A.M. 6:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	CONFIDENTIAL	H.K. Jones	12	2
DRKMAN		W. Kennedy	12	3
MTRMAN		H.W. Jones	12	7
FIREMAN		S. Guerrero	12	7
FLRMAN		D To lay down Bad TBG		
FLRMAN		T. Bledsoe	12	7
FLRMAN		J. Olivares	12	7
TRAINEE		NO ADC		
		Rig Crew	12	

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR ____ P.M. ____ P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

Rig + 4 man crew 12 hrs 1 man for 12 hrs 2 Extra men for 12 hrs to help lay down bad tubing

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

FORM 3T-5 PRINTED IN U.S.A. APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED No. 153714

AC_CPUC_0117995

No. 153713

DAILY DRILLING REPORT — REPORT NO. 4

LEASE	WELL NO.	API WELL NUMBER	DATE
Aliso Canyon	S.S. #30	7-7350	1-31-89

OPERATOR	CONTRACTOR	RIG NO.
Southern Calif Gas Co	Calif Prod Service	M-#72

SIGNATURE OF OPERATOR'S REPRESENTATIVE	SIGNATURE OF CONTRACTOR'S TOOL PUSHER
J.D. Woods	J. Dayton

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.	PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
						41	O.P.I	500 AWS	4X6"

FIELD OR DIST.	COUNTY	STATE
Aliso	L.A	Calif

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT
11 3/4		42 #47				2500
7"		23 #26	239 Perfs	8884	9240	9240
BAKER RETRIEVA		"D" Packer				8840

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED
1	8	

FT. CUT OFF — PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION — HOURS

CODE NO. — OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE		3½	
6. TRIPS		5½	
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. OTHER		3	
22.			
23.			
COMPLETION A. PERF'R'T'N			
B. TBG TRIPS			
C. TREATING			
D. SWABBING			
E. TESTING			
F. ADDIT'N'L			
G.			
TOTALS		12	

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/DPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD		
	BIT	FT.	BIT NO.		TIME		
			SIZE		WEIGHT		
	STB RMR OD	FT.	IADC CODE		PRESSURE GRADIENT		
	D.C. ID OD	FT.	MFG.		VISC.-SEC.		
	STB RMR OD	FT.	TYPE		PV/YP	/	/ /
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/ /
	STB RMR OD	FT.	JETS 1/32" /TFA in²		WL -CC'S.		
					pH		
			DEPTH OUT		SOLIDS %		
			DEPTH IN		MUD & CHEMICALS ADDED		
	STANDS DP	FT.	TOTAL FTG.		TYPE	AMT.	TYPE AMT.
	SINGLES DP	FT.	TOTAL HRS.				
	KELLY DOWN	FT.	DULL CUT. STRUC. I O D L B G O R				
	TOTAL	FT.					
	WT. OF STRING	LBS.	GPM/PUMP-PSI				

MORNING TOUR

FOOTAGE / FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PARE'L-P COMP'D-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
				Cumulative Fluid lost in Well 182 bbls
				Storage Tanks No# 1 36 bbls Poly
				No# 2 351 bbls K.C.I
				Circ Pit Vol ~~0~~ bbls
				Total Surface Vol 387 bbls
				Kill Speed @ 3 bbls @ 115 S.P.M @ 250 psi 8764

DRILLER H.K. JONES

DAY TOUR

FOOTAGE / FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PARE'L-P COMP'D-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	7:00	1	21	Rigged up Work Floor Service Equipment
7:00	8:00	1	21	" " "
8:00	9:00	1	21	" " "
9:00	10:00	1	5	Open Well @ P.S.I & Rig To Circ
10:00	11:00	1	5	Pumped 128 bbls & broke Circ
11:00	12:00	1	5	Circ Well
12:00	1:00	½-½	5-6	Circ Well & ATT To Release From Packer
1:00	2:00	1	6	ATT To Release From Packer

DRILLER H. K. JONES

EVENING TOUR

FOOTAGE / FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PARE'L-P COMP'D-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	3:00	1	6	Released & P.O.W laying down JTS w/ Pin Holes
3:00	4:00	1	6	P.O.W laying down JTS w/ Pin Holes
4:00	5:00	1	6	P.O.W To 3049'
5:00	6:00	1	6	P.O.W & Closed Well in w/ Pipe Rams Bag & Ball Valve
6:00	7:00			

DRILLER H. K. Jones

7-7350

DRILLING CREW PAYROLL DATA

DATE 1-31-89

WELL NAME & NO. Standard Season #30

COMPANY Southern Calif Gas Co

TOOL PUSHER J. Dayton RIG NO. M-#72

MORNING TOUR _____ P.M. _____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 6:00 A.M. 6:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	CONFIDENTIAL	H.K. Jones	12	2
DRKMAN		W. Kennedy	12	3
MTRMAN		H.W. Jones	12	7
FIREMAN		S. Guerrero	12	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		Rig & Crew No Acc	12	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR _____ P.M. _____ P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		& Crew 12		

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

FORM 3T-5 PRINTED IN U.S.A. APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED No. 153713

AC_CPUC_0117996

No. 153712

DAILY DRILLING REPORT — REPORT NO. 3

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CANYON	SS #30	7-7350	1-30-89

OPERATOR	CONTRACTOR	RIG NO.
SOUTHERN CALIF GAS CO.	CALIF PROD SERVICE	M-72

SIGNATURE OF OPERATOR'S REPRESENTATIVE: J.D. Woods

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J Dayton

D/P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
41	OPI	500 AWS	4X6

FIELD OR DIST.: ALISO CANYON — COUNTY: L.A. — STATE: CALIF

LAST CASING TUBING OR LINER	SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT
	11 3/4		42 47 #				2500
	7		23 26 29#		PERFS @ 8884 TO 9240		9240
	BAKER RETRIEVA 'D' AT 8840						

WIRE LINE RECORD — REEL NO.: SIZE 1 — NO. LINES 8 — FT. SLIPPED — FT. CUT OFF — PRESENT LENGTH — TON MI. OR TRIPS SINCE LAST CUT — CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION – HOURS

CODE NO. – OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN		7	
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE			
6. TRIPS			
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.		3½	
15. TEST B.O.P.		1½	
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21.			
22.			
23.			
COMPLETION A. PERF'R'T'N			
B. TBG TRIPS			
C. TREATING			
D. SWABBING			
E. TESTING			
F. ADDIT'N'L			
G.			
TOTALS		12	

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/DPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

DRILLING ASSEMBLY (At end of tour)

NO.		FT.
	BIT	
	STB RMR OD	
	D.C. ID OD	
	STB RMR OD	
	D.C. ID OD	
	STB RMR OD	
	STANDS DP	
	SINGLES DP	
	KELLY DOWN	
	TOTAL	
	WT. OF STRING	LBS.

BIT RECORD

BIT NO. / SIZE / IADC CODE / MFG. / TYPE / SER. NO. / JETS 1/32" /TFA in² / DEPTH OUT / DEPTH IN / TOTAL FTG. / TOTAL HRS.

DULL: CUT. STRUC. I O D L / B G O R

GPM/PUMP-PSI

MUD RECORD

TIME / WEIGHT / PRESSURE GRADIENT / VISC.-SEC. / PV/YP / GELS. / WL -CC'S. / pH / SOLIDS %

MUD & CHEMICALS ADDED: TYPE | AMT. | TYPE | AMT.

MORNING TOUR

DRILLING ASSEMBLY (At end of tour)

NO.		FT.
	BIT	
	STB RMR OD	
	D.C. ID OD	
	STB RMR OD	
	D.C. ID OD	
	STB RMR OD	
	STANDS DP	
	SINGLES DP	
	KELLY DOWN	
	TOTAL	
	WT. OF STRING	LBS.

BIT RECORD

BIT NO. / SIZE / IADC CODE / MFG. / TYPE / SER. NO. / JETS 1/32" /TFA in² / DEPTH OUT / DEPTH IN / TOTAL FTG. / TOTAL HRS.

DULL: CUT. STRUC. I O D L / B G O R

GPM/PUMP-PSI

MUD RECORD

TIME / WEIGHT / PRESSURE GRADIENT / VISC.-SEC. / PV/YP / GELS. / WL -CC'S. / pH / SOLIDS %

MUD & CHEMICALS ADDED: TYPE | AMT. | TYPE | AMT.

DAY TOUR

DRILLING ASSEMBLY (At end of tour)

NO.		FT.
	BIT	
	STB RMR OD	
	D.C. ID OD	
	STB RMR OD	
	D.C. ID OD	
	STB RMR OD	
	STANDS DP	
	SINGLES DP	
	KELLY DOWN	
	TOTAL	
	WT. OF STRING	LBS.

BIT RECORD

BIT NO. / SIZE / IADC CODE / MFG. / TYPE / SER. NO. / JETS 1/32" /TFA in² / DEPTH OUT / DEPTH IN / TOTAL FTG. / TOTAL HRS.

DULL: CUT. STRUC. I O D L / B G O R

GPM/PUMP-PSI

MUD RECORD

TIME / WEIGHT / PRESSURE GRADIENT / VISC.-SEC. / PV/YP / GELS. / WL -CC'S. / pH / SOLIDS %

MUD & CHEMICALS ADDED: TYPE | AMT. | TYPE | AMT.

EVENING TOUR

FOOTAGE / FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR..D RM..R CORE..C	CORE NO.	FORMATION	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SCL-S PARFL-P COM'B-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
				CUMULATIVE FLUID LOSS IN WELL = 0
				STORAGE TANKS VOLUME #1 = 213 bbls Poly
				#2 = 351 bbls K.C.l
				VOLUME IN CIRC PIT = 0
				TOTAL SURFACE VOLUME = 569

DRILLER H. K. Jones

FOOTAGE / FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR..D RM..R CORE..C	CORE NO.	FORMATION	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SCL-S PARFL-P COM'B-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
600	700	1	1	Rigged up Equipment
700	800	1	1	" " "
800	900	1	1	" " "
900	1000	1	1	" " "
1000	1100	1	1	" " "
1100	1200	1	1	Raised Rig & Tied down
1200	100	1	1	" " "
100	200	1	14	Remove Tree

DRILLER H. K. Jones

FOOTAGE / FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR..D RM..R CORE..C	CORE NO.	FORMATION	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SCL-S PARFL-P COM'B-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
200	300	1	14	Nipple up B.O.P.E
300	400	1	14	" " "
400	500	½ ½	14-15	Nipple up & Rig up Hydo Test & Test Blind Rams @ 3000 PSI (20 MINS OK) Test Pipe Rams 3000 P.S.I 20 MINS OK & Test Bag 2300 P.S.I 20 MINS & Closed Well in w/ Pipe Rams Bag & Ball Valve
500	600	1	15	

DRILLER H. K. Jones

DRILLING CREW PAYROLL DATA

DATE 1-30-89

WELL NAME & NO. STANDARD SESON #30 — 7-7350

COMPANY SOUTHERN CALIF GAS CO.

TOOL PUSHER DAYTON — RIG NO. M-72

MORNING TOUR _____ P.M. _____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER		HELD B.O.P DRLS 41 SEC		
DRKMAN		HELD SAFTY MEETING fo		
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE		(NOTE: NO GAS CO LINE AVAILABLE TO THE CHOKE LINE INTAKE)		

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 600 A.M. 6:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	0 2550	H. K. JONES	12	2
DRKMAN	0 2360	W. KENNEDY	12	3
MTRMAN	0 1588	H. W. JONES	12	7
FIREMAN	0 2399	S. GUERRERO	12	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		LABOR ONLY	7	
		Rig & CREW	5	
		NO ACC		

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR _____ P.M. _____ P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

Labor only to Rig up + Dress Rig + Crew RH

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

FORM 3T-5 — PRINTED IN U.S.A. — APPROVED — APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED — APPROVED — No. 153712

AC_CPUC_0117997

No. 153711

DAILY DRILLING REPORT — REPORT NO. 2

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CANYON	S.S. 30#	7- 7350	1-28-89

OPERATOR	CONTRACTOR	RIG NO.
SOUTHERN CALIF GAS CO.	CALIF PROD SERVICE	M-72

SIGNATURE OF OPERATOR'S REPRESENTATIVE	SIGNATURE OF CONTRACTOR'S TOOL PUSHER
W.L. Killebrew	L Dayton

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
41	OPI	500 AWS	4x6

FIELD OR DIST.	COUNTY	STATE
ALISO CANYON	L.A.	CALIF

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT
11 3/4		42 47 #				2500
7		23 26 29#	PRESH	8884 TO	9240	9240
	BAKER RETRIEVA-"D"-PKR			8840		

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED
1	8	

FT. CUT OFF — PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION – HOURS

CODE NO.	OPERATION	MORN.	DAY	EVE.
1.	RIG UP AND TEAR DOWN		8	
2.	DRILL ACTUAL			
3.	REAMING			
4.	CORING			
5.	CONDITION MUD & CIRCULATE			
6.	TRIPS			
7.	LUBRICATE RIG			
8.	REPAIR RIG			
9.	CUT OFF DRILLING LINE			
10.	DEVIATION SURVEY			
11.	WIRE LINE LOGS			
12.	RUN CASING & CEMENT			
13.	WAIT ON CEMENT			
14.	NIPPLE UP B.O.P.			
15.	TEST B.O.P.			
16.	DRILL STEM TEST			
17.	PLUG BACK			
18.	SQUEEZE CEMENT			
19.	FISHING			
20.	DIR. WORK			
21.				
22.				
23.				
COMPLETION	A. PERF'R'T'N			
	B. TBG TRIPS			
	C. TREATING			
	D. SWABBING			
	E. TESTING			
	F. ADDIT'N'L			
	G.			
TOTALS			8	

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

DRILLING ASSEMBLY (At end of tour)

NO.			
	BIT		FT.
	STB RMR OD		FT.
	D.C. ID OD		FT.
	STB RMR OD		FT.
	D.C. ID OD		FT.
	STB RMR OD		FT.
	STANDS DP		FT.
	SINGLES DP		FT.
	KELLY DOWN		FT.
	TOTAL		FT.
WT. OF STRING			LBS.

BIT RECORD

BIT NO.			
SIZE			
IADC CODE			
MFG.			
TYPE			
SER. NO.			
JETS 1/32" /TFA in²			
DEPTH OUT			
DEPTH IN			
TOTAL FTG.			
TOTAL HRS.			
DULL CUT. STRUC. I O D L B G O R			
GPM/PUMP-PSI			

MUD RECORD

TIME				
WEIGHT				
PRESSURE GRADIENT				
VISC.-SEC.				
PV/YP	/	/	/	
GELS.	/	/	/	
WL -CC'S.				
pH				
SOLIDS %				

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

MORNING TOUR

FOOTAGE

FROM	TO	DR..D RM..R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL..S PARAL..P COMP..C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

FOOTAGE

FROM	TO	DR..D RM..R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL..S PARAL..P COMP..C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
700	800	1		Load out Equipment & Move Equipment To S.S.30
800	900	1		" " " "
900	1000	1		" " " "
1000	1100			" " " "
1100	1200			Rig up
1200	100			" "
100	200			" "
200	300			" "

DRILLER H. K. JONES

EVENING TOUR

FOOTAGE

FROM	TO	DR..D RM..R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL..S PARAL..P COMP..C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DRILLING CREW PAYROLL DATA

DATE 1-28-89

WELL NAME & NO. STANDARD SESON #30 7- 7350

COMPANY SOUTHERN CALIF GAS CO.

TOOL PUSHER DAYTON RIG NO. M-72

MORNING TOUR _____ P.M. _____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 7:00 A.M. 3:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	0 25 00	H. K. JONES	8	2
DRKMAN	0 23 60	W. KENNEDY	8	3
MTRMAN	0 15 88	H. W. JONES	8	7
FIREMAN	0 23 79	S. GUERRERO	8	7
FLRMAN				
FLRMAN				
FLRMAN		LABOR ONLY	8	
TRAINEE				

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR _____ P.M. _____ P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

Crew only 8 hrs to MI & Rig up


NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

FORM 3T-5 PRINTED IN U.S.A. APPROVED APPROVED


IADC – API OFFICIAL DAILY DRILLING REPORT FORM


APPROVED APPROVED No. 153711


AC_CPUC_0117998




AC_CPUC_0117999


LEASE
SEQUOIA FOE
TRUCK NO. 9042
WELL NO. 30
HR.
9-18-76
Squeeze Hole
9080-9080-7
Disp. mud
Clean out
Pump & Rev. Circ.
Test Top
Reversing Valve
COMPANY
TICKET NUMBER
MARTIN - DECKER COMPANY
SANTA ANA, CALIF.
MADE IN U.S.A.
PSI
CHART
250 LB. PRESSURE DIVISIONS
Y48A



MARTIN – DECKER
SANTA ANA, CALIF.
MADE IN U.S.A.
V-18A
CHART
PSI
COMPANY
LEASE
WELL NO.
KIND OF JOB
DATE
30M
So Calif Gas
SS-32
Wellhead
Wellhead
Wellhead




AC_CPUC_0118002




AC_CPUC_0118003



15 M.
1 HR. 30 M.
45 M.
0
1000
2000
3000
4000
5000
6000
MARTIN-DECKER COMPANY
SANTA ANA, CALIF.
MADE IN U.S.A.
CHART
Y44
SoCal
HCAF
SS30
7"H2O
7"H2O
9-2-14




AC_CPUC_0118005



AC_CPUC_0118006



AC_CPUC_0118007



AC_CPUC_0118008

No. 5503

DAILY DRILLING REPORT

REPORT NO. 25 — 3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	SS #30	STANDARD SESNON #30	9-23-76

OPERATOR	CONTRACTOR	RIG NO.
So Calif Gas Co.	Calif Prod Serv.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: E C Bradley

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J. L. Boggs

A.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH

FIELD OR DIST.: ALISO CYN. — COUNTY: LOS-ANGELES — STATE: CALIFORNIA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF — PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION – HOURS

CODE NO. – OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			8
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE			
6. TRIPS			
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS		1½	
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. TRAVEL		1	
22. OTHER		6½	
23.			
COMPLETION A. PERF'R'T'N			
COMPLETION B. TBG TRIPS			
COMPLETION C. TREATING			
COMPLETION D. SWABBING			
COMPLETION E. TESTING			
COMPLETION F. ADDIT'N'L			
COMPLETION G.			
TOTALS		9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

DRILLING ASSEMBLY (At end of tour) — BIT RECORD — MUD RECORD

DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
BIT	FT.	BIT NO.		TIME	
		SIZE		WEIGHT	
STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
D.C. ID OD	FT.	TYPE		VISC.–SEC.	
STB RMR OD	FT.	JETS 1/32"		PV/YP	/ / /
D.C. ID OD	FT.	SER. NO.		GELS.	/ / /
STB RMR OD	FT.	DEPTH OUT		WL –CC'S.	
		DEPTH IN		pH	
		TOTAL FTG.		SOLIDS %	
		TOTAL HRS. RUN			
STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
SINGLES DP	FT.	GPM/ PD–PSI	/ /	TYPE AMT. TYPE AMT.	
KELLY DOWN	FT.				
TOTAL	FT.				
WT. OF STRING	LBS.				

MORNING TOUR

FOOTAGE — FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL–1 PAR'L'L–2 COM'D–C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DAY TOUR

FOOTAGE — FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL–1 PAR'L'L–2 COM'D–C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	11:00	5		WAITING ON ARCHER REED
11:00	11:30	½		RIGGED UP ARCHER REED
11:30	1:00	1½		SET PLUG IN TUBING @ 8930'
1:00	2:00	1		TESTED CASING & SEAL @ 1500 FOR 20 MIN. OK. FROM 8940 TO SURFACE
				SERV. THE RIG AND THE EQUIP.

DRILLER David D. Eaton

EVENING TOUR

FOOTAGE — FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL–1 PAR'L'L–2 COM'D–C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00				LOWERED MAST. LOADED OUT EQUIP.
	10:00	8		

DRILLER

DRILLING CREW PAYROLL DATA

No. 5503

DATE THUR. 9-23-76 — CPS JOB # 3-5643

WELL NAME & NO. STANDARD SESNON #30

COMPANY So Calif Gas Co

TOOL PUSHER J. L. Boggs — RIG NO. D-3

MORNING TOUR _____ P.M. _____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER			
DRKMAN			
MTRMAN			
FIREMAN			
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	560 25	D. EATON	9
DRKMAN	367 3	S. DORFMEIER	9
MTRMAN	375 0	B. FRENCH	9
FIREMAN	375 6	K. WILDER	9
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	9
		PUMP	Ø
		CREW	9

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	367 6	B. DAVIS	8
DRKMAN	371 9	T. BRANDON	8
MTRMAN	375 8	J. TOOPS	8
FIREMAN	377 3	P. SELMSER	8
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	Ø
		CREW	8

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 — Printed in U. S. A. — APPROVED — APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED — APPROVED

AC_CPUC_0118009

No. 5502

DAILY DRILLING REPORT

REPORT NO. 24 — 3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	SS #30	STANDARD SESNON #30	9-22-76

OPERATOR	CONTRACTOR	RIG NO.
So CALIF GAS Co.	CALIF PROD SERV.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: E C Anderson

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J L Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14x5½

FIELD OR DIST.: ALISO CYN. — COUNTY: LOS ANGELES — STATE: CALIFORNIA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF — PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION – HOURS

CODE NO. – OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE			4
6. TRIPS		1	
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. TRAVEL		1	
22. OTHER		7	4
23.			
COMPLETION A. PERF'R'T'N			
B. TBG TRIPS			
C. TREATING			
D. SWABBING			
E. TESTING			
F. ADDIT'N'L			
G.			
TOTALS		9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.–SEC.	
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/
	D.C. ID OD	FT.	SER. NO.		GELS.	/
	STB RMR OD	FT.	DEPTH OUT		WL –CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD–PSI	/	TYPE / AMT. / TYPE / AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
WT. OF STRING		LBS.				

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.–SEC.	
	STB RMR OD	FT.	JET 1/32"		PV/YP	/
	D.C. ID OD	FT.	SER. NO.		GELS.	/
	STB RMR OD	FT.	DEPTH OUT		WL –CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD–PSI	/	TYPE / AMT. / TYPE / AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
WT. OF STRING		LBS.				

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.–SEC.	
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/
	D.C. ID OD	FT.	SER. NO.		GELS.	/
	STB RMR OD	FT.	DEPTH OUT		WL –CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD–PSI	/	TYPE / AMT. / TYPE / AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
WT. OF STRING		LBS.				

MORNING TOUR

FOOTAGE / FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.–S PAR.–P RET.–R COM.–C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DAY TOUR

FOOTAGE / FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.–S PAR.–P RET.–R COM.–C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	7:00	1		FINISHED HYDRO TESTING & CHANGEING COLLARS, IN THE HOLE
7:30				STAB IN TO PKR SET 10,000 DOWN SPACED OUT, LANDED
				TUBING WITH 10,000 COMP. CHECKED LATCH IN PULLED 25,000
	8:30	1		OVER WEIGHT OF TUBING LANDED TUBING.
9:30	9:00	½		RIGGED DOWN HYDRO-TEST & H&H TOOLS CLEAN PIT.
9:00	12:00	3		REMOVED BOP INSTALED TUBING X-MAS TREE TESTED SAME
12:00	2:00	2		@ 4500 FOR 30 MIN OK.

DRILLER David Eaton

EVENING TOUR

FOOTAGE / FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.–S PAR.–P RET.–R COM.–C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	3:00	1		TESTED TREE @ 5,000# -20 MIN.
3:00	\	\		CHANGED OVER TO LEASE WATER
	7:00	4		RIGGING DOWN. @ E.O.T. CLOSED WELL IN, SHUT JOB DOWN.
7:00				
	10:00	3		

DRILLER

DRILLING CREW PAYROLL DATA

No. 5502

DATE WED 9-22-76 — GPS JOB # 3-5643

WELL NAME & NO. STANDARD SESNON #30

COMPANY So CALIF GAS Co

TOOL PUSHER J. L. Boggs — RIG NO. D-3

MORNING TOUR _____ P.M. _____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	CONFIDENTIAL	D. EATON	9	2
DRKMAN		S. DORFMEIER	9	3
MTRMAN		B. FRENCH	9	7
FIREMAN		K. WILDER	9	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	9	
		PUMP	8	
		CREW	9	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	CONFIDENTIAL	B. DAVIS	8	2
DRKMAN		T. BRANDON	8	3
MTRMAN		J. TOOPS	8	7
FIREMAN		P. SELMSER	8	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	4	
		CREW	8	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 — Printed in U. S. A. — APPROVED — APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED — APPROVED

AC_CPUC_0118010

No. 5501

3-564.3

DAILY DRILLING REPORT — REPORT NO. 23

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN	SS # 30	STANDARD SESNON # 30	9-21-76

OPERATOR	CONTRACTOR	RIG NO.
So CALIF GAS CO	CALIF PROD SERV.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: Edward Brandon

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: L. J. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14 x 5½

FIELD OR DIST.: ALISO CYN. | COUNTY: LOS ANGELES | STATE: CALIFORNIA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED
FT. CUT OFF	PRESENT LENGTH	

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION — HOURS

CODE NO.	OPERATION	MORN.	DAY	EVE.
1.	RIG UP AND TEAR DOWN			
2.	DRILL ACTUAL			
3.	REAMING			
4.	CORING			
5.	CONDITION MUD & CIRCULATE			
6.	TRIPS		8	8
7.	LUBRICATE RIG			
8.	REPAIR RIG			
9.	CUT OFF DRILLING LINE			
10.	DEVIATION SURVEY			
11.	WIRE LINE LOGS			
12.	RUN CASING & CEMENT			
13.	WAIT ON CEMENT			
14.	NIPPLE UP B.O.P.			
15.	TEST B.O.P.			
16.	DRILL STEM TEST			
17.	PLUG BACK			
18.	SQUEEZE CEMENT			
19.	FISHING			
20.	DIR. WORK			
21.	TRAVEL		1	
22.	OTHER			
23.				
COMPLETION	A. PERF'R'T'N			
	B. TBG TRIPS			
	C. TREATING			
	D. SWABBING			
	E. TESTING			
	F. ADDIT'N'L			
	G.			
TOTALS			9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
BIT	FT.	BIT NO.		TIME	
		SIZE		WEIGHT	
STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
D.C. ID OD	FT.	TYPE		VISC.-SEC.	
STB RMR OD	FT.	JETS 1/32"		PV/YP	
D.C. ID OD	FT.	SER. NO.		GELS.	
STB RMR OD	FT.	DEPTH OUT		WL -CC'S.	
		DEPTH IN		pH	
		TOTAL FTG.		SOLIDS %	
		TOTAL HRS. RUN			
STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
SINGLES DP	FT.	GPM/ PD-PSI		TYPE / AMT. / TYPE / AMT.	
KELLY DOWN	FT.				
TOTAL	FT.				
WT. OF STRING	LBS.				

MORNING TOUR

FOOTAGE / FORMATION (SHOW CORE RECOVERY)

FOOTAGE FROM	FOOTAGE TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PART.EL-P COMP.D-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
				NOTE ON HYDRO-TESTING IN HOLE!
				DRIFTED CEMENT OUT OF TUBING.

DRILLER

DAY TOUR

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
BIT	FT.	BIT NO.		TIME	
		SIZE		WEIGHT	
STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
D.C. ID OD	FT.	TYPE		VISC.-SEC.	
STB RMR OD	FT.	JET 1/32"		PV/YP	
D.C. ID OD	FT.	SER. NO.		GELS.	
STB RMR OD	FT.	DEPTH OUT		WL -CC'S.	
		DEPTH IN		pH	
		TOTAL FTG.		SOLIDS %	
		TOTAL HRS. RUN			
STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
SINGLES DP	FT.	GPM/ PD-PSI		TYPE / AMT. / TYPE / AMT.	
KELLY DOWN	FT.				
TOTAL	FT.				
WT. OF STRING	LBS.				

FOOTAGE / FORMATION (SHOW CORE RECOVERY)

FOOTAGE FROM	FOOTAGE TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PART.EL-P COMP.D-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
600				SERV THE RIG & THE EQUIP.
				HYDRO TESTING, CHANGING COLLARS @ 5000 PSI FOR 1 MIN.
	2:00			HELD BOP DRILL 9-21-76

DRILLER David Eaton

EVENING TOUR

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
BIT	FT.	BIT NO.		TIME	
		SIZE		WEIGHT	
STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
D.C. ID OD	FT.	TYPE		VISC.-SEC.	
STB RMR OD	FT.	JETS 1/32"		PV/YP	
D.C. ID OD	FT.	SER. NO.		GELS.	
STB RMR OD	FT.	DEPTH OUT		WL -CC'S.	
		DEPTH IN		pH	
		TOTAL FTG.		SOLIDS %	
		TOTAL HRS. RUN			
STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
SINGLES DP	FT.	GPM/ PD-PSI		TYPE / AMT. / TYPE / AMT.	
KELLY DOWN	FT.				
TOTAL	FT.				
WT. OF STRING	LBS.				

FOOTAGE / FORMATION (SHOW CORE RECOVERY)

FOOTAGE FROM	FOOTAGE TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PART.EL-P COMP.D-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00				HYDRO-TESTING IN HOLE @ 5,000 PSI FOR 1 MIN, CHANGING & BAKER-SEALING COLLARS @ E.O.T.
	10:00	9		

DRILLER

DRILLING CREW PAYROLL DATA — No. 5501

DATE TUE. 9-21-76

WELL NAME & NO. STANDARD SESNON #30 — CPS JOB # 3-564.3

COMPANY So CALIF GAS CO.

TOOL PUSHER L. J. Boggs — RIG NO. D-3

MORNING TOUR ____ P.M. ____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER			
DRKMAN			
MTRMAN			
FIREMAN			
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. — 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	562-5	D. EATON	9
DRKMAN	367-3	S. DORFMEIER	9
MTRMAN	375-0	B. FRENCH	9
FIREMAN	373-6	K. WILDER	9
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	0
		CREW	9

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. — 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	367-6	B. DAVIS	8
DRKMAN	371-9	T. BRANDON	8
MTRMAN	372-8	J. TOOPS	8
FIREMAN	377-3	P. SELMSER	8
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	0
		CREW	8

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 — Printed in U. S. A. — APPROVED — APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED — APPROVED

AC_CPUC_0118011

No. 5499

DAILY DRILLING REPORT — REPORT NO. 21 — #3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN	S.S. #30		9-18-76

OPERATOR	CONTRACTOR	RIG NO.
SO CALIF GAS CO.	CALIF. PROD. SVC	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: G. H. Dawson

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: O. K. Elston

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14x5½

FIELD OR DIST.: ALISO CYN. | COUNTY: L.A. | STATE: CA.

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

DRILLING CREW PAYROLL DATA — No. 5499 #3-5643

DATE 9-18-76

WELL NAME & NO. S.S. #30

COMPANY SO. CALIF. GAS CO. G. H. Dawson

TOOL PUSHER O. K. Elston — RIG NO. D-3

TIME DISTRIBUTION – HOURS

CODE NO.	OPERATION	MORN.	DAY	EVE.
1.	RIG UP AND TEAR DOWN			
2.	DRILL ACTUAL			
3.	REAMING			
4.	CORING			
5.	CONDITION MUD & CIRCULATE			2
6.	TRIPS		1	5½
7.	LUBRICATE RIG			
8.	REPAIR RIG			
9.	CUT OFF DRILLING LINE			
10.	DEVIATION SURVEY			
11.	WIRE LINE LOGS			
12.	RUN CASING & CEMENT			
13.	WAIT ON CEMENT			
14.	NIPPLE UP B.O.P.			
15.	TEST B.O.P.			
16.	DRILL STEM TEST			
17.	PLUG BACK			
18.	SQUEEZE CEMENT			
19.	FISHING			
20.	DIR. WORK			
21.	TRAVEL		1	
22.	OTHER		½	½
23.	ACID WASH		6½	
COMPLETION	A. PERF'R'T'N			
	B. TBG TRIPS			
	C. TREATING			
	D. SWABBING			
	E. TESTING			
	F. ADDIT'N'L			
	G.			
TOTALS			9	

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

DRILLING ASSEMBLY	FT.	BIT RECORD	MUD RECORD
BIT	FT.	BIT NO.	TIME
		SIZE	WEIGHT
STB RMR OD	FT.	MFG.	PRESSURE GRADIENT
D.C. ID OD	FT.	TYPE	VISC.–SEC.
STB RMR OD	FT.	JETS 1/32"	PV/YP
D.C. ID OD	FT.	SER. NO.	GELS.
STB RMR OD	FT.	DEPTH OUT	WL –CC'S.
		DEPTH IN	pH
		TOTAL FTG.	SOLIDS %
		TOTAL HRS. RUN	
STANDS DP	FT.	COND. 1/8's T/B/ GAGE	MUD & CHEMICALS ADDED: TYPE / AMT. / TYPE / AMT.
SINGLES DP	FT.	GPM/ PD–PSI	
KELLY DOWN	FT.		
TOTAL	FT.		
WT. OF STRING	LBS.		

MORNING TOUR

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

DRILLING ASSEMBLY	FT.	BIT RECORD	MUD RECORD
BIT	FT.	BIT NO.	TIME
		SIZE	WEIGHT
STB RMR OD	FT.	MFG.	PRESSURE GRADIENT
D.C. ID OD	FT.	TYPE	VISC.–SEC.
STB RMR OD	FT.	JET 1/32"	PV/YP
D.C. ID OD	FT.	SER. NO.	GELS.
STB RMR OD	FT.	DEPTH OUT	WL –CC'S.
		DEPTH IN	pH
		TOTAL FTG.	SOLIDS %
		TOTAL HRS. RUN	
STANDS DP	FT.	COND. 1/8's T/B/ GAGE	MUD & CHEMICALS ADDED: TYPE / AMT. / TYPE / AMT.
SINGLES DP	FT.	GPM/ PD–PSI	
KELLY DOWN	FT.		
TOTAL	FT.		
WT. OF STRING	LBS.		

DAY TOUR

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

DRILLING ASSEMBLY	FT.	BIT RECORD	MUD RECORD
BIT	FT.	BIT NO.	TIME
		SIZE	WEIGHT
STB RMR OD	FT.	MFG.	PRESSURE GRADIENT
D.C. ID OD	FT.	TYPE	VISC.–SEC.
STB RMR OD	FT.	JETS 1/32"	PV/YP
D.C. ID OD	FT.	SER. NO.	GELS.
STB RMR OD	FT.	DEPTH OUT	WL –CC'S.
		DEPTH IN	pH
		TOTAL FTG.	SOLIDS %
		TOTAL HRS. RUN	
STANDS DP	FT.	COND. 1/8's T/B/ GAGE	MUD & CHEMICALS ADDED: TYPE / AMT. / TYPE / AMT.
SINGLES DP	FT.	GPM/ PD–PSI	
KELLY DOWN	FT.		
TOTAL	FT.		
WT. OF STRING	LBS.		

EVENING TOUR

MORNING TOUR

FOOTAGE FROM / TO | DR..D RM–R CORE..C | CORE NO. | FORMATION (SHOW CORE RECOVERY) | ROTARY RPM | WT. ON BIT 1000 # | PUMP PRESS | PUMP NO. LINER SIZE / S.P.M. | PUMP NO. LINER SIZE / S.P.M. | METHOD RUN SGL–S PAR'EL–P COM'D–C

DEVIATION RECORD: DEPTH / DEV. / DIRECTION (×3)

TIME LOG FROM / TO | ELAPSED TIME | CODE NO. | DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

NOTE ON ACID SQEEZE JOB
WITH BAKERES FUL-BORE SET AT 9023 SQEEZED AWAY 5900 GAL OF 12% HF ACID
@ 8959 SQEEZED AWAY 4000 GALS.
PULLED OUT TO 8856 SQEEZED AWAY 4270 GAL
FILLED HOLE WITH 28 BBLS AFTER SQEEZE

DRILLER

MORNING TOUR ____ P.M. ____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER			
DRKMAN			
MTRMAN			
FIREMAN			
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR

FOOTAGE FROM / TO | DR..D RM–R CORE..C | CORE NO. | FORMATION (SHOW CORE RECOVERY) | ROTARY RPM | WT. ON BIT 1000 # | PUMP PRESS | PUMP NO. LINER SIZE / S.P.M. | PUMP NO. LINER SIZE / S.P.M. | METHOD RUN SGL–S PAR'EL–P COM'D–C

DEVIATION RECORD: DEPTH / DEV. / DIRECTION (×3)

TIME LOG FROM / TO | ELAPSED TIME | CODE NO. | DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS
				SERV. RIG & EQUIP.
6:00				RIH TO 9023' USING HALLIBURTON & BAKER'S F. BORE, SPOTTED FOLLOWING AMTS OF 12% HF ACID @ INDICATED DEPTHS: 3900 GALS @ 9023', 4,000 GALS @ 8959', 4270 GALS @ 8856'. RELEASED & SAFETIED TOOL. RIGGED HALLIBURTON
	12:30	6½		DOWN. FILLED HOLE W/ 28 BBLS.
12:30				RIGGED GUIBERSON DOWN. P.O.H. @ E.O.T.
	2:00	1½		

DRILLER G. H. Dawson

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	36 76	B. DAVIS	9
DRKMAN	37 19	T. BRANDON	9
MTRMAN	37 28	J. TOOPS	9
FIREMAN	37 73	P. SELMSER	9
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	1
		CREW	9

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR

FOOTAGE FROM / TO | DR..D RM–R CORE..C | CORE NO. | FORMATION (SHOW CORE RECOVERY) | ROTARY RPM | WT. ON BIT 1000 # | PUMP PRESS | PUMP NO. LINER SIZE / S.P.M. | PUMP NO. LINER SIZE / S.P.M. | METHOD RUN SGL–S PAR'EL–P COM'D–C

DEVIATION RECORD: DEPTH / DEV. / DIRECTION (×3)

TIME LOG FROM / TO | ELAPSED TIME | CODE NO. | DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS
2:00	3:00	1		PULL OUT OF HOLE W/ Baker F Bore
3:00	6:00	3		RUN IN HOLE W/ BIT SCRAPPER
6:00	8:00	2		CIRC. HOLE @ 9240
8:00	9:30	1½		PULL OUT OF HOLE
9:30	10:00	½		CLOSED WELL IN SHUT JOB DOWN

DRILLER B. J. French

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	37 90	B. J. FRENCH	8
DRKMAN	36 73	S. DORFMEIER	8
MTRMAN	37 36	K. Wilder	8
FIREMAN	37 90	J. K. Ward	8
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	2
		CREW	8

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 — Printed in U. S. A. — APPROVED — APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED — APPROVED

AC_CPUC_0118012

No. 5498

DAILY DRILLING REPORT — REPORT NO. 20 — #3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	SS #30		9-17-76

OPERATOR	CONTRACTOR	RIG NO.
SO. CALIF. GAS CO.	CALIF. PROD. SVC.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: P. H. Margetts

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J. L. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT. O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14x5½

FIELD OR DIST.: ALISO CYN. — COUNTY: L.A. — STATE: CA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF — PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION – HOURS

CODE NO. – OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. ~~CONDITION MUD~~ & CIRCULATE		1½	1½
6. TRIPS			6
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. TRAVEL		1	
22. OTHER			½
23. WASH PERFS		6½	
COMPLETION A. PERF'R'T'N			
B. TBG TRIPS			
C. TREATING			
D. SWABBING			
E. TESTING			
F. ADDIT'N'L			
G.			
TOTALS		9	9

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.				
HRS. W/OPR. D.P.				
HRS. WO/D.P.				
HRS. STANDBY				
TOTAL DAY WORK				

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

MORNING TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD				
	BIT	FT.	BIT NO.		TIME				
			SIZE		WEIGHT				
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT				
	D.C. ID OD	FT.	TYPE		VISC.-SEC.				
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/	/	/	
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/	/	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.				
			DEPTH IN		pH				
			TOTAL FTG.		SOLIDS %				
			TOTAL HRS. RUN						
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED				
	SINGLES DP	FT.	GPM/ PD-PSI	/	TYPE	AMT.	TYPE	AMT.	
	KELLY DOWN	FT.							
	TOTAL	FT.							
	WT. OF STRING	LBS.							

FOOTAGE FROM	FOOTAGE TO	DR..D RM-R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PAR'EL-P COM'B-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DAY TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD				
	BIT	FT.	BIT NO.		TIME				
			SIZE		WEIGHT				
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT				
	D.C. ID OD	FT.	TYPE		VISC.-SEC.				
	STB RMR OD	FT.	JET 1/32"		PV/YP	/	/	/	
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/	/	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.				
			DEPTH IN		pH				
			TOTAL FTG.		SOLIDS %				
			TOTAL HRS. RUN						
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED				
	SINGLES DP	FT.	GPM/ PD-PSI	/	TYPE	AMT.	TYPE	AMT.	
	KELLY DOWN	FT.							
	TOTAL	FT.							
	WT. OF STRING	LBS.							

FOOTAGE FROM	FOOTAGE TO	DR..D RM-R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PAR'EL-P COM'B-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	12:30	6½		SERV. RIG & EQUIP. WASHED PERFS. FROM 8880'-9080. USING HALLIBURTON
12:30				CIRC. HOLE.
	2:00	1½		

DRILLER

EVENING TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD				
	BIT	FT.	BIT NO.		TIME				
			SIZE		WEIGHT				
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT				
	D.C. ID OD	FT.	TYPE		VISC.-SEC.				
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/	/	/	
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/	/	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.				
			DEPTH IN		pH				
			TOTAL FTG.		SOLIDS %				
			TOTAL HRS. RUN						
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED				
	SINGLES DP	FT.	GPM/ PD-PSI	/	TYPE	AMT.	TYPE	AMT.	
	KELLY DOWN	FT.							
	TOTAL	FT.							
	WT. OF STRING	LBS.							

FOOTAGE FROM	FOOTAGE TO	DR..D RM-R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PAR'EL-P COM'B-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	3:30	1½		SERV. RIG & EQIP. CIRC HOLE
3:30	4:00	½		REMOVED GUIBERSON STRIPER
4:00	7:00	3		PULLED OUT OF THE HOLE W/ WASHER LOADED OUT SAME
7:00				MADE UP BAKERES FUL-BORE RAN IN THE HOLE TO
				9661 INSTALED GUIBERSON STRIPER CLOSED WELL
	10:00	3		IN SHUT JOB DOWN

DRILLER David E. Toops

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

Form 3T-5 — Printed in U. S. A. — APPROVED — APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

DRILLING CREW PAYROLL DATA — No. 5498 #3-5643

DATE 9-17-76

WELL NAME & NO. S.S #30

COMPANY SO. CALIF. GAS CO. P.H. Margetts

TOOL PUSHER J. L. Boggs — RIG NO. D-3

MORNING TOUR _____ P.M. _____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER			
DRKMAN			
MTRMAN			
FIREMAN			
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	36 76	B. DAVIS	9
DRKMAN	37 19	T. BRANDON	9
MTRMAN	37 28	J. TOOPS	9
FIREMAN	37 73	P SELMSER	9
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	2
		CREW	9

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	56 25	D. EATON	8
DRKMAN	36 73	S. DOREMEIER	8
MTRMAN	37 50	B FRENCH	8
FIREMAN	37 36	K. WILDER	8
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	1½
		CREW	8

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

APPROVED — APPROVED

AC_CPUC_0118013

No. 5497

DAILY DRILLING REPORT — REPORT NO. 19 — CPS JOB NO. 3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	SS #30	STANDARD SESNON #30	9-16-76

OPERATOR	CONTRACTOR	RIG NO.
So CALIF GAS CO	CALIF PROD SERV.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: G. R. Wargats

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: D. L. Boggs

O.D. SIZE	WT./FT.	GRADE	INCL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14 x 5½

FIELD OR DIST.: ALISO CYN — COUNTY: LOS ANGELES — STATE: CALIFORNIA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF — PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

DRILLING CREW PAYROLL DATA — No. 5497

DATE THUR. 9-16-76 — CPS JOB NO. 3-5643

WELL NAME & NO. STANDARD SESNON #30

COMPANY So CALIF. GAS CO. G. R. Wargats

TOOL PUSHER D. L. Boggs — RIG NO. D-3

TIME DISTRIBUTION – HOURS

CODE NO. – OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. ~~CONDITION MUD~~ & CIRCULATE		3½	
6. TRIPS	1½	4½	4½
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. TRAVEL		1	
22. OTHER	1		½
23.			
COMPLETION A. PERF'R'T'N			
B. TBG TRIPS			
C. TREATING			
D. SWABBING			
E. TESTING			
F. ADDIT'N'L			
G.			
TOTALS	1½	9	5

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			
NO. OF DAYS FROM SPUD			
CUMULATIVE ROTATING HRS.			
TOTAL MUD COST			

DAY TOUR

DRILLING ASSEMBLY (At end of tour)

NO.			
1	BIT	50	FT.
	STB RMR OD		FT.
	D.C. ID OD		FT.
	STB RMR OD		FT.
	D.C. ID OD		FT.
	STB RMR OD		FT.
1	SCRAPER	4.50	
20	STANDS DP	1247.19	FT.
	SINGLES DP		FT.
	KELLY DOWN		FT.
	TOTAL		FT.
WT. OF STRING			LBS.

BIT RECORD

BIT NO.	
SIZE	
MFG.	
TYPE	
JETS 1/32"	
SER. NO.	
DEPTH OUT	
DEPTH IN	
TOTAL FTG.	
TOTAL HRS. RUN	
COND. 1/8's T/B/ GAGE	
GPM/ PD–PSI	

MUD RECORD

TIME	
WEIGHT	
PRESSURE GRADIENT	
VISC.–SEC.	
PV/YP	
GELS.	
WL –CC'S.	
pH	
SOLIDS %	

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

DRILLING ASSEMBLY (At end of tour)

NO.			
1	BIT ~~SCRAPER~~	5.00	FT.
	STB RMR OD		FT.
	D.C. ID OD		FT.
	STB RMR OD		FT.
	D.C. ID OD		FT.
	STB RMR OD		FT.
49	STANDS DP	921.97	FT.
	SINGLES DP		FT.
	KELLY DOWN	15.00	FT.
	TOTAL	923.97	FT.
WT. OF STRING		58,000	LBS.

BIT RECORD

BIT NO.	
SIZE	
MFG.	
TYPE	
JET 1/32"	
SER. NO.	
DEPTH OUT	
DEPTH IN	
TOTAL FTG.	
TOTAL HRS. RUN	
COND. 1/8's T/B/ GAGE	
GPM/ PD–PSI	

MUD RECORD

TIME	
WEIGHT	
PRESSURE GRADIENT	
VISC.–SEC.	
PV/YP	
GELS.	
WL –CC'S.	
pH	
SOLIDS %	

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

DRILLING ASSEMBLY (At end of tour)

NO.			
	BIT		FT.
	STB RMR OD		FT.
	D.C. ID OD		FT.
	STB RMR OD		FT.
	D.C. ID OD		FT.
	STB RMR OD		FT.
	STANDS DP		FT.
	SINGLES DP		FT.
	KELLY DOWN		FT.
	TOTAL		FT.
WT. OF STRING			LBS.

BIT RECORD

BIT NO.	
SIZE	
MFG.	
TYPE	
JETS 1/32"	
SER. NO.	
DEPTH OUT	
DEPTH IN	
TOTAL FTG.	
TOTAL HRS. RUN	
COND. 1/8's T/B/ GAGE	
GPM/ PD–PSI	

MUD RECORD

TIME	
WEIGHT	
PRESSURE GRADIENT	
VISC.–SEC.	
PV/YP	
GELS.	
WL –CC'S.	
pH	
SOLIDS %	

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

FOOTAGE — FROM / TO — DR.–D RM.–R CORE.–C — CORE NO. — FORMATION (SHOW CORE RECOVERY) — ROTARY RPM — WT. ON BIT 1000# — PUMP PRESS — PUMP NO. LINER SIZE / S.P.M. — PUMP NO. LINER SIZE / S.P.M. — METHOD RUN SGL.–S PARL.–P COMP.–C

DEVIATION RECORD — DEPTH / DEV. / DIRECTION (×3)

TIME LOG FROM / TO — ELAPSED TIME — CODE NO. — DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
12:00	1:00	1		SERV THE RIG AND THE EQUIP
1:00	1:30	½		RIGGED DOWN DRESSER-ATLAS WIRE LINE SERV.
				RUNNING IN THE HOLE WITH BIT & SCRAPER
				CLOSED WELL IN SHUT THE JOB DOWN

DRILLER David Eaton

FOOTAGE — FROM / TO — DR.–D RM.–R CORE.–C — CORE NO. — FORMATION (SHOW CORE RECOVERY) — ROTARY RPM — WT. ON BIT 1000# — PUMP PRESS — PUMP NO. LINER SIZE / S.P.M. — PUMP NO. LINER SIZE / S.P.M. — METHOD RUN SGL.–S PARL.–P COMP.–C

DEVIATION RECORD — DEPTH / DEV. / DIRECTION (×3)

TIME LOG FROM / TO — ELAPSED TIME — CODE NO. — DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	8:00	2		SERV. RIG & EQUIP.
8:00	11:30	3½		RIH TO 9240' W/BIT & SCRAPER.
11:30				CIRC. HOLE CLEAN.
				P.O.H. C.E.O.T.
	2:00	2½		

DRILLER G. R. Wargats

MORNING TOUR 12:00 P.M. 1:30 A.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	CONFIDENTIAL	D. EATON	1½
DRKMAN		S. DORFMEIER	1½
MTRMAN		B. FRENCH	1½
FIREMAN		K. WILDER	1½
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	1½
		PUMP	Ø
		CREW	1½

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	CONFIDENTIAL	B. DAVIS	9
DRKMAN		T. BRANDON	9
MTRMAN		J. TOOPS	9
FIREMAN		P SELMSER	9
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	3½
		CREW	9

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR

FOOTAGE — FROM / TO — DR.–D RM.–R CORE.–C — CORE NO. — FORMATION (SHOW CORE RECOVERY) — ROTARY RPM — WT. ON BIT 1000# — PUMP PRESS — PUMP NO. LINER SIZE / S.P.M. — PUMP NO. LINER SIZE / S.P.M. — METHOD RUN SGL.–S PARL.–P COMP.–C

DEVIATION RECORD — DEPTH / DEV. / DIRECTION (×3)

TIME LOG FROM / TO — ELAPSED TIME — CODE NO. — DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	4:00	2		SERV. the Rig and the EQUIP.
				Finished pulling out of the hole.
				Broke off bit and SCRAPER
4:00				Make up. circ. wash tool
	6:30	2½		Ran in hole to 9661
6:30	7:00	½		CLOSED WELL IN SHUT JOB DOWN

DRILLER David Eaton

EVENING TOUR 2:00 P.M. 7:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	CONFIDENTIAL	D. EATON	5
DRKMAN		S. DORFMEIER	5
MTRMAN		B. FRENCH	5
FIREMAN		K. WILDER	5
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	5
		PUMP	Ø
		CREW	5

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 — Printed in U. S. A. — APPROVED — APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED — APPROVED

AC_CPUC_0118014

No. 5496

DAILY DRILLING REPORT — REPORT NO. 18 — #3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	S.S. #30		9-15-76

OPERATOR	CONTRACTOR	RIG NO.
SO. CALIF. GAS CO.	CALIF. PROD. SVC.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: C. M. Dargatz

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J. L. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14X5½

FIELD OR DIST.: ALISO CYN. — COUNTY: L.A. — STATE: CA.

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF — PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION – HOURS

CODE NO. – OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL		2½	
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE		2½	
6. TRIPS		2	2
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. TRAVEL		1	
22. OTHER		1	
23.			
COMPLETION A. PERF'R'T'N			8
B. TBG TRIPS			
C. TREATING			
D. SWABBING			
E. TESTING			
F. ADDIT'N'L			
G.			
TOTALS		9	10

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

MORNING TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		
	BIT		FT.
	STB RMR OD		FT.
	D.C. ID OD		FT.
	STB RMR OD		FT.
	D.C. ID OD		FT.
	STB RMR OD		FT.
	STANDS DP		FT.
	SINGLES DP		FT.
	KELLY DOWN		FT.
	TOTAL		FT.
WT. OF STRING			LBS.

BIT RECORD: BIT NO. | SIZE | MFG. | TYPE | JETS 1/32" | SER. NO. | DEPTH OUT | DEPTH IN | TOTAL FTG. | TOTAL HRS. RUN | COND. 1/8's T/B/ GAGE | GPM/ PD-PSI

MUD RECORD: TIME | WEIGHT | PRESSURE GRADIENT | VISC.-SEC. | PV/YP | GELS. | WL -CC'S. | pH | SOLIDS % | MUD & CHEMICALS ADDED (TYPE, AMT., TYPE, AMT.)

DAY TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		
1	BIT ESCRAPER	5.00	FT.
	STB RMR OD		FT.
	D.C. ID OD		FT.
	STB RMR OD		FT.
149	STANDS DP	9219.97	FT.
	SINGLES DP		FT.
	KELLY DOWN	15.00	FT.
	TOTAL	9239.97	FT.
WT. OF STRING	58,000		LBS.

BIT RECORD: BIT NO. | SIZE | MFG. | TYPE | JET 1/32" | SER. NO. | DEPTH OUT | DEPTH IN | TOTAL FTG. | TOTAL HRS. RUN | COND. 1/8's T/B/ GAGE | GPM/ PD-PSI

MUD RECORD: TIME | WEIGHT | PRESSURE GRADIENT | VISC.-SEC. | PV/YP | GELS. | WL -CC'S. | pH | SOLIDS % | MUD & CHEMICALS ADDED (TYPE, AMT., TYPE, AMT.)

EVENING TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		
	BIT	.50	FT.
	STB RMR OD		FT.
	D.C. ID OD		FT.
	STB RMR OD		FT.
	D.C. ID OD		FT.
	STB RMR OD		FT.
	SCRAPER	4.50	
20	STANDS DP		FT.
	SINGLES DP		FT.
	KELLY DOWN		FT.
	TOTAL		FT.
WT. OF STRING			LBS.

BIT RECORD: BIT NO. | SIZE | MFG. | TYPE | JETS 1/32" | SER. NO. | DEPTH OUT | DEPTH IN | TOTAL FTG. | TOTAL HRS. RUN | COND. 1/8's T/B/ GAGE | GPM/ PD-PSI

MUD RECORD: TIME | WEIGHT | PRESSURE GRADIENT | VISC.-SEC. | PV/YP | GELS. | WL -CC'S. | pH | SOLIDS % | MUD & CHEMICALS ADDED (TYPE, AMT., TYPE, AMT.)

MORNING TOUR

FOOTAGE: FROM | TO — DR.-D RM.-R CORE.-C — CORE NO. — FORMATION (SHOW CORE RECOVERY) — ROTARY RPM — WT. ON BIT 1000# — PUMP PRESS — PUMP NO. LINER SIZE | S.P.M. — PUMP NO. LINER SIZE | S.P.M. — METHOD RUN SGL.-S PAR'EL-P COM'D-C

DEVIATION RECORD: DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION

TIME LOG: FROM | TO — ELAPSED TIME — CODE NO. — DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

NOTE ON PERFS, WITH 2-½" HOLES PER FOOT
9080' - 9040' WITH GOLDEN JET CHARGE
9020' - 8972' PERFORATEING DONE BY
8955' - 8921' DRESSER-ATLAS
8906' 8894'

DRILLER David Eaton

DAY TOUR

FOOTAGE: FROM | TO — DR.-D RM.-R CORE.-C — CORE NO. — FORMATION (SHOW CORE RECOVERY) — ROTARY RPM — WT. ON BIT 1000# — PUMP PRESS — PUMP NO. LINER SIZE | S.P.M. — PUMP NO. LINER SIZE | S.P.M. — METHOD RUN SGL.-S PAR'EL-P COM'D-C

DEVIATION RECORD: DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION

TIME LOG: FROM | TO — ELAPSED TIME — CODE NO. — DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS
				SERV. RIG & EQUIP.
6:00	8:30	2½		RIH TO 9100' CLEANED OUT TO 9240', WORKING
				THROUGH TIGHT SPOT @9210'
8:30	11:00	2½		CIRC. HOLE CLEAN.
11:00	12:00	1		RIG DOWN & LOADED OUT POWER SWIVEL & GUIB.
12:00				P.O.H. @ E.O.T.
	2:00	2		HELD B.O.P.E. DRILL

DRILLER J. L. Boggs

EVENING TOUR

FOOTAGE: FROM | TO — DR.-D RM.-R CORE.-C — CORE NO. — FORMATION (SHOW CORE RECOVERY) — ROTARY RPM — WT. ON BIT 1000# — PUMP PRESS — PUMP NO. LINER SIZE | S.P.M. — PUMP NO. LINER SIZE | S.P.M. — METHOD RUN SGL.-S PAR'EL-P COM'D-C

DEVIATION RECORD: DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION

TIME LOG: FROM | TO — ELAPSED TIME — CODE NO. — DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS
200	330	1½		FINISHED PULLING OUT OF THE HOLE WITH B.I.T & SCRAPER
330	400	½		RIGGED UP DRESSER ATLAS WIRE LINE SERV.
400				PERFORATED WITH 2-½" HOLES PER FOOT WITH GOLDEN-
	1200	8		JET CHARGE, AS PROGRAMED

DRILLER David Eaton

DRILLING CREW PAYROLL DATA

No. 5496 #3-5643

DATE 9-15-76

WELL NAME & NO. S.S. #30

COMPANY SO. CALIF. GAS CO. C. M. Dargatz

TOOL PUSHER J. L. Boggs — RIG NO. D-3

MORNING TOUR _____ P.M. _____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	36 76	B. DAVIS	9	2
DRKMAN	37 19	T. BRANDON	9	3
MTRMAN	37 28	J. TOOPS	9	7
FIREMAN	37 73	P. SELMSER	9	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	5	
		CREW	9	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 200 P.M. 12:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	56 25	D. EATON	10	2
DRKMAN	36 73	S. DOREMEIER	10	3
MTRMAN	37 50	B. FRENCH	10	7
FIREMAN	37 36	K. WILDER	10	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	10	
		PUMP	0	
		CREW	10	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 — Printed in U. S. A. — APPROVED — APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED — APPROVED

AC_CPUC_0118015

No. 5495

DAILY DRILLING REPORT — REPORT NO. 17 — #3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	SS #30		9-14-76

OPERATOR	CONTRACTOR	RIG NO.
SO CALIF GAS CO.	CALIF PROD SVC.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: R M Morgan

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J. L. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14x5½

FIELD OR DIST.: ALISO CYN. COUNTY: L.A. STATE: CA.

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION — HOURS

CODE NO. — OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			4
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE		1½	2
6. TRIPS		5½	2
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. TRAVEL		1	
22. OTHER		1	
23.			
COMPLETION A. PERF'R'T'N			
COMPLETION B. TBG TRIPS			
COMPLETION C. TREATING			
COMPLETION D. SWABBING			
COMPLETION E. TESTING			
COMPLETION F. ADDIT'N'L			
COMPLETION G.			
TOTALS		9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.	
HRS. W/OPR. D.P.	
HRS. WO/D.P.	
HRS. STANDBY	
TOTAL DAY WORK	
NO. OF DAYS FROM SPUD	
CUMULATIVE ROTATING HRS.	
TOTAL MUD COST	

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.-SEC.	
	STB RMR OD	FT.	JETS 1/32"		PV/YP	
	D.C. ID OD	FT.	SER. NO.		GELS.	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD-PSI		TYPE / AMT. / TYPE / AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

MORNING TOUR

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.-SEC.	
	STB RMR OD	FT.	JET 1/32"		PV/YP	
	D.C. ID OD	FT.	SER. NO.		GELS.	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD-PSI		TYPE / AMT. / TYPE / AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

DAY TOUR

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.-SEC.	
	STB RMR OD	FT.	JETS 1/32"		PV/YP	
	D.C. ID OD	FT.	SER. NO.		GELS.	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD-PSI		TYPE / AMT. / TYPE / AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

EVENING TOUR

FOOTAGE / FORMATION / DEVIATION RECORD

FOOTAGE FROM	FOOTAGE TO	DR..D RM..R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SCL..S PAR'EL..P COM'B..C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

DRILLER

TIME LOG — MORNING TOUR

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

TIME LOG — DAY TOUR

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	8:00	2		RIH TO 8890'
8:00				RIGGED UP GUIBERSON & POWER SWIVEL. CIRC. OVER
	10:00	2		PLUG, RELEASED SAME. & CIRC.
10:00	1:30	3½		P.O.H BROKE DOWN & LOADED OUT JOHNSTON'S TOOLS
1:30				MADE UP BIT & SCRAPER ON TBG. RIH. W/SAME @ E.O.T.
	2:00	½		

DRILLER

TIME LOG — EVENING TOUR

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	3:30	1½		FINISHED RUNNIN IN THE HOLE WITH BIT & SCRAPER
3:30	7:30	4		TAG FILL @ 8919 CLEANED OUT CEMENT FROM 8919 TO 9095
7:30	9:30	2		CIRC HOLE CLEAN
9:30	10:00	½		PULLED OUT TO ABOVE PERFS CLOSED WELL IN SHUT JOB DWN

DRILLER

DRILLING CREW PAYROLL DATA

No. 5495 #3-5643

DATE 9-14-76

WELL NAME & NO. SS #30

COMPANY SO CALIF GAS CO. R M Morgan

TOOL PUSHER J. L. Boggs RIG NO. D-3

MORNING TOUR ____ P.M. ____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER			
DRKMAN			
MTRMAN			
FIREMAN			
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	36 76	B DAVIS	9
DRKMAN	37 19	T. BRANDON	9
MTRMAN	37 28	J. TOOPS	9
FIREMAN	37 73	P. SELMSER	9
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	1½
		CREW	9

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	56 25	D. EATON	8
DRKMAN	36 73	S. DORFMEIER	8
MTRMAN	37 50	B. FRENCH	8
FIREMAN	37 90	J.K. WARD	8
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	6
		CREW	8

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

AC_CPUC_0118016

No. 5494 #3-5643

DAILY DRILLING REPORT — REPORT NO. 16

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	SS #30		9-13-76

OPERATOR	CONTRACTOR	RIG NO.
SO. CALIF. GAS CO.	CALIF. PROD. SVC.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: T. Mangan

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J. L. Boyce

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14x5½

FIELD OR DIST.: ALISO CYN. | COUNTY: L.A. | STATE: CA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION — HOURS

CODE NO. — OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE			2½
6. TRIPS		6	4½
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. TRAVEL		1	
22. OTHER		2	1
23.			
COMPLETION A. PERF'R'T'N			
B. TBG TRIPS			
C. TREATING			
D. SWABBING			
E. TESTING			
F. ADDIT'N'L			
G.			
TOTALS		9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.	
HRS. W/OPR. D.P.	
HRS. WO/D.P.	
HRS. STANDBY	
TOTAL DAY WORK	
NO. OF DAYS FROM SPUD	
CUMULATIVE ROTATING HRS.	
TOTAL MUD COST	

DRILLING ASSEMBLY (At end of tour)

NO.			
	BIT		FT.
	STB RMR	OD	FT.
	D.C. ID	OD	FT.
	STB RMR	OD	FT.
	D.C. ID	OD	FT.
	STB RMR	OD	FT.
	STANDS DP		FT.
	SINGLES	DP	FT.
	KELLY DOWN		FT.
	TOTAL		FT.
WT. OF STRING			LBS.

BIT RECORD

BIT NO.	
SIZE	
MFG.	
TYPE	
JETS 1/32"	
SER. NO.	
DEPTH OUT	
DEPTH IN	
TOTAL FTG.	
TOTAL HRS. RUN	
COND. 1/8's T/B/ GAGE	
GPM/ PD-PSI	

MUD RECORD

TIME	
WEIGHT	
PRESSURE GRADIENT	
VISC.-SEC.	
PV/YP	
GELS.	
WL.-CC'S.	
pH	
SOLIDS %	

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

MORNING TOUR

FOOTAGE / FORMATION

FROM	TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PAR.-P COM.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DAY TOUR

FOOTAGE / FORMATION

FROM	TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PAR.-P COM.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00				SERV. RIG & EQUIP.
				P.O.H. W/ RET. TOOL. RIH W/ BIT & SCRAPER
2:00	8			

DRILLER

EVENING TOUR

FOOTAGE / FORMATION

FROM	TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PAR.-P COM.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	2:30	½		SERV THE RIG AND THE EQUIP.
2:30	3:00	½		FINISHED RUNNING IN THE HOLE WITH BIT & SCRAPER
3:00	3:30	½		TAG SAND AT 8868 INSTALED GUIBERSON PICKED UP SWIVEL.
3:30	6:00	2½		CLEANED OUT SAND FROM 8868' TO TOP of Plug @ 8890'
6:00	9:30	3½		CIRC HOLE CLEAN
9:30	10:00	½		PULLED OUT OF THE HOLE WITH BIT AND SCRAPER
				MADE UP RET. TOOL RUNNING IN THE HOLE AT END OF TR
				HELD BOP DRILL 9-13-76

DRILLER David O Eaton

DRILLING CREW PAYROLL DATA

No. 5494 #3-5643

DATE 9-13-76

WELL NAME & NO. S.S. #30

COMPANY SO. CALIF. GAS CO. T. Mangan

TOOL PUSHER J. L. Boyce RIG NO. D-3

MORNING TOUR _____ P.M. _____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER			
DRKMAN			
MTRMAN			
FIREMAN			
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	CONFIDENTIAL	B. DAVIS	9
DRKMAN		T. BRANDON	9
MTRMAN		J. TOOPS	9
FIREMAN		P. SELMSER	9
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	Ø
		CREW	9

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	CONFIDENTIAL	D. EATON	8
DRKMAN		S. DOREMEIER	8
MTRMAN		B. FRENCH	8
FIREMAN		T. BRANDON	1
FLRMAN		J.K. WARD	7
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	3
		CREW	8

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 Printed in U. S. A. APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED

AC_CPUC_0118017

No. 5492

DAILY DRILLING REPORT — REPORT NO. 14 — 3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	SS #30	STANDARD SESNON #30	9-10-76

OPERATOR	CONTRACTOR	RIG NO.
So CALIF GAS Co	CALIF PROD SERV	

SIGNATURE OF OPERATOR'S REPRESENTATIVE: E C Shaffer

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J. L. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT. O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14 x 5½

FIELD OR DIST.: ALISO CYN — COUNTY: LOS ANGELES — STATE: CALIFORNIA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF — PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

DRILLING CREW PAYROLL DATA — No. 5492

DATE FRI 9-10-76 — CPS JOB # 3-5643

WELL NAME & NO. STANDARD SESNON #30

COMPANY So CALIF GAS CO

TOOL PUSHER J. L. Boggs — RIG NO. D-3

TIME DISTRIBUTION – HOURS

CODE NO. – OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE			
6. TRIPS		4½	5
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS		1½	
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. TRAVEL		1	
22. OTHER		2	3
23.			
COMPLETION A. PERF'R'T'N			
COMPLETION B. TBG TRIPS			
C. TREATING			
D. SWABBING			
E. TESTING			
F. ADDIT'N'L			
G.			
TOTALS		9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.	
HRS. W/OPR. D.P.	
HRS. WO/D.P.	
HRS. STANDBY	
TOTAL DAY WORK	
NO. OF DAYS FROM SPUD	
CUMULATIVE ROTATING HRS.	
TOTAL MUD COST	

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.-SEC.	
	STB RMR OD	FT.	JETS 1/32"		PV/YP	
	D.C. ID OD	FT.	SER. NO.		GELS.	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD-PSI		TYPE / AMT. / TYPE / AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

MORNING TOUR

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.-SEC.	
	STB RMR OD	FT.	JET 1/32"		PV/YP	
	D.C. ID OD	FT.	SER. NO.		GELS.	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD-PSI		TYPE / AMT. / TYPE / AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

DAY TOUR

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.-SEC.	
	STB RMR OD	FT.	JETS 1/32"		PV/YP	
	D.C. ID OD	FT.	SER. NO.		GELS.	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD-PSI		TYPE / AMT. / TYPE / AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

EVENING TOUR

FOOTAGE / FORMATION / PUMP

FOOTAGE FROM	FOOTAGE TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PARL.-P COMP.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

FOOTAGE / FORMATION / PUMP

FOOTAGE FROM	FOOTAGE TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PARL.-P COMP.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	9:00	2		SERV. THE RIG & EQUIP
9:00	9:30	½		FINISHED PULLING OUT OF THE HOLE
9:30	11:00	1½		RIGGED UP McCULLOUGH WIRE LINE SERV.
11:00	10:30	½		RAN IN WITH WIRE LINE TO 9953 SHOT 4-½" HOLES @ 9953
10:30	11:30	1		RIGGED DOWN McCULLOUGH WIRE LINE SERV.
11:30	2:00	2½		MADE UP LYNNES TESTER
				RUNNING IN THE HOLE WITH TESTER @ END OF TOUR

DRILLER David Eaton

FOOTAGE / FORMATION / PUMP

FOOTAGE FROM	FOOTAGE TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PARL.-P COMP.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION
WSOK on Wales 8853'	Petro P Wyatt	Div Of Oil & Gas						

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	3:00	1		FINISHED RIH W/LYNNES TESTER. SET SAME W/TAIL @
3:00	4:30	1½		8821. MADE WSO. TEST.
4:30	8:30	4		P.O.H. BROKE DOWN & LOADED OUT TESTER.
8:30				RIH OPEN-ENDED @ E.O.T. CLOSED WELL IN, SHUT JOB
				DOWN.
	10:00	1½		

DRILLER Jack McCall

MORNING TOUR — P.M. — A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 3:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	562 5	D EATON	9	2
DRKMAN	567 3	S. DOREMEIER	9	3
MTRMAN	375 0	B. FRENCH	9	7
FIREMAN	379 1	BL. FAUSNET	9	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	9	
		PUMP	9	
		CREW	9	

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	367 6	B. DAVIS	8	2
DRKMAN	371 9	T. BRANDON	8	3
MTRMAN	372 8	J. TOOPS	8	7
FIREMAN	377 3	P. SELMSER	8	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	8	
		CREW	8	

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 — Printed in U. S. A. — APPROVED — APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED — APPROVED

AC_CPUC_0118018

No. 5493

DAILY DRILLING REPORT — REPORT NO. 15 — 3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	SS #30	STANDARD SESNON #30	9-11-76

OPERATOR	CONTRACTOR	RIG NO.
So CALIF GAS CO.	CALIF PROD SERV.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: E. C Brumley

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J. L. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14 X 5½

FIELD OR DIST.: ALISO CYN. — COUNTY: LOS ANGELES — STATE: CALIFORNIA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF — PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION – HOURS

CODE NO. – OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			2
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE			1
6. TRIPS		3	4
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. TRAVEL		1	
22. OTHER		2	1
23. TESTING CSG		3	
COMPLETION A. PERF'R'T'N			
COMPLETION B. TDG TRIPS			
COMPLETION C. TREATING			
COMPLETION D. SWABBING			
COMPLETION E. TESTING			
COMPLETION F. ADDIT'N'L			
COMPLETION G.			
TOTALS		9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

DAY TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD		
	BIT	FT.	BIT NO.		TIME		
			SIZE		WEIGHT		
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT		
	D.C. ID OD	FT.	TYPE		VISC.–SEC.		
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/	/
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/
	STB RMR OD	FT.	DEPTH OUT		WL –CC'S.	/	/
			DEPTH IN		pH		
			TOTAL FTG.		SOLIDS %		
			TOTAL HRS. RUN				
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED		
	SINGLES DP	FT.	GPM/ PD–PSI	/	TYPE / AMT. / TYPE / AMT.		
	KELLY DOWN	FT.					
	TOTAL	FT.					
	WT. OF STRING	LBS.					

DAY TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD		
	BIT	FT.	BIT NO.		TIME		
			SIZE		WEIGHT		
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT		
	D.C. ID OD	FT.	TYPE		VISC.–SEC.		
	STB RMR OD	FT.	JET 1/32"		PV/YP	/	/
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/
	STB RMR OD	FT.	DEPTH OUT		WL –CC'S.	/	/
			DEPTH IN		pH		
			TOTAL FTG.		SOLIDS %		
			TOTAL HRS. RUN				
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED		
	SINGLES DP	FT.	GPM/ PD–PSI	/	TYPE / AMT. / TYPE / AMT.		
	KELLY DOWN	FT.					
	TOTAL	FT.					
	WT. OF STRING	LBS.					

EVENING TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD		
	BIT	FT.	BIT NO.		TIME		
			SIZE		WEIGHT		
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT		
	D.C. ID OD	FT.	TYPE		VISC.–SEC.		
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/	/
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/
	STB RMR OD	FT.	DEPTH OUT		WL –CC'S.	/	/
			DEPTH IN		pH		
			TOTAL FTG.		SOLIDS %		
			TOTAL HRS. RUN				
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED		
	SINGLES DP	FT.	GPM/ PD–PSI	/	TYPE / AMT. / TYPE / AMT.		
	KELLY DOWN	FT.					
	TOTAL	FT.					
	WT. OF STRING	LBS.					

MORNING TOUR

FOOTAGE FROM / TO — DR..D RM–R CORE..C — CORE NO. — FORMATION (SHOW CORE RECOVERY) — ROTARY RPM — WT. ON BIT 1000# — PUMP PRESS — PUMP NO. LINER SIZE / S.P.M. — PUMP NO. LINER SIZE / S.P.M. — METHOD RUN SGL–S PAR'L–P COM'P–C

DEVIATION RECORD — DEPTH / DEV. / DIRECTION (×3)

TIME LOG FROM / TO — ELAPSED TIME — CODE NO. — DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DAY TOUR

FOOTAGE FROM / TO — DR..D RM–R CORE..C — CORE NO. — FORMATION (SHOW CORE RECOVERY) — ROTARY RPM — WT. ON BIT 1000# — PUMP PRESS — PUMP NO. LINER SIZE / S.P.M. — PUMP NO. LINER SIZE / S.P.M. — METHOD RUN SGL–S PAR'L–P COM'P–C

DEVIATION RECORD — DEPTH / DEV. / DIRECTION (×3)

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	7:00	1		SERV. THE RIG AND THE EQUIP
7:00	8:30	1½		PULLED OUT OF THE HOLE
8:30	9:30	1		MADE UP BAKER'S FUL-BORE RAN IN THE HOLE TO 4500'
9:30	10:00	½		RIGGED UP H&H PUMP TEST CASING FROM 8860 TO 4500 OK.
10:00	11:30	1½		TEST FROM 4500 TO SURF. @ 1500 PSI FOR 20 MIN. OK.
11:30	12:30	1		PULLED OUT OF THE HOLE TO 3250 TESTED CASING @ 2000 PSI OK
12:30	1:30	1		PULLED OUT OF THE HOLE 2250 TESTED CASING @ 2500 PSI FOR 20 MIN OK.
1:30	2:00	½		PULLED OUT TO 1750 TEST CASING @ 4000 PSI FOR 20 MIN RIGGED DOWN H&H
				PULLED OUT OF THE HOLE

DRILLER David Eaton

EVENING TOUR

FOOTAGE FROM / TO — DR..D RM–R CORE..C — CORE NO. — FORMATION (SHOW CORE RECOVERY) — ROTARY RPM — WT. ON BIT 1000# — PUMP PRESS — PUMP NO. LINER SIZE / S.P.M. — PUMP NO. LINER SIZE / S.P.M. — METHOD RUN SGL–S PAR'L–P COM'P–C

DEVIATION RECORD — DEPTH / DEV. / DIRECTION (×3)

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	2:30	½		FINISHED P.O.H. BROKE & LOADED OUT F. BORE.
2:30	5:00	2½		RIH TO 8856.' RIGGED UP GUIBERSON & SWIVEL.
5:00				TRADED OUT POWER SWIVELS. RIGGED POOR-BOY DOWN & POWER
	8:00	3		SWIVEL UP. DRILLED FROM 8856'–8868' UNABLE TO
				GO FURTHER. RIGGED CIRC. EQUIP. DOWN.
8:00				P.O.H. @ E.O.T. CLOSED WELL IN, SHUT-TOOL DOWN
	10:00	2		

DRILLER

DRILLING CREW PAYROLL DATA

No. 5493

DATE SAT. 9-11-76 — CPS JOB # 3-5643

WELL NAME & NO. STANDARD SESNON #30

COMPANY So CALIF GAS CO.

TOOL PUSHER J. L. Boggs — RIG NO. D-3

MORNING TOUR _____ P.M. _____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 3:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	56 25	D. ERTON	9	2
DRKMAN	36 73	S. DORFMEIER	9	3
MTRMAN	37 50	B. FRENCH	9	7
FIREMAN	37 90	J.K. WARD	9	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	Ø	
		CREW	9	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	36 76	B. DAVIS	8	2
DRKMAN	37 19	T. BRANDON	8	3
MTRMAN	37 28	J. TOOPS	8	7
FIREMAN	37 73	P. SELMSER	8	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	2	
		CREW	8	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 — Printed in U. S. A. — APPROVED — APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED — APPROVED

AC_CPUC_0118019

No. 5491

DAILY DRILLING REPORT

REPORT NO. 13 — 3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	SS 30	STANDARD SESNON #30	9-9-76

OPERATOR	CONTRACTOR	RIG NO.
So CALIF GAS Co	CALIF PROD SERV.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE	SIGNATURE OF CONTRACTOR'S TOOL PUSHER
E C Dralle	J. J. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14 x 5½

FIELD OR DIST. ALISO CYN. | COUNTY LOS ANGELES | STATE CALIFORNIA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION – HOURS

CODE NO. – OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			2
3. REAMING			
4. CORING			
5. ~~CONDITION MUD~~ & CIRCULATE			3
6. TRIPS		7	2½
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. TRAVEL		1	
22. OTHER		1	½
23.			
COMPLETION A. PERF'R'T'N			
B. TBG TRIPS			
C. TREATING			
D. SWABBING			
E. TESTING			
F. ADDIT'N'L			
G.			
TOTALS		9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			
NO. OF DAYS FROM SPUD			
CUMULATIVE ROTATING HRS.			
TOTAL MUD COST			

DRILLING ASSEMBLY (At end of tour) — BIT RECORD — MUD RECORD

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.–SEC.	
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/ / /
	D.C. ID OD	FT.	SER. NO.		GELS.	/ / /
	STB RMR OD	FT.	DEPTH OUT		WL –CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE	/	MUD & CHEMICALS ADDED: TYPE / AMT. / TYPE / AMT.	
	SINGLES DP	FT.	GPM/ PD–PSI	/		
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

MORNING TOUR

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.–SEC.	
	STB RMR OD	FT.	JET 1/32"		PV/YP	/ / /
	D.C. ID OD	FT.	SER. NO.		GELS.	/ / /
	STB RMR OD	FT.	DEPTH OUT		WL –CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE	/	MUD & CHEMICALS ADDED: TYPE / AMT. / TYPE / AMT.	
	SINGLES DP	FT.	GPM/ PD–PSI	/		
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

DAY TOUR

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
1	BIT SCRAPER 5.00	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.–SEC.	
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/ / /
	D.C. ID OD	FT.	SER. NO.		GELS.	/ / /
	STB RMR OD	FT.	DEPTH OUT		WL –CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
143	STANDS DP 8849. —	FT.	COND. 1/8's T/B/ GAGE	/	MUD & CHEMICALS ADDED: TYPE / AMT. / TYPE / AMT.	
	SINGLES DP	FT.	GPM/ PD–PSI	/		
	KELLY DOWN 6. —	FT.				
	TOTAL 8860'	FT.				
	WT. OF STRING 53,000	LBS.				

EVENING TOUR

FOOTAGE — FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR..D RM..R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.–S PARREL–P COM'D–C

DEVIATION RECORD — DEPTH / DEV. / DIRECTION / DEPTH / DEV. / DIRECTION / DEPTH / DEV. / DIRECTION

TIME LOG — DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

FOOTAGE — FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR..D RM..R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S. P. M.	METHOD RUN SGL.–S PARREL–P COM'D–C

DEVIATION RECORD — DEPTH / DEV. / DIRECTION / DEPTH / DEV. / DIRECTION / DEPTH / DEV. / DIRECTION

TIME LOG — DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	6:30	½		SERV. THE RIG & EQUIP
6:30	10:30	4		BLEED DOWN CASING & TUBING
10:30	11:00	½		PULLED OUT OF THE HOLE BAKERS FULBORE WOULD NOT SAFETY
11:00	2:00	3		REPLACED BAD 2" VALVE IN BOP
				MADE UP BIT AND SCRAPER RUNNING IN THE HOLE
				HELD BOP DRILL 9-9-76

DRILLER David Eaton

FOOTAGE — FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR..D RM..R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.–S PARREL–P COM'D–C

DEVIATION RECORD — DEPTH / DEV. / DIRECTION / DEPTH / DEV. / DIRECTION / DEPTH / DEV. / DIRECTION

TIME LOG — DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	2:30	½		FINISHED RIH. TAGGED CMT @ 8772'
2:30	3:00	½		RIGGED UP POWER SWIVEL & GUIBERSON
3:00	5:00	2		DRILLED OUT CMT. FROM 8772'–8860'
5:00	8:00	3		CIRC. HOLE
8:00	8:30	½		RIGGED POWER SWIVEL & GUIBERSON DOWN. T-
8:30				P.O.H. @ E.O.T. CLOSED WELL IN, SHUT IAB/ DOWN.
	10:00	1½		

DRILLER

DRILLING CREW PAYROLL DATA

No. 5491
OPS JOB # 3-5643

DATE THUR. 9-9-76
WELL NAME & NO. STANDARD SESNON #30
COMPANY So CALIF GAS CO
TOOL PUSHER J. J. Boggs RIG NO. D-3

MORNING TOUR ____ P.M. ____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	562 5	D. EATON	9	2
DRKMAN	36 73	S. DORFMEIER	9	3
MTRMAN	37 50	B. FRENCH	9	7
FIREMAN	37 81	B.L. FAUSNET	9	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	Ø	
		CREW	9	

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	36 76	B. DAVIS	8	2
DRKMAN	37 19	T. BRANDON	8	3
MTRMAN	37 28	J. TOOPS	8	7
FIREMAN	37 73	P. SELMSER	8	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	3	
		CREW	8	

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

AC_CPUC_0118020

No. 5490

DAILY DRILLING REPORT

REPORT NO. 12 — 3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	SS #30	STANDARD SESNON #30	9-8-76

OPERATOR	CONTRACTOR	RIG NO.
So CALIF GAS Co	CALIF PROD SERV.	D 3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: [illegible]

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J. J. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-30	14X5½

FIELD OR DIST.	COUNTY	STATE
ALISO CYN	LOS ANGELES	CALIFORNIA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION – HOURS

CODE NO. – OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE		½	
6. TRIPS		3½	
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. ~~CASING~~ & CEMENT		2	
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT		3½	
19. FISHING			
20. DIR. WORK			
21. TRAVEL	1		
22. OTHER	2	½	
23.			
COMPLETION A. PERF'R'T'N			
B. TBG TRIPS			
C. TREATING			
D. SWABBING			
E. TESTING			
F. ADDIT'N'L			
G.			
TOTALS	9	8	

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			
NO. OF DAYS FROM SPUD			
CUMULATIVE ROTATING HRS.			
TOTAL MUD COST			

DRILLING ASSEMBLY (At end of tour)

NO.			
BIT			FT.
STB RMR	OD		FT.
D.C. ID	OD		FT.
STB RMR	OD		FT.
D.C. ID	OD		FT.
STB RMR	OD		FT.
STANDS DP			FT.
SINGLES	DP		FT.
KELLY DOWN			FT.
TOTAL			FT.
WT. OF STRING			LBS.

BIT RECORD

BIT NO.	
SIZE	
MFG.	
TYPE	
JETS 1/32"	
SER. NO.	
DEPTH OUT	
DEPTH IN	
TOTAL FTG.	
TOTAL HRS. RUN	
COND. 1/8's T/B/ GAGE	
GPM/ PD–PSI	

MUD RECORD

TIME	
WEIGHT	
PRESSURE GRADIENT	
VISC.–SEC.	
PV/YP	
GELS.	
WL –CC'S.	
pH	
SOLIDS %	

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

MORNING TOUR

FOOTAGE

FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.–S PAR'L–P COMB.–C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DAY TOUR

FOOTAGE

FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.–S PAR'L–P COMB.–C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
600	630	½		FINISHED RUNNING IN HOLE TO 8664
630	700	½		RIGGED UP DOWELL
700	930	2½		SET CEMENT TOOL @ 8664 SPOTED CEMENT BACKSIDE OUT
930	1230	3		PULLED OUT OF THE HOLE
1230	200	1½		WAITING ON FULL-BORE

DRILLER David Eaton

EVENING TOUR

FOOTAGE

FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.–S PAR'L–P COMB.–C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2'.00				W/O. BAKER
				MADE UP FULL-BORE ON TBG. RIH TO 8664' TESTED CSG.
				FROM 8664' TO SURFACE @ 1,000# - 10 MIN - TEST O.K.
				CMT. JOB #2 - SQUEEZED 100 SKS. CLASS 'G' NEET CMT.
				TESTED @ 4,000# - TEST O.K. BROKE OUT DOWELL. CLOSED
				WELL IN, SHUT TOR DOWN.
	10'.00	8		HELD B.O.P.E. DRILL

DRILLER [signature]

DRILLING CREW PAYROLL DATA

No. 5490

DATE WED. 9-8-76

CPS JOB # 3-5643

WELL NAME & NO. STANDARD SESNON #30

COMPANY So CALIF GAS CO.

TOOL PUSHER J. J. Boggs RIG NO. D-3

MORNING TOUR _____ P.M. _____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5'.00 A.M. 2'.00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER		D. EATON	9	2
DRKMAN		S. DORFMEIER	9	3
MTRMAN	CONFIDENTIAL	B.L. FAUSNET	9	7
FIREMAN		J.K. WARD	9	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	Ø	
		CREW	9	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2'.00 P.M. 10'.00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER		B. DAVIS	8	2
DRKMAN		T. BRANDON	8	3
MTRMAN	CONFIDENTIAL	J. TOOPS	8	7
FIREMAN		P. SELMSER	8	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	Ø	
		CREW	8	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 Printed in U. S. A. APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED

AC_CPUC_0118021

No. 5489

DAILY DRILLING REPORT

REPORT NO. 11

3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	SS #30	STANDARD SESNON #30	9-7-76

OPERATOR	CONTRACTOR	RIG NO.
So CALIF GAS Co	CALIF PROD SERV	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: S C [illegible]

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J. F. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.	PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
						10	EMSCO	D-300	14x5½

FIELD OR DIST.: ALISO CYN. | COUNTY: LOS ANGELES | STATE: CALIFORNIA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED
FT. CUT OFF	PRESENT LENGTH	
TON MI. OR TRIPS SINCE LAST CUT		
CUMULATIVE TON MI. OR TRIPS		

TIME DISTRIBUTION – HOURS

CODE NO.	OPERATION	MORN.	DAY	EVE.
1.	RIG UP AND TEAR DOWN			
2.	DRILL ACTUAL			
3.	REAMING			
4.	CORING			
5.	CONDITION MUD & CIRCULATE		½	
6.	TRIPS		1½	3½
7.	LUBRICATE RIG			
8.	REPAIR RIG			
9.	CUT OFF DRILLING LINE			
10.	DEVIATION SURVEY			
11.	WIRE LINE LOGS			3½
12.	RUN CASING & CEMENT			
13.	WAIT ON CEMENT			
14.	NIPPLE UP B.O.P.			
15.	TEST B.O.P.			
16.	DRILL STEM TEST			
17.	PLUG BACK			
18.	SQUEEZE CEMENT			
19.	FISHING			
20.	DIR. WORK			
21.	TRAVEL		1	
22.	OTHER		6½	1
23.				
COMPLETION	A. PERF'R'T'N			
	B. TBG TRIPS			
	C. TREATING			
	D. SWABBING			
	E. TESTING			
	F. ADDIT'N'L			
	G.			
TOTALS			9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.				
HRS. W/OPR. D.P.				
HRS. WO/D.P.				
HRS. STANDBY				
TOTAL DAY WORK				

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

MORNING TOUR

DRILLING ASSEMBLY (At end of tour)

NO.			
BIT			FT.
STB RMR	OD		FT.
D.C. ID	OD		FT.
STB RMR	OD		FT.
D.C. ID	OD		FT.
STB RMR	OD		FT.
STANDS DP			FT.
SINGLES	DP		FT.
KELLY DOWN			FT.
TOTAL			FT.
WT. OF STRING			LBS.

BIT RECORD

BIT NO.			
SIZE			
MFG.			
TYPE			
JETS 1/32"			
SER. NO.			
DEPTH OUT			
DEPTH IN			
TOTAL FTG.			
TOTAL HRS. RUN			
COND. 1/8's T/B/ GAGE			
GPM/ PD-PSI	/	/	/

MUD RECORD

TIME			
WEIGHT			
PRESSURE GRADIENT			
VISC.-SEC.			
PV/YP	/	/	/
GELS.	/	/	/
WL -CC'S.			
pH			
SOLIDS %			

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

FOOTAGE

FROM	TO	DR..D RM..R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PART'L-P COMP'D-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DAY TOUR

DRILLING ASSEMBLY (At end of tour)

NO.			
BIT			FT.
STB RMR	OD		FT.
D.C. ID	OD		FT.
STB RMR	OD		FT.
D.C. ID	OD		FT.
STB RMR	OD		FT.
STANDS DP			FT.
SINGLES	DP		FT.
KELLY DOWN			FT.
TOTAL			FT.
WT. OF STRING			LBS.

BIT RECORD

BIT NO.			
SIZE			
MFG.			
TYPE			
JET 1/32"			
SER. NO.			
DEPTH OUT			
DEPTH IN			
TOTAL FTG.			
TOTAL HRS. RUN			
COND. 1/8's T/B/ GAGE			
GPM/ PD-PSI	/	/	/

MUD RECORD

TIME			
WEIGHT			
PRESSURE GRADIENT			
VISC.-SEC.			
PV/YP	/	/	/
GELS.	/	/	/
WL -CC'S.			
pH			
SOLIDS %			

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

FOOTAGE

FROM	TO	DR..D RM..R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PART'L-P COMP'D-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	11:30	5½		SERV. THE RIG AND THE EQUIP.
11:30	12:00	½		BACKSCUDDLE SAND FROM 8855 TO 8860 W/ POWER SWIVEL
12:00	12:30	½		BACKSCUDDLE CLEAN.
12:30	2:00	1½		RIGGED DOWN POWER SWIVEL & GUIBERSON STRIPER
				PULLING OUT OF THE HOLE

DRILLER D K Eaton

EVENING TOUR

DRILLING ASSEMBLY (At end of tour)

NO.			
BIT			FT.
STB RMR	OD		FT.
D.C. ID	OD		FT.
STB RMR	OD		FT.
D.C. ID	OD		FT.
STB RMR	OD		FT.
STANDS DP			FT.
SINGLES	DP		FT.
KELLY DOWN			FT.
TOTAL			FT.
WT. OF STRING			LBS.

BIT RECORD

BIT NO.			
SIZE			
MFG.			
TYPE			
JETS 1/32"			
SER. NO.			
DEPTH OUT			
DEPTH IN			
TOTAL FTG.			
TOTAL HRS. RUN			
COND. 1/8's T/B/ GAGE			
GPM/ PD-PSI	/	/	/

MUD RECORD

TIME			
WEIGHT			
PRESSURE GRADIENT			
VISC.-SEC.			
PV/YP	/	/	/
GELS.	/	/	/
WL -CC'S.			
pH			
SOLIDS %			

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

FOOTAGE

FROM	TO	DR..D RM..R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PART'L-P COMP'D-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	4:00	2		FINISHED P.O.H. BROKE OFF BIT & SCRAPER.
4:00				USING MCCULLOUGH W/L SVC. SHOT 4 HOLES @ 8864'
	7:30	3½		
7:30				MADE UP JOHNSTON'S SQUEEZE TOOL ON 2⅞" TBG.
				RIH W/SAME SLOWLY @ E.O.T. CLOSED WELL IN,
				SHUT JOB DOWN
	10:00	2½		

DRILLER [signature]

DRILLING CREW PAYROLL DATA

No. 5489

DATE TUE 9-7-76

WELL NAME & NO. STANDARD SESNON #30 CPS JOB # 3-5643

COMPANY So CALIF GAS Co

TOOL PUSHER J. F. Boggs RIG NO. D-3

MORNING TOUR ____ P.M. ____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER			
DRKMAN			
MTRMAN			
FIREMAN			
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 3:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	56:25	D. EATON	9
DRKMAN	36:73	S. DOREMEIER	9
MTRMAN	37:50	B. FRENCH	9
FIREMAN	37:81	B.L. FAUSNET	9
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	5
		CREW	9

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	36:76	B. DAVIS	8
DRKMAN	37:19	T. BRANDON	8
MTRMAN	37:28	J. TOOPS	8
FIREMAN	37:73	P. SELMSER	8
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	∅
		CREW	8

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 Printed in U. S. A.

APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED

AC_CPUC_0118022

No. 5488 (#3-5643)

DAILY DRILLING REPORT — REPORT NO. 10

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	S.S. #30		9-4-76

OPERATOR	CONTRACTOR	RIG NO.
SO. CALIF. GAS CO.	CALIF. PROD. SVC.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: E. C. Dudley

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J. L. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14X5½

FIELD OR DIST.: ALISO CYN. COUNTY: L.A. STATE: CA.

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION – HOURS

CODE NO.	OPERATION	MORN.	DAY	EVE.
1.	RIG UP AND TEAR DOWN			
2.	DRILL ACTUAL			
3.	REAMING			
4.	CORING			
5.	CONDITION MUD & CIRCULATE			
6.	TRIPS		4	5½
7.	LUBRICATE RIG			
8.	REPAIR RIG			
9.	CUT OFF DRILLING LINE			
10.	DEVIATION SURVEY			
11.	WIRE LINE LOGS			
12.	RUN CASING & CEMENT			
13.	WAIT ON CEMENT			
14.	NIPPLE UP B.O.P.			
15.	TEST B.O.P.			
16.	DRILL STEM TEST			
17.	PLUG BACK			
18.	SQUEEZE CEMENT			
19.	FISHING			
20.	DIR. WORK			
21.	TRAVEL	1		
22.	OTHER	4	2½	
23.				
COMPLETION	A. PERF'R'T'N			
	B. TBG TRIPS			
	C. TREATING			
	D. SWABBING			
	E. TESTING			
	F. ADDIT'N'L			
	G.			
TOTALS			9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			
NO. OF DAYS FROM SPUD			
CUMULATIVE ROTATING HRS.			
TOTAL MUD COST			

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
BIT	FT.	BIT NO.		TIME	
		SIZE		WEIGHT	
STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
D.C. ID OD	FT.	TYPE		VISC.–SEC.	
STB RMR OD	FT.	JETS 1/32"		PV/YP	/ / /
D.C. ID OD	FT.	SER. NO.		GELS.	/ / /
STB RMR OD	FT.	DEPTH OUT		WL –CC'S.	
		DEPTH IN		pH	
		TOTAL FTG.		SOLIDS %	
		TOTAL HRS. RUN			
STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED: TYPE / AMT. / TYPE / AMT.	
SINGLES DP	FT.	GPM/ PD–PSI	/ /		
KELLY DOWN	FT.				
TOTAL	FT.				
WT. OF STRING	LBS.				

MORNING TOUR

FOOTAGE / FORMATION / DEVIATION RECORD / TIME LOG

FOOTAGE FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SQ.–S PAR.–P COM.–C

DEVIATION RECORD: DEPTH / DEV. / DIRECTION / DEPTH / DEV. / DIRECTION / DEPTH / DEV. / DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DAY TOUR

FOOTAGE / FORMATION / DEVIATION RECORD / TIME LOG

FOOTAGE FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SQ.–S PAR.–P COM.–C

DEVIATION RECORD: DEPTH / DEV. / DIRECTION / DEPTH / DEV. / DIRECTION / DEPTH / DEV. / DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	7:00	1		SERV. RIG & EQUIP
				RIH. PULLED JOHNSTON B. PLUG. P.O.H. BROKE DOWN &
				LOADED OUT SAME
7:00				MADE UP JOHNSTON RET. TOOL ON TBG RIH W/SAME TO
	11:00	4		B. PLUG @ 8890' RELEASED TOOL & SET SAME @ 8890'
11:00				P.O.H. TO 8840' RIGGED UP DWELL. SPOTTED 6 SKS
				"20-40" SAND ON PLUG @ E.O.T.
	2:00	3		

DRILLER

EVENING TOUR

FOOTAGE / FORMATION / DEVIATION RECORD / TIME LOG

FOOTAGE FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SQ.–S PAR.–P COM.–C

DEVIATION RECORD: DEPTH / DEV. / DIRECTION / DEPTH / DEV. / DIRECTION / DEPTH / DEV. / DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	5:00	3		SERV THE RIG & THE EQUIP.
5:00	5:30	½		POLLED OUT OF THE HOLE
5:30	6:30	1		RIGGED UP MCCULLOUGH WIRE LINE SERV.
6:30	7:00	½		RAN IN THE HOLE WITH WIRE SERV TRG SHND @ 8942'
7:00	9:30	2½		RIGGED DOWN MCCULLOUGH WIRE LINE SERV
9:30	10:00	½		MADE UP BIT AND SCRAPER RAN IN THE HOLE
				CLOSED WELL IN SHUT JOB DOWN
				HELD BOP DRILL 9-4-76

DRILLER David E. Eaton

DRILLING CREW PAYROLL DATA

No. 5488 (#3-5643)

DATE 9-4-76

WELL NAME & NO. S.S. #30

COMPANY SO. CALIF. GAS CO.

TOOL PUSHER J. L. Boggs RIG NO. D-3

MORNING TOUR ____ P.M. ____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	36 76	B. DAVIS	9	2
DRKMAN	37 19	T. BRANDON	9	3
MTRMAN	37 28	J. TOOPS	9	7
FIREMAN	37 73	P SELMSER	9	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	Ø	
		CREW	9	

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	56 25	D EATON	8	2
DRKMAN	36 73	S. DORFMEIER	8	3
MTRMAN	37 50	B. FRENCH	8	7
FIREMAN	37 36	K. WILDER	8	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	Ø	
		CREW	8	

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 Printed in U. S. A.

APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED

AC_CPUC_0118023

No. 5487 #3-5643

DAILY DRILLING REPORT — REPORT NO. 9

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	S.S. #30		9-3-76

OPERATOR	CONTRACTOR	RIG NO.
SO. CALIF. GAS CO.	CALIF. PROD. SVC.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE	SIGNATURE OF CONTRACTOR'S TOOL PUSHER
E.C. Bradbury	J. L. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14x5½

FIELD OR DIST.: ALISO CYN | COUNTY: LA | STATE: CA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION — HOURS

CODE NO.	OPERATION	MORN.	DAY	EVE.
1.	RIG UP AND TEAR DOWN			
2.	DRILL ACTUAL			
3.	REAMING			
4.	CORING			
5.	CONDITION MUD & CIRCULATE			
6.	TRIPS			
7.	LUBRICATE RIG			
8.	REPAIR RIG			
9.	CUT OFF DRILLING LINE			
10.	DEVIATION SURVEY			
11.	WIRE LINE LOGS			
12.	RUN CASING & CEMENT			
13.	WAIT ON CEMENT			
14.	NIPPLE UP B.O.P.			
15.	TEST B.O.P.			5
16.	DRILL STEM TEST			
17.	PLUG BACK			
18.	SQUEEZE CEMENT			
19.	FISHING			
20.	DIR. WORK			
21.	TRAVEL		1	
22.	OTHER		8	3
23.				
COMPLETION	A. PERF'R'T'N			
	B. TBG TRIPS			
	C. TREATING			
	D. SWABBING			
	E. TESTING			
	F. ADDIT'N'L			
	G.			
TOTALS			9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

MORNING TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD				
	BIT	FT.	BIT NO.		TIME				
			SIZE		WEIGHT				
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT				
	D.C. ID OD	FT.	TYPE		VISC.-SEC.				
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/	/	/	
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/	/	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.				
			DEPTH IN		pH				
			TOTAL FTG.		SOLIDS %				
			TOTAL HRS. RUN						
	STANDS DP	FT.	COND. 1/B's T/B/ GAGE		MUD & CHEMICALS ADDED	TYPE	AMT.	TYPE	AMT.
	SINGLES DP	FT.	GPM/ PD-PSI	/					
	KELLY DOWN	FT.							
	TOTAL	FT.							
WT. OF STRING		LBS.							

FOOTAGE FROM	FOOTAGE TO	DR.-D RM-R CORE-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PAR'EL-P COM'P-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DAY TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD				
	BIT	FT.	BIT NO.		TIME				
			SIZE		WEIGHT				
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT				
	D.C. ID OD	FT.	TYPE		VISC.-SEC.				
	STB RMR OD	FT.	JET 1/32"		PV/YP	/	/	/	
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/	/	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.				
			DEPTH IN		pH				
			TOTAL FTG.		SOLIDS %				
			TOTAL HRS. RUN						
	STANDS DP	FT.	COND. 1/B's T/D/ GAGE		MUD & CHEMICALS ADDED	TYPE	AMT.	TYPE	AMT.
	SINGLES DP	FT.	GPM/ PD-PSI	/					
	KELLY DOWN	FT.							
	TOTAL	FT.							
WT. OF STRING		LBS.							

FOOTAGE FROM	FOOTAGE TO	DR.-D RM-R CORE-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PAR'EL-P COM'P-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	11:30	5½		SERV. RIG & EQUIP.
11:30	2:00	2½		UNLANDED 7" LANDED SAME W/240,000# ON SLIPS. INSTALLED SEAL FLANGE, TBG HANGER & B.O.P.E.
				HELD B.O.P.E. DRILL

DRILLER

EVENING TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD				
	BIT	FT.	BIT NO.		TIME				
			SIZE		WEIGHT				
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT				
	D.C. ID OD	FT.	TYPE		VISC.-SEC.				
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/	/	/	
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/	/	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.				
			DEPTH IN		pH				
			TOTAL FTG.		SOLIDS %				
			TOTAL HRS. RUN						
	STANDS DP	FT.	COND. 1/B's T/B/ GAGE		MUD & CHEMICALS ADDED	TYPE	AMT.	TYPE	AMT.
	SINGLES DP	FT.	GPM/ PD-PSI	/					
	KELLY DOWN	FT.							
	TOTAL	FT.							
WT. OF STRING		LBS.							

FOOTAGE FROM	FOOTAGE TO	DR.-D RM-R CORE-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PAR'EL-P COM'P-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	4:00	2		SERV. THE RIG AND THE EQUIP.
4:00	5:00	1		FINISHED TESTING SEALS FLANGES
5:00	10:00	5		FINISHED INSTALING BOP + KILL LINES
				TESTED BOP HYDRIL @ 3000 O.K. PIPE RAMS + BLINDS @ 4000
				ALL TESTS OK FOR 20 MIN.

DRILLER

DRILLING CREW PAYROLL DATA

No. 5487 #3-5643

DATE 9-3-76

WELL NAME & NO. S.S. #30

COMPANY SO. CALIF. GAS CO.

TOOL PUSHER J. L. Boggs RIG NO. D-3

MORNING TOUR ____ P.M. ____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	36 76	B. DAVIS	9	2
DRKMAN	37 19	T. BRANDON	9	3
MTRMAN	37 28	J. TOOPS	9	7
FIREMAN	37 73	P. SELMSER	9	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	Ø	
		CREW	9	

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	56 25	D. EATON	8	2
DRKMAN	36 73	S. DOREMEIER	8	3
MTRMAN	37 50	B. FRENCH	8	7
FIREMAN	37 36	K. WILDER	8	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	Ø	
		CREW	8	

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 Printed in U. S. A.

APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED

AC_CPUC_0118024

No. 5487 #3-5643

DAILY DRILLING REPORT — REPORT NO. 9

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	S.S. #30		9-3-76

OPERATOR	CONTRACTOR	RIG NO.
SO. CALIF. GAS CO.	CALIF. PROD. SVC.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE	SIGNATURE OF CONTRACTOR'S TOOL PUSHER
E.C. Bradbury	J. L. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14x5½

FIELD OR DIST.: ALISO CYN | COUNTY: LA | STATE: CA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION — HOURS

CODE NO.	OPERATION	MORN.	DAY	EVE.
1.	RIG UP AND TEAR DOWN			
2.	DRILL ACTUAL			
3.	REAMING			
4.	CORING			
5.	CONDITION MUD & CIRCULATE			
6.	TRIPS			
7.	LUBRICATE RIG			
8.	REPAIR RIG			
9.	CUT OFF DRILLING LINE			
10.	DEVIATION SURVEY			
11.	WIRE LINE LOGS			
12.	RUN CASING & CEMENT			
13.	WAIT ON CEMENT			
14.	NIPPLE UP B.O.P.			
15.	TEST B.O.P.			5
16.	DRILL STEM TEST			
17.	PLUG BACK			
18.	SQUEEZE CEMENT			
19.	FISHING			
20.	DIR. WORK			
21.	TRAVEL		1	
22.	OTHER		8	3
23.				
COMPLETION	A. PERF'R'T'N			
	B. TBG TRIPS			
	C. TREATING			
	D. SWABBING			
	E. TESTING			
	F. ADDIT'N'L			
	G.			
TOTALS			9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

MORNING TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD				
	BIT	FT.	BIT NO.		TIME				
			SIZE		WEIGHT				
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT				
	D.C. ID OD	FT.	TYPE		VISC.-SEC.				
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/	/	/	
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/	/	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.				
			DEPTH IN		pH				
			TOTAL FTG.		SOLIDS %				
			TOTAL HRS. RUN						
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED				
	SINGLES DP	FT.	GPM/ PD-PSI	/	TYPE	AMT.	TYPE	AMT.	
	KELLY DOWN	FT.							
	TOTAL	FT.							
	WT. OF STRING	LBS.							

FOOTAGE FROM	FOOTAGE TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PARL.-P COMP.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DAY TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD				
	BIT	FT.	BIT NO.		TIME				
			SIZE		WEIGHT				
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT				
	D.C. ID OD	FT.	TYPE		VISC.-SEC.				
	STB RMR OD	FT.	JET 1/32"		PV/YP	/	/	/	
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/	/	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.				
			DEPTH IN		pH				
			TOTAL FTG.		SOLIDS %				
			TOTAL HRS. RUN						
	STANDS DP	FT.	COND. 1/8's T/D/ GAGE		MUD & CHEMICALS ADDED				
	SINGLES DP	FT.	GPM/ PD-PSI	/	TYPE	AMT.	TYPE	AMT.	
	KELLY DOWN	FT.							
	TOTAL	FT.							
	WT. OF STRING	LBS.							

FOOTAGE FROM	FOOTAGE TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PARL.-P COMP.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	11:30	5½		SERV. RIG & EQUIP.
11:30	2:00	2½		UNLANDED 7" LANDED SAME W/240,000# ON SLIPS. INSTALLED SEAL FLANGE, TBG HANGER & B.O.P.E.
				HELD B.O.P.E. DRILL

DRILLER

EVENING TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD				
	BIT	FT.	BIT NO.		TIME				
			SIZE		WEIGHT				
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT				
	D.C. ID OD	FT.	TYPE		VISC.-SEC.				
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/	/	/	
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/	/	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.				
			DEPTH IN		pH				
			TOTAL FTG.		SOLIDS %				
			TOTAL HRS. RUN						
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED				
	SINGLES DP	FT.	GPM/ PD-PSI	/	TYPE	AMT.	TYPE	AMT.	
	KELLY DOWN	FT.							
	TOTAL	FT.							
	WT. OF STRING	LBS.							

FOOTAGE FROM	FOOTAGE TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.-S PARL.-P COMP.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	4:00	2		FINISHED TESTING SEALS FLANGES
4:00	5:00	1		FINISHED INSTALING BOP + KILL LINES
5:00	10:00	5		TESTED BOP HYDRIL @ 3000 OK. PIPE RAMS + BLINDS @ 4000 ALL TESTS OK FOR 20 MIN.

DRILLER

DRILLING CREW PAYROLL DATA

No. 5487 #3-5643

DATE 9-3-76

WELL NAME & NO. S.S. #30

COMPANY SO. CALIF. GAS CO.

TOOL PUSHER J. L. Boggs RIG NO. D-3

MORNING TOUR — _____ P.M. _____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	36 76	B. DAVIS	9	2
DRKMAN	37 19	T. BRANDON	9	3
MTRMAN	37 28	J. TOOPS	9	7
FIREMAN	37 73	P. SELMSER	9	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	Ø	
		CREW	9	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	56 25	D. EATON	8	2
DRKMAN	36 73	S. DOREMEIER	8	3
MTRMAN	37 50	B. FRENCH	8	7
FIREMAN	37 36	K. WILDER	8	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	Ø	
		CREW	8	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 Printed in U. S. A. APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED

AC_CPUC_0118025

No. 5486

DAILY DRILLING REPORT

REPORT NO. 8 #3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	SS #30		9-2-76
OPERATOR		**CONTRACTOR**	**RIG NO.**
SO. CALIF GAS CO.		CALIF. PROD. SVC.	D-3
SIGNATURE OF OPERATOR'S REPRESENTATIVE		**SIGNATURE OF CONTRACTOR'S TOOL PUSHER**	
S C Anderson		J. L. Boggs	

D.P. SIZE	WT./FT.	GRADE	TOOL JT. O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14X51/2

FIELD OR DIST. ALISO CYN. COUNTY L.A STATE CA

LAST CASING TUBING OR LINER	SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD REEL NO.

SIZE	NO. LINES	FT. SLIPPED
FT. CUT OFF	PRESENT LENGTH	
TON MI. OR TRIPS SINCE LAST CUT		
CUMULATIVE TON MI. OR TRIPS		

TIME DISTRIBUTION – HOURS

CODE NO. – OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE			
6. TRIPS			
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. TRAVEL	1		
22. OTHER	8	9	
23.			
COMPLETION A. PERF'R'T'N			
COMPLETION B. TBG TRIPS			
COMPLETION C. TREATING			
COMPLETION D. SWABBING			
COMPLETION E. TESTING			
COMPLETION F. ADDIT'N'L			
COMPLETION G.			
TOTALS	9	9	

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.	
HRS. W/OPR. D.P.	
HRS. NO/D.P.	
HRS. STANDBY	
TOTAL DAY WORK	
NO. OF DAYS FROM SPUD	
CUMULATIVE ROTATING HRS.	
TOTAL MUD COST	

DRILLING ASSEMBLY (At end of tour)

NO.			
	BIT		FT.
	STB RMR	OD	FT.
	D.C. ID	OD	FT.
	STB RMR	OD	FT.
	D.C. ID	OD	FT.
	STB RMR	OD	FT.
	STANDS DP		FT.
	SINGLES	DP	FT.
	KELLY DOWN		FT.
	TOTAL		FT.
WT. OF STRING			LBS.

BIT RECORD

BIT NO.	
SIZE	
MFG.	
TYPE	
JETS 1/32"	
SER. NO.	
DEPTH OUT	
DEPTH IN	
TOTAL FTG.	
TOTAL HRS. RUN	
COND. 1/8's T/B/ GAGE	
GPM/ PD-PSI	

MUD RECORD

TIME	
WEIGHT	
PRESSURE GRADIENT	
VISC.-SEC.	
PV/YP	
GELS.	
WL -CC'S.	
pH	
SOLIDS %	

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

MORNING TOUR

DRILLING ASSEMBLY (At end of tour)

NO.			
	BIT		FT.
	STB RMR	OD	FT.
	D.C. ID	OD	FT.
	STB RMR	OD	FT.
	D.C. ID	OD	FT.
	STB RMR	OD	FT.
	STANDS DP		FT.
	SINGLES	DP	FT.
	KELLY DOWN		FT.
	TOTAL		FT.
WT. OF STRING			LBS.

BIT RECORD

BIT NO.	
SIZE	
MFG.	
TYPE	
JET 1/32"	
SER. NO.	
DEPTH OUT	
DEPTH IN	
TOTAL FTG.	
TOTAL HRS. RUN	
COND. 1/8's T/B/ GAGE	
GPM/ PD-PSI	

MUD RECORD

TIME	
WEIGHT	
PRESSURE GRADIENT	
VISC.-SEC.	
PV/YP	
GELS.	
WL -CC'S.	
pH	
SOLIDS %	

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

DAY TOUR

DRILLING ASSEMBLY (At end of tour)

NO.			
	BIT		FT.
	STB RMR	OD	FT.
	D.C. ID	OD	FT.
	STB RMR	OD	FT.
	D.C. ID	OD	FT.
	STB RMR	OD	FT.
	STANDS DP		FT.
	SINGLES	DP	FT.
	KELLY DOWN		FT.
	TOTAL		FT.
WT. OF STRING			LBS.

BIT RECORD

BIT NO.	
SIZE	
MFG.	
TYPE	
JETS 1/32"	
SER. NO.	
DEPTH OUT	
DEPTH IN	
TOTAL FTG.	
TOTAL HRS. RUN	
COND. 1/8's T/B/ GAGE	
GPM/ PD-PSI	

MUD RECORD

TIME	
WEIGHT	
PRESSURE GRADIENT	
VISC.-SEC.	
PV/YP	
GELS.	
WL -CC'S.	
pH	
SOLIDS %	

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

EVENING TOUR

FOOTAGE / FORMATION

FOOTAGE FROM	FOOTAGE TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL. PAR'L-S PAR'L-P COMB.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

FOOTAGE / FORMATION

FOOTAGE FROM	FOOTAGE TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL. PAR'L-S PAR'L-P COMB.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00				SERV. RIG & EQUIP.
				FILLED SURFACE STRING W/20 BBLS (APPROX) FRESH WATER
				CUT OFF CONDUCTOR PIPE. WELDED NEW CSG. HANGER ON
				11 3/8" PUP. CUT & THREADED 7". PRESSURE TESTED CSG. HANGER
				WELD @ 1700# -20 MIN-O.K.) INSTALLED 7" 29# COLLARS;
				NIPPLE. PRESSURE TESTED SAME @ 4,000# @ E.O.T.
	2:00	8		

DRILLER

FOOTAGE / FORMATION

FOOTAGE FROM	FOOTAGE TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL. PAR'L-S PAR'L-P COMB.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	4:00	2		SERV. RIG & EQUIP.
				CONT TESTING 7" CASING @ 4000# BY OK
4:00				WELDED CASING HEAD ON & HEATED SAME & WRAPED
	10:00	6		SAME WITH ASBESTIS BLANKETS TO COOL.

DRILLER

DRILLING CREW PAYROLL DATA

No. 5486

DATE 9-2-76 #3-5643

WELL NAME & NO. SS #30

COMPANY SO CALIF. GAS CO.

TOOL PUSHER J. L. Boggs RIG NO. D-3

MORNING TOUR _____ P.M. _____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER			
DRKMAN			
MTRMAN			
FIREMAN			
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	36 76	B. DAVIS	9
DRKMAN	37 19	T. BRANDON	9
MTRMAN	37 28	J. TOOPS	9
FIREMAN	37 73	P. SELMSER	9
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	8
		CREW	9

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	56 25	D. EATON	8
DRKMAN	36 73	S. DORFMEIER	8
MTRMAN	37 50	B. FRENCH	8
FIREMAN	37 36	K. WILDER	8
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	8
		CREW	8

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 Printed in U. S. A.

APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED

AC_CPUC_0118026

No. 5485

DAILY DRILLING REPORT

REPORT NO. 7 #3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	S.S. #30		9-1-76

OPERATOR	CONTRACTOR	RIG NO.
SO CALIF GAS CO.	CALIF. PROD. SVC.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: S C Smith

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J. S. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT I.D.	TYPE THREAD	STRING NO.

PUMP NO	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14 x 5½

FIELD OR DIST. ALISO CYN. | COUNTY L.A. | STATE CA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION – HOURS

CODE NO.	OPERATION	MORN.	DAY	EVE.
1.	RIG UP AND TEAR DOWN			
2.	DRILL ACTUAL			
3.	REAMING			
4.	CORING			
5.	CONDITION MUD & CIRCULATE			
6.	TRIPS			
7.	LUBRICATE RIG			
8.	REPAIR RIG			
9.	CUT OFF DRILLING LINE			
10.	DEVIATION SURVEY			
11.	WIRE LINE LOGS			
12.	RUN CASING & CEMENT			
13.	WAIT ON CEMENT			
14.	NIPPLE UP B.O.P.			
15.	TEST B.O.P.			
16.	DRILL STEM TEST			
17.	PLUG BACK			
18.	REMOVE SQUEEZE CEMENT		8	
19.	FISHING			
20.	DIR. WORK			
21.	TRAVEL		1	
22.	OTHER			
23.				
COMPLETION	A. PERF'R'T'N			
	B. TBG TRIPS			
	C. TREATING			
	D. SWABBING			
	E. TESTING			
	F. ADDIT'N'L			
	G.			
TOTALS			9	

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.	
HRS. W/OPR. D.P.	
HRS. WO/D.P.	
HRS. STANDBY	
TOTAL DAY WORK	
NO. OF DAYS FROM SPUD	
CUMULATIVE ROTATING HRS.	
TOTAL MUD COST	

MORNING TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD				
	BIT	FT.	BIT NO.		TIME				
			SIZE		WEIGHT				
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT				
	D.C. ID OD	FT.	TYPE		VISC.-SEC.				
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/	/	/	
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/	/	
	STB RMR OD	FT.	DEPTH OUT		WL.-CC'S.				
			DEPTH IN		pH				
			TOTAL FTG.		SOLIDS %				
			TOTAL HRS. RUN						
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED				
	SINGLES DP	FT.	GPM/ PD-PSI	/	TYPE	AMT.	TYPE	AMT.	
	KELLY DOWN	FT.							
	TOTAL	FT.							
	WT. OF STRING	LBS.							

DAY TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD				
	BIT	FT.	BIT NO.		TIME				
			SIZE		WEIGHT				
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT				
	D.C. ID OD	FT.	TYPE		VISC.-SEC.				
	STB RMR OD	FT.	JET 1/32"		PV/YP	/	/	/	
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/	/	
	STB RMR OD	FT.	DEPTH OUT		WL.-CC'S.				
			DEPTH IN		pH				
			TOTAL FTG.		SOLIDS %				
			TOTAL HRS. RUN						
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED				
	SINGLES DP	FT.	GPM/ PD-PSI	/	TYPE	AMT.	TYPE	AMT.	
	KELLY DOWN	FT.							
	TOTAL	FT.							
	WT. OF STRING	LBS.							

EVENING TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD				
	BIT	FT.	BIT NO.		TIME				
			SIZE		WEIGHT				
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT				
	D.C. ID OD	FT.	TYPE		VISC.-SEC.				
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/	/	/	
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/	/	
	STB RMR OD	FT.	DEPTH OUT		WL.-CC'S.				
			DEPTH IN		pH				
			TOTAL FTG.		SOLIDS %				
			TOTAL HRS. RUN						
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED				
	SINGLES DP	FT.	GPM/ PD-PSI	/	TYPE	AMT.	TYPE	AMT.	
	KELLY DOWN	FT.							
	TOTAL	FT.							
	WT. OF STRING	LBS.							

MORNING TOUR

FOOTAGE FROM / TO | DR..D RM..R CORE..C | CORE NO. | FORMATION (SHOW CORE RECOVERY) | ROTARY RPM | WT. ON BIT 1000# | PUMP PRESS | PUMP NO. LINER SIZE | PUMP NO. S.P.M. | PUMP NO. LINER SIZE | PUMP NO. S.P.M. | METHOD RUN SGL.-S PAR.EL-P COM.D-C

DEVIATION RECORD: DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION

TIME LOG FROM / TO | ELAPSED TIME | CODE NO. | DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DAY TOUR

FOOTAGE FROM / TO | DR..D RM..R CORE..C | CORE NO. | FORMATION (SHOW CORE RECOVERY) | ROTARY RPM | WT. ON BIT 1000# | PUMP PRESS | PUMP NO. LINER SIZE | PUMP NO. S.P.M. | PUMP NO. LINER SIZE | PUMP NO. S.P.M. | METHOD RUN SGL.-S PAR.EL-P COM.D-C

DEVIATION RECORD: DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6.00				SERV. RIG & EQUIP
				JACKHAMMERING OUT CELLAR
	2:00	8		

DRILLER

EVENING TOUR

FOOTAGE FROM / TO | DR..D RM..R CORE..C | CORE NO. | FORMATION (SHOW CORE RECOVERY) | ROTARY RPM | WT. ON BIT 1000# | PUMP PRESS | PUMP NO. LINER SIZE | PUMP NO. S.P.M. | PUMP NO. LINER SIZE | PUMP NO. S.P.M. | METHOD RUN SGL.-S PAR.EL-P COM.D-C

DEVIATION RECORD: DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION | DEPTH | DEV. | DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2.00				SERV. THE RIG AND THE EQUIP
				JACKHAMMERING & DIGGING OUT CELLAR.
	10:00	8		

DRILLER

DRILLING CREW PAYROLL DATA

No. 5485

DATE 9-1-76 #3-5643

WELL NAME & NO. S.S. #30

COMPANY SO. CALIF. GAS CO

TOOL PUSHER J. S. Boggs RIG NO. D-3

MORNING TOUR ____ P.M. ____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER			
DRKMAN			
MTRMAN			
FIREMAN			
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	CONFIDENTIAL	B. DAVIS	9
DRKMAN		T. BRANDON	9
MTRMAN		J. TOOPS	9
FIREMAN		P. SELMSER	9
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	0
		CREW	9

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 12:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER	CONFIDENTIAL	D. EATON	8
DRKMAN		S. DORFMEIER	8
MTRMAN		B. FRENCH	8
FIREMAN		K. WILDER.	8
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			
		RIG	8
		PUMP	0
		CREW	8

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 Printed in U. S. A. APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED

AC_CPUC_0118027

No. 5484 #3-5643

DAILY DRILLING REPORT — REPORT NO. 6

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	S.S. #30		8-31-76

OPERATOR	CONTRACTOR	RIG NO.
SO. CALIF GAS CO.	CALIF PROD. SVC.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: E. A. Sulk

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J. L. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14 X 5½

FIELD OR DIST.: ALISO CYN. COUNTY: L.A. STATE: CA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION — HOURS

CODE NO.	OPERATION	MORN.	DAY	EVE.
1.	RIG UP AND TEAR DOWN			
2.	DRILL ACTUAL			
3.	REAMING			
4.	CORING			
5.	CONDITION MUD & CIRCULATE			
6.	TRIPS		4½	
7.	LUBRICATE RIG			
8.	REPAIR RIG			
9.	CUT OFF DRILLING LINE			
10.	DEVIATION SURVEY			
11.	WIRE LINE LOGS			
12.	RUN CASING & CEMENT			
13.	WAIT ON CEMENT			
14.	NIPPLE UP B.O.P.			
15.	TEST B.O.P.			
16.	DRILL STEM TEST			
17.	PLUG BACK			
18.	SQUEEZE CEMENT			
19.	FISHING			
20.	DIR. WORK			
21.	TRAVEL		1	
22.	OTHER		5½	9
23.				
COMPLETION	A. PERF'R'T'N			
	B. TBG TRIPS			
	C. TREATING			
	D. SWABBING			
	E. TESTING			
	F. ADDIT'N'L			
	G.			
TOTALS			9	9

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.	
HRS. W/OPR. D.P.	
HRS. WO/D.P.	
HRS. STANDBY	
TOTAL DAY WORK	
NO. OF DAYS FROM SPUD	
CUMULATIVE ROTATING HRS.	
TOTAL MUD COST	

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD				
	BIT	FT.	BIT NO.		TIME				
			SIZE		WEIGHT				
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT				
	D.C. ID OD	FT.	TYPE		VISC.-SEC.				
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/	/	/	
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/	/	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.				
			DEPTH IN		pH				
			TOTAL FTG.		SOLIDS %				
			TOTAL HRS. RUN						
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	TYPE	AMT.	TYPE	AMT.
	SINGLES DP	FT.	GPM/ PD-PSI	/					
	KELLY DOWN	FT.							
	TOTAL	FT.							
WT. OF STRING		LBS.							

MORNING TOUR

FOOTAGE / FORMATION

FROM	TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SOL.-S PAR.EL-P COM.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD				
	BIT	FT.	BIT NO.		TIME				
			SIZE		WEIGHT				
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT				
	D.C. ID OD	FT.	TYPE		VISC.-SEC.				
	STB RMR OD	FT.	JET 1/32"		PV/YP	/	/	/	
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/	/	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.				
			DEPTH IN		pH				
			TOTAL FTG.		SOLIDS %				
			TOTAL HRS. RUN						
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	TYPE	AMT.	TYPE	AMT.
	SINGLES DP	FT.	GPM/ PD-PSI	/					
	KELLY DOWN	FT.							
	TOTAL	FT.							
WT. OF STRING		LBS.							

DAY TOUR

FOOTAGE / FORMATION

FROM	TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SOL.-S PAR.EL-P COM.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00				SERV. RIG & EQUIP. (FILLED HOLE-70BBLS)
	8:30	2½		SET JOHNSTON BRIDGE PLUG @ 8850'. P.O.H. TO 8795'
8:30	12:00	3½		TESTED PLUG @ 1,000# - 20 MIN.
12:00	12:30	½		P.O.H. W/ RET. TOOL
				RIH W/ JOHNSTON B. PLUG SET SAME @ 100' - TESTED
				SAME @ 1,500# - 20 MIN.
12:30	1:00	½		FINISHED TEST (ABOVE) P.O.H. W/ RET. TOOL
1:00				CELLAR WORK - REMOVING B.O.P.E @ E.O.T.
	2:00			

DRILLER

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD				
	BIT	FT.	BIT NO.		TIME				
			SIZE		WEIGHT				
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT				
	D.C. ID OD	FT.	TYPE		VISC.-SEC.				
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/	/	/	
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/	/	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.				
			DEPTH IN		pH				
			TOTAL FTG.		SOLIDS %				
			TOTAL HRS. RUN						
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	TYPE	AMT.	TYPE	AMT.
	SINGLES DP	FT.	GPM/ PD-PSI	/					
	KELLY DOWN	FT.							
	TOTAL	FT.							
WT. OF STRING		LBS.							

EVENING TOUR

FOOTAGE / FORMATION

FROM	TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SOL.-S PAR.EL-P COM.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	5:00	3		SERV. THE RIG & EQUIP.
5:00	6:00	1		REMOVED BOP CLEANED OUT CELLAR
6:00	6:30	½		RIGGED UP CASING JACKS
6:30	10:00	3½		MADE UP MID-WAYS SPEAR & TOOLS
10:30				UNLANDED CASING CUT WELL HEAD OFF FILLED SURFACE
				STRING CELLAR WORK.

DRILLER

DRILLING CREW PAYROLL DATA — No. 5484 #3-5643

DATE 8-31-76

WELL NAME & NO. S.S. #30

COMPANY SO. CALIF GAS CO.

TOOL PUSHER J. L. Boggs — RIG NO. D-3

MORNING TOUR ____ P.M. ____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	CONFIDENTIAL	B. DAVIS	9	2
DRKMAN		T. BRANDON	9	3
MTRMAN		J. TOOI	—	—
FIREMAN		P SELMSER	9	7
FLRMAN		B.L. FAUSNET	9	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	1	
		CREW	9	

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	CONFIDENTIAL	D. EATON	8	2
DRKMAN		S. DOREMEIER	8	3
MTRMAN		B. FRENCH	8	7
FIREMAN		K. WILDER	8	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	0	
		CREW	8	

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 Printed in U. S. A. APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED

AC_CPUC_0118028

No. 5483 #3-5643

DAILY DRILLING REPORT — REPORT NO. 5

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	SS #30		8-30-76

OPERATOR	CONTRACTOR	RIG NO.
SO. CALIF. GAS CO.	CALIF. PROD SVC	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: E. E. Guilkey

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J. L. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14X5½

FIELD OR DIST.: ALISO CYN. | COUNTY: L.A. | STATE: CA

LAST CASING TUBING OR LINER	SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED
FT. CUT OFF	PRESENT LENGTH	
TON MI. OR TRIPS SINCE LAST CUT		
CUMULATIVE TON MI. OR TRIPS		

TIME DISTRIBUTION — HOURS

CODE NO. — OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE			
6. TRIPS		½	3½
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS		7½	4½
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. TRAVEL		1	
22. OTHER			
23.			
COMPLETION A. PERF'R'T'N			
COMPLETION B. TBG TRIPS			
COMPLETION C. TREATING			
COMPLETION D. SWABBING			
COMPLETION E. TESTING			
COMPLETION F. ADDIT'N'L			
COMPLETION G.			
TOTALS		9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.	
HRS. W/OPR. D.P.	
HRS. WO/D.P.	
HRS. STANDBY	
TOTAL DAY WORK	
NO. OF DAYS FROM SPUD	
CUMULATIVE ROTATING HRS.	
TOTAL MUD COST	

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.-SEC.	
	STB RMR OD	FT.	JETS 1/32"		PV/YP	
	D.C. ID OD	FT.	SER. NO.		GELS.	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/B's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD-PSI		TYPE AMT. TYPE AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

MORNING TOUR

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.-SEC.	
	STB RMR OD	FT.	JET 1/32"		PV/YP	
	D.C. ID OD	FT.	SER. NO.		GELS.	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD-PSI		TYPE AMT. TYPE AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

DAY TOUR

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.-SEC.	
	STB RMR OD	FT.	JETS 1/32"		PV/YP	
	D.C. ID OD	FT.	SER. NO.		GELS.	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD-PSI		TYPE AMT. TYPE AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

EVENING TOUR

FOOTAGE / FORMATION (SHOW CORE RECOVERY) / DEVIATION RECORD

FOOTAGE FROM	FOOTAGE TO	DR..D RM-R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL-S PAR'L-P COM'D-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG / DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

FOOTAGE / FORMATION (SHOW CORE RECOVERY) / DEVIATION RECORD

FOOTAGE FROM	FOOTAGE TO	DR..D RM-R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S. P. M.	METHOD RUN SGL-S PAR'L-P COM'D-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG / DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	6:30	½		SERV. RIG & EQUIP
6:30				P.O.H. W/BIT & SCRAPER
				RIGGED UP DRESSER-ATLAS LOGGING AS PROGRAMMED
	2:00	7½		

DRILLER

FOOTAGE / FORMATION (SHOW CORE RECOVERY) / DEVIATION RECORD

FOOTAGE FROM	FOOTAGE TO	DR..D RM-R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL-S PAR'L-P COM'D-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG / DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	6:00	4		SERV THE RIG AND THE EQUIP.
6:00	6:30	½		LOG WELL AS PROGRAMED
6:30	10:00	3½		RIGGED DOWN DRESSER-ATLAS WIRE LINE SERV.
				RUN IN HOLE W/PLUG TO 8785 SHUT JOB DOWN
				TILL A.M.

DRILLER David O Eaton

DRILLING CREW PAYROLL DATA

No. 5483 #3-5643

DATE 8-30-76

WELL NAME & NO. S.S. #30

COMPANY SO. CALIF. GAS CO.

TOOL PUSHER J. L. Boggs RIG NO. D-3

MORNING TOUR _____ P.M. _____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	36 76	B. DAVIS	9	2
DRKMAN	37 19	T. BRANDON	9	3
MTRMAN	37 28	J. TOOPS	9	7
FIREMAN	37 73	P SELMSER	9	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	8	
		CREW	9	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	56 25	D. EATON	8	2
DRKMAN	36 73	S. DORFMEIER	8	5
MTRMAN	37 50	B. FRENCH	8	7
FIREMAN	37 36	K. WILDER	8	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	⊖	
		CREW	8	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 Printed in U. S. A. APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED

AC_CPUC_0118029

No. 5482

DAILY DRILLING REPORT — REPORT NO. # 4

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN-	55 #30	STANDARD SESNON #30	8-28-76

OPERATOR	CONTRACTOR	RIG NO.
So CALIF GAS CO-	CALIF Prod. Service	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE	SIGNATURE OF CONTRACTOR'S TOOL PUSHER
E C Butler	

D.P. SIZE	WT./FT.	GRADE	TOOL JT. O.D.	TYPE THREAD	STRING NO.	PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH

FIELD OR DIST. ALISO CYN- | COUNTY L-A- | STATE CALIF-

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

DRILLING CREW PAYROLL DATA — No. 5482

DATE 8-28-76

WELL NAME & NO. STANDARD SESNON #30 = 35643

COMPANY So CALIF GAS CO-

TOOL PUSHER _____ RIG NO. D-3-

TIME DISTRIBUTION – HOURS

CODE NO. – OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE			3
6. TRIPS		½	4½
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. Travel		1	
22. Other		½	½
23.			
COMPLETION A. PERF'R'T'N			
COMPLETION B. TBG TRIPS			
COMPLETION C. TREATING			
COMPLETION D. SWABBING			
COMPLETION E. TESTING			
COMPLETION F. ADDIT'N'L			
COMPLETION G.			
TOTALS		9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			
NO. OF DAYS FROM SPUD			
CUMULATIVE ROTATING HRS.			
TOTAL MUD COST			

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.–SEC.	
	STB RMR OD	FT.	JETS 1/32"		PV/YP	
	D.C. ID OD	FT.	SER. NO.		GELS.	
	STB RMR OD	FT.	DEPTH OUT		WL –CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD–PSI		TYPE AMT. TYPE AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

MORNING TOUR

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.–SEC.	
	STB RMR OD	FT.	JET 1/32"		PV/YP	
	D.C. ID OD	FT.	SER. NO.		GELS.	
	STB RMR OD	FT.	DEPTH OUT		WL –CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD–PSI		TYPE AMT. TYPE AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

DAY TOUR

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT SCRAPER 4.50	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.–SEC.	
	STB RMR OD	FT.	JETS 1/32"		PV/YP	
	D.C. ID OD	FT.	SER. NO.		GELS.	
	STB RMR OD	FT.	DEPTH OUT		WL –CC'S.	
			DEPTH IN		pH	
MINUS 10			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
149	STANDS DP 9246.21	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD–PSI		TYPE AMT. TYPE AMT.	
	KELLY DOWN	FT.				
	TOTAL 9241.71	FT.				
	WT. OF STRING 54,000	LBS.				

EVENING TOUR

FOOTAGE / FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.–S PAR.EL–P COM.D-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

MORNING TOUR — P.M. _____ A.M. _____

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

FOOTAGE / FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.–S PAR.EL–P COM.D-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00	8:30	2½		PULLING OUT of Hole S.L.M.
8:30	10:00	1½		LAID down BOTTOM ASSY.
10:00	2:00	D		MAKE UP BIT & SCRAPPER RUN IN Hole

DRILLER B.J. French

DAY TOUR — 5:00 A.M. 3:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	37 50	B.J. FRENCH	9	2
DRKMAN	36 73	S. DonFMeier	9	3
MTRMAN	37 36	K. Wilder	9	7
FIREMAN	37 90	J.K. WARD	9	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	8	
		Crew	9	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

FOOTAGE / FORMATION (SHOW CORE RECOVERY)

FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.–S PAR.EL–P COM.D-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00				FINISHED RIH W/BIT & SCRAPER TO 9242'
	4:00	2		
4:00				CIRC. HOLE
	7:00	3		
7:00				P.O.H. @ EOT. CLOSED WELL IN, SHUT JOB DOWN
	10:00	3		HELD B.O.P. & DRILL

DRILLER

EVENING TOUR — 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	36 76	B. DAVIS	8	2
DRKMAN	37 19	T. BRANDON	8	3
MTRMAN	37 28	J. TOOPS	8	7
FIREMAN	37 73	P. SELMSER	8	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	3	
		CREW	8	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 Printed in U. S. A.

APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED

AC_CPUC_0118030

No. 5481

DAILY DRILLING REPORT

REPORT NO. 3

~~5-5643~~ 3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN.	~~55~~ #30	STANDARD SESNON #30	8-27-76

OPERATOR	CONTRACTOR	RIG NO.
So CALIF GAS Co	CALIF PROD SERV.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE	SIGNATURE OF CONTRACTOR'S TOOL PUSHER
[signature]	J. L. Boggs

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14x5½

FIELD OR DIST.	COUNTY	STATE
ALISO CYN	LOS ANGELES	CALIFORNIA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION – HOURS

CODE NO. – OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE		4	4
6. TRIPS			3
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS		4	
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. TRAVEL		1	
22. OTHER			1
23.			
COMPLETION A. PERF'R'T'N			
B. TBG TRIPS			
C. TREATING			
D. SWABBING			
E. TESTING			
F. ADDIT'N'L			
G.			
TOTALS		9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

MORNING TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD		
	BIT	FT.	BIT NO.		TIME		
			SIZE		WEIGHT		
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT		
	D.C. ID OD	FT.	TYPE		VISC.–SEC.		
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/	/
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/
	STB RMR OD	FT.	DEPTH OUT		WL –CC'S.		
			DEPTH IN		pH		
			TOTAL FTG.		SOLIDS %		
			TOTAL HRS. RUN				
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED		
	SINGLES DP	FT.	GPM/ PD–PSI	/	TYPE	AMT.	TYPE AMT.
	KELLY DOWN	FT.					
	TOTAL	FT.					
	WT. OF STRING	LBS.					

FOOTAGE FROM	TO	DR..D RM–R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL–S PAR'L–P COM'B–C

DEVIATION RECORD	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DAY TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD		
	BIT	FT.	BIT NO.		TIME		
			SIZE		WEIGHT		
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT		
	D.C. ID OD	FT.	TYPE		VISC.–SEC.		
	STB RMR OD	FT.	JET 1/32"		PV/YP	/	/
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/
	STB RMR OD	FT.	DEPTH OUT		WL –CC'S.		
			DEPTH IN		pH		
			TOTAL FTG.		SOLIDS %		
			TOTAL HRS. RUN				
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED		
	SINGLES DP	FT.	GPM/ PD–PSI	/	TYPE	AMT.	TYPE AMT.
	KELLY DOWN	FT.					
	TOTAL	FT.					
	WT. OF STRING	LBS.					

FOOTAGE FROM	TO	DR..D RM–R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S. P. M.	METHOD RUN SGL–S PAR'L–P COM'B–C

DEVIATION RECORD	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6 00	10 00	4		SERV. THE RIG AND THE EQUIP.
10 00	2 00	4		RIGGED UP ARCHER-REED WIRE LINE PULLED TUB PLUG
				RIGGING UP KILL LINE CIRC. WELL @ END of TOUR.

DRILLER [signature]

EVENING TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD		
	BIT	FT.	BIT NO.		TIME		
			SIZE		WEIGHT		
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT		
	D.C. ID OD	FT.	TYPE		VISC.–SEC.		
	STB RMR OD	FT.	JETS 1/32"		PV/YP	/	/
	D.C. ID OD	FT.	SER. NO.		GELS.	/	/
	STB RMR OD	FT.	DEPTH OUT		WL –CC'S.		
			DEPTH IN		pH		
			TOTAL FTG.		SOLIDS %		
			TOTAL HRS. RUN				
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED		
	SINGLES DP	FT.	GPM/ PD–PSI	/	TYPE	AMT.	TYPE AMT.
	KELLY DOWN	FT.					
	TOTAL	FT.					
	WT. OF STRING	LBS.					

FOOTAGE FROM	TO	DR..D RM–R CORE..C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL–S PAR'L–P COM'B–C

DEVIATION RECORD	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	6:00	4:		CONT. TO KILL WELL
6:00	7:00	1		REMOVED DO-NUT STUDS
7:00				RELEASED PKR. P.O.H. MEAS OUT @ E.O.T. CLOSED
				WELL IN, SHUT JOB DOWN
	10:00	3		

DRILLER [signature]

DRILLING CREW PAYROLL DATA

No. 5481

DATE FRI 8-27-76

WELL NAME & NO. STANDARD SESNON #30 3-5643

COMPANY So CALIF GAS CO

TOOL PUSHER J. L. Boggs RIG NO. D-3

MORNING TOUR _____ P.M. _____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 5:00 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	56 25	D. EATON	9	2
DRKMAN	36 73	S. DOREMEIER	9	3
MTRMAN	37 50	B. FRENCH	9	7
FIREMAN	37 73	P SELMSER	9	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	4	
		CREW	9	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	36 76	B DAVIS	8	2
DRKMAN	37 19	T. BRANDON	8	3
MTRMAN	37 28	J. TOOPS	8	7
FIREMAN	~~37~~ 73	P. SELMSER	—	7
FLRMAN	37 36	K. WILDER	8	7
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	4	
		CREW	8	

NO. OF DAYS _____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 Printed in U. S. A.

APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED

AC_CPUC_0118031

No. 5480

DAILY DRILLING REPORT — REPORT NO. (2) 3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
ALISO CYN	SS #30	STANDARD SESNON #30	8-26-76

OPERATOR	CONTRACTOR	RIG NO.
So CALIF GAS CO.	CALIF PROD SERV.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE	SIGNATURE OF CONTRACTOR'S TOOL PUSHER
E.C. Bradley	J. Dutton

D.P. SIZE	WT./FT.	GRADE	TOOL JT. O.D.	TYPE THREAD	STRING NO.	PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
						10	EMSCO	D-300	14x5½

FIELD OR DIST. ALISO CYN | COUNTY LOS ANGELES | STATE CALIFORNIA

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION — HOURS

CODE NO. — OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN		8	1
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE			
6. TRIPS			
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			1
15. TEST B.O.P.			5
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21. TRAVEL		1	
22. OTHER			1
23.			
COMPLETION A. PERF'R'T'N			
COMPLETION B. TBG TRIPS			
COMPLETION C. TREATING			
COMPLETION D. SWABBING			
COMPLETION E. TESTING			
COMPLETION F. ADDIT'N'L			
COMPLETION G.			
TOTALS		9	8

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

DRILLING ASSEMBLY (At end of tour) / BIT RECORD / MUD RECORD

NO.	DRILLING ASSEMBLY		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.-SEC.	
	STB RMR OD	FT.	JETS 1/32"		PV/YP	
	D.C. ID OD	FT.	SER. NO.		GELS.	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD-PSI		TYPE / AMT. / TYPE / AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

MORNING TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.-SEC.	
	STB RMR OD	FT.	JET 1/32"		PV/YP	
	D.C. ID OD	FT.	SER. NO.		GELS.	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD-PSI		TYPE / AMT. / TYPE / AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

DAY TOUR

NO.	DRILLING ASSEMBLY (At end of tour)		BIT RECORD		MUD RECORD	
	BIT	FT.	BIT NO.		TIME	
			SIZE		WEIGHT	
	STB RMR OD	FT.	MFG.		PRESSURE GRADIENT	
	D.C. ID OD	FT.	TYPE		VISC.-SEC.	8
	STB RMR OD	FT.	JETS 1/32"		PV/YP	
	D.C. ID OD	FT.	SER. NO.		GELS.	
	STB RMR OD	FT.	DEPTH OUT		WL -CC'S.	
			DEPTH IN		pH	
			TOTAL FTG.		SOLIDS %	
			TOTAL HRS. RUN			
	STANDS DP	FT.	COND. 1/8's T/B/ GAGE		MUD & CHEMICALS ADDED	
	SINGLES DP	FT.	GPM/ PD-PSI		TYPE / AMT. / TYPE / AMT.	
	KELLY DOWN	FT.				
	TOTAL	FT.				
	WT. OF STRING	LBS.				

EVENING TOUR

FOOTAGE / FORMATION (SHOW CORE RECOVERY) / PUMP NO. / METHOD RUN

FOOTAGE FROM	FOOTAGE TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SCL.-S PAR'L.-P COM'D.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

FOOTAGE / FORMATION (SHOW CORE RECOVERY) / PUMP NO. / METHOD RUN

FOOTAGE FROM	FOOTAGE TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S. P. M.	METHOD RUN SCL.-S PAR'L.-P COM'D.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
6:00				SERV. THE RIG & THE EQUIP.
				MOVED RIG AND EQUIP FROM SESNON FEE #7 TO
				STANDARD SESNON # 30 RIG UP MAST RIGGING UP
				PUMP
	2:00	8		

DRILLER David O Eaton

FOOTAGE / FORMATION (SHOW CORE RECOVERY) / PUMP NO. / METHOD RUN

FOOTAGE FROM	FOOTAGE TO	DR.-D RM.-R CORE.-C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000#	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SCL.-S PAR'L.-P COM'D.-C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG FROM	TIME LOG TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
2:00	4:00	2		REMOVED PROD HEAD, INSTALLED CLASS III B.O.P.E.
4:00				TESTED B.O.P.E. USING DOWELL (H_2O) & NOWSCO (N_2)
				AS FOLLOWS CSO & P. RAMS @ 4,000#-20 MIN. HYDRIL
	9:00	5		@ 3000#-20 MIN. - TESTS O.K
9:00				RIGGING UP PUMP & RIGGING TO PULL TBG.
				CLOSED WELL IN, SHUT JOB DOWN.
	10:00	1		

DRILLER

DRILLING CREW PAYROLL DATA — No. 5480 / 3-5643

DATE THUR. 8-26-76

WELL NAME & NO. STANDARD SESNON #30

COMPANY So CALIF GAS Co

TOOL PUSHER J. Dutton — RIG NO. D-3

MORNING TOUR ____ P.M. ____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER				
DRKMAN				
MTRMAN				
FIREMAN				
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR 500 A.M. 2:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	56 25	D. EATON	9	2
DRKMAN	36 73	S. DOREMEIER	9	3
MTRMAN	37 50	B. FRENCH	9	7
FIREMAN	37 36	K. WILDER	9	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	9	
		PUMP	0	
		CREW	9	

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 2:00 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	36 76	B. DAVIS	8	2
DRKMAN	37 19	T. BRANDON	8	3
MTRMAN	37 28	J. TOOPS	8	7
FIREMAN	37 73	P. SELMSER	8	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	8	
		PUMP	0	
		CREW	8	

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 Printed in U. S. A. APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED

AC_CPUC_0118032

No. 5479

DAILY DRILLING REPORT

REPORT NO. 1 3-5643

LEASE	WELL NO.	API WELL NUMBER	DATE
17LISO CYN.	SS #30	STANDARD SESNON	8-25-7

OPERATOR	CONTRACTOR	RIG NO.
So CALIF GAS	CALIF PROD SERV.	D-3

SIGNATURE OF OPERATOR'S REPRESENTATIVE: E C Bradley

SIGNATURE OF CONTRACTOR'S TOOL PUSHER: J S Dutton

FIELD OR DIST.: ALISO CYN | COUNTY: L.A. | STATE: CALIF

D.P. SIZE	WT./FT.	GRADE	TOOL JT O.D.	TYPE THREAD	STRING NO.

PUMP NO.	PUMP MANUFACTURER	TYPE	STROKE LENGTH
10	EMSCO	D-300	14x5½

LAST CASING TUBING OR LINER

SIZE	MAKE	WT. & GR.	NO. JOINTS	FEET	RKB. TO CSG. HD.	SET AT

WIRE LINE RECORD — REEL NO.

SIZE	NO. LINES	FT. SLIPPED

FT. CUT OFF | PRESENT LENGTH

TON MI. OR TRIPS SINCE LAST CUT

CUMULATIVE TON MI. OR TRIPS

TIME DISTRIBUTION – HOURS

CODE NO. – OPERATION	MORN.	DAY	EVE.
1. RIG UP AND TEAR DOWN			
2. DRILL ACTUAL			
3. REAMING			
4. CORING			
5. CONDITION MUD & CIRCULATE			
6. TRIPS			
7. LUBRICATE RIG			
8. REPAIR RIG			
9. CUT OFF DRILLING LINE			
10. DEVIATION SURVEY			
11. WIRE LINE LOGS			
12. RUN CASING & CEMENT			
13. WAIT ON CEMENT			
14. NIPPLE UP B.O.P.			
15. TEST B.O.P.			
16. DRILL STEM TEST			
17. PLUG BACK			
18. SQUEEZE CEMENT			
19. FISHING			
20. DIR. WORK			
21.			
22.			
23.			
COMPLETION A. PERF'R'T'N			
B. TBG TRIPS			
C. TREATING			
D. SWABBING			
E. TESTING			
F. ADDIT'N'L			
G.			
TOTALS			

DAY WORK TIME SUMMARY (OFFICE USE ONLY)

HRS. W/CONTR. D.P.			
HRS. W/OPR. D.P.			
HRS. WO/D.P.			
HRS. STANDBY			
TOTAL DAY WORK			

NO. OF DAYS FROM SPUD

CUMULATIVE ROTATING HRS.

TOTAL MUD COST

DRILLING ASSEMBLY (At end of tour) — MORNING TOUR

NO.			
BIT			FT.
STB RMR	OD		FT.
D.C. ID	OD		FT.
STB RMR	OD		FT.
D.C. ID	OD		FT.
STB RMR	OD		FT.
STANDS DP			FT.
SINGLES	DP		FT.
KELLY DOWN			FT.
TOTAL			FT.
WT. OF STRING			LBS.

BIT RECORD — MORNING TOUR

BIT NO.	
SIZE	
MFG.	
TYPE	
JETS 1/32"	
SER. NO.	
DEPTH OUT	
DEPTH IN	
TOTAL FTG.	
TOTAL HRS. RUN	
COND. 1/8's T/B/ GAGE	
GPM/ PD–PSI	

MUD RECORD — MORNING TOUR

TIME	
WEIGHT	
PRESSURE GRADIENT	
VISC.–SEC.	
PV/YP	
GELS.	
WL –CC'S.	
pH	
SOLIDS %	

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

FOOTAGE — MORNING TOUR

FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.–S PAR.EL–P COM.D–C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG — MORNING TOUR

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DRILLING ASSEMBLY (At end of tour) — DAY TOUR

NO.			
BIT			FT.
STB RMR	OD		FT.
D.C. ID	OD		FT.
STB RMR	OD		FT.
D.C. ID	OD		FT.
STB RMR	OD		FT.
STANDS DP			FT.
SINGLES	DP		FT.
KELLY DOWN			FT.
TOTAL			FT.
WT. OF STRING			LBS.

BIT RECORD — DAY TOUR

BIT NO.	
SIZE	
MFG.	
TYPE	
JET 1/32"	
SER. NO.	
DEPTH OUT	
DEPTH IN	
TOTAL FTG.	
TOTAL HRS. RUN	
COND. 1/8's T/B/ GAGE	
GPM/ PD–PSI	

MUD RECORD — DAY TOUR

TIME	
WEIGHT	
PRESSURE GRADIENT	
VISC.–SEC.	
PV/YP	
GELS.	
WL –CC'S.	
pH	
SOLIDS %	

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

FOOTAGE — DAY TOUR

FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.–S PAR.EL–P COM.D–C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG — DAY TOUR

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS

DRILLER

DRILLING ASSEMBLY (At end of tour) — EVENING TOUR

NO.			
BIT			FT.
STB RMR	OD		FT.
D.C. ID	OD		FT.
STB RMR	OD		FT.
D.C. ID	OD		FT.
STB RMR	OD		FT.
STANDS DP			FT.
SINGLES	DP		FT.
KELLY DOWN			FT.
TOTAL			FT.
WT. OF STRING			LBS.

BIT RECORD — EVENING TOUR

BIT NO.	
SIZE	
MFG.	
TYPE	
JETS 1/32"	
SER. NO.	
DEPTH OUT	
DEPTH IN	
TOTAL FTG.	
TOTAL HRS. RUN	
COND. 1/8's T/B/ GAGE	
GPM/ PD–PSI	

MUD RECORD — EVENING TOUR

TIME	
WEIGHT	
PRESSURE GRADIENT	
VISC.–SEC.	
PV/YP	
GELS.	
WL –CC'S.	
pH	
SOLIDS %	

MUD & CHEMICALS ADDED

TYPE	AMT.	TYPE	AMT.

FOOTAGE — EVENING TOUR

FROM	TO	DR.–D RM.–R CORE.–C	CORE NO.	FORMATION (SHOW CORE RECOVERY)	ROTARY RPM	WT. ON BIT 1000 #	PUMP PRESS	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	PUMP NO. LINER SIZE	PUMP NO. S.P.M.	METHOD RUN SGL.–S PAR.EL–P COM.D–C

DEVIATION RECORD

DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION	DEPTH	DEV.	DIRECTION

TIME LOG — EVENING TOUR

FROM	TO	ELAPSED TIME	CODE NO.	DETAILS OF OPERATIONS IN SEQUENCE AND REMARKS
400				SERV. RIG & EQUIP.
	1000			CLEAN TANKS RIGGED DOWN MAST & CPS EQUIP

DRILLER

DRILLING CREW PAYROLL DATA

No. 5479 3-5643

DATE WED. 8-25-76

WELL NAME & NO. ~~SESNON~~ SS #30

COMPANY So CALIF GAS CO

TOOL PUSHER J S Dutton RIG NO. D-3

MORNING TOUR ____ P.M. ____ A.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER			
DRKMAN			
MTRMAN			
FIREMAN			
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

DAY TOUR ____ A.M. ____ P.M.

CREW	SOC. SEC. NO.	NAME	HRS.
DRILLER			
DRKMAN			
MTRMAN			
FIREMAN			
FLRMAN			
FLRMAN			
FLRMAN			
TRAINEE			

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

EVENING TOUR 400 P.M. 10:00 P.M.

CREW	SOC. SEC. NO.	NAME	HRS.	
DRILLER	CONFIDENTIAL	D. EATON	6	2
DRKMAN		T. BRANDON	6	3
MTRMAN		J TOOPS	6	7
FIREMAN		P SELMER	6	7
FLRMAN				
FLRMAN				
FLRMAN				
TRAINEE				
		RIG	6	
		PUMP	Ø	
		CREW	6	

NO. OF DAYS ____ SINCE LAST LOST TIME ACCIDENT

Form 3T-5 Printed in U. S. A.

APPROVED APPROVED

IADC – API OFFICIAL DAILY DRILLING REPORT FORM

APPROVED APPROVED

AC_CPUC_0118033

FLO-LOG INC.

Company So Cal Gas Co
Type of Survey Temp-Noise Log
Date of Survey 11-17-87, 11-18-87
Lease, Well No. SS #29
Field ALISO CANYON

AC_CPUC_0118034

FLO-LOG

PRODUCTION LOGGING SURVEY DATA SHEET

COMPANY So Cal Gas Co DATE 11-18-87

WELL NO. SS #29 FIELD Aliso canyon

COUNTY L/A STATE Calif.

REPRESENTATIVE ~~Dave~~ Horstman SURVEY CREW Bailey, sturgess

TYPE OF SURVEY Modified Noise LOG

PURPOSE OF SURVEY Relog after plug set in NO-go (TBG)

CASING AND TUBING RECORD

SIZE	WEIGHT	FROM	TO
See	Data	sheet	
From	11-17-87		

Effective Depth 9077 PLug

Perforations

W.S.O. C.P.

Tubing Size 2 7/8 Depth 8049

Packer(s) 8040

Mandrel(s)

Measurement Datum ? See DATA

Reference Point

WELL STATUS gas storage S/I

Meter Rate — BWPD Oil Rate — b/d

Flow Loss — BWPD Oil Gravity — °

Obs. Rate — BWPD Gas Rate — Mcf/d

Reported Tbg Press. — psi Obs. 2180

Reported Csg Press. NO-GO psi Obs. 2180

Pickup 8038 ← DDA Fill —

Bottom Temp. N/A °F Fluid Level N/A

no temp RUN

SPINNER STATS

Depth	Counts	Rate	Depth	Counts	Rate

Reset Depth (from) 8048 (to) 8038

Depth Corrected to ~~top of~~ plug -18'

Logging Unit 711 Line Size 3/16 Line Length 10,000

Tools Used Head, SB, SB, SB, CCL temp, Noise Stab

Tool Numbers 4029

Tool Diameter 1 3/8

Time Arrived on Location 11:15 Off Location 12:45 Total Hours 1.5

Time of Run	Run No.	Type of Survey	Survey Calib.	Line Speed	Direction	Logged Interval (from)	(to)
11:35A	one	Noise Log	N	—	up	8038	6000
	Just	noise	Log		RW		

REMARKS: well HAD very High Amount of Noise thru Zone and up thru Entire well, plug was set in TBG and Relogged to check for Leak OR Just Zone activity

FLO-LOG INC.

NOISE LOG DATA SHEET

Page one

Company So Cal Gas Co Well No. 1SS #29

Date 11-18-87 Noise Tool Number 4079 Calibration N

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
11:35 AM	8030	62.5	34.9	27.9	2.7	MODIfied
	8020	42.3	28.0	18.8	2.9	Noise Log
	8000	20.9	18.1	16.2	2.4	
	80	19.0	16.60	15.50	2.10	20mV
	60	19.0	16.66	15.48	2.11	Ringing flowing Sound
	40	18.70	16.70	15.44	2.13	
	20	21.3	18.9	17.3	2.1	200 mV
	7900	23.7	20.2	18.0	2.0	
	*					
	7850	25.4	22.8	20.6	2.1	Log 1
	7800	26.0	23.4	20.5	2.1	
	7750	23.5	21.0	18.6	2.4	
	7700	22.8	19.4	17.8	2.0	
	7650	24.4	20.9	18.5	2.6	
	7600	22.7	18.7	16.0	2.5	
	*					100' STOPS 200 mV
	7500	18.6	14.5	12.1	2.1	
	7400	15.52	11.49	9.40	1.84	20 mV
	7300	12.72	7.97	5.66	1.98	
	7200	12.29	7.32	5.11	1.92	End of log # 1
11:55	*					
	8030	94.5	54.3	41.7	2.6	log # 2 Repeat 200mV
	8000	27.0	24.1	21.2	2.4	
	7950	27.1	24.6	22.1	2.2	
	7900	25.9	22.9	20.6	2.5	
	7850	26.5	24.7	22.9	2.4	
	7800	25.8	24.0	21.3	2.6	Log 2
	7750	26.8	24.6	22.5	2.1	
	7700	22.6	19.9	17.6	2.3	
	7650	20.9	18.5	16.7	2.1	
	7600	19.6	17.5	15.3	2.7	
	*					100' STOPS
11.59	7500	17.6	14.8	12.8	2.2	
	7400	14.6	11.9	10.1	2.2	
	7300	13.6	10.0	7.3	2.5	
	7200	9.57	6.96	5.43	1.85	20mV End of Repeat log #2

AC_CPUC_0118037

FLO-LOG INC.

NOISE LOG DATA SHEET

Company Southern Calif Gas Co. Well No. SS #29

Date 11-18-89 Noise Tool Number 4079 Calibration

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
12:05	7000	11.82	9.73	8.48	2.03	log #7 continued
	6800	8.95	7.14	6.14	2.09	
	6600	6.95	5.14	4.07	1.97	
	6400	6.65	5.87	5.32	1.92	
	6200	6.25	5.34	4.92	1.95	
12:12	6000	5.91	5.08	4.61	1.93	
						END OF Log

FLO-LOG

PRODUCTION LOGGING SURVEY DATA SHEET

COMPANY So CAL Gas Co DATE 11-17-87

WELL NO. SS #29 FIELD Aliso Canyon

COUNTY L/A STATE Calif.

REPRESENTATIVE Jim Mansdoerfer SURVEY CREW Bailey, Sturgess

TYPE OF SURVEY Temp & Noise Log

PURPOSE OF SURVEY Ck for shoe & WSO Leak

CASING AND TUBING RECORD

SIZE	WEIGHT	FROM	TO
7"	23-26	0	8180
5"	18	8075	9790

Effective Depth 9077 PLUG Cmt'd
Perforations 8456 - 8727

W.S.O. 8180 C.P. —

Tubing Size 2 7/8 Depth 8049
Packer(s) 8040
Mandrel(s) —

Measurement Datum KB 7'
Reference Point MAT

WELL STATUS Gas Storage (S/I)

Meter Rate — BWPD Oil Rate — b/d
Flow Lose — BWPD Oil Gravity — °
Obs. Rate — BWPD Gas Rate — Mcf/d
Reported Tbg Press. — psi Obs. 2180
Reported Csg Press. — psi Obs. 2160

Pickup 8994 Fill 83'
Bottom Temp. 191.0° °F Fluid Level 8540 ± Temp

SPINNER STATS

Depth	Counts	Rate	Depth	Counts	Rate

Reset Depth (from) 8107 (to) 8075
Depth Corrected to -32' to L.J.

Logging Unit 711 Line Size 3/16 Line Length 10,000
Tools Used Head, SB, SB, SB, ccl, temp, cap, Noise 4079
Tool Numbers
Tool Diameter 1 3/8

Time Arrived on Location 11:45A Off Location 3:45 Total Hours 4.0

Time of Run	Run No.	Type of Survey	Survey Calib.	Line Speed	Direction	Logged Interval (from)	(to)
12:00	one	temp/ccl	5"/inch	90	DN	200	9026
Repeat	TWO	Temp/ccl	5"/inch	80	DN	7800	9000
1:30 pm	three	Noise Log	normal	—	UP	9000	200'

REMARKS: possible Shoe Leak (700mv of noise)

REFERENCE DATUM		ELEVATION	
LOG MEASURED FROM	7' K.B.	CORRECTED TO	CASED TOP
DRILLING MEAS. FROM	K.B.	PERMANENT DATUM	GROUND
TOP OF LOGGED INTERVAL	8200'	BOTTOM LOGGED INTERVAL	8594'
TYPE OF FLUID IN HOLE	GAS	FLUID LEVEL	8340' TEMPERATIVE
LOG RECORDED BY	D. BAILEY	WITNESSED BY	JIM MARSHHEFER

TUBING AND TUBING RECORD				WELL STATUS	51 GAS STORAGE		
SIZE	WEIGHT	GRADE	DEPTH		Primary	Producing	Injection
11-3/4"	54.5#		1042'	Gas	1196		1196
7"	23.0#	H	8185'	Oil	2180		2180
4-1/2"	12.6#	BUTT	8073'	Water			
				Gas Lift			

CASING	2-7/8" TO 8045'	METHOD	CO	Starts	on
MILLING	NONE	Production Zone			
PERFORATING	NONE	Reservoir Temp.			
PERFORATING	8434- 8727' W [INTERVALS	BOTTOM TEMPERATURE	191°F		

CASING AND TUBING	711
GOOD HOLE	HEAD,CLUSIMED BARS,CCL,TEMP,CAPACITANCE,NOISE
TOOL NUMBERS	6379
Diameter 1.50"	5

RESULTS AND REMARKS: FIRST SURVEY ON 11-17-07 SHOWED NOISE ACTIVITY IN THE STORAGE ZONE.

THE SECOND SURVEY ON 11-18-07 WAS RUN AFTER SETTING A PLUG IN THE TUBING TAIL, EVEN THOUGH THERE I [illegible] NOISE ACTIVITY, THE NOISE FREQUENCY DOES NOT APPEAR TO BE ORIGINATING IN THE TOOL NOISE OR RESPONDING TO DISTANT ZONE ACTIVITY.

Sec. Twp. Rge.	36 - 32S - 23E	Other Services	
Permanent Datum	GROUND	Elev.	K.B. 7 ft.
Log Measured From	K.B. 7 ft. Above Perm. Datum		D.F. 6 ft.
Drilling Measured From	K.B.		G.L. 1 ft.

COUNTY Ellis STATE Kansas

WELL Standard #29 FIELD Dreiling

COMPANY Flo-Log, Inc.

TEMPERATURE AND NOISE LOG

RUN ONE FOR DATE AND NOISE

RECORDED BY DATE

WITNESSED BY

FLO-LOG

WELL NO. Standard #29

DATE 11-17-07
11-18-07

SECTION

TEMPERATURE

Log #1 (11-17-07)

Log #2 11-17-07 (11:04hrs)

Log 3 (11-18-07)

Log #4 (11-18-07)

AC_CPUC_0110040

PERMANENT DATUM	ELEVATION
LOG MEASURED FROM 7' B.F.	CORRECTED TO LOWER TOP
DRILLING MEASURED FROM KB	PERMANENT DATUM STORAGE
TOP OF LOGGED INTERVAL 6000	BOTTOM LOGGED INTERVAL 8994
TYPE OF FLUID IN HOLE GAS	FLUID LEVEL
LOG RECORDED BY BAILEY	WITNESSED BY JIM MACKOSKEE

RUN NO.	ONE	
DATE	11-17-87	
TYPE LOG	TEMP	
DEPTH-DRILLER	8994'	
DEPTH-LOGGER	8993'	
BTM. LOG INTERVAL	8990'	
TOP LOG INTERVAL	6000'	
CASING-DRILLER	7" @ 6045'	
CASING-LOGGER	6045'	
BIT SIZE	6"	
TYPE FLUID IN HOLE	GAS	
DENS. / VISC.		
PH / FLUID LOSS		
SOURCE OF SAMPLE		
RM @ MEAS. TEMP.		
RMF @ MEAS. TEMP.		
RMC @ MEAS. TEMP.		
SOURCE OF RMF / RMC		
RM @ BHT		
TIME SINCE CIRC.		
MAX. REC. TEMP.		
EQUIP. LOCATION		
RECORDED BY		
WITNESSED BY		

RUN NO.	ONE
DATE	11-17-87
TYPE LOG	TEMP
DEPTH-DRILLER	8994'
DEPTH-LOGGER	8993'
BTM. LOG INTERVAL	8990'
TOP LOG INTERVAL	6000'
CASING-DRILLER	7" @ 6045'
CASING-LOGGER	6045'
BIT SIZE	6"
TYPE FLUID IN HOLE	GAS
DENS. / VISC.	
PH / FLUID LOSS	
SOURCE OF SAMPLE	
RM @ MEAS. TEMP.	
RMF @ MEAS. TEMP.	
RMC @ MEAS. TEMP.	
SOURCE OF RMF / RMC	
RM @ BHT	
TIME SINCE CIRC.	
MAX. REC. TEMP.	
EQUIP. LOCATION	
RECORDED BY	
WITNESSED BY	

RUN NO.	
DATE	
TYPE LOG	
DEPTH-DRILLER	
DEPTH-LOGGER	
BTM. LOG INTERVAL	
TOP LOG INTERVAL	
CASING-DRILLER	
CASING-LOGGER	
BIT SIZE	
TYPE FLUID IN HOLE

PERMANENT DATUM	ELEVATION
LOG MEASURED FROM 3' G.L.	GROUND ELEV. 13606 TOP
DRILLING MEASURED FROM KB	TOTAL DEPTH (DRILLER) 8793'
TYPE OF LOGGING UNIT(S) USED	BOTTOM LOGGED INTERVAL 8793'
TYPE OF FLUID IN HOLE GAS	PLUG BACK INTERVAL 8758 MANOMETER
GAS MEASURED BY X - BASIN	DATE(S) RUN 11-17-97

CASING AND TUBING RECORD			
SIZE	WEIGHT	GRADE	DEPTH
9 5/8"	36#	J55	2100
4 1/2"	10.5#	K55	8793
2 7/8"	6.5#	J55	7100

TUBING RECORD			
SIZE	WEIGHT	GRADE	DEPTH
2-7/8"	6.5#	J55	8656

PACKER RECORD			
MANUFACTURER	MODEL	SIZE	DEPTH
BAKER		5.75	8656

BOTTOM HOLE TEMPERATURE	191°F
SPECIAL EQUIPMENT AND SERVICES	
LOGGING UNIT NO.	711
RECORDED BY	HEAD,CLINKER HARD,CCL,TEMP,CAPACITANCE,NOISE
WITNESSED BY	MIKE

MAXIMUM RECORDED TEMPERATURE	191°F @ INTERVALS
LOGGING UNIT NO.	711
RECORDED BY	HEAD,CLINKER HARD,CCL,TEMP,CAPACITANCE,NOISE
WITNESSED BY	MIKE

RESULTS AND REMARKS: FIRST SURVEY ON 11-17-97 SHOWED MUCH ACTIVITY IN THE STORAGE ZONE.

THE SECOND SURVEY ON 11-18-97 WAS RUN AFTER SETTING A PLUG IN THE TUBING TAIL. EVEN THOUGH THERE IS TOTAL ZONAL ISOLATION, THE TEMPERATURE SHOWS NO INITIAL CHANGE IN ACTIVITY. HENCE, THE TOOL MUST BE RESPONDING TO DISTANT ZONE ACTIVITY.

COMPANY	FLO-LOG INC.
WELL	Standard #29
FIELD	Basin Dakota
COUNTY	San Juan
STATE	New Mexico
LOCATION	Sec. 29, T32N, R10W
OTHER SERVICES	
PERMANENT DATUM	
ELEV.	K.B.
LOG MEASURED FROM	K.B.
DRILLING MEASURED FROM	K.B.
DATE	11-17-97, 11-18-97
RUN NO.	ONE
DEPTH-DRILLER	8793
DEPTH-LOGGER	8793
BTM. LOG INTERVAL	8758
TOP LOG INTERVAL	0
CASING-DRILLER	9 5/8" @ 2100
CASING-LOGGER	2100
BIT SIZE	7 7/8"
TYPE FLUID IN HOLE	GAS
DENS. / VISC.	
PH / FLUID LOSS	
SOURCE OF SAMPLE	
RM @ MEAS. TEMP.	
RMF @ MEAS. TEMP.	
RMC @ MEAS. TEMP.	
SOURCE RMF / RMC	
RM @ BHT	
TIME SINCE CIRC.	
MAX. REC. TEMP.	191°F
EQUIP. NO. & LOCATION	711
RECORDED BY	HEAD,CLINKER HARD,CCL,TEMP,CAPACITANCE,NOISE
WITNESSED BY	MIKE

TEMPERATURE AND NOISE LOG

To Accompany Sundry Notice Dated 12-2-97

Re: Packer Leakage Test

FLO-LOG INC.

WELL NO. Standard #29 DATE 11-17-97 11-18-97

SECTION

TEMPERATURE

80° 85° 90° 95° 100° 105° 110°

2-7/8" 6.5# J55 TUBING

LOG #1 (11-17-97)

10.0mv 100.0mv

CBP PRESENT

PLUG SET @ 8758'

155°

150°

LOG #2 11-18-97 (10.0mv) (100.0mv)

PLUG LOCATED @ 8758'

LOG 2 (11-18-97) 10.0mv 100.0mv

LOG #1 (11-17-97) 10.0mv 100.0mv

AC_CPUC_0110042

FLO-LOG INC.

NOISE LOG DATA SHEET

Page ONE

Company So Cal Gas Co Well No. SS #29

Date 11-17-87 Noise Tool Number _____ Calibration Normal

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
	8900	2.13	2.03	1.99	1.87	50' STOPS 20mV
	50	2.21	2.13	2.05	1.90	
	8800	2.17	2.05	2.02	1.90	
	50	2.42	2.16	2.09	1.91	
	8700	28.9	13.1	7.5	3.5	200 mV Sounds like gas Flo
	50	39.3	24.9	11.6	7.1	
	8600	524	397	253	47	2V
	50	685	419	297	72	
	8500	678	436	296	80	
	50	582	493	347	55	
13:35	8400	500	427	325	53	(log 1)
	50	501	431	310	59	
	8300	481	445	324	66	
	50	432	369	276	39	
	8200	427	351	272	39	possible shoe leak
	50	391	314	243	31	
	8100	416	361	263	38	2 Volts
	50	299	232	194	20	
	8000	486	403	295	25	
	50	165	139	117	13	
	7900	180	163	140	11	
	50	178	171	150	9	
	*					100' STOP
	7800	187	168	141	7	
	*					
	7500	157	136	97	3	
1:00p	8900	2.42	2.14	2.05	1.91	20 mV
	50	2.56	2.30	2.18	1.98	Log 2
	8600	2.25	2.19	2.08	1.97	
	50	2.66	2.14	2.05	1.92	Repeat
	8700	16.62	7.17	4.64	2.46	
	50	26.7	18.6	6.3	2.1	
	8600	560	293	272	44	2V
	50	696	416	297	73	
	8500	773	484	325	101	log 2 continued Page 2

AC_CPUC_0118043

FLO-LOG INC.

NOISE LOG DATA SHEET

Page 9

Company So Cal Gas Co Well No. SS #29

Date 11-17-87 Noise Tool Number _____ Calibration _____

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
2:03 pm	8250	585	506	361	66	2U 50' STOPS
	8200	565	492	345	59	Repeat log #2
	50	509	435	309	55	Continued
	8300	489	421	313	47	
	50	472	402	292	45	
	8200	2164	401	298	39	
	50	437	378	276	36	
	8100	463	395	285	35	
	50	322	270	196	23	2U 50' STOPS
	8000	530	439	312	33	
	50	184	169	139	16	
	7900	192	180	150	13	
	56	197	181	150	11	
	7866	218	203	165	13	
	*					
2:15 pm	7500	167	149	102	7	End of Repeat
	*					
	7400	161.4	142.7	92.4	3.3	
	7200	129.6	104.9	62.8	2.9	Log # 1 continued
	7000	124.4	103.7	55.8	2.8	200' STOPS 200mV
	6800	93.7	77.6	56.4	3.5	
	6600	84.8	69.1	46.8	2.6	
	6400	71.00	55.7	36.5	3.0	
	6200	53.8	41.5	25.3	2.5	Log 1 Cont
	6000	46.3	36.9	25.6	2.9	
	5800	38.9	31.7	24.5	2.3	
	5600	31.5	25.7	20.5	2.1	
	5400	28.2	22.5	16.7	2.1	
	5200	25.3	19.6	14.1	2.1	
	5000	22.1	17.0	12.0	2.1	
	*					500' STOPS
	4500	11.69	8.81	6.35	1.74	20mV
	4000	10.13	7.82	5.35	1.88	
	3500	7.83	5.35	3.56	1.99	
	3000	6.92	4.67	3.41	2.22	
	2500	7.86	3.75	2.45	1.91	

FLO-LOG INC.


NOISE LOG DATA SHEET

Page THREE


Company So Cal Gas Co Well No. SS #29

Date 11-17-87 Noise Tool Number _____ Calibration _____

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
2:59	2000	4.78	2.89	2.21	1.87	20 mV 500' STOPS
	1500	8.75	6.32	4.33	2.23	
	1000	8.65	4.82	3.24	2.00	
	500	6.22	3.60	2.77	2.06	
	X					
	200	13.65	8.13	5.99	2.01	



AC_CPUC_0118046



No. BN 6277
PRINTED IN U.S.A.


AC_CPUC_0118047

[redacted]

Standard Sesnon 29 Aliso Cyn.
Well Log File

AC_CPUC_0118048

PRESSURE LOG



0600

0700

FINAL HYDROSTATIC
3754.2 #

SHUT IN
#

1 HOUR

Form J-228a

AC_CPUC_0118050

SCHLUMBERGER WELL SURVEYING CORPORATION

Electrical Log

COMPANY TIDE WATER ASSOC. OIL COMPANY

WELL STATE OF CALIFORNIA NO. 1

FIELD ALISO CANYON

LOCATION FT. FROM

COUNTY LOS ANGELES STATE CALIFORNIA

Location of Well

Sec. 16 T. 2 S. R. 15 W. S.B.B.&M.

Elevations: K.B. 1,000 ft. D.F. G.L.

Permanent Datum: Sea Level

Log Measured from: K.B. 10 ft. above Perm. Datum

Drilling Measured from: Rotary Table

Run No. | 1 | 2 | 3 | 4 | 5

Date | 8-23-52 | 9-2-52 | 9-2-52 | 9-2-52 | 9-17-52

Depth—Driller | 5,000 | 5,000 | 5,000 | 5,000 | 5,000

Depth—Logger | 5,000 | 5,000 | 5,000 | 5,000 | 5,000

Bottom Logged Interval | 5,000 | 5,000 | 5,000 | 5,000 | 5,000

Top Logged Interval | 5,000 | 5,000 | 5,000 | 5,000 | 5,000

Type Fluid in Hole | Gel-Base | Gel-Base | Gel-Base | Gel-Base | Gel-Base

Salinity, P.P.M. Cl | 1,000 | 1,000 | 1,000 | 1,000 | 1,000

Density | 9.4 | 9.4 | 9.4 | 9.4 | 9.4

Level | Full | Full | Full | Full | Full

Max. Rec. Temp. Deg. F. | 120 | 120 | 120 | 120 | 120

Operating Time | 12 | 12 | 12 | 12 | 12

Recorded By | Wagner | Wagner | Wagner | Wagner | Wagner

Witnessed By | Mr. Hall | Mr. Hall | Mr. Hall | Mr. Hall | Mr. Hall

Run No. | 1 | 2

Date | 9-17-52 | 9-17-52

Depth—Driller | 5,000 | 5,000

Depth—Logger | 5,000 | 5,000

Bottom Logged Interval | 5,000 | 5,000

Top Logged Interval | 4,000 | 4,000

Type Fluid in Hole | Gel-Base | Gel-Base

Salinity, P.P.M. Cl | 1,000 | 1,000

Density | 9.4 | 9.4


Level | Full | Full


Max. Rec. Temp. Deg. F. | 120 | 120

Operating Time | 12 | 12


Recorded By | Wagner | Wagner

Witnessed By | Mr. Hall | Mr. Hall



RESISTIVITY
ohms m²/m
SPONTANEOUS POTENTIAL
millivolts



AC_CPUC_0118053



AC_CPUC_0118055


7400
7500
7600
7700
7800
7900
8000
8100
8200
8300
8400
8500
8600
8700
8800
8900
9000
9100
125
145
TEMPERATURE
SCALE CHANGE
145
165
145
125
TEMPERATURE
SCALE CHANGE
165
145
125
145
TEMPERATURE
SCALE CHANGE
145
165
145
165
TEMPERATURE
SCALE CHANGE
165
185
3.500" DIA
5.000" DIA
32'
PICK-UP

PERMANENT DATUM	7' K.B.	ELEVATION	2849'
LOG MEASURED FROM	7' AGL.	CORRECTED TO	LINER TOP
TOTAL DEPTH	9077' PBTD	OBSERVED DEPTH (Pickup)	8998
TOP OF LOGGED INTERVAL	7800	BOTTOM LOGGED INTERVAL	8998
TYPE OF FLUID IN HOLE	GAS	FLUID LEVEL	NONE
LOG RECORDED BY	FINDLAY	WITNESSED BY	R. ADAMCZYK

CASING AND TUBING RECORD

Size	Weight	From	To
11-3/4	42 &47	0	1042
7	23 &26	0	8180
5	18	8075	9790
TUBING	2-7/8" TO 8040		
PACKER(S)	8040		
MANDREL(S)	8002		
PERFORATIONS	8456-8694		

WELL STATUS: CASING FLOW

	Pressure	Producing	Injecting	Shut-in
TBG		2410		2450
CSG				

INJ. RATE: TYPE
OBS. RATE

METERED PRODUCTION RATES			*API
	Oil	Gravity:	
	Water		
	Gas	15MMcf/d	
BOTTOM TEMPERATURE		188.4°	

LOGGING UNIT	711	LINE SIZE 3/16"	LINE LENGTH
TOOLS USED	4-5' BARS.CAPACITANCE.COLLAR LOCATOR.TEMPERATURE.SPINNER		
TOOL NUMBERS			
DIAMETER 1-3/8"			

RESULTS AND REMARKS: OBSERVED THE MAJOR SOURCE OF GAS TO ENTER BETWEEN 8456 (TOP PERF) AND 8465'. THERE MUST BE ANOTHER SMALL ENTRY AROUND 8685' SINCE THERE IS A COOLING ON THE TEMPERATURE THERE.

THE HEATING ON THE TEMPERATURE BELOW 8727 SUGGESTS LITTLE OR NO GAS HAS BEEN MOVING DOWN THERE. HOWEVER, THE CAPACITANCE SHOWS NO LIQUIDS AT THE BOTTOM OF THE WELL. ONLY GAS. SINCE ONE NORMALLY EJECTS TO FIND SOME LIQUIDS AT BOTTOM. PERHAPS THE LIQUIES WERE LIIFTED OR PUSHED AWAY BY A SMALL AMOUNT OF GAS.


FIELD INVENTORY WAS 44.092 BCF DURING THE SURVEY.

COMPANY: SOUTHERN CALIFORNIA GAS
WELL NO.: STANDARD SESNON 29
FIELD: ALISO CANYON
COUNTY: LOS ANGELES STATE: CA
DATE: 7-25-90

FLO-LOG INC.

FLUID ENTRY SURVEY

PURPOSE OF SURVEY: FIND SOURCE OF GAS



AC_CPUC_0118058

FLO-LOG INC.

NOISE AND TEMPERATURE SURVEY

COMPANY SOUTHERN CAL. GAS OFFICE BLDG CANYON | WELL NAME & NO. STANDARD SCIMON #29

SURVEY DATA

DATE OF SURVEY	10-21-91 / 10-17-91
RUN NUMBER	ONE
FIRST READING	SURFACE WATER
FLUID TYPE	WATER
FLUID LEVEL	9563'
MEASURED FROM	GROUND LEVEL
LOGGING DEPTH (DRLR)	9800'
LOGGING DEPTH (WLM)	9800'
CASING RECORDED BY	ALL CASINGS
LOG RECORDED BY	Mr. BRAND
WITNESSED BY	MR. CHUCK JOHN FOR SOUTHERN CALIFORNIA GAS CO.
REMARKS	FIELD INVENTORY WAS AS NOTED.

WELLBORE DATA

CASING RECORD	SIZE	WEIGHT	FROM	TO
1ST STRING	11 3/4"	42 & 47#	0'	1042'
2ND STRING	7"	23 & 26#	0'	8782'
PLUG BACK TD	7"	26#	8782'	9780'

OPEN HOLE	DRILLBIT TO	9780'	
CASING RECORD	FROM	TO	
1ST STRING	0'	1042'	
2ND STRING	0'	8782'	
PRODUCTION	8782'	9779'	SLOTTED

PRESSURE: 2300 PSIG

8782'

@ 2100' 9563'

CASING SHOE

CASING JNT	112
LENGTH OF TOOL	3.5'
DIAMETER OF TOOL	1 1/2"

LINE SIZE 3/16" | LINE LENGTH 24,600' | TOOL NO. 4954

MEASUREMENT BEFORE DEPTH REFERENCE

LINER TOP

TEMPERATURE

75°	80°	85°	90°	95°	100°	105°

FREQUENCY RESPONSE (AMPLIFICATION) 2000 HERTZ | 1000 HERTZ | 600 HERTZ | 200 HERTZ (LO FREQUENCY)

VOLTS

9800'

9563'

(REPEAT #1)

(REPEAT #2)

FLUID LEVEL 9563'

(LOGGED ON 10-21-1991

PRESSURES: CASING: 1600 psig TUBING: 2100 psig

REPEAT #1

NEAR GAS FLOW

NEAR LOOSE GAS SOUND

(REPEAT #2 AT EXPANDED SCALE OF 1"=20')

(LOGGED ON 10-18-1991 DRIVEN BY MOORE

PRESSURES: CASING: 2150 psig TUBING: 2100 psig


REPEAT #1 (@ 10-17-91)

(LOGGED ON 10-17-1991 DRIVEN BY MOORE

PRESSURE: CASING: 1750 psig TUBING: 2500 psig

(REPEAT #1 (@ 10-17-91)

AC_CPUC_119801


9400
9600
5" 18#
90
9800

PRODUCTION LOGGING SERVICES, INC.

TEMPERATURE & NOISE LOG
STANDARD SESNON 29

COMPANY SOUTHERN CALIFORNIA GAS COMPANY
WELL S.S. 29 FIELD ALISO CANYON
COUNTY L.A. STATE CA

Type Log							
Depth - Driller	9094						
Depth - Logger	9094						
Bottom Logged Interval	9090						
Top Logged Interval	9000						
Casing - Logger	5"						
Bit Size	4"						
Type Fluid in Hole	SALT WATER						
Density / Viscosity							
Max. Rec. Temp. Deg. F.							
Estimated Temp.							
Operating Rig Time							
Recorded By	LARRY CLIFF						
Witnessed By							

DRILL DATA

Run No.	Bore-Hole Record		Casing Record		
	Size	To	Size	Wgt.	To
1	4"	9094	5"	15	9090
2	4"	9094	5"	15	9090
3	4"	9094	5"	15	9090

Type Log			
Depth - Driller	9094		
Depth - Logger	9094		
Bottom Logged Interval	9090		
Top Logged Interval	9000		
Casing - Logger	5"		
Bit Size	4"		
Type Fluid in Hole	SALT WATER		
Density / Viscosity			
Max. Rec. Temp. Deg. F.			
Estimated Temp.			
Operating Rig Time			
Recorded By	LARRY CLIFF		
Witnessed By			

Run No.	Bore-Hole Record		Casing Record		
	Size	To	Size	Wgt.	To
1	4"	9094	5"	15	9090
2	4"	9094	5"	15	9090
3	4"	9094	5"	15	9090

DRILL DATA

Run No.	Bore-Hole Record		Casing Record		
	Size	To	Size	Wgt.	To
1	4"	9094	5"	15	9090
2	4"	9094	5"	15	9090
3	4"	9094	5"	15	9090

Type Log
Depth - Driller 9094
Depth - Logger 9094
Bottom Logged Interval 9090
Top Logged Interval 9000
Casing - Logger 5"
Bit Size 4"
Type Fluid in Hole SALT WATER
Density / Viscosity
Max. Rec. Temp. Deg. F.
Estimated Temp.
Operating Rig Time
Recorded By LARRY CLIFF
Witnessed By

FLO-LOG INC.

NOISE AND TEMPERATURE SURVEY

COMPANY So. Cal. Gas Co. FIELD Aliso Canyon WELL NAME & NO. Standard Sesnon #29

SURVEY DATA

DATE OF SURVEY	8-30-90
WELL STATUS	GAS STORAGE
TYPE OF FLUID	OIL & WATER
FLUID RATE (B)	SHUTIN
EFFECTIVE DEPTH	9027' PBTD
LOGGERTS DEPTH (PICKUP)	8992'
AMOUNT OF FILL	85'
LOG WITNESSED BY:	R. MCDONALD
LOG RECORDED BY	J. RISER
REASON FOR SURVEY	CHECK SHOE AND CHECK TEMPERATURE ANOMALIES @ 8000'

RESULTS AND REMARKS:

SUBSURFACE SAFETY VALVE IS OPEN.
FIELD VOLUME IS 46.524 MCF.

WELLBORE DATA

CASING AND TUBING RECORD

	SIZE	WEIGHT	FROM	TO	PRESSURE	FLUID LEVEL
	11-3/4"	42 & 47#	0'	1042'		
	7	23 & 26	0	8180	2500 PSI	
	5	18	8072	9790		NONE OBS.
	2-7/8"	TUBING	0	8049	2500 PSI	

PACKER (S) 8040 MANDREL (S)

PERFORATIONS 8456-8694' @ INTERVALS 8727-9077-9027' SLOTTED

LOGGING UNIT 711 LINE SIZE 3/16" LINE LENGTH 23900' NOISE TOOL NO. 4030

DIAGRAM OF TOOLS USED:

DIAMETER OF TOOLS 1-3/8"

3-60° SINKER BARS, COLLAR LOCATOR, TEMPERATURE,NOISE

MEASUREMENT DATUM 7' K.B.
DEPTH REFERENCE LINER TOP


TEMPERATURE

70° 75° 80° 85° 90° 95° 100°

FREQUENCY RESPONCE (HI FREQUENCY) 2000 HERTZ 1000 HERTZ 600 HERTZ 200 HERTZ (LO FREQUENCY)

MILLIVOLTS

2 3 4 5 7 10 2 3 4 5 7 10 20 30 40 50 70 100 200 300 400 500 700 1000



AC_CPUC_0118062

FLO-LOG INC.

NOISE AND TEMPERATURE SURVEY

COMPANY SOUTHERN CAL. GAS FIELD ALISO CANYON WELL NAME & NO. STANDARD SESNON #29

SURVEY DATA

DATE OF SURVEY	8-8-90
WELL STATUS	GAS STORAGE SHUT-IN
TYPE OF FLUID	OIL & WATER & GAS
FLUID RATE (B)	NONE
EFFECTIVE DEPTH	9094 PBTD
LOGGER'S DEPTH (PICKUP)	8993
AMOUNT OF FILL	101
LOG WITNESSED BY	
LOG RECORDED BY	J. RISER
REASON FOR SURVEY	CHECK FOR CASING SHOE I.E.R.

RESULTS AND REMARKS:

WELLBORE DATA

CASING AND TUBING RECORD

	SIZE	WEIGHT	FROM	TO	PRESSURE	FLUID LEVEL
	11-3/4"	42 & 47#	0	1042	2482	
	7	23 & 26	0	8180		
	5	18	8075	9790		
	2-7/8	TUBING	0	8049	2450PSI	

PACKER (S) 8040 MANDREL (S) NONE

PERFORATIONS 8456-8694 & INTERVALS 8727-9077 SLOTTED

LOGGING UNIT 711 LINE SIZE 3/16" LINE LENGTH 23,950' NOISE TOOL NO. 2107

DIAGRAM OF TOOLS USED:

DIAMETER OF TOOLS 1-3/8"

3-60° BARS, CAPACITANCE, COLLAR LOCATOR, TEMPERATURE, NOISE

MEASUREMENT DATUM
7' DF
DEPTH REFERENCE
TUBING TAIL


TEMPERATURE

75° 80° 85° 90° 95° 100° 105°

FREQUENCY RESPONCE: (HI FREQUENCY) 2000 HERTZ 1000 HERTZ 600 HERTZ 200 HERTZ (LO FREQUENCY)

MILLIVOLTS

2-7/8"



AC_CPUC_0118063

PERMANENT DATUM	7 EB
LOG MEASURED FROM	7 AGL
TOTAL DEPTH	9077
TOP OF LOGGED INTERVAL	100
TYPE OF FLUID IN HOLE	WATER
LOG RECORDED BY	HELMS

ELEVATION	
CORRECTED TO	LINER TOP
OBSERVED DEPTH (Finish)	9011
BOTTOM LOGGED INTERVAL	9011
FLUID LEVEL	8881
WITNESSED BY	ROBINSON

CASING AND TUBING RECORD

Size	Weight	From	To
11 3/4	42 & 47	0	1042
7	23 & 26	0	8180
5	18	8073	9190

TUBING	2-7/8" TO 8049
PACKERS	8040
BAKER/MLBS	SSSV @ 8002
PERFORATIONS	8436-9077 AT INTERVALS

LOGGING UNIT	712
TOOLS USED	2-5" TUNGSTEN BARS, CAPACITANCE,CCL,TEMP.,NOISE
TOOL NUMBERS	
DIAMETER	1-3/8"

WELL STATUS: SHUTIN GAS STORAGE

	Producing	Injecting	Shut-in
TBG PRESS.			2100
CSG PRESS.			2100
INJ. RATE		TYPE	
OBS. RATE			
METERED PRODUCTION RATES	Oil	Gravity	°API
	Water		
	Gas		

BOTTOM TEMPERATURE 191.2°

LINE SIZE 3/16" LINE LENGTH 22,000

RESULTS AND REMARKS:

COMPANY SOUTHERN CALIFORNIA GAS
WELL NO. SS STORAGE #29
FIELD
COUNTY Los Angeles STATE CA
DATE 10-20-89

FLO-LOG INC.
TEMPERATURE & NOISE

PURPOSE OF SURVEY
CHECK FOR POSSIBL GAS MIGRATION UP PAST SHOE

10.0 MILLIVOLTS
1.0 2 3 4 5 6 7 8 9

2-7/8"
11-3/4" @ 1042
7" @ 8180
5" @ 9190

70° 100° 100 200°

100°
130°
140°
150°
160°
170°
180°
190°

8002
8073
8180
8436
8440
8456
9190
9190'

2-1 8350'
2-4 8440'

NO
100 MV
100 MV

RERUN AFTER SEALING ALL SURFACE VALVES

PERMANENT DATUM	7,840
TOTAL DEPTH	9200
DEPTH DRILLER	9200
TYPE OF FLUID IN HOLE	GEL
LOG RECORDED BY	J. BAILEY

ELEVATION	
CORRECTED TO	1,910' TOF
PERMANENT DATUM (Formation)	7,840
MEASURED FROM (Elevation)	9200
ELEV. LEVEL	9,540' TEMPERATURE
RECORDED BY	JIM MAGGINETTE

DATE	11/17/87, 11/18/87
RUN NO.	ONE
TYPE LOG	RADIAL CALIPER, TEMP.
DEPTH-DRILLER	9200
DEPTH-LOGGER	9200
BTM. LOG INTERVAL	9200
TOP LOG INTERVAL	SURFACE
CASING-DRILLER	13 3/8" @ 1,910'
CASING-LOGGER	1,910'
BIT SIZE	12 1/4"
TYPE FLUID IN HOLE	GEL
DENS. VISC.	9.2 LBS/GAL 40 SEC
PH	10.5
FLUID LOSS	6 CC
SOURCE OF SAMPLE	CIRCULATED
RM @ MEAS. TEMP.	.2 @ 150
RMF @ MEAS. TEMP.	.2 @ 150
RMC @ MEAS. TEMP.	.2100
SOURCE RMF	RMC
RM @ BHT	
TIME SINCE CIRC.	24 HRS.
MAX. REC. TEMP.	150
EQUIP. LOCATION	91 GAS STORAGE
RECORDED BY	J. BAILEY
WITNESSED BY	

CASING RECORD	SIZE / WGT. / GRADE / FROM / TO
	13 3/8" / 54.5# / K-55 / SURFACE / 1910'
	9 5/8" / 47# / S-95 / 1910' / 9700'
	5" / 18# / S-95 / 9700' / 9200'
TUBING RECORD	2 7/8" EU 8RD&" / 9000'
PACKER SET AT	NONE
BRADENHEAD	NONE
PERFORATING	8656- 8727' @ INTERVALS

LOGGING UNIT	314
TRUCK NBR.	
REMARKS	
Scale Int. 1:50"	

LOGGING DISTRICT	NOB
LOGGING ENGINEER	
WITNESS	

RESULTS AND REMARKS: FIRST SURVEY ON 11-17-87 SHOWED MUCH ACTIVITY IN THE 8656-8727' PERFORATED INTERVAL.

THE SECOND SURVEY ON 11-18-87 WAS RUN AFTER SETTING A PLUG IN NO VISAN SLIP. HIGH TEMPS FROM 11-17-87 STILL SOME RESIDUAL HEATH. THE HIGH FREQUENCY DOES SHOW NO LOCAL ACTIVITY. HENCE, THE COOL MUDD IS RESPONDING TO DISTANT ZONE ACTIVITY.

Sec. Twp. Rge. Qtr.
Acctg. Code
Permit No.
Field
County
State
Location
Other Services
Date
Run No.
Type Log
Depth-Driller
Depth-Logger
Bottom Log Interval
Top Log Interval
Casing-Driller
Casing-Logger
Bit Size
Type Fluid in Hole
Dens. Visc.
pH
Fluid Loss
Source of Sample
Rm @ Meas. Temp.
Rmf @ Meas. Temp.
Rmc @ Meas. Temp.
Source Rmf
Rm @ BHT
Time Since Circ.
Max. Rec. Temp.
Equip. Location
Recorded By
Witnessed By

FLO-LOG INC.
TEMPERATURE AND RADIAL CALIPER
Acctg. Code
Permit No.
Field
County
State
Location
Other Services
Date
Run No.
Type Log
Depth-Driller
Depth-Logger
Bottom Log Interval
Top Log Interval
Casing-Driller
Casing-Logger
Bit Size
Type Fluid in Hole
Dens. Visc.
pH
Fluid Loss
Source of Sample
Rm @ Meas. Temp.
Rmf @ Meas. Temp.
Rmc @ Meas. Temp.
Source Rmf
Rm @ BHT
Time Since Circ.
Max. Rec. Temp.
Equip. Location
Recorded By
Witnessed By

FLO-LOG INC.
TEMPERATURE AND RADIAL CALIPER
Acctg. Code
Permit No.
Field
County
State
Location
Other Services
Date
Run No.
Type Log
Depth-Driller
Depth-Logger
Bottom Log Interval
Top Log Interval
Casing-Driller
Casing-Logger
Bit Size
Type Fluid in Hole
Dens. Visc.
pH
Fluid Loss
Source of Sample
Rm @ Meas. Temp.
Rmf @ Meas. Temp.
Rmc @ Meas. Temp.
Source Rmf
Rm @ BHT
Time Since Circ.
Max. Rec. Temp.
Equip. Location
Recorded By
Witnessed By

FLO-LOG INC.
TEMPERATURE AND RADIAL CALIPER

FLO-LOG

WELL NO. Standard #25
Seimon

DATE 11-17-87
11-18-87

TEMPERATURE

85° 90° 95° 100° 105° 110°

200'
400
600
800
1000
1200
1400
1600
1800
2000
2200
2400
2600
2800
3000
3200
3400
3600
3800
4000
4200
4400
4600
4800
5000
5200
5400
5600
5800
6000
6200
6400
6600
6800
7000
7200
7400
7600
7800
8000
8200
8400
8600
8800
9000
9200

3-7/8"

7 5/8" @ 6,200'

9 5/8" @ 9,700'

5" @ 9,200'

SURVEY #1 (11-17-87)

10.0mv

100.0mv

HIGH FREQUENCY

SURVEY #2 11-17-87)
(10.0mv)
(100.0mv)

SURVEY #2 (11-18-87)

10.0mv

100.0mv

SURVEY #1 (11-18-87)

10.0mv

100.0mv

AC_CPUC_0118065

TRIANGLE SERVICE, INC.

AUDIO ANALYZER SURVEY

COMPANY SOUTHERN CALIFORNIA GAS COMPANY

WELL STANDERD 29 FIELD ALISO CANYON

COUNTY L.A. STATE CALIFORNIA

OTHER SERVICES:

ELEVATIONS:
KB.
DF.
GL.

WELL DATA

		Casing and Tubing Record			
Date	10-3-1980				
Run No.		Size	Wgt.	From	To
Type Log	A/A	7"		0	8180'
Depth — Drill		5"		8075'	8727'
Depth — Log (Pick up)					
Bottom Logged Interval	8600'				
Top Logged Interval	500'				
Type Hole Fluid	Gas	Packer @			
Fluid Level		Tbg. Tail to			
Max. Rec. Temp. °F.		Perforations			
Recorded By	Clark-Gilson-Sawyer				
Witnessed By	Bob Hazel	Measurement Reference			


EQUIPMENT and TEST DATA

Run No.		Truck No.	1650
Well Status	Shut in	Tool No.	114
Production — Oil, b/d	0	Tool Size	3/16"
Water, b/d	0		
Gas, mcf	0		
Injection Rate	0		
Pressure — TBG. psi	2900 PSI		
CSG. psi	0		
Log Speed — fpm			
Temp. Sens. °F./inch		R/A Sens.	
Diff. Sens.		R/A Spacing	
T.C.			


SURVEY RESULTS: A/A indicates no gas movement

REMARKS:

Form 128



AC_CPUC_0118066




GR Calibration
After Log

API UNITS OF CALIB. STD	224
SENSITIVITY READING	200
MULTIPLIER	X1
ZERO SUPPRESSION	0
TIME CONSTANT	3.0
MEASURED CHART DIVISIONS	6.0

GR Calibration
Before Log

API UNITS OF CALIB. STD	224
SENSITIVITY READING	200
MULTIPLIER	X1
ZERO SUPPRESSION	0
TIME CONSTANT	3.0
MEASURED CHART DIVISIONS	6.0



FIELD NOTE

SERVICE TICKET NO. 69452 API SERIAL NO. 037-00041 FCM VERSION H.L.S DLS HO 1.0


DOWN		RUN NO.		RUN NO.		TEMPERATURE	
RUN NO.	ONE	SERIAL NO.	27912	SERIAL NO.	27912	SERIAL NO.	
SERIAL NO.	27912	MODEL NO.	CNSG	MODEL NO.	CNSG	MODEL NO.	
MODEL NO.	CNSG	DIAMETER	1-11/16"	DIAMETER	1-11/16"	DIAMETER	
DIAMETER	1-11/16"	LOG TYPE	N/A	LOG TYPE	N/A		
DETECTOR MODEL NO.	N/A	SOURCE TYPE	3MCi-AM				
TYPE	SCINT	STRENGTH	67-SNB				
LENGTH	N/A	SERIAL NO.					
DISTANCE TO SOURCE	4.5	STRENGTH	5Ci				


LOGGING UNITS

DOWN				GAMMA		TEMPERATURE		NEUTRON		
RUN	DATUM	SPEED	TOOL	SCALE		SCALE		SCALE		
NO.	ITEM	FT./MIN.	POSITION	TC/TL	L	F	TC/TL	L	F	TC/TL	L	F	MISC
ONE	8300	30	FREE	5CF	0	100				1KC	1100	1400	

REMARKS: LOG RUN TO POSITION TOP GUNS
FIRST PASS GUNS 5 DEEP
SECOND PASS GUNS ON DEPTH

HALLIBURTON LOGGING SERVICES, INC. DOES NOT GUARANTEE THE ACCURACY OF ANY INTERPRETATION OF LOG DATA. CONVERSION OF LOG DATA TO PHYSICAL WELL PARAMETERS OF RECOMMENDATIONS WHICH MAY BE GIVEN BY HLS PERSONNEL OF WHICH ANY EMPLOYEE ON THE LOG OR IN ANY OTHER FORM OF ANY KIND OF SUCH DATA. INTERPRETATIONS, CONVERSIONS OR RECOMMENDATIONS MADES THAT HLS IS NOT RESPONSIBLE. EXCEPT WHERE DUE TO GROSS NEGLIGENCE OF WILFUL MISCONDUCT FOR ANY LOSS, DAMAGES OR EXPENSES RESULTING FROM THE USE THEREOF.





WELL LOCATION ALISO CANYON
WELL NAME SS-29

ENG H L S DLS CH U4 20 LIS 07-27-90

LOG TAPE ID 300870001
DATE 10-30-91

ENG H L S DLS CH U4 20 LIS 07-27-90
SUB SERIAL # MODEL SOURCE # CALB # INTL INTL MPRC INT2 DLY TCH
GR 27912 CNSG SMSR 250 0 2403 2077 0 0 7.5 AS
NDR 27912 CNSG 01-228 0 1 1 0 0 4 AS
CCL 27912 CNSG 01 0 1 0 0125 0 0 0 4 AS


ENG H L S DLS CH U4 20 LIS 07-27-90
SERVICE ID TRK UNIT SCL RPRATE TYPE STYP OPFL DFFL OFF LIS OVCT
L P L_P
GR 1 1 API 0 1.00 Y Y 0 LIN 1.25 1.75 0 Y VNYZ
NDR 1 4 API 1000 1500 Y Y 0 LIN 1.25 1.75 0 Y VNYZ
CCLU 6 1 0 1.00 Y Y 0 LIN 0 0 0 Y GNN


ENG H L S DLS CH U4 20 LIS 07-27-90
PLOT TABLE


OPFL			UDR			OPFZ		
SCALE 2400	ANNOTATION 100	SCALE 0	ANNOTATION 100	SCALE 0	ANNOTATION 100			
TRK1 LIN	TRK2 LIN	TRK3 LIN	TRK1 LIN	TRK2 LIN	TRK3 LIN	TRK1 LIN	TRK2 LIN	TRK3 LIN


ENG H L S DLS CH U4 20 LIS 07-27-90
PARAMETER TABLE


TBKY OFF	TAPE 1	RATE 30	TOOL A=2	ACZP 18	DSHF 64	7-16 NO	
THSU 0	THSZ 10	DIST 2.441	PIP 1.59375	TOD 1	KT 1	KSLS 1	
TRIG NEG	MSGP ON	VISW 80	SMSH 13	GRSM ON			
MMDU CLSH	SO 0	CMCT 0	ASKV NO				
BS 0	CSIZ 0	TELE YES	LIS YES	DLV YES	DSP UP	PLOT FULL	











AC_CPUC_01160721

Play back File : 07.COSMO .68402 .LG

Logged on 30/Oct/91 at 10:20

COSMO **REPEAT SECTION**


COSMO

HALLIBURTON LOGGING SERVICES DDL-V Logging System - V3.24

PLAYBACK RAW DATA - TOP DEPTH 7796.2 ft

Reel : 01.SCGC COSMO .68402 .RH
Play back File : 08.COSMO .68402 .LG

Logged on 30/Oct/91 at 10:26



HALLIBURTON LOGGING SERVICES DDL-V Logging System - V3.24

PLAYBACK RAW DATA - BOTTOM DEPTH 8909.7 ft

Reel : 01.SCGC COSMO .68402 .RH
Play back File : 08.COSMO .68402 .LG

Logged on 30/Oct/91 at 10:26

COSMO


COSMO **REPEAT SECTION**

HALLIBURTON LOGGING SERVICES DDL-V Logging System - V3.24

PLAYBACK RAW DATA - TOP DEPTH 8653.0 ft

Reel : 01.SCGC COSMO .68402 .RH
Play back File : 07.COSMO .68402 .LG

Logged on 30/Oct/91 at 10:20



HALLIBURTON LOGGING SERVICES DDL-V Logging System - V3.24


PLAYBACK RAW DATA - BOTTOM DEPTH 8909.5 ft


Reel : 01.SCGC COSMO .68402 .RH
Play back File : 07.COSMO .68402 .LG

Logged on 30/Oct/91 at 10:20

COSMO **REPEAT SECTION**

AC_CPUC_0118072


(A-14)
A-20
Shale
A-36
Shale
>0.3 good Pet Odor
(A-12)
>0.3 Med Oder
>0.3 good odor
P-7
P-13
P-23
P-39
D
5000
5100
5200
5300
5400
5500
5600
5700
5800
5900
6000
6100
6200
6300
6400
6500
6600
6700
6800
6900
7000
7100
7200


Mud
D-6
D-12
AMP. S.N.
TLN 8075'
MP
S-1
S-4
S-8
HZ
V-14
TOP FREN (503)
#1 IFT
#2 IFT
#3 IFT
#4 IFT
#5 IFT
#6 IFT
V-23
T1 CRETACEOUS
Standard Sesnon 1-29
STD SESNON 1-29
SPONTANEOUS POTENTIAL
100 millivolts
RESISTIVITY
-ohms. m²/m
REVISIONS

T.D. 9790'
D.F. 2856
Pg. 9077

SPONTANEOUS-POTENTIAL
– 100 millivolts +

RESISTIVITY
0 -ohms. m²/m 60

RESISTIVITY
0 -ohms. m²/m 60

Bottom of casing 9077'

REVISIONS
CASING - 4/26/61
GEOLOGY - 7/12/66

STD. SESNON 1-29

K+E SEMI-LOGARITHMIC 3 CYCLES X 150 DIVISIONS
KEUFFEL & ESSER CO. MADE IN U.S.A.

47 5490

SS #29

11-17-81

6200
6400
6600
6800
7000
7200
7400
7600
7800
8000
8200
8400
8600
8800
9000
9200

2
4
80
56
2
26
50
2
38
66
56
74
98
37
98
77
9770
TD.

P.U @ 9005

Tool Check

open bleeder valve
To check tool

4 5 6 7 8 9 10
20 30 40 50 10

Format: Azimuthal Resistivity 3 Track Vertical Scale: 2" per 100 feet Creation Date: Sat, Feb 10, 2007, 10:44:03 PM

To: Jim [illegible]

SS-29

5529

(SP)

0 MV 100

(AO10)

0 OHMM 60

(AM16)

0 OHMM 60

(AO19)


0 OHMM 60


8500


8600

8700


FREW



8800
8900
9000
9100
9200


9200
9300
9400
9500
9600
9700
DST
SH
K1 (SH)
944'
15' REC
0.5' REC. AS ABOVE
2' REC.




Format: Azimuthal Resistivity 3Track Vertical Scale: 2" per 100 feet Creation Date: Sat, Feb 10, 2007, 10:44:03 PM


7/23
To: JIM MANSDORFER
FROM: S. CARDIFF
PER E-MAIL.
8400
SS 29
8500
S8 8525 (-5668)
8600
S14
HZ
8700
FREW 8730 (-5873)
8800
CORE
8810-24: CONGLOMERATE, w/ FINE-MEDIUM OIL SD MATRIX
8824-35: NO RECOVERY
8835-36: HD CGL, MATRIX OF HD CMTD GRAY SD + OIL SD
8836-58: HD CGL, MATRIX OF HD dK GREY SD + HD OIL SD
8858-8881: HD CGL w/ MATRIX OF HD CMTD GREY SD & HD OILED HD FINE-MEDIUM OIL SD, HD GREY SD.
10' REC.
8881-8905: HD CGL w/ MATRIX OF HD GREY SD + HD OIL SD.
4' RECOVERY
8900
8905-8911: NO RECOVERY
8914-42: 1' RECOVERY. VERY HARD PIECES OF QUARTZITE BOULDERS
8942-44: 2' RECOVERY. PIECES OF QUARTZITE.
9000
9035-40: 0.5' RECOVERY. FRAGMENTS OF GRANITIC GNEISS BOULDERS
9048-58: 1' RECOVERY. HD MEDIUM MICACEOUS GRAY SD



Format: Azimuthal Resistivity Track Vertical Scale: 2" per 100 feet Creation Date: Tue, Jul 01, 2008, 05:05:58 PM



AC_CPUC_0118088

Standard Sesnon 29 Aliso Cyn.
Well History File

DHS viewer
Not installed or wrong
version
update from login
page

WORKOVER PROGRAM

OPERATOR: Southern California Gas Company

FIELD: Aliso Canyon

WELL: SS 29

CONTRACTOR: Pride 447

OBJECTIVE: Install SCSSV

APPROXIMATE LOCATION:

ELEVATION: Ground level 2849'. Take all measurements from KB 7' above ground level.

SAFETY: Hard hats are to be worn by all personnel on or near a rig. No smoking is permitted within 100' of the wellhead or near any other flammable material.

PRESENT CONDITIONS:

0'	- 999'	11-3/4"	42# .	
999'	1042'	11-3/4	47#	
0'	974'	7"	23#	N-80
974'	4454'	7"	23#	J-55
4454'	6494'	7"	23#	N-80
6494'	8170'	7"	26#	N-80 Otis 'BWB'@ 8032'
8075'	9790'	5"	18#	See perforation detail on mechanical. WSO squeezed w/100 sx @ 8330'-8331'.

2-7/8" Tubing Detail Attached

WORK CATEGORY:

PR

- o Prepare surface as required.
- o Perform any required piano wire work.
- o Spot open top storage tank on location.
- o Check with the Storage Field Engineer to determine any changes and condition of the well since writing of this program and current bottom-hole pressure in the vicinity of the well.
- o Well Kill Requirements:

  a. Top of zone 8428' M. D.
  b. Estimated bottom-hole pressure = 3150 psig.
  c. Calculated fluid density to provide 300 psi overbalance =59 lbs / cu.ft. Use 63 lbs/cu.ft 2% KCl fluid.
  d. Wellbore fluid volumes:

Tubing	=	47 bbls.
Casing/Liner	=	19 bbls.
Annulus	=	254 bbls.
Total		320 bbls.

* Be sure to bleed off surface string annulus.

* Maintain surface fluid volume equal to or greater than well volume during workover.

PROGRAM

MI 1. Move in and rig up.

- o Bleed off all casing annuli to zero pressure.
- o Rig up drip pans and plastic sheeting and dike area as necessary for spill control.
- o Be sure well is completely dead. Notify Drilling Engineer if well is not in this condition.
- o Set equalizing back pressure valve in doughnut.
- o Remove xmas tree. Send xmas tree in for repairs as required.

WW 2. Install 9" Class III 5000 psi BOPE.

- o Include Hydril bag and double gate with 2-7/8" pipe rams and blind rams.
- o Bag and both sets of rams are to be actuated hydraulically by a 3000 psi, minimum 60 gallon accumulator with dual remote controls and auxiliary nitrogen.
- o Install 9" 5000 psi spool with choke and kill lines as well as check valve.
- o Choke manifold to have discharge to Gas Company system, with block

valve and bleeder as well as connections to fluid tank.

- o Inspect Hydril bag when installing BOPE.
- o Use new Rx API rings on all untested BOPE connections.

WW 3. Pressure test BOPE.

- o Blind rams, 2-7/8" pipe rams and choke manifold are to be tested to 5000 psi with water.
- o Test Hydril bag to 3500 psi with water.

CO 4. Pull tubing.

- o Remove back pressure valve.
- o Release tubing from packer.
- o If unable to release from packer, contact the Drilling Engineer. Have tubing visually inspected while pulling out of hole. Send good tubing in for rack inspection.

5. Install tubing string.

- o Gator hawk tubing to 4000 psig while running in well.
- o Tubing string to include :

Otis guide shoe
Otis seal assembly, (2) seals
Otis J-latch
Crossover from seal assembly to 3-1/2"8Rd EUE

One joint 3-1/2" 8Rd EUE tubing
3-1/2" Otis XN no-go nipple (2.666" ID).
One joint 3-1/2" 8Rd EUE tubing
Otis 3-1/2" "XD" sliding sleeve (closed).
One joint 3-1/2" 8Rd EUE tbg.
3-1/2" BST KBMG gas lift mandrel with dummy valve.
One joint 3-1/2" 8Rd EUE tbg.
Crossover 3-1/2" 8Rd EUE pin X 4-1/2" 8Rd EUE box
4-1/2" 8Rd EUE tubing to approximately 500' from surface.
Crossover 4-1/2" 8Rd EUE pin X 3-1/2" 8Rd EUE box
One 3-1/2" Baker T5 series SCSSV
3-1/2" 8Rd EUE tubing and pups to surface as necessary.

- Pull 20,000 lbs over tubing weight to check latch on packer.
- Space out and land tubing on Otis model "BWB" packer at 8032' with 10,000#.
- Pressure casing to 1500 psig ,keep tubing full and check for return.
- Run in with wireline and open sliding sleeve.

  Test SCSSV in accordance with attached procedure.

CO 6. Remove BOPE and Install Xmas Tree.

- Install equalizing back pressure

valve in tubing hanger.

- o Remove BOPE.
- o Install xmas tree.
- o Pressure test seals, xmas tree, seal flange, and tubing head to 5000 psig with oil for 20 minutes.
- o Tighten all wellhead bolts.
- o Check and close all wellhead valves.
- o Install tapped blind flanges with bleeder valves on all wellhead valves.

MO 7. Rig down and move out rig.

- o Inform the Storage Field Engineer before moving off wellsite so proper wellsite safety protection can be arranged.
- o Release rig.
- o Clean up wellsite. All trash, debris, equipment and materials to be removed from site.


A walk-through inspection by a Drilling Department representative and the Storage Field Engineer or their designee is conducted after the site is cleaned.

E. S. Sinclair

October 07, 1994

Approved: _____
J. D. Mansdorfer

cc:
I. R. Binmore	w/o att.
N. W. Buss	w/o att.
T. Holland	w/o att
D. G. Neville	att.
CPS Tool Pushers	att.
H. Robinson	w/o att.
T. Schroeder	w/o att.
M. A. Woiemberghe	w/o att.
Well file	att.



Standard Sesnon #29

Aliso Canyon

Status: Injection/Withdrawal

Flow Regime: Casing Flow

Elevation: 2849' G.L.
7' K.B.
KB to MV: 6'

Surface Location: Approximately 750'S & 6100'W of Station 84, T3N, R16W, Sec. 28

Btm. Hole Loc: Straight Hole at effective TVD of 9077'.

4/26/53 - 9/29/53: Well spudded and completed.

2/2/73 - 2/28/73: Pressure tested 7" casing, converted to gas storage by perforation in Sesnon zone. Cleaned out to 9074'. Ran tubing with SSSV.

7/31/73 - 8/7/73: Installed wireline SSSV. Cleaned out to 9077'.

8/27/77 - 9/9/77: Cleaned out to 9072'. Pressure tested casing. Reran tubing with SSSV.

3/5/79 - 3/10/79: Replaced safety system. Set packer at 8040'.

9/20/91 - 11/6/91: Milled packer. Shot 4, 1/2" SPF at 8330' - 8331'. Squeezed shoe leak with 100 sx class "G" cement. Ran tubing conveyed perforation guns and shot 6, 1/2" SPF at: 8428'-8436', 8454'-8502', 8522'-8560', 8602'-8636', 8660'-8668', 8674'-8694', 8727'-8737', 8750'-8760', 8810'-8820'. Completed with 7" Otis "BWB" packer and 2-7/8" tubing.

Volume	Cu.Ft.	Bbls.
Tubing	261	46.5
Annulus	1427	254
Casing/Liner	109	19
Total	1797	319.5

5" Liner Detail:
18#, Flushjoint, 8075' - 9077'
(4.276" I.D.)

8075' - 8727': J55, Perforated 6, 1/2" SPF 8428'-8436',

10, 1/2" SPF 8454'-8502', 8528'-8552', 8602'-8638', 8658'-8668', 8674'-8694'.

8727' - 9077': N80 slotted, .012" gauge, 12 rows, 6" centers, 6 deg. undercut. Perforated 6, 1/2" SPF 8727'-8737', 8750'-8760', 8810'-8820'.

Top Of Zones

	M.D.
MP	8150'
S1	8346'
S2	8382'
S4	8428'
S8	8522'
Frew	8728'

Note: Fish consists of 2 partially milled Robison 5" drillable retainers.

Reviewed

Department	By:	Date
Drilling	R.H. Doull	9/1/92
Petroleum Eng.		9/1/92
Division		9/11/92

AC_CPUC_0118097

OTIS

GENERAL PRODUCT INFORMATION

No. 12.1.1.2A


Product Code

Date: 11-4-91

Product Name: 'WE' Permanent Packer

Page: 1

SOU CAL GAS CO.
ALISO CANYON
SS#29



PACKER - OTIS BWB (212BWB 70700-A) 3.25" I.D.

23-29#

Note: These instructions describe desired results from use of Otis equipment, but such results are not guaranteed. Operation of equipment is subject to mechanical limitations and Otis shall only be liable for its merchandise and service as set forth in its general terms and conditions.


AC_CPUC_0118098

TUBING DETAIL

WELL: STANDARD SESNON #29
FIELD: ALISO CANYON

STATUS: Injection/Withdrawal
DATE: 11-6-91

DIAGRAM



	TUBING	TUBING	TUBING	
SIZE	2 7/8"			
WEIGHT	6.5			
GRADE	J55			
THREAD	8RD EUE			
DEPTH	8035'			
I.D.	2.441			
DRIFT ID	2.347			
O.D.	3.668 TJ			

ITEM #	DESCRIPTION	LENGTH	DEPTH
1.	KB	6.92	6.92
2.	G.L. TO TBG HEAD	-.14	6.78
3.	HANGER 7" 2 7/8" EUE X 2 7/8" EUE BOX	.60	7.38
4.	FATIGUE NIPPLE 2 7/8 EUE PIN X PIN	.68	8.06
5.	PUP JT 2 7/8" 6.5# N80 EUE	4.09	12.15
6.	250 JTS. 2 7/8" 6.5# J55 EUE	7907.35	7919.50
7.	BST 'MMA' GLM W/ 1 1/2" RA LATCH	12.92	7932.42
8. ✓	1 JT. 2 7/8 EUE J55 TBG.	31.49	7963.91
9. ✓	OTIS 2.313" 'XD' SSD	3.21	7967.12
10. ✓	1 JT 2 7/8" EUE J55" TBG	31.55	7998.67
11. ✓	OTIS 2.205" 'XN' NO-GO NIPPLE	1.28	7999.50
12. ✓	1 JT. 2 7/8" EUE J55 TBG	31.55	8031.50
13. ✓	OTIS J-LATCH W/ 2 SEAL UNITS	1.50 / 2.49	8032
14. ✓	OTIS MULE SHOE GUIDE	.60	
15.			
16.			
17.			
18.	A. OTIS 7" 23-29# 'BWB' PKR		
19.	3.25" I.D. SET AT:		8032'
20.			
	TUBING LANDED W/ 8000#		
	DOWN ON PACKER		

AC_CPUC_0118099

WELLHEAD DESCRIPTION

Well No. SS-29

Field Aliso

Date Prepared 5-4-81

Wellhead Mfgr Shaffer

1. Casing Head Shaffer Size 13-5/8" Type KD

   Slips & Pack-off 13-5/8" x 7"

   A. Surface Csg. Size 11-3/4" Wt 42# Grade H-40

   B. Casing Head Valve Marpac Size 2" 3000 psi Fig.No. CSB-790-JN

2. Seal Flange Shaffer Size 13-5/8" x 10" 5000 psi

   A. Type Seal PS Ring BX-160 & R-54

3. Tubing Head Shaffer Size 10" x 8" 5000 psi Type 63-L-1

   Ring R-54 & Ring R-50

   Outlets 2-3" Sec.Seal PS

   Valve Removal Thrd 2-1/2" API

   A. Tubing Hanger Shaffer Size 8" x 2-7/8" Type AJO

   B.P.V. Size 2-7/8" Thrd

   B. Tubing Head Valves 2 Mc Evo Size 3" 5000 psi Fig.No. 129

   C. Automatic Csg. Valve WKM Size 3" 5000 psi Fig.No. 114522

4. Adapter Seal Flange Shaffer Size 8"x2-1/2"x 2-9/16" Type AJO

   A. Ring Size R-50 & R-27

5. Master Valve McEvoy Size 2-1/2" 5000 psi Fig.No. 129

6. Xmas Tree Cross Shaffer Size 2-9/16"x2-9/16"x2-1/16"x 2-1/16"x2" Bore Thru 2-9/16"

   Across 2-1/16"

7. Tubing Wing Valves Rockwell Size 2" 5000 psi Fig.No. 21055

   A. Automatic Tbg. Valve WKM Size 2" 5000 psi Fig. No. 114522

8. Unibolt Size 3" 5000 psi Inside Thrds


9. Wt. Landed in Csg. Head 8170' 7" Wt. 26# 23# Grade N-80 ST&C

10. Wt. Landed on Doughnut 8030' 2-7/8" 10,000 Wt. 6.5 Grade N-80 8Rd EUE

11. Tubing Head to Ground Level

AC_CPUC_0118100

TYPE IV



Well Name: SS 29 - Aliso Canyon

Mfgr.: Shaffer

Date Prepared: 12-20-82

AC_CPUC_0118101

SUBMIT IN DUPLICATE

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION

DIVISION OF OIL AND GAS

History of Oil or Gas Well

Operator Southern California Gas Company Field Aliso Canyon County Los Angeles
Well Standard Sesnon #29, Sec. 28, T 3N, R 16W, SB B. & M.
A.P.I. No. 037-00041 Name R.D. Phillips (Person submitting report) Title Agent (President, Secretary or Agent)
Date November 26, 1991.

Signature R.M. Dowell
R. M. Dowell for R. D. Phillips
P. O. Box 3429 Terminal Annex, Los Angeles, CA 90051 (213) 244-2666
(Address) (Telephone Number)

History must be complete in all detail. Use this form to report all operations during drilling and testing of the well or during redrilling or altering the casing, plugging, or abandonment with the dates thereof. Include such items as hole size, formation test details, amounts of cement used, top and bottom of plugs, perforation details, sidetracked junk, bailing tests and initial production data.

Date	
1991	
9-20	Set in rig pump. Removed lines from casing and well head. Killed and shut in well.
9-23	Moved in and rigged up. Circulated well and spotted 100 Bbls high viscosity pill.
9-24	Filled well. Installed back pressure plug. Removed tree and installed BOPE. Tested blind, pipe rams and choke manifold to 4000 psi. Tested annular preventor to 2850 psi. BOPE test waived by Steve Fields with D.O.G.
9-25	Replaced packing in donut studs. Pressure tested donut studs to 3000 psi. Released from packer. Began laying down 2-7/8" tubing.
9-26	Rig down for repairs.
9-27	Pulled and laid down 259 joints of 2-7/8" J-55 tubing and production equipment. Ran in with bit and scraper on 2-3/8" drill pipe.
9-28	Finished picking up and running drill pipe to packer at 8042'. Pulled out of well. Made up Otis packer retrieving tool. Ran in well to 7340'.

OG103 (6/91/GSR1/5M)
Mailed 12/6/91

AC_CPUC_0118102

9-30 Ran in well with packer retrieving tool to 8029'. Latched into packer at 8040' and pulled 30,000 lbs over string weight. Released packer. Pulled and laid down packer. Made up 4-1/8" bit on 5" 18# scraper, 116' of 3-1/8" drill collars and 945' of 2-3/8" tubing crossed over to 2-7/8" drill pipe. Ran in well to 8000'.

10-01 Ran in well to 9010'. Hit fill at 9067'. Cleaned out to 9072'. Unable to clean out past 9072' (T.D. 9077'). Circulated well clean. Pulled out of well. Made up and ran 5" drillable retainer. Set retainer at 8345'. Pulled up to 8042'.

10-02 Ran in well to 8343'. Pressure tested cement retainer to 1200 psi. Changed well over to clean 2% KCl water. Pulled up to 8075' and dumped 1 sack of 8-12 gravel and displaced with 36 Bbls of KCl water. Waited one hour. Ran in and tagged top of sand at 8335'. Pulled out of well. Ran 3-1/8" perforating gun on wireline. Stopped at 8309' (26' high). Ran in well with 4-1/8" mill.

10-03 Measured in well with drill pipe and tagged fill at 8322'. Changed well over to polymer fluid. Cleaned out fill to 8337'. Milled up cement retainer and pushed down well to 9055'. Unable to get deeper. Circulated well clean. Pulled to kill string.

10-04 Pulled out of well. Ran and set 5" cement retainer on wireline at 8361'. Tested cement retainer to 1200 psi. Ran in well with 1040' of 2-3/8" tubing tail on 2-7/8" drill pipe to 8361'. Changed well over to 2% KCl water with tubing tail at 8346'. Dumped 1 sack of 8-12 gravel and displaced with 34 Bbl KCl water. Pulled to top of 5" liner. Shut well in.

10-05 Ran in well and tagged top of sand at 8351'. Pulled out of well. Shot four 3/8" holes from 8330' to 8331'. Pressure holes to 2200 psi. Bled off 450 psi in 20 min. Ran in well with 5" full bore packer with 30' of 2-3/8" tubing tail and 315' of 2-3/8" tubing above tool crossed over to 2-3/8" drill pipe.

10-07 With tubing tail at 8334', pumped 50 cu.ft. of 12% HCl/3% HF acid and displaced with 28 Bbls of KCL water. Set packer at 8303' and pumped 50 cu.ft. of acid out holes at 8330'. Final injection rate: 1-1/2 Bbls/min at 1700 psi. Pulled up and placed tail at 8120' and packer at 8087'. Squeezed 25 cu.ft. 6% HCl/1-1/2% HF acid followed by 50 cu.ft. Class "G" cement with fluid loss additives. Final squeeze pressure: 1600 psi at 4 cu.ft/min. Displaced holes by 25 cu.ft. Waited 4 hours on cement. Pulled tool loose and reset packer at 8018'. Could not obtain pressure test on packer and/or unloading tool. Pulled to kill string.

10-08 Pulled out of well. Replaced full bore packer with same. Ran in well to 8120'. Packer failed to hold pressure. Pulled out of well. Ran in well with 63' of 2-3/8" tubing tail with drill pipe tester, and 7" full bore packer on 2-7/8" drill pipe. Ran in well to 2569'. Set packer (would not hold pressure). Dropped ball in test sub. Drill pipe would not test.

10-09 Located leak in drill pipe on 27th and 28th joint connection. Ran in well with 7" full bore packer and drill pipe tester on 2-7/8" drill pipe with 60' tubing tail below packer and set at 8120'. Attempted to break down holes at 8330'. Failed to achieve breakdown. Pulled out of well to 2193'.

10-10 Pulled out of well. Made up 356' of 2-3/8" tubing and full bore packer. Tested to 3000 psi. Ran in well to 8324'. Spotted 50 cu.ft. of acid. Established injection rate of 7 cu.ft./min at 1950 psi. Pulled tubing tail up to 8120'. Mixed and pumped 50 cu.ft. of class "G" cement. Displaced with 39-1/2 Bbls KCl water. Squeezed 36 cu.ft. class "G" cement. Final squeeze pressure: 2560 psi.

10-11 Released packer and pulled out of well. Ran in well with 4-1/8" bit on 5" scraper. Tagged top of cement at 8196'. Drilled hard cement from 8196' to 8326'. Pulled to liner top.

10-12 Ran in to 8326'. Drilled out cement to 8343'. Circulated well clean at 8351'. Pressure tested squeeze holes at 8330' to 2160 psi for 30 minutes (410 psi bleed off). Pulled out of well. Made up 30' of 2-3/8" tubing tail on 5" full bore packer with 315' of 2-3/8" tubing crossed over to 2-7/8" drill pipe. Ran in well to 8029'.

10-14 Ran in well with 5" full bore packer to 8334'. Pressure tested holes at 8330' to 2200 psi for 20 min. Pulled out of well. Ran in well with 4-1/8" mill on four 3-1/8" drill collars, 945' of 2-3/8" tubing and 2-7/8" drill pipe to 8347'. Changed over hole fluid to polymer fluid. Pulled up to 8026'.

10-15 Ran in well to 8347'. Milled on 5" bridge plug from 8361' to 8363'. Pushed junk down well to 9035'. Milled for one hour without success. Pulled out of well. Ran in well with 7" RTTS packer with pressure control valve and circulating port to 7998'.

10-16 Rigged up flow lines to Gas Co. withdrawal system. Tested lines to 3000 psi. Flowed well for 12 hours.

10-17 Ran noise log survey from 8560' to 5000'. Anomaly detected across downhole tools.

10-18 Ran noise log survey from 8600' to surface. Anomaly detected across down hole tools.

10-19 Installed and pressure tested surface lines to 2000 psi. Placed well on injection for 10 hours. Surface injection pressure: 2620 psi (120 psi over shut in wellhead pressure). Closed down hole and surface valves.

10-21 Opened subsurface valve. Ran noise log survey from 8600' to surface. Noise log indicated possible gas movement up above the M-P marker. Pumped 30 Bbls of high vis pill followed by 30 Bbls of polymer fluid. Opened circulating port. Rigged down surface flow lines.

10-22 Released packer. Pulled out of well. Ran in well with full bore packer with mechanical circulating port to 7544'. Rigged up flow lines.

10-23 Finished rigging up flow lines. Tested flow lines to 3000 psi. Injected gas to provide 1800 psi underbalance. Placed well on withdrawal.

10-24 Continued withdrawal from well. Total hours on withdrawal: 17-1/2; Final surface flowing pressure: 850 psi.

10-25 Detected leak on surface flow manifold above wellhead. Re-killed well.

10-26 Rigged up and tested surface lines to 3000 psi. Placed well on withdrawal for 9 hours. Shut in well.

10-27 Ran temperature and noise log surveys. Logs indicated no gas movement behind casing. Pumped 80 Bbls to kill well. Dismantled surface flow line. Released packer.

10-28 Bled off 100 psi on drill pipe and casing. Pulled out of well. Made up 4-1/8" mill on 166' of 3-1/8" drill collars and 918' of 2-3/8" drill pipe crossed over to 2-7/8" drill pipe. Ran in well to 9035'. Milled on retainer and pushed it down to 9055'. Milled on retainer at 9055'.

10-29 Ran in well to 9055'. Milled on retainer. Cleaned out to 9066'. Mill stopped. Changed over hole fluid to clean filtered KCl water. Pulled out of well to 2782'.

10-30 Pulled out of well. Installed shooting flange. Ran Gamma Ray/Neutron collar log from 8900' to 7800'. Made up tubing conveyed perforating guns and ran in well to 3862', filling drill pipe so as to provide 500 psi underbalance.

10-31 Ran in well. Ran Gamma Ray/CCL log and correlated guns. Set Otis packer at 8306'. Tested surface lines to 3000 psi. Tested packer to 1000 psi. Dropped bar. No blow or fluid rise to surface. Unsuccessfully attempted to fish drop bar on wireline.

11-01 Attempted to fish drop bar. Fill apparently above bar. Pulled packer loose and pulled out of well. All guns fired. Made up 4-1/4" bit on 5" scraper, 3-1/8" drill collars and 2-3/8" drill pipe crossed over to 2-7/8" drill pipe. Ran in well to liner top.

11-02 Ran in and tagged fill at 9050'. Cleaned out to 9066'. Pulled out of well laying down drill pipe. Picked up 2-7/8" tubing and ran in well to kill string.

11-04 Pulled kill string out of well. Ran and set 7" Otis "BWB" packer on wireline at 8030'. Made up test seals on 2-7/8" 8RD tubing and started in well.

11-05 Finished picking up tubing. Latched into packer. Pulled 20,000 lbs over string weight to check latch. Set 10,000 lbs on packer. Tested packer and seals to 1500 psi. Changed 3-1/8" valve on tubing head and tested to 1500 psi. Pulled out of well. Made up production equipment and ran in well Hydrotesting to 4000 psi. Ran in well to kill string.

11-06 Finished running tubing. Latched in to packer. Pulled 20,000 lbs over string weight to check latch. Landed with 8,000 lbs on packer. Tested seals and packer to 1500 psi. Removed BOPE. Installed xmas tree. Tested to 5000 psi. Opened Otis "XD" sliding sleeve. Changed fluid over to double inhibited 2% KCl. Released rig.

WELL NO. SS 29

LOCATION Aliso Canyon

DATE WANTED 11-10-94

REQUESTED BY ESS

	SIZE	FOOTAGE	DESCRIPTION
CASING			
TUBING	3-1/2"	600'	8 Rd EUE
	4-1/2"	7500'	8 Rd EUE
LINER & ACCESSORIES			
	DESCRIPTION		
CASING HEAD			
TUBING HEAD	Cross 3-1/8" x 3-1/8" x 3-1/8" x 2-1/16"		
	9" x 3-1/8" x 5000# Double Studded AJO Seal Flange		
	9" x 3-1/8" EUE 8 Rd Type 75 AJO Tubing Hanger		
	3" x 3-1/8"x5000# Unibolt Cap		
	One 3-1/8" Wing Valve, One 3-1/8" Master Valve, One 2-16" Wing		
MISCELLANEOUS	Baker Series T5 SCSSV		

STANDARD SESNON #29 - ALISO CANYON

Program to replace packer, pressure test casing and install new down hole safety system.

CASING WITHDRAWAL AND INJECTION

Take all measurements from original derrick floor 6.92' above ground.

PRESENT CONDITION:

11 3/4" cemented 1042' 42# H-40
7" cemented 8170', WSO on shoe
1002' 5" landed 9077', T.D., 9790', plugged
with cement to 9094', cp'd 8725', top 8075'
Slotted 9077' - 8727', WSO on lap
Water not shut off 8710', squeezed, WSO 8705'
Perforated 8694' - 8674'
8668' - 8658'
8638' - 8602'
8552' - 8528'
8502' - 8456'
18# J-55 flush joint

CASING DETAILS:			100% Safety Factor BURST	COLLAPSE
7"	0 - 974'	23# N-80	6340	4300
	974' - 4452'	23# J-55	4360	3290
	4452' - 6494'	23# N-80	6340	4300
	6494' - 8170'	26# N-80	7240	5320
5"	8075' - 8725'	18# J-55	7000	6530

TUBING DETAIL:

Baker Model "D" packer 8517' (5")
Camco hydrostatic packer 8421' (5")
2 3/8" and 2 7/8" 8rd EUE J-55 landed 8522'
Camco 1.81" "NOGO" nipple 8518' (plug in place)
2 3/8" Otis polished nipple 8505'
2 3/8" slotted tubing 8503' - 8483'
Otis X nipple 2 3/8" 8482'
Otis polished nipple 8478'
2 3/8" slotted tubing 8476' - 8456'
Otis X nipple 2 3/8" 8455'
Otis X nipple 2 3/8" 8390'
Camco sliding sleeve 8359' (open)
Otis X nipple 2 7/8" 8017'
4 Camco gas lift mandrels with valves
2 3/8" tubing to 8048', 2 7/8" to surface

AC_CPUC_0118108

PROGRAM:

1. Move in and rig up. Pressure test wellhead seals to 4000 psi.

2. Kill well with 74#/cu. ft. brine polymer drilling fluid. Check bottom hole pressure before moving in rig. Volume of well = 360 barrels.

3. Install back pressure valve in doughnut. Remove Xmas tree and install class III 5000 psi BOPE. Pressure test complete shut-off rams and pipe rams to 4000 psi with water and nitrogen.

4. Unseat Camco hydrostatic packer (turn to release) and pull tubing. If necessary cut tubing to recover packer. Mill over and recover Model "D" packer at 8517'.

5. Run 6 1/8" bit and casing scraper. Clean out to top of 5" liner at 8075'. Run 4 1/8" bit and casing scraper. Clean out to 9077'.

6. Set bridge plug at 8425' and test with rig pump. Circulate out polymer drilling fluid with fresh water treated with surface tension agent. pressure test casing, using cement retainer and cement pump truck equipped with calibrated pressure chart and pressure gauge, as follows:

3800'	to	8425'	with	2500 psi	for	60	minutes
3800'	"	Surface	"	2700 psi	"	60	"
3300'	"	"	"	2900 psi	"	60	"
2900'	"	"	"	3100 psi	"	60	"
2500'	"	"	"	3300 psi	"	60	"
2000'	"	"	"	3500 psi	"	60	"
1100'	"	"	"	4000 psi	"	60	"

Change to polymer drilling fluid.

7. Perform any remedial work indicated by pressure testing. Pull bridge plug at 8425'.

8. Run Otis Permatrieve packer on wire line and using reference collars set packer near 8430'. Do not set packer in a collar.

9. Run 2 3/8" and 2 7/8" tubing, change collars, clean pins, apply Baker seal, and hydrotest to 5000 psi holding each test for one minute. Tubing to include:

Otis production tube
" 4 seals
" Latch-in-locator
" 10' heavy wall tube
" 1.56" "NOGO" nipple with 2 3/8" threads
" 20' heavy wall tube
" annular flow safety system
2 3/8" tubing to 8000'
2 7/8" tubing to surface with top 500' N-80 tubing

10. Land tubing on packer with up to a maximum of 10,000 pounds on packer - pull 25,000 pounds over weight of tubing to check latch.

AC_CPUC_0118109

PROGRAM: (Concluded)

11. Set back pressure valve in doughnut. Remove BOPE and reinstall Xmas tree. Pressure test Xmas tree to 5000 psi.

12. Circulate brine polymer drilling fluid out of well with waste salt water. Set tubing plug in "NOGO" nipple. Pressure test seals and packer to 2000 psi. Pull tubing plug and release rig.

G. C. ABRAHAMSON
August 25, 1977

cc: Rig Supervisor
Contract Pusher (2)
Relief Rig Supervisor
Book Copy

B. Jones ✓
D. Smiley
J. Melton
D. Justice)
M. Grijalva)

Division of Oil and Gas

Well File
Spare Copy

GCA/jp

AC_CPUC_0118110

TIME AND COST ESTIMATES - Standard Sesnon #29 (Aliso Canyon)

Work over rig - 2 Tours - 6day week

TIME ESTIMATE

ITEM	TOURS
Move in and rig up	2
Kill well	1
Install B.O.P.E. and test	1
Pull tubing and packer	4
Mill over "D" packer	4
Clean out to 9077'	3
Pressure test	4
Remedial contingency	4
Run packer	1
Complete well	4
Sub-Total	28
Contingencies	3
Grand Total	31 Tours

CALENDAR DAYS = 18

COST ESTIMATE

ITEM	$
Rig 31 x 8 x 150	37,000
Drilling fluid	5,000
Fishing and milling	6,000
Pressure test	6,000
Remedial contingency	6,500
Packer and safety valve	15,000
Tubing replacement	5,000
Trucking and miscellaneous	10,000
Sub-Total	$ 90,500
Company Labor	3,000
Contingencies	7,500
Mud Plant Prorate	7,500
Grand Total	$108,500

COST BREAKDOWN

Company Labor	$ 3,000
Direct Non Labor	23,000
Direct Contract	82,500
Total	$108,500

2/28/77

AC_CPUC_0118111

TUBING DETAIL

No. Jts.	Item	Length	Depth
	Below K. B.	6.90	
	2-7/8" donut and pup joint	6.00	
	2-7/8" EU 8 thd. pup jt.	3.95	
184	2-7/8" EU 8 thd. J-55 tubing	5668.65	
	2-7/8" EU 8 thd. pup jt.	4.05	5689.55
	2-1/2" Camco KBMG mandrel w/1/4" BK 925# valve	7.35	5696.90
40	2-7/8" EU 8 thd. J-55	1224.08	
	2-7/8" EU 8 thd. pup jt.	4.03	6925.01
	2-1/2" Camco KBMG mandrel w/1/4" BK 915# valve	7.35	6932.36
34	2-7/8" EU 8 thd. J-55 tubing	1041.10	
	2-7/8" EU 8 thd. pup jt.	4.08	7977.54
	2-1/2" Camco KBMG mandrel w/1/4" BK 905# valve	7.35	7984.89
1	2-7/8" EU 8 thd. J-55 tubing	31.37	
	2-7/8" x 2.313" Otis "X" landing nipple	1.00	8017.26
1	2-7/8" EU 8 thd. J-55 tubing	30.23	
	2-7/8" x 2-3/8" EU 8 thd. crossover	1.15	8048.64
9	2-3/8" EU 8 thd. J-55 tubing	273.63	
	2-3/8" Camco B mandrel w/1/4" J-40 895# valve	4.10	8326.37
1	2-3/8" EU 8 thd. J-55 tubing	30.15	
	2-3/8" x 1.93 Camco sliding sleeve	2.70	8359.22
1	2-3/8" EU 8 thd. J-55 tubing	29.97	
	2-3/8" x 1.875 Otis "X" landing nipple	.95	8390.14
1	2-3/8" EU 8 thd. J-55 tubing	29.98	
	2-3/8" x 5" 18# Camco Hydrostatic set packer HRP-1 16 turns right to release	5.65	
1	2-3/8" EU 8 thd. J-55 tubing	29.73	
	2-3/8" x 1.875 Otis "X" landing nipple	.95	8456.45
	2-3/8" EU 8 thd. pup jt. w/20 mesh slots	10.00	8466.45
	2-3/8" EU 8 thd. pup jt. w/20 mesh slots	10.00	8476.45
	2-3/8" Otis polish nipple	1.50	8477.95
	2-3/8" EU 8 thd. pup jt.	4.20	
	2-3/8" x 1.875 Otis "X" landing nipple	.95	8483.10
	2-3/8" EU 8 thd. pup jt. w/20 mesh slots	10.20	8493.30
	2-3/8" EU 8 thd. pup jt. w/20 mesh slots	10.00	8503.30
	2-3/8" Otis polish nipple	1.50	8504.80
	2-3/8" EU 8 thd. pup jt.	4.05	
	2-3/8" EU 8 thd. pup jt.	8.00	
	2-3/8" x 1.81 Camco type "D" seating nipple	.95	8517.80
	2-3/8" Baker locator sub for Model "D" packer @ 8517'	.40	8518.20
	Baker seals 5 sets for Model "D" packer	4.60	8522.22

NOTE: The slotted tubing above is J-55 with special clearance N-80 collars slotted 20M, 12 rows, 1-1/2" slots on 6" centers.

AC_CPUC_0118112

CULATION SHEET

REF. _____ 2-17-73

BY DSS

CHECKED _____


DATE 12-22-72

SHEET NO. ____ OF ____ SHEETS

TITLE STANDARD SESSION 29


ELEV. G.L. 2848.77'

ORIG. ZERO 6.92' ABOVE G.L.



AC_CPUC_0118113

PRESSURE test STANDARD SESNON #29 ALISO CANYON



Water - C -
0433

Safety Factor 1.0

7"
23# N80-0-974. 6340
23# J55-974-4452- 4360
23# N80-4452-6494- 6340
26# N80-6494-8170- 7240
18# J55-8075-8725- 7000

AC_CPUC_0118114

1-71
Printed in U. S. A.

GAS RESEARCH AND ENGINEERING SERVICE
5119 KINSIE STREET
LOS ANGELES, CALIFORNIA 90040
PHONE 261-9726

VICTOR F. GARMAN

ROBERT P. CHAFFEY

GAS ANALYSIS BY CHROMATOGRAPH

SOUTHERN CALIFORNIA GAS COMPANY

Sample Description: Gas from SS - 29 (Gas Flowing)

Date 3-11-74 10:39 a.m. Type 2 Area or/ Plant No. Aliso Canyon Meter No. or Sample No. SG-N181

ANALYSIS REPORT

1. ROYALTY GAS
2. OTHER GAS
3. L. P. G.
4. GASOLINE

1. BREA
2. LONG BEACH
3. VENTURA
4. TEN SECTIONS

5. MOLINO
6. SACRAMENTO RIVER GAS SYSTEM
7. ALASKA

	MOL. %		G/M		LIQUID VOL. %		B.T.U.	SPEC. GRAV.
O_2	.01							
N_2	.93							
Co_2	2.28							
H_2								
Air								
Methane	89.86							
Ethane	5.21							
Propane	1.08		.298					
Iso - Butane	.11	+	.036	+ .237				
N - Butane	.20		.063					
Iso - Pentane	.06	+	.022	+ .138				
N - Pentane	.06		.022					
Hexane	.06		.025					
Heptane	.07		.032					
Octane	.06		.031					
Nonane plus	.01		.006					
Decane								
TOTAL	100.00		.535				1055	.628

Pressure 580 psig

AC_CPUC_0118115

BY DSS

TITLE STANDARD SESNON 29


CHECKED

ELEV. G.L. 2848.77'

DATE 12-22-72

ORIG. ZERO 6.92' ABOVE G.L.

SHEET NO. ____ OF ____ SHEET



7" CSG. DETAIL

	I.D.	DRIFT	BURST	COLL
0-974' 23# N-80	6.366	6.241	6340	4300
974'-4452' 23# J-55	"	"	4360	3290
4452'-6494' 23# N-80	"	"	6340	4300
6494'-8170' 26# N-80	6.276	6.151	7240	5320

26# IS JAPANESE T&C

23# IS YOUNGSTOWN T&C

CEMENTED @ 8170' WITH 550 SK. COLTON HI-TEMP

WSO HISTORY

1. SHOE TEST - FOUND SHOE AT 8180'. C.O. TO 8186' LIGHT STEADY BLOW FOR 3 MIN. THEN DEAD. 30' RISE DRLG. MUD. W.S.O. APPROVED BY D.O.G.
2. SPLICE TEST - 1 PUFF, THEN DEAD. 90' RISE DRLG. MUD, NO WATER. SPLICE TEST OK'D BY COMPANY.
3. C.O. TO 8720. 4 JET HOLES AT 8710'. MEDIUM STEADY BLOW FOR 45 MIN., THEN DEAD. 1450' RISE OIL, WNSO. SET RETAINER AT 8650'. BREAKDOWN 6000 PSI. 4 CU. FT. PER MIN. AT 3300 PSI. SQZ'D 34 SX. BELOW RETAINER. 28 SX. TO FORMATION F.P. 7200 PSI.
4. C.O. TO 8720'. 4 HOLES AT 8705'. LIGHT STEADY BLOW FOR 2 MIN. THEN DEAD. 20' RISE DRLG. FLUID. WSO OK BY D.O.G.

WITHDRAWAL ONLY

AC_CPUC_0118116

1-71
Printed in U. S. A.

GAS RESEARCH AND ENGINEERING SERVICE
5119 KINSIE STREET
LOS ANGELES, CALIFORNIA 90040
PHONE 261-9726

VICTOR F. GARMAN ROBERT P. CHAFFEY

GAS ANALYSIS BY CHROMATOGRAPH

SOUTHERN CALIFORNIA GAS COMPANY

Sample Description: SS - 29 (8000') 1500 psig, 177°F.

Received Date 5-4-73 Type 2 Area or/ Plant No. Aliso Canyon Meter No. or Sample No. SG-N113

ANALYSIS REPORT

1. ROYALTY GAS
2. OTHER GAS
3. L. P. G.
4. GASOLINE

1. BREA
2. LONG BEACH
3. VENTURA
4. TEN SECTIONS

5. MOLINO
6. SACRAMENTO RIVER GAS SYSTEM
7. ALASKA

NOTE: Water in sample tank.

	MOL. %		Mol. % w/Air		LIQUID VOL. %		B.T.U.	SPEC. GRAV.
O_2	.00		.090					
N_2	.37		.708					
Co_2	.16		.156					
H_2								
Air								
Methane	91.52		91.131					
Ethane	4.62		4.596					
Propane	1.78		1.769					
Iso - Butane	.27	+	.270	+				
N - Butane	.42		.419					
Iso - Pentane	.16	+	.159	+				
N - Pentane	.14		.139					
Hexane	.18		.184					
Heptane	.21		.212					
Octane	.11		.114					
Nonane	.05		.046					
Decane plus	.01		.007					
TOTAL	100.00		100.000				1119	.629

AIR FREE

AC_CPUC_0118117

Shaffer

201 S. REDWOOD AVE., P. O. BOX 398, BREA, CALIFORNIA 92621, 714/529-2134

Southern California Gas Company
P. O. Box 3249, Terminal Annex
Los Angeles, California 90051

ATTENTION: ROD GEDDIS

STANDARD SESNON 29
tubing head

This is to certify that this equipment, Serial # 1886I-T has been tested to A.P.I. specifications and witnessed by me this date 2/8/73.

RUCKER SHAFFER

R. L. Dowell

Robert L. Dowell
Sales Engineer

RLD:cn

AC_CPUC_0118118

DAILY DRILLING REPORT

2-23 Pulled Johnston 5" bridge plug from 8578' which was run on 2-17-73. Ran Baker squeeze tools to treat two sections of Sesnon Zone with Clay-Loc. Treated perforations 8528'to 8552' (24'), 8602' to 8638' (36') with Clay-Loc and KCL (300 barrels each). Attempted to treat perforations 8658' to 8668' and 8674' to 8694'. Unable to pump away fluid at 3500 psi. Decision was made to discontinue treatment. Pulled tools out of liner.

2-24 Pulled squeeze tools. Ran 5" Baker Model D packer to 8519'. Ran 481' of 2-3/8" tubing string, Baker nipples, Page valves, Camco packer, two circulating sleeves, two gas lift valves. Could not run 2-7/8" tubing because collar would not accept 1/4" liner protector. These required special machining for set of 2-7/8" collar

2-25 Shut-in.

2-26 Ran and tested 2-7/8" tubing string at 5000 psi. Ran and tested 1/4" control line at 5000 psi. Landed tubing string with 9000 lbs. on the Baker packer. Tested rubing hanger--control line connection, 5000 psi.

2-27 Removed BOPE. Installed well head. Tested at 5000 psi; tubing hanger seals and lower seals on extended neck; upper seals on extended neck and area above; control line port connection and both seals on extended neck. Displaced 210 barrels of fluid; set Camco packer with nitrogen pressure. Opened circulating sleeve to perforated 8456' to 8502'.

2-28 Displaced 200 barrels of salt water with nitrogen (down annulus to #1 gas lift valve at 5695'). Pulling nitrogen from annulus and tubing to -0- pressure. Left all well heads closed. 5000 psi on 1/4" control line. Moved out equipment.

AC_CPUC_0118119

SS 29

DAILY DRILLING REPORT

2-12 Opened valve at surface for final flow at 6:20 AM. Flowed for 12 hours. Maximum rate of 2.7 M^2cf/d. Shut-in at tool at 6:20 PM.

2-13 Pulled tester loose. Dropped down with tester to retrieve and relocate bridge plug in preparation to retest upper S-8 sand. Could feel to fill and had no apparent difficulty latching onto bridge plug. Could not pull plug loose. Could not back tester off of plug. Jarred for 5 hours with no results. Maximum pull was 90,000 lbs., dropped bar and back scuttled for 6 hours through knock out plug in tubing at 8305'. Mud in good condition. Rigged up McCullough. Ran chemical cutter in tubing and cut same at 8301'. Wire line measurement 8297'. Pipe measurement pulled out of hole. Top of fish at 8297'.

2-14 Made up fishing tool consisting of overshot for 2-3/8" tubing, four 3-3/4" drill collars, bumper sub, and s jars. Ran overshot to 8297' and latched onto fish. Jarred loose. Pulled out of hole with tubing and test string leaving bridge plug only in hole. Started in with bridge plug overshot.

2-15 Could not latch onto bridge plug fish. Circulated out fill but could make little hole with overshot. Pulled out and ran Johnston tungsten carbide toothed retrieving tool. Circulated and drilled using tongs. Latched onto and released bridge plug. Pulled out of hole without fish. Laid down drill collars and started back in with overshot bumper sub and jars.

2-16 & 17 Recovered 5" bridge plug. Reran test tools and flow tested from 8578' to 8516'. Left 5" bridge plug at 8578'.

2-18 Shut in.

2-19, 20 & 21
Ran 7" bridge plug to 8065'. Tested to 1050 psi for 10 minutes.

2-22 Pulled tubing. Removed BOPE. Removed old well head. Installed well head. Reinstalled BOPE. Tested rams and Hydril at 1200 psi for 15 minutes. Pulled bridge plug from 8065'. Ran 5" bridge plug and packer. Treated S-4 zone (8456' to 8502') with Clay-Loc. Treated upper S-8 Zone (8528' to 8552' and 8602' to 8638'). Relocated tools. Attempted to Clay-Loc treat lower S-8 (8658' to 8668' and 8674' to 8694'). Unable to pump any material away to formation at 3500 psi.

AC_CPUC_0118120

SS 29

DAILY DRILLING REPORT

2-2 through
2-6 Mixed fluid and killed well. Moved in CPS and rigged up. Installed BOPE. Pulled tubing and packer. Ran 4-1/8" bit and 5" scraper. Found fill at 8970'. Cleaned out sand bridges and tagged bottom at 9074'. Circulated on bottom for 2 hours.

2-7 Ran 7" casing scraper and tagged top of liner at 8082'. Rigged up Dresser Atlas. Ran Cement Bond Log 7950' to 9056'. Neutron Life-time Log and Gama Ray Log 8280' to 9050', and Densi Log 8294' to 8788'. Cement bond at top of S-4, very good. Good WSO at shoe above. No WSO test at top of S-4 is required.

2-8 Ran in with bridge plug on full bore packer. Set bridge plug at 8065'. Pulled full bore to 8025' and tested bridge plug with 1910' psi for 15 minutes, OK. Pulled up and set full bore at 3444'. Tested 3444' to 8065' with 2060 psi for 15 minutes, OK. Tested from surface to 3444' with 2550 psi for 15 minutes, OK. Pulled up and set full bore at 2341'. Tested from surface to 2341' with 3000 psi for 15 minutes, OK. Pulled up and set full bore at 1180'. Tested from surface to 1180' with 3550 # casing. Test OK. Ran in from 1180' and retrieved bridge plug. Rigged up Dresser-Atlas. Jet perforated four 1/2" holes per foot: 8528' to 8552', 8602'to 8638', 8658' to 8668' and 8674' to 8694'.

2-9 Made up and ran Johnston tester and bridge plug. Set bridge plug at 8715'. Pulled up and set test tool at 8486', tail to 8511'. Opened tool at 11:12 AM. Could not overcome minimum trap pressure. Maximum pressure, 142 psi. Closed tool at 12:32 PM. Recovered bridge plug and set at 8580'. Pulled up and set test tool at 8480', tail to 8505'. Opened tool to 1:10 PM. Tool open 1 hour Maximum pressure, 20 psi. Recovered bridge plug and set at 8515'. Started out of hole with tester. Fluid heading out of hole at 5918' above tester. Dropped bars. Back scuttled valves, did not spot. Continued pulling test tool and turning heading fluid to tanks. Total fluid rise, approximately 300' of thin oily gas cut workover fluid and 5600' of gas cut oil. Recovered fine sand and test tool. Charts showed first test OK. Second test plugged tool. Rigged up Dresser-Atlas and Jet perforated four 1/2" holes per foot at 8456' to 8502'.

2-10 Made up and ran Johnston tester. Set packer at 8436' with tail to 8454'. Opened tool at 10:37 AM. Shut-in at surface after 5 hour clean up flow.

2-11 Idle.

AC_CPUC_0118121

Shaffer

201 S. REDWOOD AVE., P. O. BOX 398, BREA, CALIFORNIA 92621, 714/529-2134

Southern California Gas Company
P. O. Box 3249, Terminal Annex
Los Angeles, California 90051

ATTENTION: ROD GEDDIS

STANDARD - SESNON 29

Csg head 4 1/16 3/4" studs

This is to certify that this equipment, Serial # 15099

has been tested to A.P.I. specifications and witnessed

by me this date 1/2/72.

RUCKER SHAFFER

R L Dowell

Robert L. Dowell
Sales Engineer

RLD:cn

AC_CPUC_0118122

FORM 107

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION

DIVISION OF OIL AND GAS

Notice of Intention to Deepen, Redrill, Plug or Alter Casing in Well

This notice must be given before work begins; one copy only

Los Angeles Calif. January 19, 1973

DIVISION OF OIL AND GAS

In compliance with Section 3203, Chapter 93, Statutes of 1939, notice is hereby given that it is our intention to commence the work of deepening, redrilling, plugging or altering casing at Well No. SFZU SS29 well file
(Cross out unnecessary words)

_____, Sec. 28, T. 3N, R. 16W, SB B. & M.

Aliso Canyon Field, Los Angeles County.

The present condition of the well is as follows:

1. Total depth. 9790'; Pg. 9094'

2. Complete casing record, including plugs:

11-3/4", 42# C 1042'
7" 23# & 26# C 8170'; WSO out shoe, 8180'*
1002'-5", 18# L 9077'
Pf: 8727'-9077' (120M x 12R x 6"C)
TLH 8075'
WSO - 8705'*

* Approved by D.O.G.

3. Last produced. _____ (Date) _____ (Oil, B/D) _____ (Water, B/D) _____ (Gas Mcf/D)

The proposed work is as follows:

Jet perforate four 1/2" holes per foot and/or reperforate 2-1/2" holes per foot in the Sesnon zone as required to convert well to a gas storage well.

P. O. Box 54790, Terminal Annex
Los Angeles, California 90054
(Address)

(213) 689-3561
(Telephone No.)

Pacific Lighting Service Company
(Name of Operator)

By R. S. Magruder Jr.

ADDRESS ONE COPY OF NOTICE TO DIVISION OF OIL AND GAS IN DISTRICT WHERE WELL IS LOCATED

AC_CPUC_0118123

JOHNSTON

PRESSURE LOG*


Field Report No. 29031-Z

Instrument: Number T-504

Capacity 7000 p.s.i.

Depth — ft.

*a continuous tracing of the original chart



MEM 3-7-73

Form J-231b

AC_CPUC_0118124


SOUTHERN CALIFORNIA GAS COMPANY
S.S. #29
LOS ANGELES COUNTY, CALIFORNIA
FIELD: ALISO CANYON
DATE: 2-23-73

INSTRUMENT RUN BELOW RETRIEVABLE
BRIDGE PLUG.

JOHNSTON

FIELD REPORT NO.	RECORDER NO.
29031 Z	T-504
CAPACITY	REPORTS REQUESTED
7000#	5-

b.b/tw
8552



AC_CPUC_0118125

JOHNSTON

Schlumberger

technical report

F. R. # 02553 C

COMPANY SOUTHERN CALIFORNIA GAS COMPANY WELL S.S. #29 TEST NO. 3 COUNTY LOS ANGELES STATE CALIFORNIA

AC_CPUC_0118126

JOHNSTON

PRESSURE LOG*


Field Report No. 02553C

Instrument:
Number T-159

Capacity 7000 p.s.i.

Depth 8530 ft.

*a continuous tracing of the original chart



Form L-238h

AC_CPUC_01118127

JOHNSTON
...found a better way

SURFACE INFORMATION

Description (Rate of Flow)	Time	Pressure (P.S.I.G.)	Surface Choke
Opened Tool	1300	-	-
PULLED PACKER LOOSE	1505	-	-

Cushion Type	Amount	Pressure	Bottom Choke Size
	-		1/2"

MUD DATA

Mud Type SALT WATER GEL Wt. 63
Viscosity 45 Water Loss - C.C.
Resist: of Mud - @ - °F; of Filtrate - @ - °F
Chloride Content - PPM

EQUIPMENT & HOLE DATA

Type Test M. F. E. CASING
Formation Tested FREW
Elevation - Ft.
Net Productive Interval 34 Ft.
Estimated Porosity - %
All Depths Measured From KELLY BUSHING
Total Depth - Ft.
Main Hole/Casing Size 7"
Rat Hole/Liner Size 5" x 18#
Drill Collar Length - I.D. -
Drill Pipe Length 8493' I.D. -
Packer Depth(s) 8516 Ft.

MULTI-FLOW EVALUATOR FLUID SAMPLE DATA

Sampler Pressure ____ P.S.I.G. at Surface
Recovery: Cu. Ft. Gas ____
cc. Oil ____
cc. Water ____
cc. Mud ____
Tot. Liquid cc. ____
Gravity ____ °API @ ____ °F.
Gas/Oil Ratio ____ cu. ft./bbl.

		RESISTIVITY	CHLORIDE CONTENT
Recovery Water	@ °F.		ppm
Recovery Mud	@ °F.		
Recovery Mud Filtrate	@ °F.		ppm
Mud Pit Sample	@ °F.		
Mud Pit Sample Filtrate	@ °F.		ppm

RECOVERY DESCRIPTION	FEET	BARRELS	% OIL	% WATER	% OTHERS	API GRAVITY	RESISTIVITY	CHL. PPM
OIL (APPROXIMATELY)	2076	10.0	100			@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	

Remarks: ____

Address 1200 WEST LINCOLN STREET; MONTEBELLO, CALIFORNIA 90640

Company SOUTHERN CALIFORNIA GAS COMPANY Field ALISO CANYON
Well S.S. #29 Location -
Test Interval 8528' TO 8552' Test # 3 Date 2-17-73

County LOS ANGELES State CALIFORNIA
Technician FRY (VENTURA) Test Approved By MR. DON SMILEY

Field Report No. 02553 C
No. Reports Requested 5

AC_CPUC_0118128

JOHNSTON
...found a better way

PRESSURE DATA

Instrument No.		T-159	T-217	
Capacity (P.S.I.G.)		7000	7000	
Instrument Depth		8530'	8535'	
Instrument Opening		INSIDE	OUTSIDE	
Pressure Gradient P.S.I./Ft.				
Well Temperature °F.		183	183	
Initial Hydrostatic Mud	A	3728	3767	
Initial Shut-in	B	-	-	
Initial Flow	C	231	229	
	C-1	776	802	
Final Flow	D	746	772	
Final Shut-in	E	-	-	
Final Hydrostatic Mud	F	3739	3775	

Field Report No. 02553 C

TIME DATA

	Time Given	Time Computed
	- Mins.	Mins.
	- Mins.	Mins.
	- Mins.	Mins.
	- Mins.	Mins.
	125 Mins.	Mins.
	- Mins.	Mins.

Remarks:

*Shut in pressure did not reach static reservoir pressure.

Clock Travel _____ inches per min.


PRESSURE INCREMENTS

Point Minutes	Pressure	$\frac{T+\Delta t}{\Delta t}$	Point Minutes	Pressure	$\frac{T+\Delta t}{\Delta t}$	Point Minutes	Pressure	$\frac{T+\Delta t}{\Delta t}$

AC_CPUC_0118129

JOHNSTON
...found a better way

GUIDE TO IDENTIFICATION OF DRILL STEM TEST PRESSURE CHARTS




A. Initial Hyd. Mud
B. Initial Shut-in
C. Initial Flow
D. Final Flow
E. Final Shut-in
F. Final Hyd. Mud

The following points are either fluctuating pressures or points indicating other packer settings, (testing different zones).

A-1, A-2, A-3, etc. Initial Hyd. Pressures
B-1, B-2, B-3, etc. Subsequent Shut-in Pressures
C-1, C-2, C-3, etc. Flowing Pressures
D-1, D-2, D-3, etc. Subsequent Final Flow Pressures
E-1, E-2, E-3, etc. Subsequent Final Shut-in Pressures
F-1, F-2, F-3, etc. Final Hyd. Mud Pressures
Z — Special pressure points such as pumping pressure recorded for formation breakdown.

JOHNSTON


FIELD REPORT NO.	RECORDER NO.
02553 C	T-159
CAPACITY	**REPORTS REQUESTED**
7000#	5+



AC_CPUC_0118130

JOHNSTON
...found a better way

GUIDE TO IDENTIFICATION OF DRILL STEM TEST PRESSURE CHARTS




A. Initial Hyd. Mud
B. Initial Shut-in
C. Initial Flow
D. Final Flow
E. Final Shut-in
F. Final Hyd. Mud

The following points are either fluctuating pressures or points indicating other packer settings, (testing different zones).

A-1, A-2, A-3, etc. Initial Hyd. Pressures
B-1, B-2, B-3, etc. Subsequent Shut-in Pressures
C-1, C-2, C-3, etc. Flowing Pressures
D-1, D-2, D-3, etc. Subsequent Final Flow Pressures
E-1, E-2, E-3, etc. Subsequent Final Shut-in Pressures
F-1, F-2, F-3, etc. Final Hyd. Mud Pressures
Z — Special pressure points such as pumping pressure recorded for formation breakdown.

JOHNSTON

FIELD REPORT NO.	RECORDER NO.
02553 C	T-217
CAPACITY	**REPORTS REQUESTED**
7000#	5+



AC_CPUC_0118131

COMPANY SOUTHERN CALIFORNIA GAS COMPANY WELL S.S. #29 TEST NO. 2 COUNTY LOS ANGELES STATE CALIFORNIA

JOHNSTON

Schlumberger

technical report

F. R. # 20090 B

AC_CPUC_0118132

JOHNSTON ...found a better way

SURFACE INFORMATION

Description (Rate of Flow)	Time	Pressure (P.S.I.G.)	Surface Choke
Opened Tool (2-10-73)	1037	-	1/8"
OPENED ON SURFACE	1047	980	"
	1055	1039	3/8"
	1110	921	1/2"
	1140	668	"
	1240	730	"
	1340	747	"
	1440	757	"
CLOSED ON SURFACE	1537	762	"
(INITIAL SHUT-IN)			
(2-12-73)			
OPENED WELL TO TRAP	0620	1180	CLOSED
	0700	779	1/2"
	0800	810	"
	0930	827	"
	1030	807	"
	1130	767	"
	1230	777	"
	1330	767	"
	1430	767	"
	1630	765	"
	1730	765	"
	1820	765	"
CLOSED FOR FINAL SHUT-IN	1823	765	"
(2-13-73)			
PULLED PACKER LOOSE	0640	-	-

Cushion Type	Amount	Pressure	Bottom Choke Size
	-		1/2"

MUD DATA

Mud Type WATER AND GEL Wt. 63

Viscosity - Water Loss - C.C.

Resist: of Mud - @ - °F; of Filtrate - @ - °F

Chloride Content - PPM

EQUIPMENT & HOLE DATA

Type Test M. F. E. CASING

Formation Tested -

Elevation - Ft.

Net Productive Interval 46 Ft.

Estimated Porosity - %

All Depths Measured From KELLY BUSHING

Total Depth 9077 Ft.

Main Hole/Casing Size 7"

Rat Hole/Liner Size 5"

Drill Collar Length - I.D. -

Drill Pipe Length 8395' I.D. -

Packer Depth(s) 8423 Ft.

MULTI-FLOW EVALUATOR FLUID SAMPLE DATA

Sampler Pressure ____ P.S.I.G. at Surface

Recovery: Cu. Ft. Gas

cc. Oil

cc. Water

cc. Mud

Tot. Liquid cc.

Gravity ____ °API @ ____ °F.

Gas/Oil Ratio ____ cu. ft./bbl.

	RESISTIVITY	CHLORIDE CONTENT
Recovery Water	____ @ ____ °F.	____ ppm
Recovery Mud	____ @ ____ °F.	
Recovery Mud Filtrate	____ @ ____ °F.	____ ppm
Mud Pit Sample	____ @ ____ °F.	
Mud Pit Sample Filtrate	____ @ ____ °F.	____ ppm

RECOVERY DESCRIPTION	FEET	BARRELS	% OIL	% WATER	% OTHERS	API GRAVITY @ °F.	RESISTIVITY @ °F.	CHL. PPM
-								
						@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	

Remarks:

Address 1200 WEST LINCOLN; MONTEBELLO, CALIFORNIA 90640; ATTN: MR. DON SMILEY

Company SOUTHERN CALIFORNIA GAS COMPANY Field ALISO CANYON

Well S.S. #29 Location -

Test Interval 8456' TO 8502' Test # 2 Date 2-10-73

County LOS ANGELES State CALIFORNIA

Technician BOGGS (VENTURA) Test Approved By MR. D. S. SMILEY

Field Report No. 20090 B

No. Reports Requested 5

AC_CPUC_0118133

JOHNSTON
...found a better way

PRESSURE DATA

Instrument No.		T-159	T-217	
Capacity (P.S.I.G.)		7000	7000	
Instrument Depth		8435'	8439'	
Instrument Opening		INSIDE	INSIDE	
Pressure Gradient P.S.I./Ft.				
Well Temperature °F.		183	183	
Initial Hydrostatic Mud	A	3729.3	3749.5	
Initial Shut-in	B	1470.6	-	
Initial Flow	C	1304.6	1303.1	
	C-3	1419.4	1398.2	
	C-4	1447.1	-	
Final Flow	D	1424.9	-	
Final Shut-in	E	1476.1	-	
Final Hydrostatic Mud	F	3754.2	3779.9	
Remarks:	C-1	1456.7	1457.7	
	C-2	1442.9	1437.9	

Field Report No. 20090 B

TIME DATA

	Time Given	Time Computed
	2323 Mins.	2322 Mins.
	300 Mins.	303 Mins.
	- Mins.	- Mins.
	- Mins.	- Mins.
	723 Mins.	721 Mins.
	737 Mins.	737 Mins.

INSTRUMENT NUMBER T-217; THE CLOCK STOPPED AT POINT "C-3" LABELED ON CHART, THEN BEGAN RUNNING AGAIN DURING THE FINAL SHUT-IN.

*Shut in pressure did not reach static reservoir pressure.

Clock Travel 0.02059 inches per min.


PRESSURE INCREMENTS

INITIAL FLOW			FINAL FLOW			INITIAL SHUT-IN		
Point Minutes	Pressure	$\frac{T+\Delta t}{\Delta t}$	Point Minutes	Pressure	$\frac{T+\Delta t}{\Delta t}$	Point Minutes	Pressure	$\frac{T+\Delta t}{\Delta t}$
C 0	1304.6		C-4 0	1447.1		C-3 0	1419.4	
2	1321.2		1	1442.9		2	1442.9	
4	1344.7		2	1436.0		4	1462.3	
6	1364.1		3	1431.8		6	1467.8	
8	1397.3		4	1429.1		8	1469.2	
10	1426.3		5	1429.1		10	1470.6	
12	1444.3		6	1429.1			NO CHANGE IN PRESSURE	
14	1452.6		7	1429.1			FROM 10 MINUTES THROUGH	
16	1456.7		8	1429.1			2322 MINUTES	
18	1456.7		9	1429.1		B 2322	1470.6	
20	1456.7		10	1429.1				
22	1448.4		20	1429.1			FINAL SHUT-IN	
24	1447.1		30	1427.7		D 0	1424.9	
26	1444.3		40	1427.7		1	1459.5	
28	1444.3		50	1426.3		2	1466.4	
30	1442.9		60	1426.3		3	1469.2	
32	1441.5		70	1426.3		4	1472.0	
34	1441.5		80	1426.3		5	1474.7	
36	1427.7		90	1424.9		6	1476.1	
38	1422.2			NO CHANGE IN PRESSURE			NO CHANGE IN PRESSURE	
40	1419.4			FROM 90 MINUTES THROUGH			FROM 6 MINUTES THROUGH	
42	1419.4			721 MINUTES			737 MINUTES	
44	1418.0		D 721	1424.9		E 737	1476.1	
46	1418.0							
48	1418.0							
50	1419.4							
	NO CHANGE IN PRESSURE							
	FROM 52 MINUTES THROUGH							
	303 MINUTES							
C-3 303	1419.4							

AC_CPUC_0118134

JOHNSTON
...found a better way


GUIDE TO IDENTIFICATION OF DRILL STEM TEST PRESSURE CHARTS



A. Initial Hyd. Mud
B. Initial Shut-in
C. Initial Flow
D. Final Flow
E. Final Shut-in
F. Final Hyd. Mud

The following points are either fluctuating pressures or points indicating other packer settings, (testing different zones).


A-1, A-2, A-3, etc. Initial Hyd. Pressures
B-1, B-2, B-3, etc. Subsequent Shut-in Pressures
C-1, C-2, C-3, etc. Flowing Pressures
D-1, D-2, D-3, etc. Subsequent Final Flow Pressures
E-1, E-2, E-3, etc. Subsequent Final Shut-in Pressures
F-1, F-2, F-3, etc. Final Hyd. Mud Pressures
Z — Special pressure points such as pumping pressure recorded for formation breakdown.



AC_CPUC_0118135

JOHNSTON
...found a better way


GUIDE TO IDENTIFICATION OF DRILL STEM TEST PRESSURE CHARTS



A. Initial Hyd. Mud
B. Initial Shut-in
C. Initial Flow
D. Final Flow
E. Final Shut-in
F. Final Hyd. Mud

The following points are either fluctuating pressures or points indicating other packer settings, (testing different zones).

A-1, A-2, A-3, etc. Initial Hyd. Pressures
B-1, B-2, B-3, etc. Subsequent Shut-in Pressures
C-1, C-2, C-3, etc. Flowing Pressures
D-1, D-2, D-3, etc. Subsequent Final Flow Pressures
E-1, E-2, E-3, etc. Subsequent Final Shut-in Pressures
F-1, F-2, F-3, etc. Final Hyd. Mud Pressures
Z — Special pressure points such as pumping pressure recorded for formation breakdown.



AC_CPUC_0118136

JOHNSTON

Schlumberger

technical report

F. R. # 20089 B

COMPANY SOUTHERN CALIFORNIA GAS COMPANY WELL S.S. #29 TEST NO. 1 COUNTY LOS ANGELES STATE CALIFORNIA

AC_CPUC_0118137

JOHNSTON

PRESSURE LOG*


Field Report No. 20089 B

Instrument: Number T-159

Capacity 7000 p.s.i.

Depth 1st setting 8498 ft.
2nd setting —

*a continuous tracing of the original chart



Form J-228a

AC_CPUC_0118138

JOHNSTON
...found a better way

SURFACE INFORMATION

Description (Rate of Flow)	Time	Pressure (P.S.I.G.)	Surface Choke
Opened Tool	1102	-	-
	1115	102	-
	1135	125	-
	1150	137	-
	1205	142	-
OPENED LINE AND BLED OFF			
PRESSURE IN 15 MINUTES.			
PULLED PACKER LOOSE	1232	-	-
RETRIEVED BRIDGE PLUG.			
RE-SET BRIDGE PLUG ABOVE			
PERFORATIONS AT 8528' TO			
8552'.			
RE-SET PACKER	1308	-	-
RE-OPENED TOOL	1310	-	-
LIGHT BLOW FOR BALANCE OF			
TEST.			
PULLED PACKER LOOSE	1410	-	-

Cushion Type	Amount	Pressure	Bottom Choke
	-		Size 1/2"

MUD DATA

Mud Type WATER WITH GEL Wt. 63
Viscosity - Water Loss - C.C.
Resist: of Mud - @ - °F; of Filtrate - @ - °F
Chloride Content - PPM

EQUIPMENT & HOLE DATA

Type Test M. F. E. CASING
Formation Tested -
Elevation - Ft.
Net Productive Interval 90 Ft.
Estimated Porosity - %
All Depths Measured From -
Total Depth 9077 Ft.
Main Hole/Casing Size 7"
Rat Hole/Liner Size 5"
Drill Collar Length - I.D. -
Drill Pipe Length 8456' I.D. -
Packer Depth(s) 8486 Ft.

MULTI-FLOW EVALUATOR FLUID SAMPLE DATA

Sampler Pressure _____ P.S.I.G. at Surface
Recovery: Cu. Ft. Gas _____
cc. Oil _____
cc. Water _____
cc. Mud _____
Tot. Liquid cc. _____
Gravity _____ °API @ _____ °F.
Gas/Oil Ratio _____ cu. ft./bbl.

	RESISTIVITY	CHLORIDE CONTENT
Recovery Water	_____ @ _____ °F.	_____ ppm
Recovery Mud	_____ @ _____ °F.	
Recovery Mud Filtrate	_____ @ _____ °F.	_____ ppm
Mud Pit Sample	_____ @ _____ °F.	
Mud Pit Sample Filtrate	_____ @ _____ °F.	_____ ppm

RECOVERY DESCRIPTION	FEET	BARRELS	% OIL	% WATER	% OTHERS	API GRAVITY	RESISTIVITY	CHL. PPM
GAS	-	-				@ °F.	@ °F.	
DRILLING FLUID	300	-				@ °F.	@ °F.	
OIL	5500	-				@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	
						@ °F.	@ °F.	

Remarks:

Address 1200 WEST LINCOLN; MONTEBELLO, CALIFORNIA 90640; ATTN: MR. DON SMILEY

Company SOUTHERN CALIFORNIA GAS COMPANY Field ALISO CANYON
Well S.S. #29 Location -
Test Interval 8528' TO 8552'; 8602' TO 8638'; 8658' TO 8668'; 8674' TO 8694' Test # 1 Date 2-9-73
County LOS ANGELES State CALIFORNIA
Technician BOGGS (VENTURA) Test Approved By MR. D. S. SMILEY
Field Report No. 20089 B
No. Reports Requested 5

AC_CPUC_0118139

JOHNSTON
...found a better way

PRESSURE DATA

		1ST. SETTING		2ND. SETTING	
Instrument No.		T-159			
Capacity (P.S.I.G.)		7000			
Instrument Depth		8498'		-	
Instrument Opening		INSIDE			
Pressure Gradient P.S.I./Ft.					
Well Temperature °F.		160			
Initial Hydrostatic Mud	A	3773	A-1	3755	
Initial Shut-in	B	-		-	
Initial Flow	C	511	C-4	3616	
	C-1	665		-	
	C-2	1102		-	
Final Flow	D	1113	D-1	2001	
Final Shut-in	E	-		-	
Final Hydrostatic Mud	F	3763	F-1	3784	
Remarks:	C-3	1039			

Field Report No. 20089 B

TIME DATA

	Time Given 1ST. SETTING	Time GIVEN 2ND. SETTING
	- Mins.	- Mins.
	- Mins.	- Mins.
	- Mins.	- Mins.
	- Mins.	- Mins.
	90 Mins.	60 Mins.
	- Mins.	- Mins.

Shut in pressure did not reach static reservoir pressure.

Clock Travel _____ inches per min.


PRESSURE INCREMENTS

Point Minutes	Pressure	$\frac{T+\Delta t}{\Delta t}$	Point Minutes	Pressure	$\frac{T+\Delta t}{\Delta t}$	Point Minutes	Pressure	$\frac{T+\Delta t}{\Delta t}$

AC_CPUC_0118140

JOHNSTON
...found a better way


GUIDE TO IDENTIFICATION OF DRILL STEM TEST PRESSURE CHARTS



A. Initial Hyd. Mud
B. Initial Shut-in
C. Initial Flow
D. Final Flow
E. Final Shut-in
F. Final Hyd. Mud

The following points are either fluctuating pressures or points indicating other packer settings, (testing different zones).

A-1, A-2, A-3, etc. Initial Hyd. Pressures
B-1, B-2, B-3, etc. Subsequent Shut-in Pressures
C-1, C-2, C-3, etc. Flowing Pressures
D-1, D-2, D-3, etc. Subsequent Final Flow Pressures
E-1, E-2, E-3, etc. Subsequent Final Shut-in Pressures
F-1, F-2, F-3, etc. Final Hyd. Mud Pressures
Z — Special pressure points such as pumping pressure recorded for formation breakdown.



AC_CPUC_0118141

JOHNSTON
...found a better way

PRESSURE DATA

		1ST. SETTING	2ND. SETTING
Instrument No.		T-217	
Capacity (P.S.I.G.)		7000	
Instrument Depth		8503'	-
Instrument Opening		INSIDE	
Pressure Gradient P.S.I./Ft.			
Well Temperature °F.		160	
Initial Hydrostatic Mud	A	3797	A-1 3776
Initial Shut-in	B	-	-
Initial Flow	C	503	C-4 3643
	C-1	646	-
	C-2	1115	-
Final Flow	D	1115	D-1 1988
Final Shut-in	E	-	-
Final Hydrostatic Mud	F	3785	F-1 3796
Remarks:	C-3	1044	

Field Report No. 20089 B

TIME DATA

	Time Given 1ST. SETTING	Time GIVEN 2ND. SETTING
	- Mins.	- Mins.
	- Mins.	- Mins.
	- Mins.	- Mins.
	- Mins.	- Mins.
	90 Mins.	60 Mins.
	- Mins.	- Mins.

*Shut in pressure did not reach static reservoir pressure.


Clock Travel _____ inches per min.

PRESSURE INCREMENTS

Point Minutes	Pressure	$\frac{T+\Delta t}{\Delta t}$	Point Minutes	Pressure	$\frac{T+\Delta t}{\Delta t}$	Point Minutes	Pressure	$\frac{T+\Delta t}{\Delta t}$

JOHNSTON
...found a better way


GUIDE TO IDENTIFICATION OF DRILL STEM TEST PRESSURE CHARTS




A. Initial Hyd. Mud
B. Initial Shut-in
C. Initial Flow
D. Final Flow
E. Final Shut-in
F. Final Hyd. Mud

The following points are either fluctuating pressures or points indicating other packer settings, (testing different zones).

A-1, A-2, A-3, etc. Initial Hyd. Pressures
B-1, B-2, B-3, etc. Subsequent Shut-in Pressures
C-1, C-2, C-3, etc. Flowing Pressures
D-1, D-2, D-3, etc. Subsequent Final Flow Pressures
E-1, E-2, E-3, etc. Subsequent Final Shut-in Pressures
F-1, F-2, F-3, etc. Final Hyd. Mud Pressures
Z — Special pressure points such as pumping pressure recorded for formation breakdown.



AC_CPUC_0118143



AC_CPUC_0118144

Report Date: 03/16/95

DAILY WELL ACTIVITIES SS 29

DATE	ACTIVITY/REMARKS

02/05/91 Sand test: SIWHP 1660, FWHP 1505, FWHT 110, ER 0.1, Q 25 MMcf/d

05/07/91 Ran temperature survey, some cooling above S-1, work over planned for SL repair, PU - 8800' (stop depth)

09/19/91 Installed two temporary - set rig anchors

09/19/91 Ran temperature survey, cooling above S-1, rig moving in on 9/20/91 to workover well, PU - 9025' (Inv - 63.0 BCF).

09/20/91 Well workover: well killed by rig personnel estimate 600 bbls lost to formation during well kill, milled old packer, squeezed cement @ 8330' re[erfprated well from 8428'-8820' OA, installed new packer and ran tubing, rig released 11/6/91

10/27/91 Ran noise log (during workover), quiet following squeeze, OK (Inv - 59.1 BCF)

12/19/91 Unloaded well into flowline, delay in unloading well due to full-field SI and continuing construction work on West side of field, temporary-set rig anchors (2) removed.

01/08/92 Sandtest: SIWHP - 1880, FWHP - 1320, FWHT - 104, SC - 0.800, ER - 1.3, Q - 18, Inv - 38.1

04/27/92 Ran temperature survey, temp. breaks near top of S-1 (cement squeeze @ 8330'), OK, PU - 9025' (Inv - 12.9 BCF)

08/13/92 Ran temperature survey, temp. gradient appears to break high (near 8125'), plan detail, PU - 9030' (Inv - 44.4 BCF)

09/14/92 Ran temperature detail (7000'-TD), most of cooling is confined to below S-4 top, cooling is below squeeze job OK, PU - 9050' (Inv - 52.0 BCF)

Report Date: 02/08/90

DAILY WELL ACTIVITIES SS 29

DATE	ACTIVITY/REMARKS
01/04/89	Sand tested, WKM partially closed during test, took well out of service to inspect the valve, piping and instrumentation. Sand tested: SIWHP 1560, FWHP 1070, FWHT 95, SC 1.20", ER 1.10%, Q 33 MMcf/d
01/09/89	Inspected casing WKM and casing lateral, OK. Put well back in service.
01/09/89	Removed 1.20" choke, installed 1.30" choke
01/17/89	Removed 1.30" choke, installed Open choke. Sand tested SIWHP 1280, FWHP 505, FWHT 95, SC Open, ER 0.8%, Q 25 MMcf/d
04/07/89	Removed Open choke, installed 1.20 choke
04/21/89	Ran temperature survey, OK
09/28/89	Ran temperature survey, OK
10/20/89	Ran temperature and noise survey, noise at shoe, will run tracer survey
11/10/89	Ran R/A tracer survey to check for shoe leak, survey shows gas movement outside the casing past the MP zone
12/13/89	Sand test: SIWHP 2030, FWHP 1570, FWHT 105, SC 1.10, ER 3.4%, Q 40 MMcf/d
01/03/90	Removed 1.10 choke, installed 1.20 choke
01/04/90	Sand test: SIWHP 1570, FWHP 1090, FWHT 104, SC 1.2, ER 6%, Q 34 MMcf/d
01/04/90	Sandtested: SIWHP 1570, FWHP 1090, FWHT 104, Choke 1.2, Rate 34, Eros 6.0

Report Date: 02/15/89

DAILY WELL ACTIVITIES SS 29

DATE	ACTIVITY/REMARKS
05/26/83	Ran temperature survey, no anomalies
10/25/83	Ran temperature survey, no anomalies
03/28/84	Ran temperature survey, no anomalies
08/23/84	Ran temperature survey, no anomalies
01/30/85	Sand test: no choke, SIWHP 1330 psi, Q 30 MMcf/d, ER 2.38%
04/02/85	Ran bottomhole pressure survey
04/17/85	Ran bottomhole pressure survey, pressure at datum (8256') 1537 psi, FL 8470'
04/29/85	Ran temperature survey insufficient shut-in prior to survey, no apparent anomalies
08/12/85	Ran temperature survey, OK
01/07/86	Sand testing: SC 1.30, SIWHP 1850, ER 0.2%, Q 47 MMcf/d
03/20/86	Ran temperature survey, OK
09/04/86	Ran temperature survey, slight anomaly above S-1, will run detail.
09/16/86	Ran detail (7300'-9000') survey, OK.
12/08/86	Sand testing: SC 1.30, SIWHP 1730, ER 12.0% (6" line); Q 40 MMcf/d
02/03/87	Eroded sacrificial sand probe.
02/05/87	X-rayed casing w/d lateral, OK.
02/06/87	Sand testing: SC 1.30, SIWHP 1215, ER 9.3% (6" line); Q 13 MMcf/d
03/20/87	Ran temperature survey, temp breaks slightly high, will monitor.
09/24/87	Ran temperature survey, anomaly above shoe possibly due to inadequate shut-in, will rerun
11/12/87	Ran temperature survey, anomaly above shoe, plan noise log.
11/17/87	Ran noise log to investigate temp anomaly shoe, high noise levels present, plan to set plug and rerun.
11/18/87	Set blanking plug in nipple @ 8029', ran noise log above plug. Noise levels were an order of magnitude lower than without the plug but still indicative of possible leak, plan tracer survey.
11/19/87	Pulled blanking plug.
11/20/87	Attempted to run tracer survey but ejector tool malfunctioned.
11/30/87	Attempted to run tracer survey but background log indicated well still contaminated from previous attempt
12/08/87	Ran tracer survey to check shoe leak, first run after shooting tracer showed large "bump" @ MP which was absent on second and all subsequent runs, no other indication of leakage.
03/16/88	Ran temperature survey, OK
04/22/88	Ran pressure survey, FL 8500', P @ S-4 (8428') 2024 psi
10/14/88	Ran temperature survey, OK
01/03/89	Removed 1.10" choke, installed 1.20" choke

WELL ACTIVITY REPORTS FOR SS 29

DATE	ACTIVITY/REMARKS
1/11/79	Attempted to pull separation tool. Would not come
1/12/79	Pulled separation tool and SSSV
1/24/79	Flow test: 13.7 MM, SIWHP - 1820 psi
3/19/79	Unloaded well. Rig work completed, changed to new Camco tubing retrieveable safety system
3/28/79	Foster shot fluid level. FL 8349 SIWHP 1760
4/4/79	Revised tubing detail
4/11/79	Foster shot fluid level. FL 8349 SIWHP 1750
5/4/79	Put well on tubing cleanup flow 5/2/79. S/I well 5/3/79. Realsed well for injeciton
8/10/79	Ran temperature survey. Could not get down. Plug in new Camco SSSV
8/15/79	Pulled Otis choke. Made feeler run to 9047'
10/11/79	Hanson set empty choke mandrel. ID .750
10/23/79	Foster shot fluid level. FL 8189 SIWHP 2910
10/29/79	Foster shot fluid level. FL 8213 SIWHP 3020
11/5/79	Foster shot fluid level. FL 8213 SIWHP 2960
11/13/79	Foster shot fluid level. FL 8217 SIWHP 3060
11/21/79	Foster shot fluid level. FL 8217 SIWHP 3050
11/26/79	Foster shot fluid level. FL 8220 SIWHP 3050
6/10/80	Smith attempted temperature survey. Hydrate plug below master valve. Dumped methanol in well but still could not get through plug.
8/26/80	Archer-Reed pulled BH choke, choke holder had come off and went to bottom of well. Cost $206.50
9/8/80	Gurevich ran temperature survey
10/3/80	Triangle ran noise log. (No apparent leak) Cost $2,628.00
10/10/80	Archer-Reed set .860 BHC. Cost $186.50
4/27/81	Fred ran temperature survey
9/17/81	Fred pulled BHC
9/18/81	Pruett pulled BHC. Cost $291.00
9/21/81	Harry ran temperature survey
9/24/81	Pruett ran BHC. Cost $343.00
9/25/81	Pruett pulled BHC
10/6/81	Triangle ran noise log
11/20/81	Pruett ran BHC
12/4/81	Installed snad test probes
12/14/81	Ran sand tests
1/26/82	Pruett pulled BHC
1/27/82	Sand testing
6/22/82	Temperature survey. No anomalies.
7/9/82	Ran 2½" Otis BHC, didn't set reran choke to 8027'. Well back in service. Archer Reed #32753, $428.00
10/18/82	Temperature survey. No anomalies
11/3/82	Reran BHC. Archer Reed #33172, $803.50
2/14/83	Archer Reed pulled Otis 2.205" choke from 8029'. AR#33498, $115.00

INTEROFFICE SOUTHERN CALIFORNIA gas COMPANY CORRESPONDENCE

Richard L. Adamczyk

TO J. B. Lane FROM Richard L. Adamczyk DATE September 13, 1990

SUBJECT SS 29 Workover, Aliso Canyon

The workover to repair the SS 29 suspected shoe leak should be deferred. A noise log was run on 8/30/90. Additional discussion and evaluation indicates that the suspected leak does not warrant remedial action at this time.

Plans are to closely monitor the well over the next year. A noise log and tracer survey may be run next year if temperature survey results show an anomaly.

However, if inventory reaches approximately 55 BCF this fall, we plan on running a tracer survey at that time.

If you have any questions, please advise.

RLA:ll

cc: N. W. Buss
R. C. Hazel
L. D. Krohmer
M. E. Melton
Well History File

64-F

file

INTEROFFICE CORRESPONDENCE

SOUTHERN CALIFORNIA gas COMPANY

M E Melton

TO R. W. Weibel FROM M. E. Melton DATE April 12, 1988

SUBJECT Deferral and Monitoring Plan for SS-29 Possible Shoe Leak

I agree with Jim Mansdorfer's memo of January 8, 1988 and Ken Taira's memo of April 8, 1988. SS-29 should be deferred until a new monitor log is run in the Fall.

Should further monitoring indicate the need for workover, repair the leak first, then consider stimulation as recommended by WelChem.

MEM:hr
Attachment

Approved by: R W Weibel
R. W. Weibel

cc: J. D. Mansdorfer
R. E. Wallace

64-F

AC_CPUC_0118150

INTEROFFICE SOUTHERN CALIFORNIA gas COMPANY CORRESPONDENCE

TO M. E. Melton FROM K. M. Taira DATE April 8, 1988

SUBJECT Monitor SS-29 for Possible Shoe Leak

SS-29 is a casing-flow injection/withdrawal well that may have a small shoe leak. Attached is Jim Mansdorfer's memo in which he estimates a 95% probability of a shoe leak.

RECOMMENDATION

Continue to monitor the probable shoe leak. Repeat the noise R/A tracer surveys when the reservoir is at a higher pressure. If the shoe leak becomes bad enough to require a workover, use the following workover procedure:

1. Kill well and pull 2-7/8" tubing string.

2. Pull Baker Retrieva-D packer.

3. Pull liner and squeeze cement at shoe or use an inflatable packer.

4. Consider stimulation as proposed by WelChem.

5. Re-install packer and tubing string.

DISCUSSION

In his memo, Jim explains that temperature surveys run on September 24, 1987 and November 12, 1987 indicated gas moving to the MP. Two noise surveys, on November 17 and on November 18 (after a tubing plug was set) both indicated gas movement above the shoe. A R/A tracer survey on December 8 showed an accumulation of tracer at 8160', the location of the MP. This accumulation of tracer then disappears quickly. Jim tells me that this is characteristic of shoe leaks at Aliso Canyon.

I agree with Jim's conclusion that there is probably a very small shoe leak in this well and that we should continue to monitor it.

KMT:hr
Attachments

64-F

VR 1/19/88
8829

SOUTHERN CALIFORNIA gas COMPANY

INTEROFFICE CORRESPONDENCE

JDM

TO R. W. Weibel FROM J. D. Mansdorfer DATE Jan. 14, 1988

SUBJECT Aliso Canyon Shoe Leaks

Currently there are four wells at Aliso Canyon that have indications of shoe leaks on both noise logs and RA tracer surveys. These wells are IW-77, SS-17, SS-29, and SS-30. A fifth well, F-6, had indications of a possible shoe leak on the noise log, but like SS-30 it does not have an injection or kill line and we did not get a tracer survey run on it before reservoir pressure was drawn down. Because there is no known way of calculating the leakage rate of shoe leaks, and since according to your memo of January 6 the average cost of repairing shoe leaks in 1986-87 was over $400,00, the merit of repairing these leaks is problematical. I will defer this decision to you. In the following paragraphs is some pertinent information, and attached are specifics on each well.

MP-Zone

On all four tracer surveys, the only indication of gas moving up was a "bump" at the MP zone. My interpretation of this behavior is that the MP zone is acting as the "receiving zone" for the gas that is moving up. Our recent test of the MP zone in Porter 4 indicates that this zone is very tight, so that the amount of gas that could be injected into it from the storage zone must be very low.

Surface Indications

None of the five wells currently have high annulus pressure or gas present in the soil (as of the Jan 7 flame ionization survey), although several nearby wells do exhibit these symptoms.

Helium Level of Upper Producing Zones

The fourth quarter helium survey of wells producing from zones above the storage zone continued its general downward trend. Only one well had over 20 ppm helium (storage gas is typically 300-400 ppm, native California gas is 5 ppm). Since these zones are significantly below hydrostatic pressure, they would be a logical "receiving zone" for any gas that gets past the MP. Even if all the gas produced from these zones was storage gas, its annual value would be approximately equal to the cost of just one shoe leak repair.

JDM:db

Attachments

cc: N. D. Stevenson
Well Files
A:M43

64-F

SOUTHERN CALIFORNIA gas COMPANY

INTEROFFICE CORRESPONDENCE

JDM

TO R. W. Weibel FROM J. D. Mansdorfer DATE Jan. 8, 1988

SUBJECT SS-29 Shoe Leak

Temperature surveys run on September 24 and November 12, 1987 indicated possible migration from the storage zone up to the MP. A noise log run on November 17 had noise levels of 500 mV. A noise log run on November 18 after setting a plug had noise levels of about 25 mV. A tracer survey was attempted on November 20 but was scrubbed because of a malfunction in the ejector tool. This contaminated the well and it was several weeks before another attempt could be made. On December 8 a tracer survey was successfully run, and indicated gas going away at the MP. I estimate a 95% probability that gas is moving up outside the casing to the MP.

JDM:db

cc: N. D. Stevenson
Well File


A:M45

64-F

AC_CPUC_0118153

Elevation: 2849' DF: 7'

Standard Sesnon 29



6/53 Well spud
9/29/53 Well completed
2/2/73-2/28/73 Pressure tested 7" casing, converted to gas storag by perforating in Sesnon Zone, cleaned out to 9074', ran tubing with SSSV
7/31/73-8/7/73 Installed wireline SSSV, cleaned out to 9077'
8/27/77-9/9/77 Cleaned out to 9072', pressure tested casing, reran tubing with SSSV
3/5/79-3/10/79 Replaced safety system, set packer at 8040'


WELL VOLUME

	Cu.Ft.	Bbl.
Tubing	262	47
Csg/Lnr.	105	19
Annulus	1405	250

6/12/84

AC_CPUC_0118154

WELL PROFILE



Southern California Gas Co.
OPERATOR

WELL # S.S. #29

FIELD Aliso Canyon

COUNTY Los Angeles

STATE California

DATE March 13, 1979

☐ NEW COMPLETION ☐ WORKOVER

	CASING	LINER	TUBING 1	TUBING 2	TUBING 3
SIZE					
WEIGHT					
GRADE					
THREAD					
DEPTH					

ITEM NO.	TUBING DETAILS	LENGTH	DEPTH
1.	Kelly Bushing	6.92	-
2.	Tubing Hanger	.30	6.92
3.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	1.18	7.72
4.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	3.15	8.90
5.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	10.25	12.05
6.	16 joints 2 7/8" 6.5# N-80 8rd EUE	500.84	22.30
7.	243 Joints 2 7/8" 6.5# J-55 8rd EUE	7473.19	523.14
8.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	4.09	7996.33
9.	Otis "X" nipple 2.350" I.D.	1.13	8000.42
10.	Otis Annular Flow Safety System 4.88" O.D., 2.313" I.D.	7.66	8001.55
11.	Otis blast joint with 4 centralizers 5.50" O.D., 2.375" I.D.	19.82	8009.21
12.	Otis "XN" No-Go Nipple 2.205" I.D.	1.17	8029.03
13.	Otis Blast Joint 3.668" O.D. 2.375" I.D.	9.80	8030.20
14.	Otis "J" latch locator	1.16	8040.00
15.	Otis "Permatrieve" 7" packer (new) (20-26#) 5.87" O.D. 3.25" I.D.	4.16	8040.00
16.	Otis seal assembly (4) 3.29" O.D., 2.38" I.D.	4.05	8041.16
17.	Otis Production Tube	2.96	8045.21
18	Otis Guide Shoe	.42	8048.17
	End of Tubing		8048.59

NOTES


Side door choke in safety system

Tubing landed with 10,000X compression on packer

Corrected tubing measurments (7,482.13) to meet wireline measurments.

COMMENTS:

AC_CPUC_0118155



AC_CPUC_0118156

ALISO CANYON

SS 29

SHUT IN 5 DAYS PRIOR TO SURVEY.

INJ WELL 323 INJ PRIOR TO SHUT IN

55-29 9-24-87

80 100 120 140 160 180

0 1000 2000 3000 4000 5000 6000 7000 8000 9000

ANOMALY ABOVE SHOE POSSIBLY DUE TO INADEQUATE SHUT-IN. WILL RERUN.

TBG 2180

CSG 2180

T.D. 9021

PKR 8840

SHOE 9120

100 FT/MIN

RUN 9-25-87

55-29

461510

10 X 10 TO THE CENTIMETER
KEUFFEL & ESSER CO. MADE IN U.S.A.

AC_CPUC_0118157

10 DAYS

ALISO CANYON

SS 29

SS-29
11-12-87

50 70 90 110 130 150 170

0 1 2 3 4 5 6 7 8 9

1000 2000 3000 4000 5000 6000 7000 8000 9000

ANOMALY ABOVE SHOE - PLAN
NOISE LOG

T - 2180
C - 2160
TD 9025'

RUN-READ RM
PLOT RM

SS-27
11-13-87

100-FT/INCH

H-25-84


46 1510

10 X 10 TO THE CENTIMETER 18 X 25 CM
KEUFFEL & ESSER CO. MADE IN U.S.A.

AC_CPUC_0118158

SS-29


11-17-87



AC_CPUC_0118159

SS-29
11-18-87

w/ PLUG



AC_CPUC_0118160

R/A Tracer Summary: 55-29 (11-20-87)

Injected 100 mc of Iodine 131 tracer from 8440'-8460' with well on slight injection: Tubing pressure of 2190 psig (2180 psig shut-in); Casing pressure of 2180 psig (shut-in). Made three runs with tubing on injection and casing shut-in and observed a relatively consistent increase in count rates throughout the well. Put casing on injection (approx. 2190 psig) and two more runs (runs #4 & 5). Again, a consistent increase in count rate was observed throughout the well. Prior to making run #6, the gamma ray tool was removed from the well and cleaned in an attempt wether tool contamination had occurred.

Ran back in with tools and made two additional runs (#'s 6 & 7) with well shut-in. Again, the increased count rates were observed throughout the well. Placed the well on slight injection and made three more runs (#'s 8, 9 & 10) each displaying the same character as runs #1-7. Finally, the injection pressure was increased to approx. 2240 psig (tubing & casing) and logged again with the same character observed as before. All indications pointed to a malfunction of the injector tool. Will place well on injection and attempt another R/A tracer in 1-2 weeks.


AC_CPUC_0118161

R/A Tracer Summary: SS-29 (12-8-87)

Injected 100 mc of Iodine 131 from 8460'-8440' with well on slight injection: Tubing pressure = Csg. pressure = 1845 psig (1840 psig shut-in). Made 12 runs during which several minor accumulations of tracer were observed. The most significant accumulation was recorded on run #1 at approximately 8150' (correlates with zone just below the MP). However, the accumulation at 8150' was not observed on subsequent runs leading me to conclude that either the tracer was inside the well and was subsequently pushed out the perforations, or that the accumulation had built up inside the pipe and was displaced into the zone below the MP.

Injection pressure was increased to approximately 1850-1855 psig and five more runs were made (#'s 13-17) during which the tracer accumulations noted on previous runs did not appear to increase in magnitude or change in character. Possibly these accumulations are at collars or irregularities inside the pipe. Logged through the slug on run #17 and observed count rates as high as 1000 cps from 8460'-8440'. The count rates dropped back to the background level above 8440' indicating good slug isolation. I recommend running another R/A on this well at higher inventory prior to drawing any conclusions or planning a course of action.

AC_CPUC_0118162



AC_CPUC_0118163

WELLHEAD DESCRIPTION

Well No. SS-29

Field Aliso

Date Prepared 5-4-81

Wellhead Mfgr Shaffer

1. Casing Head Shaffer Size 13-5/8" Type KD

   Slips & Pack-off 13-5/8" x 7"

   A. Surface Csg. Size 11-3/4" Wt 42# Grade H-40

   B. Casing Head Valve Marpac Size 2" 3000 psi Fig.No. CSB-790-JN

2. Seal Flange Shaffer Size 13-5/8" x 10" 5000 psi

   A. Type Seal PS Ring BX-160 & R-54

3. Tubing Head Shaffer Size 10" x 8" 5000 psi Type 63-L-1

   Ring R-54 & Ring R-50

   Outlets 2-3" Sec.Seal PS

   Valve Removal Thrd 2-1/2" API

   A. Tubing Hanger Shaffer Size 8" x 2-7/8" Type AJO

   B.P.V. Size 2-7/8" Thrd

   B. Tubing Head Valves 2 Mc Evoy Size 3" 5000 psi Fig.No. 129

   C. Automatic Csg. Valve WKM Size 3" 5000 psi Fig.No. 114522

4. Adapter Seal Flange Shaffer Size 8"x2-1/2"x 2-9/16" Type AJO

   A. Ring Size R-50 & R-27

5. Master Valve McEvoy Size 2-1/2" 5000 psi Fig.No. 129

6. Xmas Tree Cross Shaffer Size 2-9/16"x2-9/16"x2-1/16"x 2-1/16"x2" Bore Thru 2-9/16"

   Across 2-1/16"

7. Tubing Wing Valves Rockwell Size 2" 5000 psi Fig.No. 21055

   A. Automatic Tbg. Valve WKM Size 2" 5000 psi Fig. No. 114522

8. Unibolt Size 3" 5000 psi Inside Thrds


9. Wt. Landed in Csg. Head 8170' 7" Wt. 26# 23# Grade N-80 ST&C

10. Wt. Landed on Doughnut 8030' 2-7/8" 10,000 Wt. 6.5 Grade N-80 8Rd EUE

11. Tubing Head to Ground Level

AC_CPUC_0118164

TYPE IV




Well Name: SS 29 - Aliso Canyon

Mfgr.: Shaffer

Date Prepared: 12-20-82

AC_CPUC_0118165

WELL PROFILE



OPERATOR: Southern California Gas Co.

WELL #: S.S. #29

FIELD: Aliso Canyon

COUNTY: Los Angeles

STATE: California

DATE: March 13, 1979

☐ NEW COMPLETION ☐ WORKOVER

	CASING	LINER	TUBING 1	TUBING 2	TUBING 3
SIZE					
WEIGHT					
GRADE					
THREAD					
DEPTH					

ITEM NO.	TUBING DETAILS	LENGTH	DEPTH
1.	Kelly Bushing	6.92	-
2.	Tubing Hanger	.30	6.92
3.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	1.18	7.72
4.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	3.15	8.90
5.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	10.25	12.05
6.	16 joints 2 7/8" 6.5# N-80 8rd EUE	500.84	22.30
7.	243 Joints 2 7/8" 6.5# J-55 8rd EUE	7473.19	523.14
8.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	4.09	7996.33
9.	Otis "X" nipple 2.350" I.D.	1.13	8000.42
10.	Otis Annular Flow Safety System 4.88" O.D., 2.313" I.D.	7.66	8001.55
11.	Otis blast joint with 4 centralizers 5.50" O.D., 2.375" I.D.	19.82	8009.21
12.	Otis "XN" No-Go Nipple 2.205" I.D.	1.17	8029.03
13.	Otis Blast Joint 3.668" O.D. 2.375" I.D.	9.80	8030.20
14.	Otis "J" latch locator	1.16	8040.00
15.	Otis "Permatrieve" 7" packer (new) (20-26#) 5.87" O.D. 3.25" I.D.	4.16	8040.00
16.	Otis seal assembly (4) 3.29" O.D., 2.38" I.D.	4.05	8041.16
17.	Otis Production Tube	2.96	8045.21
18	Otis Guide Shoe	.42	8048.17
	End of Tubing		8048.59

NOTES

Side door choke in safety system

Tubing landed with 10,000X compression on packer

Corrected tubing measurments (7,482.13) to meet wireline measurments.

COMMENTS:

AC_CPUC_0118166

Recd GSL 9/9/77
file

INTEROFFICE SOUTHERN CALIFORNIA gas COMPANY CORRESPONDENCE

Gift

TO JOHN L. MELTON FROM G. C. ABRAHAMSON DATE September 8, 1977

SUBJECT SAND NOTED IN STANDARD SESNON #29 - Aliso Canyon

When we pulled the tubing out of STANDARD SESNON #29, 40' of fine (face-powder type) sand was packed in the blanking plug landed at 8517'. The sand evidently came from the S_4 Zone since it was the only Zone above there.

c.c. Ben Jones ✓

GCA/jp

FORM 64-1D

AC_CPUC_0118167

cc: RWW ✓
ESS
Sr. D.E. 11/15/89
m

SOUTHERN CALIFORNIA gas COMPANY

INTEROFFICE CORRESPONDENCE

TO N. W. Buss
M. E. Melton

FROM S. P. Robinson

DATE 11/14/89

SUBJECT Shoe Leak Repair for SS-29 - Aliso Canyon

Repair the shut-off leak on SS-29 and plug back the HZ and Frew intervals.

The radioactive tracer survey run on 11/10/89 verified the shoe leak that the 11/87 and 10/89 noise logs showed. Gas is moving up past the top of the Sesnon zone to the MP sand and above (See Figure 1).

While working on SS-29, we should take advantage of an opportunity to improve the well low inventory deliverability. We can do this by plugging back the HZ and Frew intervals. Fluids from these intervals load up the well at low inventories.

Include the following in the rework:


- Cement squeeze to shut off the leak between the sesnon and MP.
- Plug back the well at the base of the Sesnon (approximately 8695').
- Run a casing inspection log to 8075'.
- Complete the well with Otis 2.205 XN, 2-7/8 XD SSD, 2-7/8 GLM
- Rebuild the master valve and casing wing valves.

The Division pre and post rig cost should be $10,000 ($2000 labor; $3000 non-labor; $5000 contract).


SPR:db

cc: N. D. Stevenson


64-F



AC_CPUC_0118169



AC_CPUC_0118170


SS 29
10/20/89
5800
6000
6200
6400
6600
6800
7000
7200
7400
7600
7800
8000
8200
8400
8600
130°
140°
150°
160°
8002
8049
8075
7"
8130
8456
5" TO 9790'

Dict 10/3/88 mc

SOUTHERN CALIFORNIA gas COMPANY

INTEROFFICE CORRESPONDENCE

TO Recipients of Aliso Canyon FROM R. E. Wallace DATE Oct. 3, 1988

SUBJECT Changes to the Porter 37, Porter 46, Sesnon 8 and Sesnon 9 Programs

Please note the following changes to the subject well workover program:

Step	Changes
7	Include an Otis "XD" sliding sleeve and one joint of tubing, one joint above the No-Go Nipple.
8	Increase the pressure test from 1500 psi to 1900 psi.

REW:mc

64-F

AC_CPUC_0118172

xc: REW
RMD 55-29

INTEROFFICE CORRESPONDENCE

SOUTHERN CALIFORNIA gas COMPANY

M E Melton

TO R. W. Weibel FROM M. E. Melton DATE Sept. 2, 1988

SUBJECT Candidate Wells for Casing Inspection, Aliso Canyon Field

Attached is Dave Horstman's recommendations and priorities for inspection of casing flow wells originally completed in the 1940's and 50's.

I agree with Dave's priorities and recommend that all 19 wells listed be logged and pressure tested over the next two year period.

MEM:hr
Attachments

cc: N. W. Buss
J. D. Mansdorfer

SOUTHERN CALIFORNIA gas COMPANY

INTEROFFICE CORRESPONDENCE

TO M. E. Melton FROM D. R. Horstman DATE August 30, 1988

SUBJECT Candidate Wells for Casing Inspection, Aliso Canyon Field

Attached is a listing of all casing flow wells of 1940's and 1950's vintage currently in operation at the subject field. It is recommended that casing inspection surveys (vertilogs) be run to determine the mechanical condition of each well casing. In addition, each well should be pressure tested to identify any leaks at the casing collars.

The wells included on the attached list are prioritized based upon deliverability, operational history, and the length of time since their last workover. Please advise should you have any questions or require additional information.

DRH:hr
Attachments

Aliso Canyon Casing Flow Wells of 1940's and 1950's Vintage

Well	Completed	Deliverability @ 19.8 Bcf (MMcf/d)	Most Recent Workover	Comments	Priority
P 34	5/45	9	10/77	Casing pressure tested, SSSV run.	High
P 37	8/46	24	9/77	Casing pressure tested, SSSV run.	High
P 44*	1/56	26	4/78	Redrilled from 7805', casing patch set 3971'-4012', SSSV run.	Low
P 46	2/44	35	8/77	Reperf'd 7730'-7920', SSSV run.	High
P 47	8/43	21	6/77	Pulled 2-3/8" liner, squeezed perf's @ various depths. Temp anomaly @ shoe (3/23/88).	Low
SS 2	9/43	16	8/83	Repaired shoe leak, CBL run 7/73.	Low
SS 4	1/45	0(FL)	12/81	Repaired shoe leak, CBL run 11/80.	Low
SS 6	9/45	10	9/82	Repaired shoe leak, CBL and TDT run 5/73.	Low
SS 7	2/46	1	9/77	Casing pressure tested, SSSV run.	Medium
SS 8	8/46	15	7/78	Casing pressure tested, SSSV repaired.	High
SS 9	2/47	15	2/79	Casing pressure tested, SSSV replaced.	High
SS 10*	6/47	25	12/78	Casing patch run 4474'-4516', SSSV replaced.	Low
SS 11	11/47	9	6/80	Repaired shoe leak. CBL and TDT run 7/73. New temp anomaly @ shoe (2/88).	Low
SS 17**	6/51	7	8/77	Casing pressured tested, SSSV run. Well has a shoe leak.	Low

Aliso Canyon Casing Flow Wells
of 1940' & 1950's Vintage

Well	Completed	Deliverability @ 19.8 Bcf (MMcf/d)	Most Recent Workover	Comments	Priority
SS 24	4/53	11	3/85	Repaired shoe leak. CBL run 7/73.	Low
SS 25	2/54	38	2/79	Replaced SSSV. Temp anomaly @ shoe (3/3/88).	Low
SS 29**	9/53	22	3/79	Replaced SSSV and set packer @ 8040'. Well has a shoe leak.	Low
F 2	7/44	1	9/77	Casing pressure tested, SSSV run.	Medium
F 4	1/48	12	9/77	Workover planned for 1988. Will log at that time.	-
F 5	7/48	2	8/77	SSSV run.	Medium

* Equipped with casing patch.
** Identified shoe leak. Casing will be inspected during workover.
FL - Fluid loaded

DRH:hr
8/30/88

SOUTHERN CALIFORNIA gas COMPANY

INTEROFFICE CORRESPONDENCE

TO D. S. Smiley FROM G. C. Abrahamson DATE February 28, 1979

SUBJECT Program to Install New Style Camco Tubing Retrievable Safety System in Standard Sesnon #29, Aliso Canyon.

Please find attached program, budget cost estimates and material requests for Standard Sesnon #29, Aliso Canyon.

We are estimating 16 - 8 hr. tours or 9 calendar days and total GWO cost of $65,000.

No D.O.G. Notice's are required for this job.

We understand this work is to be done with CPS Rig #D-4 following standby during withdrawal test.

If you desire any changes in the attached material, please advise.

GCA/er

64-D

AC_CPUC_0118177

WORKOVER PROGRAM

OPERATOR: Southern California Gas Company

FIELD: Aliso Canyon

WELL: Standard Sesnon #29

CONTRACTOR: California Production Service Rig #D-4

APPROXIMATE LOCATION: 750' S and 6100' W of Station #84

ELEVATION: Ground level 2848.77' Take all measurements from original derrick floor 6.92' above ground.

SAFETY: Hard hats are to be worn by all personnel on or near a rig. No smoking is permitted within 100' of the wellhead.

Present conditions:

11-3/4" 47# J-55, 42# H-40 cemented 1042'
7" cemented 8170', WSO on shoe

Casing detail

8170' - 6494'	26#	N-80	ST&C
6494' - 4452'	23#	N-80	ST&C
4452' - 974'	23#	J-55	ST&C
974' - Surface	23#	N-80	ST&C

T.D. 9790' - plug 9094'

1002' 5" 18# F.J. landed 9077', slotted
9077' - 8727', top liner 8075'
cp'd 8725' w/100 sacks
WSO on splice at 8075'
4-1/2" holes 8710', squeezed 34 sacks
4-1/2" holes 8705', WSO by DOG
Shot 4-1/2" holes per.foot 8694' - 8674', 8668' - 8658', 8638' - 8602' and 8552' - 8528'. 8502' - 8456'

AC_CPUC_0118178

Tubing Detail:

Otis 5" permatrieve packer 8301'
Otis production tube
Otis 4 seals
Otis latch-in-locator
Otis 10' blast joint
Otis 1.56" "XN" nipple
Otis 20' blast joint
Otis 2-3/8" annular flow safety system
2-3/8" tubing to 7900'
2-7/8" tubing to surface
weight of tubing 42,000#

Program:

Kill well with 63#/cu.ft. waste salt water mixed with HEC polymer provided by Professional Drilling Fluid Services. Obtain assistance from Aliso Canyon shift foreman. Bleed off gas to gas company system. Volume of well = 350 bbls. Pump down tubing at about 3 bbls. per minute using Halliburton pumping agent.

1. Move in and rig up California Production Service Rig #D-4 with Baker Tank.

2. Set back pressure valve in doughnut. Remove Xmas tree.

3. Install H & H Oil Tool Co., Inc. Class III 3000 psi B.O.P.E. Equipment to include "GK" Hydril bag and double gate both hydraulically operated with 80 gallon 3000 psi accumulator, auxiliary nitrogen and dual control stations. Also install 8 x 8" 3000 psi spool with 3000 psi choke and kill manifold with discharges to Gas Company system and Baker Tank. Discharge to Gas Company system to include a block valve and bleeder. Use new API Rings on any untested B.O.P.E. connections.

4. Pressure test blind rams, 2-7/8" pipe rams and choke manifold to 3,000 psi with water and nitrogen. Pressure test Hydril bag to 2,000 psi with water and nitrogen.

5. Pull 2-7/8" and 2-3/8" tubing laying down production equipment, production tube, 4 seals, latch-in-locator, 10' and 20' blast joints, 1.56" "XN" nipple and 2-3/8" annular flow safety system. Otis to clean, inspect, repair and pressure test for reuse. Pull 1,000# - 2,000# over weight of tubing (42,000#) and turn to the right to release latch. Use Otis service man if necessary.

6. Run 6-1/8" bit and casing scraper to 2-7/8" tubing and clean out to top of 5" liner at 8075'.

7. Run 2-7/8" and 2-3/8" tubing with Otis retrieving tool. Recover 5" permatrieve packer from 8301'. If unable to retrieve packer mill and push packer to 9077'. If packer is recovered run 4-1/8" bit and casing scraper and clean out to 9077'

AC_CPUC_0118179

8. Run Otis Permatrieve packer on Go wire line and using reference collars set packer near 8050' but do not set packer in a collar.

9. Run 2-7/8" tubing with seals and locator sub. Change collars, clean pins and apply Baker seal. Land tubing on packer with 10,000#. Close pipe rams and pressure test seals and packer to 1500 psi keep tubing full and observe for returns.

10. Run 2-7/8" tubing applying Baker seal to doubles. Also drift and hydrotest to 5,000 psi holding each test for one minute.

Tubing to include:

Otis 2-7/8" production tube
Otis 4 seals
Otis latch-in-locator
Otis 10' heavy wall tube - 2-7/8" threads
Otis 2.205" "XN" nipple 2-7/8" threads
Otis 20' heavy wall tube - 2-7/8" threads
Otis 2-7/8" annular flow safety system
2-7/8" tubing to surface.

11. Space out and land tubing on packer with up to 10,000# on packer. Pull 35,000# over weight of tubing to check latch.

12. Set back pressure valve in doughnut. Remove B.O.P.E. and install Xmas tree. Pressure test Xmas tree to 5,000 psi for 20 minutes.

13. Circulate polymer drilling fluid out of well with waste salt water. Tighten all wellhead bolts. Check all wellhead valves closed. Install blind flanges on wellhead valves. Release Rig.

G. C. Abrahamson
2/28/79 GCA

cc: Rig Supervisor
Relief Rig Supervisor
Contract Pusher (2)

A. A. Awalt
D. S. Smiley
J. W. Tenfelder

Well File

AC_CPUC_0118180

WELL NO. Standard Sesnon #29 DATE WANTED: 3/8/79

LOCATION: Aliso Canyon REQUESTED BY: G. C. Abrahamson (GCA)

	SIZE	FOOTAGE	DESCRIPTION
CASING			
TUBING			
	2-7/8"	300'	65# 8Rd EUE J-55
LINER and ACCESSORIES			
	DESCRIPTION		
CASING HEAD			
TUBING HEAD			

NOTE: For MISCELLANEOUS - see Page 2.

WELL NO. Standard Sesnon #29 DATE WANTED: 3/8/79 GWA

LOCATION: Aliso Canyon REQUESTED BY: G. C. Abrahamson

	DESCRIPTION
MISCELLANEOUS	Otis production tube
	Otis 4 seals
	Otis Latch-in-locator
	Otis 10' blast joint
	Otis 2.205" "XN" nipple
	Otis 20' blast joint
	Otis 2-7/8" annular flow safety system
	20 2-7/8" N-80 8Rd EUE tubing collars
	260 2-7/8" N-55 8Rd EUE tubing collars

AC_CPUC_0118182

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Canyon WELL NAME SS-29 CONTRACTOR Pride RIG No. 447

RIG DAYS 8 MWO# _____ / TOTAL COST ESTIMATE $_____

RIG DATE 11-14-94 GWO# 93496 / TOTAL COST ESTIMATE $_____

RIG SUPERVISOR S.L. McLean DAILY COST $ 2618

CUMULATIVE COST $ 125349

CASING: OD 7 in. DEPTH 8170 ft. LINER OD 5 in. TOP 8075 ft. BOTTOM 9790 ft.

BRIEF DESCRIPTION OF ACTIVITIES

Opened well in A.M. No pressure on casing or tubing. Rigged up ISI and shot fluid level in tubing. Found fluid at 1261'. Bled pressure from SSSV and shot fluid level. Showed SSSV closed at 500'. Set BPV

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL
	and nippled down BOPE. Installed and tested tree to 5000 PSI. Transferred fluid to SS-9. Rigged down and moved off. Release rig at 2:00 PM on 11-14-94.

AC_CPUC_0118183

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS-29 Date 11 / 15 / 94 Initials SLMc

Daily Base Costs

Rig $ 159 /hour x 8 hours =	$ 1272	/day	
Extra Labor 3425	$ 75	/day	
Rig Supervisor	$ 500	/day	
BOPE Rental	$ 175	/day	
Drillpipe Rental	$	/day	Subtotal $ 2022

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$ 2022.00
Associated Serv.	6687	A07	WW	12	440.00
ISI	10428		IT	60	156.00

Daily Total $ 2618

Previous Total $ 122731

Cumulative Total $ 125349

Work Categories

- PR Pre-rig work, well kill
- MI Move in - rig up, install & test BOPE
- CO Initial/final clean out
- DD Drilling
- LR Leak repair - cmt. sqz., casing patch
- FF Fishing
- PB Plugback, redrill
- ST Stimulation - acid wash, reperforating
- GP Gravel pack
- IT Isolation test - noise log, WSO test
- WW Wellhead work
- CI Run casing/inner-string/liner
- TP Run tbg. & prod. equip.
- AA Abandonment
- RR Rig repairs
- SB Stand-by
- MO Rig down - move out
- PO Post-rig work
- ZZ Miscellaneous

Functional Indexes

- 10 Tubular goods
- 11 Tubing accessories, packers
- 12 Wellhead equip. & svcs.
- 13 Gravel pack equip. & svcs.
- 14 Casing accessories
- 20 Bits
- 21 Fluids
- 22 Cement, acid, sand, chemicals & pumping svcs.
- 23 Nitrogen and coil tubing svcs.
- 24 Filtering and solids control
- 30 Service tools
- 31 Fishing tools & svcs.
- 32 Hole openers, mills, junk subs, reamers, stabilizers
- 33 Coring, dynadrills & directional svcs.
- 35 Piano wire equip. & svcs.
- 40 Open & cased hole logging
- 41 Other Wireline svcs.
- 42 Production logging
- 43 Hydrotest, torque, tong svc, thread washing
- 44 Trucking, hauling, cranes & hot shots
- 45 Vacuum trucking, disposal charges
- 46 Tank rental, misc. rentals
- 47 Site preparation
- 60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Canyon WELL NAME SS-29 CONTRACTOR Pride RIG No. 447

RIG DAYS 7 MWO# _____ / TOTAL COST ESTIMATE $ _____

RIG DATE 11-12-94 GWO# 93496 / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR Steven L. McLean DAILY COST $ 27,989

CASING: OD 7 in. LINER OD 5 in. CUMULATIVE COST $ 122,731

DEPTH 8170 ft. TOP 8075 ft.

BOTTOM 9790 ft.

BRIEF DESCRIPTION OF ACTIVITIES

Opened well in A.M. No pressure on casing or tubing. Pulled 2⅞" doughnut and installed fatigue nipple and new 3½" doughnut. Tested subsurface safety valve to 5000 PSI. Landed doughnut with 8-10K on packer. Rigged up wireline

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL
	to set plug in "XN" nipple at 7999'. Ran in after setting plug and attempted to open sliding sleeve at 7965'. Circulated down casing/tubing annulus and pressured up to 1000 psi (sleeve not open). Pulled plug, assumed set in sleeve, and redressed. Added weight bar and reran plug. Set down again in sliding sleeve. Pulled plug and made up 2"/16" gauge ring. Ran through sliding sleeve and set down on "XN" nipple. Gauged plug and found to be 2.75" and ID through sleeve 2.75". Rigged down wireline and will check subsurface safety valve with fluid level equipment in AM on 11-14-94. Shut down operations.

SOUTHERN CALIFORNIA GAS COMPANY

AC_CPUC_0118185

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS-29 Date 11 / 12 / 94 Initials SLMc

Daily Base Costs

Rig $ 1860 /hour x 10 hours =	$ 1860	/day	
Extra Labor (3x25)	$ 75	/day	
Rig Supervisor	$ 500	/day	
BOPE Rental	$ 350	/day	
Drillpipe Rental	$	/day	Subtotal $ 2785~

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$
FMC/Gator Hawk		917	TP	43	5474~
Halliburton	617360	H04	TP	11	3985~
	617361	H04	TP	11	1389~
Oil Field Rental	1-042-4-0562	011	TP	30	205~
Shaffer Oil Tool	26965	S07	WW	12	1222~
Baker Oil Tools	10041	B36	TP	11	2047
	10042	B36	TP	11	10882~

Daily Total	$ 27,989~
Previous Total	$ 94,742~
Cumulative Total	$ 122,731~

Work Categories

- PR Pre-rig work, well kill
- MI Move in - rig up, install & test BOPE
- CO Initial/final clean out
- DD Drilling
- LR Leak repair - cmt. sqz., casing patch
- FF Fishing
- PB Plugback, redrill
- ST Stimulation - acid wash, reperforating
- GP Gravel pack
- IT Isolation test - noise log, WSO test
- WW Wellhead work
- CI Run casing/inner-string/liner
- TP Run tbg. & prod. equip.
- AA Abandonment
- RR Rig repairs
- SB Stand-by
- MO Rig down - move out
- PO Post-rig work
- ZZ Miscellaneous

Functional Indexes

- 10 Tubular goods
- 11 Tubing accessories, packers
- 12 Wellhead equip. & svcs.
- 13 Gravel pack equip. & svcs.
- 14 Casing accessories
- 20 Bits
- 21 Fluids
- 22 Cement, acid, sand, chemicals & pumping svcs.
- 23 Nitrogen and coil tubing svcs.
- 24 Filtering and solids control
- 30 Service tools
- 31 Fishing tools & svcs.
- 32 Hole openers, mills, junk subs, reamers, stabilizers
- 33 Coring, dynadrills & directional svcs.
- 35 Piano wire equip. & svcs.
- 40 Open & cased hole logging
- 41 Other Wireline svcs.
- 42 Production logging
- 43 Hydrotest, torque, tong svc, thread washing
- 44 Trucking, hauling, cranes & hot shots
- 45 Vacuum trucking, disposal charges
- 46 Tank rental, misc. rentals
- 47 Site preparation
- 60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Canyon WELL NAME SS-29 CONTRACTOR Pride RIG No. 447

RIG DAYS 6 MWO# _____ / TOTAL COST ESTIMATE $ _____

RIG DATE 11-11-94 GWO# 93496 / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR Steven L. McLean DAILY COST $ 54231~

OD 5 in. CUMULATIVE COST $ 94742~

CASING: OD 7 in. LINER TOP 8075 ft.

DEPTH 8170 ft. BOTTOM 9790 ft.

BRIEF DESCRIPTION OF ACTIVITIES

Opened well in A.M. No pressure on casing or tubing. Pumped 20 bbls of 2% KCL fluid. Measured and picked up 4½" tubing. Gator Hawked tested to 4000 psi. Made up 3½" tubing and safety valve. RIH and tagged packer at

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL
	8032'. Pulled 20K over string weight and set down 10K to obtain space out. POOH with 3½" tubing to safety valve. Made up safety valve line and tested to 5000 psi. RIH banding line and testing tubing. Made up doughnut and pup it to space out. When breaking out pup the threads crossed in the top of doughnut. Called Shaffer and new doughnut would be ready in A.M. Landed tubing on 2 7/8" doughnut and secured well and rig.

SOUTHERN CALIFORNIA GAS COMPANY

AC_CPUC_0118187

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS-29 Date 11 / 11 / 94 Initials SLMC

Daily Base Costs

Rig $ 186 /hour x 10 hours = $ 1860 /day
Extra Labor (10X31) (4X25) $ 410 /day
Rig Supervisor $ 500 /day
BOPE Rental $ 1250 /day
Drillpipe Rental $ /day Subtotal $ 4020

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$
H&H Casing	6704	H01	TP	43	3118~
H&H Oil Tool	38015	H03	TP	44	1003~
	38016	H03	TP	44	836~
591.14'	3½" EUE 8RND 9.3# N-80 ABMod.		R-2	4.75/ft	2808~
7381.88'	4½" LTEC 11.6# N-80		R-2	5.75/ft	42446~

Daily Total $ 54231~
Previous Total $ 40511~
Cumulative Total $ 94742~

Work Categories

PR Pre-rig work, well kill
MI Move in - rig up, install & test BOPE
CO Initial/final clean out
DD Drilling
LR Leak repair - cmt. sqz., casing patch
FF Fishing
PB Plugback, redrill
ST Stimulation - acid wash, reperforating
GP Gravel pack
IT Isolation test - noise log, WSO test
WW Wellhead work
CI Run casing/inner-string/liner
TP Run tbg. & prod. equip.
AA Abandonment
RR Rig repairs
SB Stand-by
MO Rig down - move out
PO Post-rig work
ZZ Miscellaneous

Functional Indexes

10 Tubular goods
11 Tubing accessories, packers
12 Wellhead equip. & svcs.
13 Gravel pack equip. & svcs.
14 Casing accessories
20 Bits
21 Fluids
22 Cement, acid, sand, chemicals & pumping svcs.
23 Nitrogen and coil tubing svcs.
24 Filtering and solids control
30 Service tools
31 Fishing tools & svcs.
32 Hole openers, mills, junk subs, reamers, stabilizers
33 Coring, dynadrills & directional svcs.
35 Piano wire equip. & svcs.
40 Open & cased hole logging
41 Other Wireline svcs.
42 Production logging
43 Hydrotest, torque, tong svc, thread washing
44 Trucking, hauling, cranes & hot shots
45 Vacuum trucking, disposal charges
46 Tank rental, misc. rentals
47 Site preparation
60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Canyon WELL NAME SS-29 CONTRACTOR Pride RIG No. 447

DAYS 5 MWO# _____ / TOTAL COST ESTIMATE $ _____

RIG DATE 11-10-94 GWO# 93496 / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR Steven L McLean DAILY COST $ $5687

CASING: OD 7 in. DEPTH 8170 ft. LINER OD 5 in. TOP 8075 ft. BOTTOM 9790 ft.

CUMULATIVE COST $ $40511

BRIEF DESCRIPTION OF ACTIVITIES

Opened well in AM. No pressure on casing or tubing. Pumped 20 bbls of 2% KCL water. Pulled out of the hole with 100 jts of 2 7/8" tubing. Laid down production equipment. Changed pipe rams from 2 7/8" to 4 1/2". Rigged up to run 3 1/2" and 4 1/2" production equipment. Made up and tested (4000 psi) 3 1/2" production equipment. Changed out 3 1/2" test equipment to 4 1/2". Made up and ran 4 1/2" production tubing. Tested to 4000 psi. RIH to 6000' and shut in until A.M.

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS-29 Date 11 / 10 / 94 Initials SLMc

Daily Base Costs

Rig $ 186 /hour x 14 hours =	$ 2604	/day
Extra Labor 4X25 (12X27)	$ 424	/day
Rig Supervisor	$ 500	/day
BOPE Rental	$ 125	/day
Drillpipe Rental	$	/day
	Subtotal $ 3653	

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$
Barnett T&K	38325 41556 38011		TP	44	493
H&H T&K	38014, 38013		TP	44	1541

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Alesio Canyon WELL NAME SS-29 CONTRACTOR Pride RIG No. 447

DAYS 4 MWO# _____ / TOTAL COST ESTIMATE $ _____

RIG DATE 11-9-94 GWO# 93496 / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR Steven L. McLean DAILY COST $ 15,314

CUMULATIVE COST $ 34824

CASING: OD 7 in. DEPTH 8170 ft. LINER OD 5 in. TOP 8075 ft. BOTTOM 9790 ft.

BRIEF DESCRIPTION OF ACTIVITIES

Opened well in A.M. No pressure on casing or tubing. Mixed and pumped a HEC high vis pill (100 bbls) Fluid level at 842' before pill and returns to surface while displacing pill. Shut fluid level 30 minutes

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL
	after displacement and found fluid level at 218'. Rigged up to pull 2 7/8" tubing. Pulled and laid down 153 joints. Left 3000' of kill string in well. Secured well and shut down until A.M.

AC_CPUC_0118191

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS-29 Date 11 / 9 / 94 Initials SLMC

Daily Base Costs

Rig $ 186 /hour x 9 hours =	$ 1674	/day
Extra Labor 2@ 85 and 3@ 25	$ 245	/day
Rig Supervisor	$ 500	/day
BOPE Rental	$ 125	/day
Drillpipe Rental	$	/day

Subtotal $ 2544~

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$
Shaffer Oil Tool	26957	507	WW	12	10,923~
MI Fluids	D07208	M26	PR	21	1511~
ISI	10426	NA	ZZ	60	340~

Daily Total $ 15,318

Previous Total $ 19,506

Cumulative Total $ 34,824

Work Categories

- PR Pre-rig work, well kill
- MI Move in - rig up, install & test BOPE
- CO Initial/final clean out
- DD Drilling
- LR Leak repair - cmt. sqz., casing patch
- FF Fishing
- PB Plugback, redrill
- ST Stimulation - acid wash, reperforating
- GP Gravel pack
- IT Isolation test - noise log, WSO test
- WW Wellhead work
- CI Run casing/inner-string/liner
- TP Run tbg. & prod. equip.
- AA Abandonment
- RR Rig repairs
- SB Stand-by
- MO Rig down - move out
- PO Post-rig work
- ZZ Miscellaneous

Functional Indexes

- 10 Tubular goods
- 11 Tubing accessories, packers
- 12 Wellhead equip. & svcs.
- 13 Gravel pack equip. & svcs.
- 14 Casing accessories
- 20 Bits
- 21 Fluids
- 22 Cement, acid, sand, chemicals & pumping svcs.
- 23 Nitrogen and coil tubing svcs.
- 24 Filtering and solids control
- 30 Service tools
- 31 Fishing tools & svcs.
- 32 Hole openers, mills, junk subs, reamers, stabilizers
- 33 Coring, dynadrills & directional svcs.
- 35 Piano wire equip. & svcs.
- 40 Open & cased hole logging
- 41 Other Wireline svcs.
- 42 Production logging
- 43 Hydrotest, torque, tong sv thread washing
- 44 Trucking, hauling, cranes & hot shots
- 45 Vacuum trucking, disposal charges
- 46 Tank rental, misc. rentals
- 47 Site preparation
- 60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Alesio Canyon WELL NAME SS 29 CONTRACTOR Pride RIG No. 447

DAYS 3 MWO# _____ / TOTAL COST ESTIMATE $ _____

RIG DATE 11-8-94 GWO# 93496 / TOTAL COST ESTIMATE $ _____

RIG SUPERVISOR Steven L McLean DAILY COST $ 13644

CUMULATIVE COST $ 19506

CASING: OD 7 in. DEPTH 8170 ft. LINER OD 5 in. TOP 8075 ft. BOTTOM 9790 ft.

BRIEF DESCRIPTION OF ACTIVITIES

Bled well down in AM with only a small amount of gas. Worked tubing out of packer without pulling seal assembly. Rigged up to run gyro survey inside tubing. Could not get below "XN" nipple at 7999'. Pulled out with

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL
	gyro and rigged down. Pulled seals out of packer and well Kicked. Shut-in well with 600 psi on casing, circulated out gas, lost circulation, pumped 270 bbls and bled pressure to zero. Mixed a 100 bbl HEC pill. Pumped pill and followed with 50 bbls of 2% KCl water. No returns. Shut well in until A.M.

AC_CPUC_0118193

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well SS-29 Date 11 / 8 / 94 Initials SLMC

Daily Base Costs

Rig $ 186 /hour x 12 hours =	$ 2232	/day
Extra Labor 3X25	$ 75	/day
Rig Supervisor	$ 500	/day
BOPE Rental	$ 125	/day
Drillpipe Rental	$	/day
	Subtotal $ 2932 ~	

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$
Weatherford	135632	W02	MI	43	515 ~
MI Fluids	D07204	M26	PR	21	727 60/xx
Baker Hughes	39200	B22	ZZ	41	6000 ~
BST Lift Systems	1796	B24	TP	60	3469 43

Daily Total	$ 13,644 ~
Previous Total	$ 5862 ~
Cumulative Total	$ 19506 ~

Work Categories

- PR Pre-rig work, well kill
- MI Move in - rig up, install & test BOPE
- CO Initial/final clean out
- DD Drilling
- LR Leak repair - cmt. sqz., casing patch
- FF Fishing
- PB Plugback, redrill
- ST Stimulation - acid wash, reperforating
- GP Gravel pack
- IT Isolation test - noise log, WSO test
- WW Wellhead work
- CI Run casing/inner-string/liner
- TP Run tbg. & prod. equip.
- AA Abandonment
- RR Rig repairs
- SB Stand-by
- MO Rig down - move out
- PO Post-rig work
- ZZ Miscellaneous

Functional Indexes

- 10 Tubular goods
- 11 Tubing accessories, packers
- 12 Wellhead equip. & svcs.
- 13 Gravel pack equip. & svcs.
- 14 Casing accessories
- 20 Bits
- 21 Fluids
- 22 Cement, acid, sand, chemicals & pumping svcs.
- 23 Nitrogen and coil tubing svcs.
- 24 Filtering and solids control
- 30 Service tools
- 31 Fishing tools & svcs.
- 32 Hole openers, mills, junk subs, reamers, stabilizers
- 33 Coring, dynadrills & directional svcs.
- 35 Piano wire equip. & svcs.
- 40 Open & cased hole logging
- 41 Other Wireline svcs.
- 42 Production logging
- 43 Hydrotest, torque, tong svc, thread washing
- 44 Trucking, hauling, cranes & hot shots
- 45 Vacuum trucking, disposal charges
- 46 Tank rental, misc. rentals
- 47 Site preparation
- 60 Miscellaneous

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL ACTIVITY REPORT

FIELD Aliso Canyon WELL NAME SS 29 CONTRACTOR Pride RIG No. 447

DAYS 2 MWO# _____ / TOTAL COST ESTIMATE $_____

RIG DATE 11-7-94 GWO# 93496 / TOTAL COST ESTIMATE $_____

RIG SUPERVISOR Steve McLean DAILY COST $ 2932

CUMULATIVE COST $ 5862

CASING: OD 7 in. DEPTH 8170 ft. LINER OD 5 in. TOP 8075 ft. BOTTOM 9790 ft.

BRIEF DESCRIPTION OF ACTIVITIES

Opened well up (Csg Press 2500 PSI, Tbg Press 2400 PSI). Rigged up to pump and choke ready to kill well. Wait on SCG Field operator to open line to bleed well down. Killed well with 345 bbls of 2% KCL water. Installed BPV, nipped

MUD PROPERTIES

MUD TYPE	FUNNEL VISCOSITY SEC	WATER LOSS CC	DENSITY #/CU. FT.	YIELD POINT #/100 SQ. FT.	PLASTIC VISC CP	pH	SOLIDS %	SUSPENDED SOLIDS %

ELAPSED TIME (HR)	OPERATIONS SEQUENCE & DETAIL
	down tree and installed BOPE. Changed pipe rams and function tested blind rams. Pressure tested BOPE with test pump. Rigged up to pull tubing. Unscrewed tubing hold down studs. Secured well and rig until AM.

SOUTHERN CALIFORNIA GAS COMPANY
DAILY WELL COST REPORT

Well 55-29 Date 11 / 7 / 94 Initials SLMC

Daily Base Costs

Rig $ 1186 /hour x 12 hours = $ 2232 /day
Extra Labor 3X25 $ 75 /day
Rig Supervisor $ 500 /day
BOPE Rental $ 125 /day
Drillpipe Rental $ ~ /day Subtotal $ 2932

Contractor Name	Ticket Number	Contractor Index	Work Category	Functional Index	Total
Daily Base Cost	—	—		01	$


Daily Total $ 2932
Previous Total $ 2930
Cumulative Total $ 5862

Work Categories

PR Pre-rig work, well kill
MI Move in - rig up, install & test BOPE
CO Initial/final clean out
DD Drilling
LR Leak repair - cmt. sqz., casing patch
FF Fishing
PB Plugback, redrill
ST Stimulation - acid wash, reperforating
GP Gravel pack
IT Isolation test - noise log, WSO test
WW Wellhead work
CI Run casing/inner-string/liner
TP Run tbg. & prod. equip.
AA Abandonment
RR Rig repairs
SB Stand-by
MO Rig down - move out
PO Post-rig work
ZZ Miscellaneous

Functional Indexes

10 Tubular goods
11 Tubing accessories, packers
12 Wellhead equip. & svcs.
13 Gravel pack equip. & svcs.
14 Casing accessories
20 Bits
21 Fluids
22 Cement, acid, sand, chemicals & pumping svcs.
23 Nitrogen and coil tubing svcs.
24 Filtering and solids control
30 Service tools
31 Fishing tools & svcs.
32 Hole openers, mills, junk subs, reamers, stabilizers
33 Coring, dynadrills & directional svcs.
35 Piano wire equip. & svcs.
40 Open & cased hole logging
41 Other Wireline svcs.
42 Production logging
43 Hydrotest, torque, tong svc, thread washing
44 Trucking, hauling, cranes & hot shots
45 Vacuum trucking, disposal charges
46 Tank rental, misc. rentals
47 Site preparation
60 Miscellaneous



Tubing
3½", 9.3#, N-80, EUE, 8RND
0-490'
4½", 11.6#, N-80, LTEC
490-7887'
3½", 9.3#, N-80, EUE, 8RND
7887'-8030'

Standard Sesnon #29

Aliso Canyon

Status: Injection/Withdrawal

Flow Regime: Tubing Flow

Elevation: 2849' G.L.
7' K.B.
KB to MV: 6'

Surface Location: Approximately 750'S & 6100'W of Station 84, T3N, R16W, Sec. 28

Btm. Hole Loc: Straight Hole at effective TVD of 9077'.

4/26/53 - 9/29/53: Well spudded and completed.

2/2/73 - 2/28/73: Pressure tested 7" casing, converted to gas storage by perforation in Sesnon zone. Cleaned out to 9074'. Ran tubing with SSSV.

7/31/73 - 8/7/73: Installed wireline SSSV. Cleaned out to 9077'.

8/27/77 - 9/9/77: Cleaned out to 9072'. Pressure tested casing. Reran tubing with SSSV.

3/5/79 - 3/10/79: Replaced safety system. Se packer at 8040'.

9/20/91 - 11/6/91: Milled packer. Shot 4, 1/2" SPF at 8330' - 8331'. Squeezed shoe leak with 100 sx class "G" cement. Ran tubing conveye perforation guns and shot 6, 1/2" SPF at: 8428'-8436', 8454'-8502', 8522'-8560', 8602'-8636', 8660'-8668', 8674'-8694', 8727'-8737', 8750'-8760', 8810'-8820'. Completed with 7" Otis "BWB" packer and 2-7/8" tubing.

11/4/94 - 11/14/94: Replaced 2⅞" tubing with 3½" and 4½" tubing flow production string

Volume	Cu.Ft.	Bbls.
Tubing	676	120
Annulus	916	163
Casing/Liner	109	19
Total	1701	302

5" Liner Detail:
18#, Flushjoint, 8075' - 9077'
(4.276" I.D.)

8075' - 8727': J55, Perforated
6, 1/2" SPF 8428'-8436',

10, 1/2" SPF 8454'-8502', 8528'-8552', 8602'-8638', 8658'-8668', 8674'-8694'.

8727' - 9077': N80 slotted, .012" gauge, 12 rows, 6" centers, 6 deg. undercut. Perforated 6, 1/2" SPF 8727'-8737', 8750'-8760', 8810'-8820'.

Top Of Zones


	M.D.
MP	8150'
S1	8346'
S2	8382'
S4	8428'
S8	8522'
Frew	8728'

Note: Fish consists of 2 partially milled Robison 5" drillable retainers.

Reviewed

Department	By:	Date
Drilling	Steve Sam Clem	11/14/94
Petroleum Eng.		
Division		

AC_CPUC_0118197



Standard Sesnon #29

Aliso Canyon

Status: Injection/Withdrawal

Flow Regime: Tubing Flow

Elevation: 2849' G.L.
7' K.B.
KB to MV: 6'

Surface Location: Approximately 750'S & 6100'W of Station 84, T3N, R16W, Sec. 28

Btm. Hole Loc: Straight Hole at effective TVD of 9077'.

4/26/53 - 9/29/53: Well spudded and completed.

2/2/73 - 2/28/73: Pressure tested 7" casing, converted to gas storage by perforation in Sesnon zone. Cleaned out to 9074'. Ran tubing with SSSV.

7/31/73 - 8/7/73: Installed wireline SSSV. Cleaned out to 9077'.

8/27/77 - 9/9/77: Cleaned out to 9072'. Pressure tested casing. Reran tubing with SSSV.

3/5/79 - 3/10/79: Replaced safety system. Set packer at 8040'.

9/20/91 - 11/6/91: Milled packer. Shot 4, 1/2" SPF at 8330' - 8331'. Squeezed shoe leak with 100 sx class "G" cement. Ran tubing conveyed perforation guns and shot 6, 1/2" SPF at: 8428'-8436', 8454'-8502', 8522'-8560', 8602'-8636', 8660'-8668', 8674'-8694', 8727'-8737', 8750'-8760', 8810'-8820'. Completed with 7" Otis "BWB" packer and 2-7/8" tubing.

11/4/94 - 11/14/94: Replaced 2⅞" tubing with 3½" and 4½" tubing flow production string.

Volume	Cu.Ft.	Bbls.
Tubing	676	120
Annulus	916	163
Casing/Liner	109	19
Total	1701	302

5" Liner Detail:
18#, Flushjoint, 8075' - 9077'
(4.276" I.D.)

8075' - 8727': J55, Perforated
6, 1/2" SPF 8428'-8436',

10, 1/2" SPF 8454'-8502', 8528'-8552', 8602'-8638', 8658'-8668', 8674'-8694'.

8727' - 9077': N80 slotted, .012" gauge, 12 rows, 6" centers, 6 deg. undercut. Perforated 6, 1/2" SPF 8727'-8737', 8750'-8760', 8810'-8820'.

Top Of Zones

	M.D.
MP	8150'
S1	8346'
S2	8382'
S4	8428'
S8	8522'
Frew	8728'

Note: Fish consists of 2 partially milled Robison 5" drillable retainers.

Reviewed

Department	By:	Date
Drilling	Steve Sam Clean	11/14/94
Petroleum Eng.		
Division		


AC_CPUC_0118198

TUBING DETAIL

WELL: SS-29
FIELD: SESNON

STATUS: Tubing FLOW
DATE: 11-11-94

TUBING PROFILE



	TUBING	TUBING	TUBING	
SIZE	3½"	4½"	3½"	
WEIGHT	9.3#	11.6#	9.3#	
GRADE	N-80	N-80	N-80	
THREAD	BUB	LTC	BUB	
DEPTH	490'	7887'	8029'	

ITEM #	TUBING DETAIL	DRIFT I.D.	O.D.	LENGTH	DEPTH
1.	K.B.	—	—	7.00	7.00
2.	DONUT	—	—	.50	7.50
3	3½" FATIGUE Nipple	2.867	3.500	.62	8.12
4.	3½" N-80 Pup JT. BUB	2.867	4.500	2.14	10.26
5.	15 JTS. 3½" N-80 Tubing BUB	2.867	4.500	466.65	476.91
6.	3½" Pup JT. N-80 BUB	2.867	4.500	4.05	480.96
7.	3½" BAKER T-5 SF. VALVE	2.813	5.375	5.47	486.43
8.	3½" Pup JT. N-80 BUB	2.867	4.500	4.17	490.60
9.	X-OVER 3½ BUB X 4½ LTC	3.125	4.500	1.56	492.16
10.	198 JTS 4½" Tubing LTC	4.000	5.000	7394.84	7887.00
11.	X-OVER 4½ LTC X 3½ BUB	3.500	5.000	1.76	7888.76
12.	1-JT. 3½" N-80 Tubing BUB	2.867	4.500	30.17	7918.93
13.	3½" N-80 Pup JT. BUB	2.867	4.500	3.95	7922.88
14.	3½" BST "K" BM 6" GAS	2.867	5.000	6.15	7929.03
	LIFT MANDREL W/ 1"	—	—	—	—
	Dummy VALVE ON In-Latch	—	—	—	—
15.	3½" N-80 Pup JT. BUB	2.867	4.500	1.48	7930.51
16.	1-JT. 3½" N-80 Tubing BUB	2.867	4.500	31.46	7961.97
17.	3½" "X" D' Sliding SLEEVE	2.750	4.000	3.60	7965.57
18.	3½" N-80 Pup JT. BUB	2.867	4.500	1.08	7966.65
19.	1-JT. 3½" N-80 Tubing BUB	2.867	4.500	31.40	7998.05
20.	2.635 XN Nipple	2.635	4.500	1.35	7999.40
21.	1-JT. 3½" N-80 Tubing BUB	2.867	4.500	30.56	8029.96
22.	X-OVER 3½" BUB X 2 7/8 BUB	2.441	4.500	1.64	8031.60
23.	J-LATCH ASSY. ABOVE	2.347	4.000	.40	8032.00
—	J-LATCH ASSY. in pkr	—	—	.75	8032.75
24.	SEAL ASSY. -2-	2.347	3.250	2.00	8034.75
25	45° GUIDE SHOE	2.347	3.200	.43	8035.18
A	7" 23-29# BWB Packer W/ 2 SAT @ 8,032'.				
	up WT. 96,000#				
	DN. WT. 84,000#				
	Tubing Landed W/ 10,000# ON pkr.				

AC_CPUC_0118199

PIPE TALLY

75-4½

LOCATION Standard Season 29 DATE 11-10-94

MAKE ____ TYPE ____ SIZE ____ WT. ____ GRADE ____ THREAD ____

REMARKS 3½ GUE 8rd w/ Production Equipment & 4½ 2tc

No.	LENGTH FEET		TOTALS FEET	No.	LENGTH FEET		TOTALS FEET	No.	LENGTH FEET		TOTALS FEET
1		43	6.5	1	37	28		1	37	32	
2	2	00	2.00	2	37	26		2	37	31	
3	.1	15	40/75 J Lokq	3	37	27		3	37	30	
4	1	64	⊗ 2.3/4 P 3.1/2 B	4	37	28		4	37	27	
5	31	56	1JT	5	37	34		5	37	30	
6	1	35	XN 21635	6	37	32		6	37	28	
7	31	40	1JT	7	37	33		7	37	28	
8	3	60	SSD XD	8	37	30		8	37	30	
9	1	08	P.J	9	37	32		9	37	29	
0	31	36	JT 3136	0	37	39		0	37	26	
—	105	57		—	373	09 ✓		—	372	91 ✓	
1	1	48	P J	1	37	35		1	37	28	
2	6	15	6Lm	2	37	32		2	37	30	
3	3	95	PJ	3	37	34		3	37	30	
4	30	17	1JT	4	37	30		4	37	30	
5	1	76	⊗ 3½ P 4½ Litae	5	37	33		5	37	28	
6	37	28		6	37	32		6	37	28	
7	37	26		7	37	31		7	37	30	
8	36	28		8	37	28		8	37	28	
9	37	30		9	37	33		9	37	28	
0	37	38		0	37	31		0	37	25	
—	229	01 ✓		—	373	19 ✓		—	372	85 ✓	
1	37	39		1	37	32		1	37	32	
2	37	39		2	37	35		2	37	32	
3	37	29		3	37	30		3	37	26	
4	37	28		4	37	32		4	37	30	
5	37	36		5	37	30		5	37	27	
6	37	32		6	37	26		6	37	26	
7	37	31		7	37	31		7	37	26	
8	37	31		8	37	31		8	37	30	
9	37	32		9	37	27		9	37	31	
0	37	28		0	37	34		0	37	29	
—	373	25 ✓		—	373	08 ✓		—	372	89 ✓	

Hunter-Bakersfield Printing Inc

TALLIED BY ____ 2945.84

75- 4½ 4-3½

AC_CPUC_0118200

PIPE TALLY

90-4½

LOCATION SS 29 DATE 11-10-94

MAKE _____ TYPE _____ SIZE _____ WT. _____ GRADE _____ THREAD _____

REMARKS 4½ LTC Page 2

SS 29

No.	LENGTH FEET		TOTALS FEET		No.	LENGTH FEET		TOTALS FEET		No.	LENGTH FEET		TOTALS FEET	
1	37	27			1	37	30			1	37	24		
2	37	30			2	37	28			2	37	30		
3	37	28			3	37	26			3	37	28		
4	37	27			4	37	29			4	37	24		
5	37	30			5	37	28			5	37	34		
6	37	30			6	37	29			6	37	25		
7	37	28			7	37	28			7	37	35		
8	37	32			8	37	30			8	37	32		
9	37	33			9	37	30			9	37	32		
0	37	32			0	37	27			0	37	34		
—	372	97			—	372	85			—	373	03		
1	37	33			1	37	28			1	37	33		
2	37	31			2	37	22			2	37	30		
3	37	34			3	37	30			3	37	28		
4	37	31			4	37	33			4	37	30		
5	37	31			5	37	31			5	37	28		
6	37	32			6	37	30			6	37	30		
7	37	25			7	37	31			7	37	31		
8	37	31			8	37	30			8	37	30		
9	37	30			9	37	27			9	37	28		
0	37	33			0	37	31			0	37	28		
—	373	11			—	372	93			—	372	96		
1	37	31			1	37	28			1	37	32		
2	37	30			2	37	28			2	37	22		
3	37	34			3	37	27			3	37	28		
4	37	31			4	37	28			4	37	30		
5	37	28			5	37	24			5	37	28		
6	37	30			6	37	29			6	37	26		
7	37	31			7	37	30			7	37	27		
8	37	27			8	37	30			8	37	30		
9	37	26			9	37	30			9	37	24		
0	37	30			0	37	24			0	37	28		
—	372	98	111906		—	372	78	1118.56		—	372	75	111874	

Hunter-Baxersfield Printing Inc

27
75 2.5
90
150 90/2

TALLIED BY _____

1118.56

75

3356.36

106 – 102

AC_CPUC_0118201

G W. O. No. 93496

MISCELLANEOUS JOB REPORT

DIVISION SS-29 DISTRICT Aliso Canyon SHEET 3 OF 3 SHEETS

DATE STARTED 11-4-94 DATE COMPLETED 11-14-94 DATE REPORTED 11-14-94

DESCRIBE BRIEFLY THE WORK PERFORMED

DESCRIBE THE UNIT OF EQUIPMENT, FACILITY, OR PLANT, AND STATE WHETHER IT WAS INSTALLED, REMOVED, RELOCATED, ALTERED, REPAIRED, OR ABANDONED. DESCRIPTION SHOULD INCLUDE SIZE, TYPE, AND LOCATION. UNDER THE DESCRIPTION SHOULD BE LISTED THE MAJOR ITEMS OF MATERIAL USED. IT IS NOT NECESSARY TO LIST MISCELLANEOUS FITTINGS 2" AND LESS IN SIZE WHICH ARE INCIDENTAL TO THE JOB UNLESS THE JOB IS COLLECTIBLE.

QUANTITY		
1	9" X 3½", EUE, 8RND, Type 75 Tubing Hanger	# 4215 SHAFFER 26965
1	3½", EUE, 8R, N-80 Pup St. (2.00')	MDR-254455 BLACK GOLD 23331 TO WEST COAST
1	3½", EUE, 8R, N-80 Pup St. (.68')	MDR-254455 BLACK GOLD 23331 MDR 254461
1	~~9" X 3½", EUE, 8RND, Type 75 Tubing Hanger~~	~~# 26956~~
	Wellhead Equipment & Tree	
1	9" X 3⅛", 5000# DS Seal Flange	# 26956 SHAFFER
2	3⅛", 5000# Barton Gate Valve	# 26956 SHAFFER
1	3⅛" X 3⅛" X 3⅛" X 2 1/16" Studded Cross	# 26956 SHAFFER
1	2 1/16 X 2" LP, 5000# Flange	MDR-254428 SHAFF
1	3⅛" X 2" LP, 5000# Flange	MDR-254428 SHAFF
1	3⅛" 5000# Blind Flange	MDR-254428 SHAFF
1	2 1/16", 5000# Barton Gate Valve	MDR-254428 SHAFF
1	9" X 3½" EUE, 8RND, Type 75 Tubing Hanger	# 26956 SHAFFER
	DAMAGED WHEN INSTALLED REMOVED AND SENT TO WEST COAST FOR INSPECTION	MDR 254461

SIGNED _____ APPROVED _____

SOUTHERN CALIFORNIA GAS CO.—6-E

AC_CPUC_0118202

MISCELLANEOUS JOB REPORT

W. O. No. 93496

DIVISION SS-29 DISTRICT Aliso Canyon SHEET 2 OF 3 SHEETS

DATE STARTED 11-4-94 DATE COMPLETED 11-14-94 DATE REPORTED 11-14-94

DESCRIBE BRIEFLY THE WORK PERFORMED

DESCRIBE THE UNIT OF EQUIPMENT, FACILITY, OR PLANT, AND STATE WHETHER IT WAS INSTALLED, REMOVED, RELOCATED, ALTERED, REPAIRED, OR ABANDONED. DESCRIPTION SHOULD INCLUDE SIZE, TYPE, AND LOCATION. UNDER THE DESCRIPTION SHOULD BE LISTED THE MAJOR ITEMS OF MATERIAL USED. IT IS NOT NECESSARY TO LIST MISCELLANEOUS FITTINGS 2" AND LESS IN SIZE WHICH ARE INCIDENTAL TO THE JOB UNLESS THE JOB IS COLLECTIBLE.

QUANTITY	
	Installed In The Well
1	Otis 45° Mule Shoe (2.441" ID) Reran
1	Otis "S" Latch and Seal Assy. Rebuilt/Reran HALLIBURTON 617360-7
1	X-Over 2 7/8", 6.5# 8RND EUE x 3½", 9.3# 8RND EUE (1.64') # 95-1002 T1 TAGAD
1	Otis "XN" Nipple (1.35') #BL-92-07758 HALLIBURTON 617360-7
1	3½", 9.3#, N-80, EUE 8R Pup St. (1.08') #BL-92-07758 HALLIBURTON 617360-7
1	3½" "XD" Sliding Sleeve (3.60') # BL-92-07758 HALLIBURTON # 617360-7
1	3½", 9.3# N-80 EUE 8R Pup St (1.48') # BL-91-02946 BST # 1796
1	3½" EUE 8R KBMg Mandrel (6.15') # BL-91-02946 BST 1796
1	DU-1-Orifice (Dummy Valve) #BL-91-02946 BST 1796
1	M-Latch Class "A" Repair MDR-252721 BST 1796
1	SOV - Operating Valve (2700 PSI) # BL-91-02946 BST 1796 DELIVERED TO REPAIR
1	3½" EUE 8R N-80 Pup St (3.95') #BL-91-02946 BST 1796
1	X-Over 3½" 9.3# EUE x 4½", 11.6# LTEC (1.76') # 95-1002 T1 TAGAD
4	Sts 3½" 9.3# EUE 8RND N-80 (124.49') # 7705
198	Sts 4½", 11.6#, LTEC, N-80 Tubing (7394.84') # 7705
1	X-Over 4½", 11.6#, LTEC x 3½", 9.3# EUE (1.56') # 95-1002 T1 TAGAD
1	3½" EUE 8R N-80 Pup St (4.17') CS-010042 BAKER
1	3½", SCSSV T-5 Subsurface Safety Valve Baker CS-010042
1	3½" EUE 8R N-80 Pup St (1.14') CS-010042
15	Sts 3½" 9.3# EUE 8RND N-80 (466.65') # 7705
1	3½" EUE 8R N-80 Pup St. (2.14') Black Gold 53331 TO WESTCO MDR 254461 BAKER
1	3½" EUE 8R N-80 Pup St (1.65') CS-010042 TO WEST CO. MDR 254461

SIGNED _____ APPROVED _____

SOUTHERN CALIFORNIA GAS CO.—6-E

AC_CPUC_0118203

G. W. O. No. 93496

MISCELLANEOUS JOB REPORT

DIVISION SS-29 DISTRICT Aliso Canyon SHEET 1 OF 3 SHEETS

DATE STARTED 11-4-94 DATE COMPLETED 11-14-94 DATE REPORTED 11-14-94

DESCRIBE BRIEFLY THE WORK PERFORMED


DESCRIBE THE UNIT OF EQUIPMENT, FACILITY, OR PLANT, AND STATE WHETHER IT WAS INSTALLED, REMOVED, RELOCATED, ALTERED, REPAIRED, OR ABANDONED. DESCRIPTION SHOULD INCLUDE SIZE, TYPE, AND LOCATION. UNDER THE DESCRIPTION SHOULD BE LISTED THE MAJOR ITEMS OF MATERIAL USED. IT IS NOT NECESSARY TO LIST MISCELLANEOUS FITTINGS 2" AND LESS IN SIZE WHICH ARE INCIDENTAL TO THE JOB UNLESS THE JOB IS COLLECTIBLE.

QUANTITY	
	Removed From the Well
253 Jts	2 7/8" EUE 8RND 6.4# J-55 Tubing MDR - 254451/254452
1	Camco "MMA" GLM w/ 1.5 S.O.V. on RA Latch MDR 252723
2	2 7/8" EUE 8RND 6.4# J-55 Pup Jt 4.09' & .68' MDR - 254453
1	Otis "XD" SSD (2.313" ID) MDR - 252685
1	Otis "XN" No-Go nipple MDR - 252685
1	Otis J-Latch and 2 seal units (2.441 ID) - Rebuilt/Reran
1	Otis Mule Shoe (2.441 ID) - Reran
	Wellhead and Tree
1	Flange 9" x 2 9/16" - 5000# ASD DS Seal Flange MDR - 254429 Shaffer
1	Cross 2 9/16" x 2 9/16" x 2 1/16" x 2 1/16" 5000# Studded Cross MDR - 254429
1	Flange 2 1/16" - 5000# Blind MDR - 254429
1	X-Mas Tree Cap 3" x 2 9/16" 5000# Uni Bolt MDR - 254429
1	Valve - 2 9/16" 5000# Barton gate MDR - 254430
1	Valve 2 9/16" 5000# Barton gate MDR - 254430
1	Tubing Hanger 7" 2 7/8" x 2 7/8" EUE 8RND
	NOT NIPPLED TO SS 9
12	4 1/2" 11.6# N-80 LT&C MBMS MDR 254459
1	3 1/2" EUE N-80 OR 9.3# MBMS "

SIGNED S. McLEAN APPROVED

SOUTHERN CALIFORNIA GAS CO.-6-E

AC_CPUC_0118204



Call the Otis divisional office nearest you!

Anchorage, AK	Santa Fe Springs, CA	Elk City, OK	Denver, CO	Oklahoma City, OK
(907) 276-4054	(213) 864-3701	Completions (405) 225-6371 Special Services (405) 225-1630	(303) 832-7541	(405) 632-2361

75-4½

PIPE TALLY

LOCATION Standard Season 29 DATE 11-10-94

MAKE _____ TYPE _____ SIZE _____ WT. _____ GRADE _____ THREAD _____

REMARKS 3½ Gas Sled w/ Production Equipment & 4½ 2 tc

No.	LENGTH FEET		TOTALS FEET	No.	LENGTH FEET		TOTALS FEET	No.	LENGTH FEET		TOTALS FEET
1		43	6.5	1	37	28		1	37	32	
2	2	06	2.00	2	37	26		2	37	31	
3	1	15	40/75 Jt Lost	3	37	27		3	37	30	
4	1	44	⊗ 2 7/8 P 3½ B	4	37	28		4	37	27	
5	31	56	IJT	5	37	34		5	37	30	
6	1	35	XN 2.635	6	37	32		6	37	28	
7	31	40	IJT	7	37	33		7	37	28	
8	3	40	SSD XD	8	37	30		8	37	30	
9	1	08	P.J	9	37	32		9	37	29	
0	31	36	JT 8136	0	37	39		0	37	26	
—	105	57		—	373	09 ✓		—	372	91 ✓	
1	1	48	P J	1	37	35		1	37	28	
2	4	15	6 Lm	2	37	32		2	37	30	
3	3	95	PJ	3	37	34		3	37	30	
4	30	17	IJT	4	37	30		4	37	30	
5	1	76	⊗ 3½ P 4½ Ltac	5	37	33		5	37	28	
6	37	28		6	37	32		6	37	28	
7	37	26		7	37	31		7	37	30	
8	36	28		8	37	28		8	37	28	
9	37	30		9	37	33		9	37	28	
0	37	38		0	37	31		0	37	25	
—	229	01 ✓		—	373	19 ✓		—	372	85 ✓	
1	37	39		1	37	32		1	37	32	
2	37	39		2	37	35		2	37	32	
3	37	29		3	37	30		3	37	26	
4	37	28		4	37	32		4	37	30	
5	37	36		5	37	30		5	37	27	
6	37	32		6	37	26		6	37	26	
7	37	31		7	37	31		7	37	26	
8	37	31		8	37	31		8	37	30	
9	37	32		9	37	27		9	37	31	
0	37	28		0	37	34		0	37	29	
—	373	25 ✓		—	373	08 ✓		—	372	89 ✓	

Hunter-Bakersfield Printing Inc

TALLIED BY _____ 2945.84

75- 4½ 4-3½

AC_CPUC_0118206

PIPE TALLY

90-4½

LOCATION SS 29 DATE 11-10-94

MAKE _____ TYPE _____ SIZE _____ WT. _____ GRADE _____ THREAD _____

REMARKS 4½ LTC Page 2

No.	LENGTH FEET	TOTALS FEET	No.	LENGTH FEET	TOTALS FEET	No.	LENGTH FEET	TOTALS FEET
1	37 27		1	37 30		1	37 24	
2	37 30		2	37 28		2	37 30	
3	37 28		3	37 24		3	37 28	
4	37 27		4	37 29		4	37 24	
5	37 30		5	37 28		5	37 34	
6	37 30		6	37 29		6	37 25	
7	37 28		7	37 28		7	37 35	
8	37 32		8	37 30		8	37 32	
9	37 33		9	37 30		9	37 32	
0	37 32		0	37 27		0	37 34	
—	~~372 97~~ ✓		—	~~372 85~~ ✓		—	~~373 03~~ ✓	
1	37 33		1	37 28		1	37 33	
2	37 31		2	37 22		2	37 30	
3	37 34		3	37 30		3	37 28	
4	37 31		4	37 33		4	37 30	
5	37 31		5	37 31		5	37 28	
6	37 32		6	37 30		6	37 30	
7	37 25		7	37 31		7	37 31	—
8	37 31		8	37 30		8	37 30	
9	37 30		9	37 27		9	37 28	
0	37 33		0	37 31		0	37 28	
—	~~373 11~~ ✓		—	~~372 93~~ ✓		—	~~372 96~~ ✓	
1	37 31		1	37 28		1	37 32	
2	37 30		2	37 28		2	37 22	
3	37 34		3	37 27		3	37 28	
4	37 31		4	37 28		4	37 30	
5	37 28		5	37 24		5	37 28	
6	37 30		6	37 29		6	37 26	
7	37 31		7	37 30		7	37 27	
8	37 27		8	37 30		8	37 30	
9	37 26		9	37 30		9	37 24	
0	37 30		0	37 24		0	37 28	
—	~~372 98~~	111906	—	~~372 78~~ ✓	1118.56	—	~~372 75~~ ✓	111874

Hunter-Bakersfield Printing Inc

75 2.7
81 2.5
156 90
1/2

118.56

TALLIED BY _____ 75

3356.36

106 – 102

AC_CPUC_0118207

PIPE TALLY

33-4½

LOCATION _____ DATE _____

MAKE _____ TYPE _____ SIZE _____ WT. _____ GRADE _____ THREAD _____

REMARKS Page 3

4½ Cut C, ⊗ Safty + 3½ Gas

No.	LENGTH FEET		TOTALS FEET		No.	LENGTH FEET		TOTALS FEET		No.	LENGTH FEET		TOTALS FEET	
1	37	25			1	37	30			1	37	23	out	4½
2	37	28			2	37	29			2	37	31		
3	37	23			3	37	32	501.04		3	37	25		
4	37	27			4	1	56	⊗ 499.48		4	37	30		
5	37	30			5	4	17	495.31		5	37	24		
6	~~35~~ 37	~~98~~			6	5	47	489.84		6	37	30		
7	37	25			7	4	05	485.79		7	37	32		
8	37	29			8	30	17	453.62 (3½)		8	37	24		
9	37	26			9	31	40	424.22		9	37	25		
0	37	26			0	31	32	392.90		0	37	24		
—	~~371~~	~~40~~			—	—	—			—	—	—		
1	37	24			1	30	01	362.89		1	37	34		
2	37	30			2	31	36	331 53		2	37	25	out	4½
3	37	27			3	31	45	300 08		3				
4	37	27			4	31	36	268 72		4				
5	37	26			5	31	35	237 37		5				
6	37	28			6	31	35	206 02		6				
7	37	30			7	31	35	174 67		7				—
8	37	28			8	31	39	143 28		8				
9	37	26			9	31	36	111 92		9				
0	37	30			0	30	03	81 89		0				
—	~~372~~	~~76~~			—	—	—			—	—	—		
1	37	26			1	31	35	50 54		1				
2	37	25			2	31	40	19.14		2				
3	37	28			3	31	46	Out		3				
4	37	29			4					4				
5	37	26			5					5				
6	37	26			6					6				
7	37	29			7					7				
8	37	31			8					8				
9	37	~~22~~			9					9				
0	37	27			0					0				
—	~~372~~	~~69~~			—	—	—			—	—	—		

Hunter-Bakersfield Printing, Inc

7/19.05

TALLIED BY _____

AC_CPUC_0118208

Load #2

WEST COAST PIPE INSPECTION
&
MAINTENANCE
5900 East Lerdo Highway • Shafter, CA 93263
Phone: (805) 399-1163

TALLY SHEET

DATE 11/8/94 JOB ORDER NO. 7705

PAGE _____ OF _____ LOAD _____ OF _____

SERVICED BY SOUTHERN CALIFORNIA GAS COMPANY - Ex: WCPI/Tryad Service, Shafter, CA

SOLD TO SOUTHERN CALIFORNIA GAS COMPANY

DESCRIPTION 4-1/2" O.D. 11.60# N-80 8rd LT&C R-3 (Bottom of Load) ☒ INSPECTED ☐ NON-INSPECTED

BEGINNING INVENTORY	69	JOINT COUNT	67	
TOTAL LOAD	67 Unsp rack	FOOTAGE	2515.70	
ENDING INVENTORY	2	7,800' Appx to fill out load		

1	3750	3750	3760	3750	
2	3760	3760	3750	3760	
3	3750	3750	3760	3760	
4	3750	3750	3750	3750	
5	3760	3750	3750	3760	
6	3760	3750	3760	3750	
7	3760	3750	3750	3760	
8	3750	3760	3750		
9	3760	3750	3760		
10	3760	3750	3760		
11	3760	3750	3750		
12	3760	3750	3750		
13	3750	3760	3750		
14	3750	3760	3760		
15	3760	3760	3750		
16	3750	3760	3760		
17	3750	3760	3760		
18	3750	3760	3750		
19	3760	3760	3760		
20	3750	3760	3750		
TOTAL	751.00	751.00	750.80	262.90	

CARRY OVER	5372.70	143
SHEET	2515.70	67
TOTAL	7888.40	210

TALLY APPROVED BY: _____

TRUCK CO. H & H Oil Tool - Will Call

THE INVENTORY OF PIPE DESCRIBED ABOVE HAS BEEN PROPERLY LOADED AND SECURED ONTO THE TRANSPORTING VEHICLE.

_____ 11-9-94
DRIVER'S SIGNATURE DATE

Creative Printing 2153

AC_CPUC_0118209

Load #1

WEST COAST PIPE INSPECTION
&
MAINTENANCE

5900 East Lerdo Highway • Shafter, CA 93263
Phone: (805) 399-1163

TALLY SHEET

DATE 11/8/94 JOB ORDER NO. 7705

PAGE ____ OF ____ LOAD ____ OF ____

SERVICED BY SOUTHERN CALIFORNIA GAS COMPANY - Ex: WCPI/Tryad Service, Shafter, CA

SOLD TO SOUTHERN CALIFORNIA GAS COMPANY

DESCRIPTION 4-1/2" O.D. 11.60# N-80 8rd LT&C R-3 (Bottom of Load) NKK ☒ INSPECTED ☐ NON-INSPECTED

BEGINNING INVENTORY JOINT COUNT 89

TOTAL LOAD 89 FOOTAGE 3345.40

ENDING INVENTORY 7,800' Approximately Needed

1	3780	3760	3760	3760	3760
2	3780	3760	3760	3760	3750
3	3770	3760	3750	3760	3750
4	3780	3650	3750	3760	3750
5	3780	3750	3750	3760	3760
6	3780	3750	3750	3760	3760
7	3780	3760	3750	3760	3760
8	3780	3770	3760	3760	3750
9	3780	3760	3750	3760	3750
10	3760	3760	3750	3760	
11	3750	3770	3750	3760	
12	3780	3770	3760	3750	
13	3750	3770	3760	3760	
14	3760	3770	3760	3760	
15	3750	3770	3760	3760	
16	3760	3760	3760	3760	
17	3750	3750	3760	3760	
18	3750	3750	3760	3760	
19	3760	3760	3750	3760	
20	3760	3760	3760	3760	
TOTAL	753.40	751.10	751.10	751.90	337.90

CARRY OVER

SHEET 3345.40 89 JT

TOTAL 3345.40 89 JT

TALLY APPROVED BY:

TRUCK CO. H & H Oil Tool - Will Call

THE INVENTORY OF PIPE DESCRIBED ABOVE HAS BEEN PROPERLY LOADED AND SECURED ONTO THE TRANSPORTING VEHICLE.

DRIVER'S SIGNATURE 11-8-94 DATE

Creative Printing 2153

AC_CPUC_0118210

Load #1

WEST COAST PIPE INSPECTION
&
MAINTENANCE

5900 East Lerdo Highway • Shafter, CA 93263
Phone: (805) 399-1163

TALLY SHEET

DATE 11/8/94 JOB ORDER NO. 7705

PAGE _____ OF _____ LOAD _____ OF _____

SERVICED BY SOUTHERN CALIFORNIA GAS COMPANY - Ex: WCPI/Tryad Service, Shafter, CA

SOLD TO SOUTHERN CALIFORNIA GAS COMPANY

DESCRIPTION 3-1/2" O.D. 9.30# N-80 8rd EUE R-2 (Top of Load) ☐ INSPECTED ☐ NON-INSPECTED

BEGINNING INVENTORY	24	JOINT COUNT	20
TOTAL LOAD	20	FOOTAGE	631.90
ENDING INVENTORY	4		620'

1	3180				
2	3070				
3	3190				
4	3200				
5	3180				
6	3180				
7	3070				
8	3190				
9	3180				
10	3190				
11	3050				
12	3180				
13	3190				
14	3180				
15	3180				
16	3190				
17	3050				
18	3180				
19	3180				
20	3180				
TOTAL	631.90				

CARRY OVER

SHEET 631.90 20 ✓

TOTAL 631.90 20 ✓

TALLY APPROVED BY:

TRUCK CO. H & H Oil Tool - Will Call

THE INVENTORY OF PIPE DESCRIBED ABOVE HAS BEEN PROPERLY LOADED AND SECURED ONTO THE TRANSPORTING VEHICLE.

Bob Hans — DRIVER'S SIGNATURE

11-8-94 — DATE

Creative Printing 2153

AC_CPUC_0118211

Load #3

WEST COAST PIPE INSPECTION
&
MAINTENANCE
5900 East Lerdo Highway • Shafter, CA 93263
Phone: (805) 399-1163

TALLY SHEET

DATE 11/8/94 JOB ORDER NO. 7705

PAGE _____ OF _____ LOAD _____ OF _____

SERVICED BY SOUTHERN CALIFORNIA GAS COMPANY - Ex: WCPI/Tryad Service, Shafter, CA

SOLD TO SOUTHERN CALIFORNIA GAS COMPANY

DESCRIPTION 4-1/2" O.D. 11.60# N-80 8rd LT&C R-3 (Bottom of Load) ☒ INSPECTED ☐ NON-INSPECTED

BEGINNING INVENTORY	123	JOINT COUNT	54
TOTAL LOAD	54 Dump rest	FOOTAGE	2027.30
ENDING INVENTORY	67		7,800' ~~Approximately~~ Full Load

1	~~B~~770	3750	3750		
2	3750	3760	3750		
3	3750	3760	3750		
4	3760	3750	3760		
5	3760	3750	3750		
6	3750	3750	3760		
7	3760	3760	3750		
8	3750	3750	3750		
9	3750	3760	3760		
10	~~8~~3750	3750	3760		
11	~~3~~750	3750	3760		
12	3750	3750	3760		
13	3760	3760	3760		
14	3750	3750	3750		
15	3760	3760			
16	3750	3750			
17	3750	3750			
18	3750	3760			
19	3750	3760			
20	3750	3760			
TOTAL	750.70	750.90	525.70		

CARRY OVER	3345.40	89
SHEET	2027.30	54
TOTAL	5372.70	143

TALLY APPROVED BY:

TRUCK CO. H & H Oil Tool - Will Call


THE INVENTORY OF PIPE DESCRIBED ABOVE HAS BEEN PROPERLY LOADED AND SECURED ONTO THE TRANSPORTING VEHICLE.

Tom L 11-9-94
DRIVER'S SIGNATURE DATE

Creative Printing 2153

AC_CPUC_0118212

⊗ ○ used on SS-29 ○ 11-12-94




1.64

3½ 6ue 8rd Coupling


2⅞ 6ue Pin

3½ 6ue 8rd Pin



1.76

4½ LT+C Coupling



1.56

3½ 6ue Coupling

4½ LT+C Pin

AC_CPUC_0118213

WORKOVER PROGRAM

OPERATOR:	Southern California Gas Company
FIELD:	Aliso Canyon
WELL:	SS 29
CONTRACTOR:	Pride 447
OBJECTIVE:	Install SCSSV
APPROXIMATE LOCATION:	
ELEVATION:	Ground level 2849'. Take all measurements from KB 7' above ground level.
SAFETY:	Hard hats are to be worn by all personnel on or near a rig. No smoking is permitted within 100' of the wellhead or near any other flammable material.

PRESENT CONDITIONS:

0'	- 999'	11-3/4"	42# .	
999'	1042'	11-3/4	47#	
0'	974'	7"	23#	N-80
974'	4454'	7"	23#	J-55
4454'	6494'	7"	23#	N-80
6494'	8170'	7"	26#	N-80 Otis 'BWB'@ 8032'
8075'	9790'	5"	18# See perforation detail on mechanical. WSO squeezed w/100 sx @ 8330'-8331'.	

2-7/8" Tubing Detail Attached

WORK CATEGORY:

PR

- o Prepare surface as required.
- o Perform any required piano wire work.
- o Spot open top storage tank on location.
- o Check with the Storage Field Engineer to determine any changes and condition of the well since writing of this program and current bottom-hole pressure in the vicinity of the well.
- o Well Kill Requirements:

  a. Top of zone 8428' M. D.
  b. Estimated bottom-hole pressure = 3150 psig.
  c. Calculated fluid density to provide 300 psi overbalance =59 lbs / cu.ft. Use 63 lbs/cu.ft 2% KCl fluid.
  d. Wellbore fluid volumes:

Tubing	=	47 bbls.
Casing/Liner	=	19 bbls.
Annulus	=	254 bbls.
Total		320 bbls.

  * Be sure to bleed off surface string annulus.

* Maintain surface fluid volume equal to or greater than well volume during workover.

PROGRAM

MI 1. Move in and rig up.

- o Bleed off all casing annuli to zero pressure.
- o Rig up drip pans and plastic sheeting and dike area as necessary for spill control.
- o Be sure well is completely dead. Notify Drilling Engineer if well is not in this condition.
- o Set equalizing back pressure valve in doughnut.
- o Remove xmas tree. Send xmas tree in for repairs as required.

WW 2. Install 9" Class III 5000 psi BOPE.

- o Include Hydril bag and double gate with 2-7/8" pipe rams and blind rams.
- o Bag and both sets of rams are to be actuated hydraulically by a 3000 psi, minimum 60 gallon accumulator with dual remote controls and auxiliary nitrogen.
- o Install 9" 5000 psi spool with choke and kill lines as well as check valve.
- o Choke manifold to have discharge to Gas Company system, with block

valve and bleeder as well as connections to fluid tank.

- o Inspect Hydril bag when installing BOPE.
- o Use new Rx API rings on all untested BOPE connections.

WW 3. Pressure test BOPE.

- o Blind rams, 2-7/8" pipe rams and choke manifold are to be tested to 5000 psi with water.
- o Test Hydril bag to 3500 psi with water.

CO 4. Pull tubing.

- o Remove back pressure valve.
- o Release tubing from packer.
- o If unable to release from packer, contact the Drilling Engineer. Have tubing visually inspected while pulling out of hole. Send good tubing in for rack inspection.

5. Install tubing string.

- o Gator hawk tubing to 4000 psig while running in well.
- o Tubing string to include :

Otis guide shoe
Otis seal assembly, (2) seals
Otis J-latch
Crossover from seal assembly to 3-1/2"8Rd EUE

One joint 3-1/2" 8Rd EUE tubing
3-1/2" Otis XN no-go nipple (2.666" ID).
One joint 3-1/2" 8Rd EUE tubing
Otis 3-1/2" "XD" sliding sleeve (closed).
One joint 3-1/2" 8Rd EUE tbg.
3-1/2" BST KBMG gas lift mandrel with dummy valve.
One joint 3-1/2" 8Rd EUE tbg.
Crossover 3-1/2" 8Rd EUE pin X 4-1/2" 8Rd EUE box
4-1/2" 8Rd EUE tubing to approximately 500' from surface.
Crossover 4-1/2" 8Rd EUE pin X 3-1/2" 8Rd EUE box
One 3-1/2" Baker T5 series SCSSV
3-1/2" 8Rd EUE tubing and pups to surface as necessary.

- Pull 20,000 lbs over tubing weight to check latch on packer.

- Space out and land tubing on Otis model "BWB" packer at 8032' with 10,000#.

- Pressure casing to 1500 psig ,keep tubing full and check for return.

- Run in with wireline and open sliding sleeve.

Test SCSSV in accordance with attached procedure.

CO 6. Remove BOPE and Install Xmas Tree.

- Install equalizing back pressure

valve in tubing hanger.

- o Remove BOPE.
- o Install xmas tree.
- o Pressure test seals, xmas tree, seal flange, and tubing head to 5000 psig with oil for 20 minutes.
- o Tighten all wellhead bolts.
- o Check and close all wellhead valves.
- o Install tapped blind flanges with bleeder valves on all wellhead valves.


MO 7. Rig down and move out rig.

- o Inform the Storage Field Engineer before moving off wellsite so proper wellsite safety protection can be arranged.
- o Release rig.
- o Clean up wellsite. All trash, debris, equipment and materials to be removed from site.

A walk-through inspection by a Drilling Department representative and the Storage Field Engineer or their designee is conducted after the site is cleaned.

E. S. Sinclair

AC_CPUC_0118219



Standard Sesnon #29

Aliso Canyon

Status:	Injection/Withdrawal
Flow Regime:	Tubing Flow
Elevation:	2849' G.L. 7' K.B. KB to MV: 6'
Surface Location:	Approximately 750'S & 6100'W of Station 84, T3N, R16W, Sec. 28
Btm. Hole Loc:	Straight Hole at effective TVD of 9077'.

4/26/53 - 9/29/53: Well spudded and completed.

2/2/73 - 2/28/73: Pressure tested 7" casing, converted to gas storage by perforation in Sesnon zone. Cleaned out to 9074'. Ran tubing with SSSV.

7/31/73 - 8/7/73: Installed wireline SSSV. Cleaned out to 9077'.

8/27/77 - 9/9/77: Cleaned out to 9072'. Pressure tested casing. Reran tubing with SSSV.

3/5/79 - 3/10/79: Replaced safety system. Set packer at 8040'.

9/20/91 - 11/6/91: Milled packer. Shot 4, 1/2" SPF at 8330' - 8331'. Squeezed shoe leak with 100 sx class "G" cement. Ran tubing conveyed perforation guns and shot 6, 1/2" SPF at: 8428'-8436', 8454'-8502', 8522'-8560', 8602'-8636', 8660'-8668', 8674'-8694', 8727'-8737', 8750'-8760', 8810'-8820'. Completed with 7" Otis "BWB" packer and 2-7/8" tubing.

11/4/94 - 11/14/94: Replaced 2⅞" tubing with 3½" and 4½" tubing flow production string.

Volume	Cu.Ft.	Bbls.
Tubing	676	120
Annulus	916	163
Casing/Liner	109	19
Total	1701	302

5" Liner Detail:
18#, Flushjoint, 8075' - 9077' (4.276" I.D.)

8075' - 8727': J55, Perforated 6, 1/2" SPF 8428'-8436',

10, 1/2" SPF 8454'-8502', 8528'-8552', 8602'-8638', 8658'-8668', 8674'-8694'.

8727' - 9077': N80 slotted, .012" gauge, 12 rows, 6" centers, 6 deg. undercut. Perforated 6, 1/2" SPF 8727'-8737', 8750'-8760', 8810'-8820'.

Top Of Zones

	M.D.
MP	8150'
S1	8346'
S2	8382'
S4	8428'
S8	8522'
Frew	8728'

Note: Fish consists of 2 partially milled Robison 5" drillable retainers.

Reviewed


Department	By:	Date
Drilling	[signature]	11/14/94
Petroleum Eng.		
Division		

AC_CPUC_0118220

October 07, 1994

Approved: J.D. Mansdorfer
J. D. Mansdorfer

cc:	I. R. Binmore	w/o att.
	N. W. Buss	w/o att.
	T. Holland	w/o att
	D. G. Neville	att.
	CPS Tool Pushers	att.
	H. Robinson	w/o att.
	T. Schroeder	w/o att.
	M. A. Woiemberghe	w/o att.
	Well file	att.



Standard Sesnon #29

Aliso Canyon

Status: Injection/Withdrawal

Flow Regime: Casing Flow

Elevation: 2849' G.L.
7' K.B.
KB to MV: 6'

Surface Location: Approximately 750'S & 6100'W of Station 84, T3N, R16W, Sec. 28

Btm. Hole Loc: Straight Hole at effective TVD of 9077'.

4/26/53 - 9/29/53: Well spudded and completed.

2/2/73 - 2/28/73: Pressure tested 7" casing, converted to gas storage by perforation in Sesnon zone. Cleaned out to 9074'. Ran tubing with SSSV.

7/31/73 - 8/7/73: Installed wireline SSSV. Cleaned out to 9077'.

8/27/77 - 9/9/77: Cleaned out to 9072'. Pressure tested casing. Reran tubing with SSSV.

3/5/79 - 3/10/79: Replaced safety system. Se packer at 8040'.

9/20/91 - 11/6/91: Milled packer. Shot 4, 1/2" SPF at 8330' - 8331'. Squeezed shoe leak with 100 sx class "G" cement. Ran tubing conveye perforation guns and shot 6, 1/2" SPF at: 8428'-8436', 8454'-8502', 8522'-8560', 8602'-8636', 8660'-8668', 8674'-8694', 8727'-8737', 8750'-8760', 8810'-8820'. Completed with 7" Otis "BWB" packer and 2-7/8" tubing.

Volume	Cu.Ft.	Bbls.
Tubing	261	46.5
Annulus	1427	254
Casing/Liner	109	19
Total	1797	319.5

5" Liner Detail:
18#, Flushjoint, 8075' - 9077'
(4.276" I.D.)

8075' - 8727': J55, Perforated 6, 1/2" SPF 8428'-8436',

10, 1/2" SPF 8454'-8502', 8528'-8552', 8602'-8638', 8658'-8668', 8674'-8694'.

8727' - 9077': N80 slotted, .012" gauge, 12 rows, 6" centers, 6 deg. undercut. Perforated 6, 1/2" SPF 8727'-8737', 8750'-8760', 8810'-8820'.

Top Of Zones

	M.D.
MP	8150'
S1	8346'
S2	8382'
S4	8428'
S8	8522'
Frew	8728'

Note: Fish consists of 2 partially milled Robison 5" drillable retainers.

Reviewed

Department	By:	Date
Drilling	R.H. Duell	9/1/92
Petroleum Eng.		9/1/92
Division		9/1/92


AC_CPUC_0118222

TUBING DETAIL

WELL: STANDARD SESNON #29
FIELD: ALISO CANYON

STATUS: Injection/Withdrawal
DATE: 11-6-91

DIAGRAM



	TUBING	TUBING	TUBING	
SIZE	2 7/8			
WEIGHT	6.5			
GRADE	J55			
THREAD	8RD EUE			
DEPTH	8035'			
I.D.	2.441			
DRIFT ID	2.347			
O.D.	3.668 TC			

ITEM #	DESCRIPTION	LENGTH	DEPTH
1.	KB	6.92	6.92
2.	G.L. TO TBG HEAD	-.14	6.78
3.	HANGER 7" 2 7/8" EUE X 2 7/8" EUE Box	.60	7.38
4.	FATIGUE NIPPLE 2 7/8 EUE Pin x Pin	.68	8.06
5.	PUP JT 2 7/8" 6.5# N80 EUE	4.09	12.15
6.	250 JTS. 2 7/8" 6.5# J55 EUE	7907.35	7919.50
7.	BST 'MMA' GLM W/ 1 1/2" RA LATCH	12.92	7932.42
8. ✓	1 JT. 2 7/8 EUE J55 TBG.	31.49	7963.91
9. ✓	OTIS 2.313" 'XD' SSD	3.21	7967.12
10. ✓	1 JT 2 7/8" EUE J55" TBG	31.55	7998.67
11. ✓	OTIS 2.205" 'XN' NO-GO NIPPLE	1.28	7999.50
12. ✓	1 JT. 2 7/8" EUE J55 TBG	31.55	8031.50
13. ✓	OTIS J-LATCH W/ 2 SEAL UNITS	1.50 / 2.49	8032
14. ✓	OTIS MULE SHOE GUIDE	.60	
15.			
16.			
17.			
18.	A. OTIS 7" 23-29# 'BWB' PKR		
19.	3.25" I.D. SET AT:		8032'
20.			
	TUBING LANDED W/ 8000#		
	DOWN ON PACKER		

AC_CPUC_0118223

OTIS

GENERAL PR UCT INFORMATION

Doc: 212.1.1.2A


Product Code

Date: 11-4-91

Product Name: 'WE' Permanent Packer

Page: 1

SOU CAL GAS CO.
ALISO CANYON
SS#29




PACKER - OTIS BWB (212BWB 70700-A) 3.25" I.D.
23-29#

Note: These instructions describe desired results from use of Otis equipment but such results are not guaranteed. Operation of equipment is subject to mechanical limitations and Otis shall only be liable for its merchandise and service as set forth in its general terms and conditions

Otis Engineering Corporation • Dallas, Texas, U.S.A.

AC_CPUC_0118224

TYPE IV



Well Name: SS 29 - Aliso Canyon

Mfgr.: Shaffer

Date Prepared: 12-20-82

WELLHEAD DESCRIPTION

Well No. SS-29

Field Aliso

Date Prepared 5-4-81

Wellhead Mfgr Shaffer

1. Casing Head Shaffer Size 13-5/8" Type KD
   Slips & Pack-off 13-5/8" x 7"
   A. Surface Csg. Size 11-3/4" Wt 42# Grade H-40
   B. Casing Head Valve Marpac Size 2" 3000 psi Fig.No. CSB-790-JN
2. Seal Flange Shaffer Size 13-5/8" x 10" 5000 psi
   A. Type Seal PS Ring BX-160 & R-54
3. Tubing Head Shaffer Size 10" x 8" 5000 psi Type 63-L-1
   Ring R-54 & Ring R-50
   Outlets 2-3" Sec.Seal PS
   Valve Removal Thrd 2-1/2" API
   A. Tubing Hanger Shaffer Size 8" x 2-7/8" Type AJO
   B.P.V. Size 2-7/8" Thrd
   B. Tubing Head Valves 2 Mc Evoy Size 3" 5000 psi Fig.No. 129
   C. Automatic Csg. Valve WKM Size 3" 5000 psi Fig.No. 114522
4. Adapter Seal Flange Shaffer Size 8"x2-1/2"x 2-9/16" Type AJO
   A. Ring Size R-50 & R-27
5. Master Valve McEvoy Size 2-1/2" 5000 psi Fig.No. 129
6. Xmas Tree Cross Shaffer Size 2-9/16"x2-9/16"x2-1/16"x 2-1/16"x2" Thru 2-9/16" Bore Across 2-1/16"
7. Tubing Wing Valves Rockwell Size 2" 5000 psi Fig.No. 21055
   A. Automatic Tbg. Valve WKM Size 2" 5000 psi Fig. No. 114522
8. Unibolt Size 3" 5000 psi Inside Thrds
9. Wt. Landed in Csg. Head 8170' 7" Wt. 26# 23# Grade N-80 ST&C
10. Wt. Landed on Doughnut 8030' 2-7/8" 10,000 Wt. 6.5 Grade N-80 8Rd EUE
11. Tubing Head to Ground Level

AC_CPUC_0118226

SUBMIT IN DUPLICATE

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION

DIVISION OF OIL AND GAS

History of Oil or Gas Well

Operator Southern California Gas Company Field Aliso Canyon County Los Angeles
Well Standard Sesnon #29, Sec. 28, T 3N, R 16W, SB B. & M.
A.P.I. No. 037-00041 Name R.D. Phillips (Person submitting report) Title Agent (President, Secretary or Agent)
Date November 26, 1991.

Signature R.M. Dowell
R. M. Dowell for R. D. Phillips
P. O. Box 3429 Terminal Annex, Los Angeles, CA 90051 (213) 244-2666
(Address) (Telephone Number)

History must be complete in all detail. Use this form to report all operations during drilling and testing of the well or during redrilling or altering the casing, plugging, or abandonment with the dates thereof. Include such items as hole size, formation test details, amounts of cement used, top and bottom of plugs, perforation details, sidetracked junk, bailing tests and initial production data.

Date	
1991	
9-20	Set in rig pump. Removed lines from casing and well head. Killed and shut in well.
9-23	Moved in and rigged up. Circulated well and spotted 100 Bbls high viscosity pill.
9-24	Filled well. Installed back pressure plug. Removed tree and installed BOPE. Tested blind, pipe rams and choke manifold to 4000 psi. Tested annular preventor to 2850 psi. BOPE test waived by Steve Fields with D.O.G.
9-25	Replaced packing in donut studs. Pressure tested donut studs to 3000 psi. Released from packer. Began laying down 2-7/8" tubing.
9-26	Rig down for repairs.
9-27	Pulled and laid down 259 joints of 2-7/8" J-55 tubing and production equipment. Ran in with bit and scraper on 2-3/8" drill pipe.
9-28	Finished picking up and running drill pipe to packer at 8042'. Pulled out of well. Made up Otis packer retrieving tool. Ran in well to 7340'.

OG103 (8/91/GSR1/SM)

Mailed 12/6/91

AC_CPUC_0118227

9-30 Ran in well with packer retrieving tool to 8029'. Latched into packer at 8040' and pulled 30,000 lbs over string weight. Released packer. Pulled and laid down packer. Made up 4-1/8" bit on 5" 18# scraper, 116' of 3-1/8" drill collars and 945' of 2-3/8" tubing crossed over to 2-7/8" drill pipe. Ran in well to 8000'.

10-01 Ran in well to 9010'. Hit fill at 9067'. Cleaned out to 9072'. Unable to clean out past 9072' (T.D. 9077'). Circulated well clean. Pulled out of well. Made up and ran 5" drillable retainer. Set retainer at 8345'. Pulled up to 8042'.

10-02 Ran in well to 8343'. Pressure tested cement retainer to 1200 psi. Changed well over to clean 2% KCl water. Pulled up to 8075' and dumped 1 sack of 8-12 gravel and displaced with 36 Bbls of KCl water. Waited one hour. Ran in and tagged top of sand at 8335'. Pulled out of well. Ran 3-1/8" perforating gun on wireline. Stopped at 8309' (26' high). Ran in well with 4-1/8" mill.

10-03 Measured in well with drill pipe and tagged fill at 8322'. Changed well over to polymer fluid. Cleaned out fill to 8337'. Milled up cement retainer and pushed down well to 9055'. Unable to get deeper. Circulated well clean. Pulled to kill string.

10-04 Pulled out of well. Ran and set 5" cement retainer on wireline at 8361'. Tested cement retainer to 1200 psi. Ran in well with 1040' of 2-3/8" tubing tail on 2-7/8" drill pipe to 8361'. Changed well over to 2% KCl water with tubing tail at 8346'. Dumped 1 sack of 8-12 gravel and displaced with 34 Bbl KCl water. Pulled to top of 5" liner. Shut well in.

10-05 Ran in well and tagged top of sand at 8351'. Pulled out of well. Shot four 3/8" holes from 8330' to 8331'. Pressure holes to 2200 psi. Bled off 450 psi in 20 min. Ran in well with 5" full bore packer with 30' of 2-3/8" tubing tail and 315' of 2-3/8" tubing above tool crossed over to 2-3/8" drill pipe.

10-07 With tubing tail at 8334', pumped 50 cu.ft. of 12% HCl/3% HF acid and displaced with 28 Bbls of KCL water. Set packer at 8303' and pumped 50 cu.ft. of acid out holes at 8330'. Final injection rate: 1-1/2 Bbls/min at 1700 psi. Pulled up and placed tail at 8120' and packer at 8087'. Squeezed 25 cu.ft. 6% HCl/1-1/2% HF acid followed by 50 cu.ft. Class "G" cement with fluid loss additives. Final squeeze pressure: 1600 psi at 4 cu.ft/min. Displaced holes by 25 cu.ft. Waited 4 hours on cement. Pulled tool loose and reset packer at 8018'. Could not obtain pressure test on packer and/or unloading tool. Pulled to kill string.

10-08 Pulled out of well. Replaced full bore packer with same. Ran in well to 8120'. Packer failed to hold pressure. Pulled out of well. Ran in well with 63' of 2-3/8" tubing tail with drill pipe tester, and 7" full bore packer on 2-7/8" drill pipe. Ran in well to 2569'. Set packer (would not hold pressure). Dropped ball in test sub. Drill pipe would not test.

10-09 Located leak in drill pipe on 27th and 28th joint connection. Ran in well with 7" full bore packer and drill pipe tester on 2-7/8" drill pipe with 60' tubing tail below packer and set at 8120'. Attempted to break down holes at 8330'. Failed to achieve breakdown. Pulled out of well to 2193'.

10-10 Pulled out of well. Made up 356' of 2-3/8" tubing and full bore packer. Tested to 3000 psi. Ran in well to 8324'. Spotted 50 cu.ft. of acid. Established injection rate of 7 cu.ft./min at 1950 psi. Pulled tubing tail up to 8120'. Mixed and pumped 50 cu.ft. of class "G" cement. Displaced with 39-1/2 Bbls KCl water. Squeezed 36 cu.ft. class "G" cement. Final squeeze pressure: 2560 psi.

10-11 Released packer and pulled out of well. Ran in well with 4-1/8" bit on 5" scraper. Tagged top of cement at 8196'. Drilled hard cement from 8196' to 8326'. Pulled to liner top.

10-12 Ran in to 8326'. Drilled out cement to 8343'. Circulated well clean at 8351'. Pressure tested squeeze holes at 8330' to 2160 psi for 30 minutes (410 psi bleed off). Pulled out of well. Made up 30' of 2-3/8" tubing tail on 5" full bore packer with 315' of 2-3/8" tubing crossed over to 2-7/8" drill pipe. Ran in well to 8029'.

10-14 Ran in well with 5" full bore packer to 8334'. Pressure tested holes at 8330' to 2200 psi for 20 min. Pulled out of well. Ran in well with 4-1/8" mill on four 3-1/8" drill collars, 945' of 2-3/8" tubing and 2-7/8" drill pipe to 8347'. Changed over hole fluid to polymer fluid. Pulled up to 8026'.

10-15 Ran in well to 8347'. Milled on 5" bridge plug from 8361' to 8363'. Pushed junk down well to 9035'. Milled for one hour without success. Pulled out of well. Ran in well with 7" RTTS packer with pressure control valve and circulating port to 7998'.

10-16 Rigged up flow lines to Gas Co. withdrawal system. Tested lines to 3000 psi. Flowed well for 12 hours.

10-17 Ran noise log survey from 8560' to 5000'. Anomaly detected across downhole tools.

10-18 Ran noise log survey from 8600' to surface. Anomaly detected across down hole tools.

10-19 Installed and pressure tested surface lines to 2000 psi. Placed well on injection for 10 hours. Surface injection pressure: 2620 psi (120 psi over shut in wellhead pressure). Closed down hole and surface valves.

10-21 Opened subsurface valve. Ran noise log survey from 8600' to surface. Noise log indicated possible gas movement up above the M-P marker. Pumped 30 Bbls of high vis pill followed by 30 Bbls of polymer fluid. Opened circulating port. Rigged down surface flow lines.

10-22 Released packer. Pulled out of well. Ran in well with full bore packer with mechanical circulating port to 7544'. Rigged up flow lines.

10-23 Finished rigging up flow lines. Tested flow lines to 3000 psi. Injected gas to provide 1800 psi underbalance. Placed well on withdrawal.

10-24 Continued withdrawal from well. Total hours on withdrawal: 17-1/2; Final surface flowing pressure: 850 psi.

10-25 Detected leak on surface flow manifold above wellhead. Re-killed well.

10-26 Rigged up and tested surface lines to 3000 psi. Placed well on withdrawal for 9 hours. Shut in well.

10-27 Ran temperature and noise log surveys. Logs indicated no gas movement behind casing. Pumped 80 Bbls to kill well. Dismantled surface flow line. Released packer.

10-28 Bled off 100 psi on drill pipe and casing. Pulled out of well. Made up 4-1/8" mill on 166' of 3-1/8" drill collars and 918' of 2-3/8" drill pipe crossed over to 2-7/8" drill pipe. Ran in well to 9035'. Milled on retainer and pushed it down to 9055'. Milled on retainer at 9055'.

10-29 Ran in well to 9055'. Milled on retainer. Cleaned out to 9066'. Mill stopped. Changed over hole fluid to clean filtered KCl water. Pulled out of well to 2782'.

10-30 Pulled out of well. Installed shooting flange. Ran Gamma Ray/Neutron collar log from 8900' to 7800'. Made up tubing conveyed perforating guns and ran in well to 3862', filling drill pipe so as to provide 500 psi underbalance.

10-31 Ran in well. Ran Gamma Ray/CCL log and correlated guns. Set Otis packer at 8306'. Tested surface lines to 3000 psi. Tested packer to 1000 psi. Dropped bar. No blow or fluid rise to surface. Unsuccessfully attempted to fish drop bar on wireline.

11-01 Attempted to fish drop bar. Fill apparently above bar. Pulled packer loose and pulled out of well. All guns fired. Made up 4-1/4" bit on 5" scraper, 3-1/8" drill collars and 2-3/8" drill pipe crossed over to 2-7/8" drill pipe. Ran in well to liner top.

11-02 Ran in and tagged fill at 9050'. Cleaned out to 9066'. Pulled out of well laying down drill pipe. Picked up 2-7/8" tubing and ran in well to kill string.

11-04 Pulled kill string out of well. Ran and set 7" Otis "BWB" packer on wireline at 8030'. Made up test seals on 2-7/8" 8RD tubing and started in well.

11-05 Finished picking up tubing. Latched into packer. Pulled 20,000 lbs over string weight to check latch. Set 10,000 lbs on packer. Tested packer and seals to 1500 psi. Changed 3-1/8" valve on tubing head and tested to 1500 psi. Pulled out of well. Made up production equipment and ran in well Hydrotesting to 4000 psi. Ran in well to kill string.

11-06 Finished running tubing. Latched in to packer. Pulled 20,000 lbs over string weight to check latch. Landed with 8,000 lbs on packer. Tested seals and packer to 1500 psi. Removed BOPE. Installed xmas tree. Tested to 5000 psi. Opened Otis "XD" sliding sleeve. Changed fluid over to double inhibited 2% KCl. Released rig.

WELL NO. SS 29

LOCATION Aliso Canyon

DATE WANTED 11-10-94

REQUESTED BY ESS

	SIZE	FOOTAGE	DESCRIPTION
CASING			
TUBING	3-1/2"	600'	8 Rd EUE
	4-1/2"	7500'	8 Rd EUE
LINER & ACCESSORIES			
	DESCRIPTION		
CASING HEAD			
TUBING HEAD	Cross 3-1/8" x 3-1/8" x 3-1/8" x 2-1/16"		
	9" x 3-1/8" x 5000# Double Studded AJO Seal Flange		
	9" x 3-1/8" EUE 8 Rd Type 75 AJO Tubing Hanger		
	3" x 3-1/8"x5000# Unibolt Cap		
	One 3-1/8" Wing Valve, One 3-1/8" Master Valve, One 2-16" Wing		
MISCELLANEOUS	Baker Series T5 SCSSV		

11-06-91 Woods

Day 41. Finished running tubing. Latched in to Otis packer. Pulled 20,000 lbs over. Spaced out with 8,000 lbs on packer. Tested seals and packer to 1500 psi (o.k.). Loaded out Hydro-test. Removed BOPE and load. Installed xmas tree. Tested to 5000 psi with Santa Paula wireline. Ran in and opened Otis "XD" sliding sleeve. Loaded out SP wireline. Changed fluid over to 2% kcl water (340 Bbls double inhibited.

MWO 99412 $346,000

Daily $ 20,350
Cumulative $407,696

10-31-91 Dayton
Day 36. Ran in well. Rigged up HLS loggers. Ran Gamma Ray/CCL log and correlated guns. Set Otis packer at 8306'. Tested surface lines to 3000 psi. Tested packer to 1000 psi. Dropped bar. No blow or fluid rise to surface. Rigged up Otis wireline to fish drop bar. Unable to fish bar. Shut in well.
MWO 99412 $346,000 Daily $ 10,621
Cumulative $288,657

11-01-91 Dayton
Day 37. Attempted to fish drop bar. Fill apparently above bar. Pulled packer loose and pulled out of well. All guns fired. Made up 4-1/4" bit on 5" scraper, 3-1/8" drill collars and 2-3/8" drill pipe, x-over to 2-7/8" drill pipe. Ran in well to liner top.
MWO 99412 $346,000 Daily $ 48,710
Cumulative $337,367

11-02-91 Dayton
Day 38. Ran in and tagged fill at 9050'. Cleaned out to 9066'. Pulled out of well laying down drill pipe. Picked up 2-7/8" tubing.
MWO 99412 $346,000 Daily $ 30,586
Cumulative $367,953

11-04-91 Woods
Day 39. Pulled kill string out of well. Made up and ran 7" Otis "BWB" packer on wireline. Set packer at 8030'. Made up Otis test seals on 2-7/8" 8RD tubing and started in well.
MWO 99412 $346,000 Daily $ 15,388
Cumulative $383,341

11-05-91 Dayton
Day 40. Finished picking up tubing. Latched into packer. Pulled 20,000 lbs over string weight. Set 10,000 lbs on packer. Tested packer and seals to 1500 psi (o.k.). Changed 3-1/8" valve on tubing head. Installed new stud and packing for tubing hanger. Tested to 1500 psi. Pulled out. Made up production equipment. Hydro-tested to 4000 psi. Ran in to kill string. Secured well.
MWO 99412 $346,000 Daily $ 4,005
Cumulative $387,346

10-24-91 Hemmerly
Day 29. Continued withdrawal from well until 12:00 noon. Total hours on withdrawal: 17-1/2; Final surface flowing pressure: 850 psi.
MWO 99412 $346,000 Daily $ 3,938
Cumulative $234,705

10-25-91 Hemmerly
Day 30. Rigged up Flo-Log to run noise survey. Detected leak on HRS flow manifold above wellhead. Re-killed well.
MWO 99412 $346,000 Daily $ 4,561
Cumulative $239,266

10-26-91 Woods
Day 31. Rigged up and tested surface lines to 3000 psi. Placed well on withdrawal at 9:00 a.m. Shut well in at 6:00 p.m.
MWO 99412 $346,000 Daily $ 4,469
Cumulative $243,735

10-27-91 Woods
ON 10/21 INDICATE LEAK ON NOISE LOG, 6 DAYS LATTER - RETEST & NO LEAK. NO ADDITIONAL WORK WAS DONE.
Day 32. Rigged up Flo-Log. Ran temperature and noise log. Log indicated no gas movement behind casing. Loaded out Flo-Log. Pumped 80 Bbls to kill well. Tore out surface line. Released packer. Pulled 3 stands. Secured well.
MWO 99412 $346,000 Daily $ 7,879
Cumulative $251,614

10-28-91 Dayton
Day 33. Bled off 100 psi on drill pipe and casing. Filled well with 66 Bbls. Pulled out of well. Made up 4-1/8" mill on 166' of 3-1/8" drill collars and 918' of 2-3/8" drill pipe x-over to 2-7/8" drill pipe. Ran in well to 9035'. Milled on retainer and pushed it down to 9055'. Milled on retainer at 9055'.
MWO 99412 $346,000 Daily $ 12,690
Cumulative $264,304

10-29-91 Dayton
Day 34. Filled well. Ran in well to 9055'. Milled on retainer. Cleaned out to 9066'. Mill stopped. Changed over hole fluid to clean filtere 67 pcf KCl water. Pulled out of well to 2782'. Shut in well.
MWO 99412 $346,000 Daily $ 4,240
Cumulative $268,544

10-30-91 Dayton
Day 35. Pulled out of well. Installed shooting flange. Rigged up HLS and ran Gamma Ray/Neutron collar log from 8900' to 7800'. Made up VANN tubing conveyed perforating guns and ran in well to 3862'. Shut in well.
MWO 99412 $346,000 Daily $ 9,492
Cumulative $278,036

10-16-91 Hemmerly
Day 22. Rigged up flow lines to Gas Co. withdrawal system Tested lines to 3000 psi using Hydrotest. Flowed well for 12 hours. Shut well in at 1:00 a.m.
MWO 99412 $346,000 Daily $ 5,643
Cumulative $179,107

10-17-91 Hemmerly
Day 23. Rigged up Flo-Log. Ran noise from 8560' to 5000'. Anomaly detected across downhole tools. Shut well in.
MWO 99412 $346,000 Daily $ 4,949
Cumulative $184,056

10-18-91 Hemmerly
Day 24. Rigged up Flo-Log. Ran noise log from 8600' to surface. Anomaly detected across down hole tools. Rigged down Flo-Log. Secured well.
MWO 99412 $346,000 Daily $ 11,051
Cumulative $195,107

10-19-91 Hemmerly
Day 25. Installed and pressure tested surface lines to 2000 psi. Placed well on injection for 10 hours. Surface injection pressure: 2620 psi (120 psi over shut in wellhead pressure). Closed down hole and surface valves. Secured well.
MWO 99412 $346,000 Daily $ 4,180
Cumulative $199,287

10-21-91 Hemmerly
Day 26. Opened subsurface valve. Rigged up Flo-log. Ran noise log from 8600' to surface. Noise log indicates apparent gas movement up above the M-P marker. Rigged down Flo-log. Pumped 30 Bbls of high vis pill followed by 30 Bbls of 67 Pcf polymer. Opened circulating port. Rigged down surface flow lines.
MWO 99412 $346,000 Daily $ 8,152
Cumulative $207,439

10-22-91 Hemmerly
Day 27. Released packer. Pulled out of well. Ran in well with Baker full bore packer with mechanical circulating port to 7544'. Rigged up flow lines. Secured well.
MWO 99412 $346,000 Daily $ 4,180
Cumulative $211,619

10-23-91 Hemmerly
Day 28. Finished rigging up flow lines. Tested to 3000 psi. Injected gas to provide 1800 psi underbalance. Placed well on withdrawal.
MWO 99412 $346,000 Daily $ 19,148
Cumulative $230,767

10-10-91 Dayton
Day 17. Pulled out of well. Made up 356' of 2-3/8" tubing and tool. Tested to 3000 psi. Ran in well to 8324'. Spotted 9 Bbls of 12% HCl/3%HF mud acid. Established injection rate of 7 cu.ft./min at 1950 psi. Pulled tubing tail up to 8120'. Mixed and pumped 50 cu.ft. of class "G" cement. Displaced with 39-1/2 Bbls KCl water. Final squeeze pressure: 2560 psi.
MWO 99412 $346,000 Daily $ 16,910
Cumulative $153,674

10-11-91 Dayton
Day 18. Released packer and pulled out of well. Made up 4-1/8" bit on 5" scraper. Ran in well. Tagged top of cement at 8196'. Drilled hard cement from 8196' to 8326'. Pulled to liner top. Shut in well.
MWO 99412 $346,000 Daily $ 4,794
Cumulative $158,468

10-12-91 Dayton
Day 19. Ran in to 8326'. Drilled out cement to 8343'. Circulated well clean at 8351'. Pressure tested squeeze holes at 8330' to 2160 psi for 30 minutes (410 psi bleed off). Pulled out of well. Made up 30' of 2-3/8" tubing tail on 5" full bore packer with 315' of 2-3/8" x-over to 2-7/8" drill pipe. Ran in well to 8029'. Shut in well.
MWO 99412 $346,000 Daily $ 4,420
Cumulative $162,888

10-14-91 Hemmerly
Day 20. Ran in well with 5" full bore packer to 8334'. Pressure tested holes at 8330' to 2200 psi for 20 min. Pulled out of well. Ran in well with 4-1/8" mill on four 3-1/8" drill collars, 945' of 2-3/8" tubing and 2-7/8" drill pipe to 8347'. Changed over hole fluid to 67 pcf polymer. Pulled up to 8026'.
MWO 99412 $346,000 Daily $ 6,396
Cumulative $161,284

10-15-91 Hemmerly
Day 21. Ran in well to 8347'. Milled on 5" bridge plug from 8361' to 8363'. Pushed junk down well to 9035'. Milled for one hour without success. Pulled out of well. Ran in well with 7" RTTS packer with pressure control valve and pumped out circulating port to 7998'. Secured well.
MWO 99412 $346,000 Daily $ 4,180
Cumulative $173,464

10-05-91 Dayton

Day 13. Ran in well and tagged top of sand at 8351'. Pulled out of well. Rigged up HLS wireline and shot 4-3/8" holes from 8330' to 8331'. Pressure holes to 2200 psi. Bled off 450 psi in 20 min. Made up 5" full bore packer with 30' of 2-3/8" tubing tail and 315' of 2-3/8" tubing above tool to drill pipe. Ran in well.

MWO 99412 $346,000 Daily $ 19,320
Cumulative $104,464

10-07-91 Dayton

Day 14. With tubing tail at 8334', pumped 50 cu.ft. of mud acid and displaced with 28 Bbls of KCL water. Set packer at 8303' and pumped 50 cu.ft. of acid out holes at 8330'. Final injection rate: 1-1/2 Bbls/min at 1700 psi. Pulled up and placed tail at 8120' and packer at 8087'. Pumped 4-1/2 Bbls, of 6% HC1/1-1/2% HF acid then one Bbl of KCL water followed by 9 Bbls of "G" cement and one Bbl water. Displaced with 20 Bbls of KCL water and closed tool. Pumped 4-1/2 Bbls of 6% HC1/1-1/2% HF cu.ft. of "G" cement with 2 gallons per sack D-603 and 2 gallons per sack D-L04 and .02 gallons per sack D-47. Displaced with 39-3/4 Bbls KCL water (final psi 1660 rate 3/4 Bbl/min. Cleared holes with 25 cu.ft. of KCL water. Waited 4 hours on cement. Pulled tool loose and reset packer at 8018'. Could not obtain pressure test on packer and/or unloading tool. Pulled to kill string. Shut in well.

MWO 99412 $346,000 Daily $ 11,259
Cumulative $222,059

10-08-91 Dayton

Day 15. Pulled out of well. Changed out full bore packer. Ran in well to 8120' with tubing tail packer at 8087'. Tested packer (would not hold). Pulled out of well. Made up 63' of 2-3/8" tubing tail on 7" full bore with drill pipe. Tested sub. Crossed back to drill pipe. Ran in well to 2569'. Set packer (would not hold pressure). Dropped ball. Drill pipe would not test. Closed in well.

MWO 99412 $346,000 Daily $ 8,761
Cumulative $129,053

10-09-91 Dayton

Day 16. Located leak in drill pipe on 27th and 28th joint connection. Ran in well and set 7" full bore packer and drill pipe tester on 2-7/8" drill pipe with 60' tubing tail below packer at 8120'. Rigged up cementers. Attempted to break down holes at 8330'. Failed to achieve breakdown. Pulled out of well to 2193'. Secured well.

MWO 99412 $346,000 Daily $ 7,711
Cumulative $136,764

9-30-91 Dayton
Day 8. Ran in well to 8029'. Pumped 65 Bbls to fill well. Latched into packer at 8040' and pulled 30,000 lbs over string weight. Released packer. Pulled out of well. Laid down packer. Made up 4-1/8" bit on 5" 18# scraper, 116' of 3-1/8" drill collars and 945' of 2-3/8" tubing. Crossed over to 2-7/8" drill pipe. Ran in well to 8000'. Shut in well.
MWO 99412 $346,000 Daily $ 6,355
Cumulative $ 43,383

10-01-91 Dayton
Day 9. Ran in well to 9010'. Hit fill at 67'. Cleaned out to 9072'. Unable to clean out past 9072' (T.D. 9077'). Circulated well clean. Pulled out of well. Made up and ran 5" drillable retainer. Set retainer at 8345'. Pulled up to 8042'. Shut well in.
MWO 99412 $346,000 Daily $ 8,217
Cumulative $ 51,600

10-02-91 Dayton
Day 10. Ran in well to 8343'. Pressure tested cement retainer to 1200 psi for 20 minutes (o.k.). Changed well over to clean 2% kcl water. Pulled up to 8075' and dumped 1 sack of 8-12 gravel and displaced with 36 Bbls of kcl water. Wated one hour. Ran in and tagged top of sand at 8335'. Pulled out of well. Rigged up HLS and ran 3-1/8" gun. Stopped 8309' 26' high. Ran in well with 4-1/8" mill. Measured in well.
MWO 99412 $346,000 Daily $ 17,305
Cumulative $ 68,905

10-03-91 Dayton
Day 11. Measured in well with drill pipe and tagged fill 8322'. Changed well over to 66# CaCl2 polymer. Cleaned out fill to 8337'. Milled up cement retainer and pushed down well to 9055'. Unable to get deeper. Circulated well clean. Pulled to kill string.
MWO 99412 $346,000 Daily $ 4,315
Cumualtive $ 73,220

9-20-91 Dayton
Day 1. Set in rig pump. Removed lines from casing and well head. Mixed 30 Bbls of high vis pill and 38 Bbls, 60 vis of polymer and pumped down tubing. Opened up casing with 2650 psi on casing. Pumped 567 Bbls of 60 vis polymer. Mixed and pumped 100 Bbls of high vis pill in casing, psi 100 tubing psi 0. Shut in well.
MWO 99412 $346,000 Daily $ 1,728
Cumulative $ 1,728

9-23-91 Dayton
Day 2. Set in rig and rigged up. Circulated well and spotted 100 Bbls high vis pill. Shut in well.
MWO 99412 $346,000 Daily $ 2,020
Cumulative $ 3,748

9-24-91 Dayton
Day 3. Filled well with 92 Bbls. Installed back pressure plug in tubing hanger. Removed tree and installed 8" 5000 psi BOPE. Tested blind, pipe rams and choke manifold to 4000 psi. Tested bag to 2850 psi. Closed in well. BOPE test waived by Steve Fields with D.O.G.
MWO 99412 $346,000 Daily $ 5,128
Cumulative $ 8,876


9-25-91 Hemmerly
Day 4. Replaced packing in donut studs. Pressure tested donut studs to 3000 psi for 20 minutes. Removed donut studs. Released from packer. Began laying down 2-7/8" tubing.
MWO 99412 $346,000 Daily $ 17,125
Cumulative $ 26,001

9-26-91 Dayton
Day 5. Rig down for repairs.
MWO 99412 $346,000 Daily $ 0
Cumulative $ 26,001

9-27-91 Woods
Day 6. Mixed 70 Bbls of high vis pill. Pumped down pipe. Pumped 100 Bbls of polymer fluid with no returns. Pulled and laid down 259 joints 2-7/8" tubing J-55, and production equipment. Made up bit and scraper. Picked up and ran 2-7/8" IF drill pipe.
MWO 99412 $346,000 Daily $ 3,776
Cumulative $ 31,701

9-28-91 Woods
Day 7. Finished picking up and running drill pipe to packer at 8042'. Pumped 80 Bbls of high vis pill. Followed with 35 fluid, with returns. Pulled out of well. Made up Otis packer retrieving tool. Ran in to 7340'. Secured well.
MWO 99412 $346,000 Daily $ 5,327
Cumulative $ 37,028

WELL PROFILE



OPERATOR	Southern California Gas Company
WELL #	STANDARD SESNON #29
FIELD	Aliso Canyon
COUNTY	Los Angeles
STATE	California
DATE	September 9, 1977

☐ NEW COMPLETION ☒ WORKOVER

	CASING	LINER	TUBING 1	TUBING 2	TUBING 3
SIZE					
WEIGHT					
GRADE					
THREAD					
DEPTH					

ITEM NO.	TUBING DETAILS	LENGTH	DEPTH
1	KB to Doughnut		6.92
2	Doughnut	.80	7.72
3	4' Pup 3' Pup 2' Pup 6' Pup 10' Pup	24.00	31.72
4	248 Jts. 2 7/8" Tubing (Top 16=N-80)	7957.69	7989.41
5	Crossover 27/8" EU 8rd x 2 3/8" EU 8rd	.85	7990.26
6	13 Jts. 2 3/8" EU 8rd Tubing	395.84	8386.61
7	2 3/8" x 4' Pup	4.10	8390.20
8	2 3/8" x 1' Nipple	1.09	8391.29
9	2 3/8" Otis Annulus Flow Safety System	8.25	8399.54
10	2 3/8" x 20' Blast Joint (Otis)	19.89	8419.43
11	2 3/8" x 1.56 NO-GO	1.12	8420.55
12	2 3/8" x 10' Blast Joint	9.88	8430.43
13	Otis Latch for Permatriev & Packer	.71	8431.14
14	Otis Seals, Extension & Mule Shoe	6.82	8437.96
	PRESSURE TESTED CASING:		
	3800' to 8425' 2500 psi 1 Hour O.K.		
	3800' to Surface 2700 psi 1 Hour O.K.		
	3300' " " 2900 psi " "		
	2900' " " 3100 psi " "		
	2500' " " 3300 psi " "		
	2000' " " 3500 psi " "		
	1100' " " 4000 psi " "		

AC_CPUC_0118241

- Meet to

1) Review what to do with damaged hangers.
2) check on MDR for tubing.
3) Original 2 pcs from Black Gold to Junk.

AC_CPUC_0118242

BAKER OIL TOOLS
A Baker Hughes company

BAKER OIL TOOLS
CERTIFICATION REPORT

THIS COPY TO REMAIN ON LOCATION

LOCATION: BROKEN ARROW
SUBSURFACE SAFETY EQUIPMENT

MANUFACTURER DATA

MANUFACTURER: BAKER OIL TOOLS EQUIPMENT NAME: FLAPPER SAFETY VALVE

API LICENSE: 14A-0004 EXPIRATION DATE: 01/19/97 MARKING DATE: N/A

SPPE CERTIFICATION: OCS-116 EXPIRATION DATE: 08/07/96 MARKING DATE: 10/20/94

MODEL NUMBER: 824-80-2810 SERIAL NUMBER: 135608-2-B

RATED WORKING PRESSURE: 5,000 SIZE: 3 1/2"

TEMPERATURE RATING: MIN: 20 MAX: 300 CLASS OF SERVICE: 3S2

SSSV FUNCTIONAL TEST DATA

OPENING PRESSURES WITH "0" TUBING PRESSURE: MAX: 1,300 MIN: 1,300

CLOSING PRESSURES WITH "0" TUBING PRESSURE: MAX: 700 MIN: 700

PERFORMED BY: SHIRL BROWN DATE: 10/20/94

CERTIFICATION DATA

I HEREBY CERTIFY THAT THE ABOVE EQUIPMENT HAS MET OR EXCEEDED ALL REQUIREMENTS OF THE REFERENCED STANDARD(S) CITED IN EFFECT ON THE STAMPING DATE AS APPLICABLE. I ALSO CERTIFY THAT PERFORMANCE TEST NUMBER

SWRI: #1146 DATED: 07/15/93

BAKER: N/A DATED: N/A

REPRESENTS THAT THIS EQUIPMENT DESIGN HAS BEEN PERFORMANCE TESTED IN ACCORDANCE WITH THE REFERENCED STANDARDS.

NAME: [signature] TITLE: QA/E DATE: 10/20/94

SHIPPING REPORT

PURCHASER: The Gas Company ORDER NO: CS 01 0042 SHIP DATE: 11-11-94

I HEREBY CERTIFY THAT THE ABOVE EQUIPMENT HAS MET OR EXCEEDED ALL REQUIREMENTS OF REFERENCE STANDARDS CITED ABOVE.

NAME: [signature] TITLE: Dly Rep DATE: 11-14-94

RECEIVING REPORT - OPERATOR DATA

DATE RECEIVED: 11-11-94

COMPANY NAME: The Gas Company

ORGANIZATION UNIT: The Gas Company

FIELD: Aliso Canyon

LEASE: 55

WELL: 29

CONDITION PRIOR TO INSTALLATION: New

CONNECTIONS TIGHT: Yes

OPENING PRESSURE: 1225

CLOSING PRESSURE: ~~1ES~~ 1200

INSPECTED BY: [signature]

INSPECTOR/SUPERVISOR:

CRR-1A (REV 12, 03/01/94)

THIS COPY TO REMAIN ON LOCATION

AC_CPUC_0118243

BAKER OIL TOOLS CERTIFICATION REPORT

BAKER OIL TOOLS
A Baker Hughes company

LOCATION: BROKEN ARROW
SUBSURFACE SAFETY EQUIPMENT

MANUFACTURER DATA

MANUFACTURER: BAKER OIL TOOLS EQUIPMENT NAME: BOTTOM SUB

API LICENSE: 14A-0004 EXPIRATION DATE: 01/19/97 MARKING DATE: N/A

SPPE CERTIFICATION:OCS-116 EXPIRATION DATE: 08/07/96 MARKING DATE: 09/21/94

MODEL NUMBER: 824-94-2801 SERIAL NUMBER: 133511-1-B

RATED WORKING PRESSURE: 5,000 SIZE: 3 1/2 X 2.81

TEMPERATURE RATING: MIN: N/A MAX:N/A CLASS OF SERVICE: 3S2

SSSV FUNCTIONAL TEST DATA

OPENING PRESSURES WITH "0" TUBING PRESSURE: MAX: N/A MIN: N/A

CLOSING PRESSURES WITH "0" TUBING PRESSURE: MAX: N/A MIN: N/A

PERFORMED BY: N/A DATE: N/A

CERTIFICATION DATA

I HEREBY CERTIFY THAT THE ABOVE EQUIPMENT HAS MET OR EXCEEDED ALL REQUIREMENTS OF THE REFERENCED STANDARD(S) CITED IN EFFECT ON THE STAMPING DATE AS APPLICABLE. I ALSO CERTIFY THAT PERFORMANCE TEST NUMBER

SWRI: N/A DATED: N/A

BAKER: #1030 DATED: 04/13/94

REPRESENTS THAT THIS EQUIPMENT DESIGN HAS BEEN PERFORMANCE TESTED IN ACCORDANCE WITH THE REFERENCED STANDARDS.

NAME: [signature] TITLE: [signature] DATE: 10/27/94

SHIPPING REPORT

PURCHASER: The Yasco ORDER NO: CS010042 SHIP DATE: 11-11-94

I HEREBY CERTIFY THAT THE ABOVE EQUIPMENT HAS MET OR EXCEEDED ALL REQUIREMENTS OF REFERENCE STANDARDS CITED ABOVE.

NAME: [signature] TITLE: Duty Rep DATE: 11-14-94

RECEIVING REPORT - OPERATOR DATA

DATE RECEIVED: COMPANY NAME:

ORGANIZATION UNIT: FIELD:

LEASE: WELL:

CONDITION PRIOR TO INSTALLATION: CONNECTIONS TIGHT:

OPENING PRESSURE: CLOSING PRESSURE:

INSPECTED BY: INSPECTOR/SUPERVISOR:

CRR-1A (REV 12, 03/01/94)

AC_CPUC_0118244

BAKER OIL TOOLS CERTIFICATION REPORT

BAKER OIL TOOLS
A Baker Hughes company

LOCATION: BROKEN ARROW
SUBSURFACE SAFETY EQUIPMENT

MANUFACTURER DATA

MANUFACTURER: BAKER OIL TOOLS EQUIPMENT NAME: NIPPLE ADAPTER

API LICENSE: 14A-0004 EXPIRATION DATE: 01/19/97 MARKING DATE:N/A

SPPE CERTIFICATION:OCS-116 EXPIRATION DATE: 08/07/96 MARKING DATE:06-15-94

MODEL NUMBER: 824-90-2841 SERIAL NUMBER: 130092-1B-12

RATED WORKING PRESSURE: 5,000 SIZE: 3 1/2

TUBING RETRIEVABLE ONLY: TEMPERATURE RATING: MIN: N/A MAX: N/A

INTERNAL YIELD PRESSURE: N/A PSIG CLASS OF SERVICE: 3S2

COLLAPSE PRESSURE: N/A PSIG

TENSILE LOAD STRENGTH: N/A PSIG

SSSV FUNCTIONAL TEST DATA

OPENING PRESSURES: MAX: N/A MIN: N/A

CLOSING PRESSURES: MAX: N/A MIN: N/A

LEAKAGE RATE: 100% WORKING PRESSURE: 0 LOW PRESSURE GAS: 0

PERFORMED BY: SHIRL BROWN DATE: 04-26-94

CERTIFICATION DATA

I HEREBY CERTIFY THAT THE ABOVE EQUIPMENT HAS MET OR EXCEEDED ALL REQUIREMENTS OF THE REFERENCED STANDARD(S) CITED IN EFFECT ON THE STAMPING DATE AS APPLICABLE. I ALSO CERTIFY THAT PERFORMANCE TEST NUMBER SWRI#: N/A DATED: N/A REPRESENTS THAT THIS EQUIPMENT DESIGN HAS BEEN PERFORMANCE TESTED IN ACCORDANCE WITH THE REFERENCED STANDARDS.

NAME: [signature] TITLE: QA. Engineer DATE: 17-June-94

SHIPPING REPORT SHIP DATE:

PURCHASER: The Gas Co ORDER NO: CS01 0042 SHIP BY: 11-11-94

I HEREBY CERTIFY THAT THE ABOVE EQUIPMENT HAS MET OR EXCEEDED ALL REQUIREMENTS OF REFERENCE STANDARDS CITED ABOVE.

NAME: [signature] TITLE: QA. Engineer DATE: 17-June-94

RECEIVING REPORT - OPERATOR DATA

DATE RECEIVED: COMPANY NAME:

ORGANIZATION UNIT: FIELD:

LEASE: WELL:

CONDITION PRIOR TO INSTALLATION: CONNECTIONS TIGHT:

OPENING PRESSURE: CLOSING PRESSURE:

INSPECTED BY: INSPECTOR/SUPERVISOR:

CRR-1A (REV 11. 04-24-92)

AC_CPUC_0118245

BAKER OIL TOOLS
A Baker Hughes company

SC S.S.V. APPEARANCE

THIS COPY TO REMAIN ON LOCATION

P. O. Box 3048
Houston, Texas 77253-3048
Tel: 713/923-9351
Fax: 713/923-9528
Telex: 4620079 BAKR UI

1) UPON ARRIVAL ON LOCATION VERIFY CERTIFICATION PAPERS (SER. NOS. AND COMMODITY NUMBERS MATCH) WITH VALVE.

Top Sub 824-90-2841 13560 8-2-B

PAPERS: BTM Sub 824-94-2801 SER.# & DUE DATE: 13009 2-1B YES ✓ NO___
VALVE: 824-80-2810 SER.# & DUE DATE: 135608-2-B YES ✓ NO___

2) CHECK SAFETY VALVE APPEARANCE.

VALVE DAMAGED	YES___	NO ✓
SET SCREWS INSTALLED	YES ✓	NO___
THREADS DAMAGED	YES___	NO ✓
PACKING DAMAGED	YES___	NO ✓
PORT PLUGGED	YES ✓	NO___

3) WIRELINE RETRIEVABLE SAFETY VALVE.

FISHING NECK TIGHT	YES___	NO___
LOCK TIGHT	YES___	NO___
RUN TOOLS INSTALL OKAY	YES___	NO___
VALVE UNLOCKS WITH RUN TOOL INSTALLED	YES___	NO___
VALVE LOCKS WITH RUN TOOL OFF	YES___	NO___
FISHING NECK OKAY	YES___	NO___
PULLING TOOL LATCHES & UNLOCKS VALVE	YES___	NO___

4) CHECK FOR OCS STAMPING.

STAMPED YES ✓ NO___

PRERUN CHECK

5) VALVE OPENING AND CLOSING.

1: OPENING 1225 CLOSING 1200
2: OPENING 1250 CLOSING 1225

6) HYDRO STATIC TEST VALVE OPEN. 5,000 psi

TEST PRESSURE: 5-K- PSI LEAKS: YES___ NO ✓

7) HYDRO STATIC TEST VALVE CLOSED.

TEST PRESSURE: 2,000 psi LEAKS: YES___ NO ✓

RUN

8) INSTALL CONTROLLINE.

CHECK FURREL OKAY: YES ✓ NO___

AC_CPUC_0118246

THE GAS COMPANY
PORTER

SS-29
SS-29
ALISO CANYON
CALIFORNIA

S U R V E Y L I S T I N G

by
Baker Hughes INTEQ

Your ref : SEEKER GYRO
Our ref : svy3727
License :

Date printed : 12-Dec-94
Date created : 8-Nov-94
Last revised : 8-Nov-94

Field is centred on 0.000,0.000,999.00000,+
Structure is centred on 0.000,0.000,3.00000,N

Slot location is s0 0 7.442,w1 30 18.968
Slot Grid coordinates are N -229.216, E -1864.293
Slot local coordinates are 750.00 S 6100.00 W
Reference North is True North

AC_CPUC_0118247

11/04/94 Jackson

Day 1. Moved rig to SS 29. Mixed 2% KCl workover fluid treated with biocide.

GWO 93496

Daily	$ 2,930
Cumulative	$ 2,930

11/07/94 McLean

Day 2. Opened well (casing press 2500 psi, tubing press 2400 psi). Rigged up pump and choke manifold. Prepared tokill well. Waited on field operator to open line to bleed well down. Killed well with 345 bbls of 2% KCl water. Installed BPV, nippled down tree and installed BOPE. Changed pipe rams and function tested blind rams. Pressure tested BOPE with test pump. Rigged up to pull tubing. Unscrewed tubing hold down studs.

GWO 93496

Daily	$ 2,932
Cumulative	$ 5,862

11/08/94 McLean

Day 3. Bled well down with only a small amount of gas. Worked tubing out of packer without pulling seal assembly. Rigged up to run gyro survey inside tubing. Could not get below XN nipple at 7999'. Pulled out with gyro and rigged down. Pulled seals out of packer and well kicked. Shut in well with 600 psi on casing. Circulated out gas, lost circulation, pumped 270 bbls and bled pressure to zero. Mixed a 100 bbl HEC pill. Pumped pill and followed with 50 bbls of KCl water. No returns.

GWO 93496

Daily	$ 13,644
Cumulative	$ 19,506

11/09/94 McLean

Day 4. Opened well. No pressure on casing or tubing. Mixed and pumped a HEC high vis pill (100 bbls). Fluid level at 842' before pill and returns to surface while displacing pill. Shot fluid level 30 minutes after displacement and found fluid level at 218'. Rigged up to pull 2-7/8" tubing. Pulled and laid down 153 joints. Left 3000' of kill string in well.

GWO 93496

Daily	$ 15,314
Cumulative	$ 34,824

11/10/94 McLean

Day 5. Opened well. No pressure on casing or tubing. Pumped 20 bbls of 2% KCl water. Pulled out of well with 100 joints of 2-7/8" tubing. Laid down production equipment. Changed pipe rams from 2-7/8" to 4-1/2". Rigged up to run 3-1/2" and 4-1/2" production equipment. Made up and tested (4000 psi) 3-1/2" production equipment. Changed out 3-1/2" test equipment to 4-1/2". Made up and ran 4-1/2" production tubing. Tested to 4000 psi. Ran in hole to 6000'.

GWO 93496

Daily	$ 5,687
Cumulative	$ 40,511

11/11/94 McLean

Day 6. Opened well. No pressure on casing or tubing. Pumped 20 bbls of 2% KCl fluid. Measured and picked up 4-1/2" tubing. Externally pressure tested to 4000 psi. Made up 3-1/2" tubing and SCSSV. Ran in well and tagged packer at 8032'. Pulled 20,000 lbs over string weight and set down 10,000 lbs to obtain space out. Pulled out of well with 3-1/2" tubing to SCSSV. Made up control line and tested to 5000 psi. Ran in well banding line and testing tubing. Made up doughnut and pup joint to space. When breaking out pup, the threads crossed in the top of doughnut. Landed tubing on 2-7/8" doughnut and secured well.

GWO 93496

Daily	$ 54,231
Cumulative	$ 94,742

11/14/94 McLean

Day 8. Opened well. No pressure on casing or tubing. Rigged up to shoot fluid level in tubing. Found fluid at 1261'. Bled pressure from SSSV and shot fluid level. Showed SSSV closed at 500'. Set BPV and nippled down BOPE. Installed and tested tree to 5000 psi. Transferred fluid to SS-9. Rigged down and moved off. Released rig.

GWO 93496


Daily	$ 2,618
Cumulative	$ 125,349

TUBING DETAIL

WELL: SS-29
FIELD: SESNON

STATUS: Tubing Flow
DATE: 11-11-94

TUBING PROFILE



	TUBING	TUBING	TUBING	
SIZE	3½"	4½"	3½"	
WEIGHT	9.3 #	11.6 #	9.3 #	
GRADE	N-80	N-80	N-80	
THREAD	EUE	LTC	EUE	
DEPTH	490'	7887'	8029'	

ITEM #	TUBING DETAIL	DRIFT	I.D.	O.D.	LENGTH	DEPTH
1.	K.B.	—	—		7.00	7.00
2.	DONUT	—	—		.50	7.50
3.	3½" Fox Eue Nipple	2.867	3.500		.62	8.12
4.	3½" N-80 Pup JT. EUE	2.867	4.500		2.14	10.26
5.	15 JTS. 3½" N-80 Tubing EUE	2.867	4.500		466.65	476.91
6.	3½" Pup JT. N-80 EUE	2.867	4.500		4.05	480.96
7.	3½" B Hook X-5 SF. Valve	2.813	5.375		5.47	486.43
8.	3½" Pup JT. N-80 EUE	2.867	4.500		4.17	490.60
9.	X-OVER 3½ EUE X 4½ LTC	3.125	4.500		1.56	492.16
10.	198 JTS 4½" Tubing LTC	4.000	5.000		7394.84	7887.00
11.	X-OVER 4½ LTC X 3½ EUE	3.500	5.000		1.26	7888.26
12.	1-JT. 3½" N-80 Tubing EUE	2.867	4.500		30.17	7918.43
13.	3½" N-80 Pup JT. EUE	2.867	4.500		3.95	7922.38
14.	3½" BST "CAMCO" Gas Lift Mandrel w/ 1" Dummy Valve Shear-Latch	2.867	5.000		6.15	7928.03
15.	3½" N-80 Pup JT. EUE	2.867	4.500		1.48	7930.61
16.	1-JT. 3½" N-80 Tubing EUE	2.867	4.500		31.46	7961.97
17.	3½" "X" D'S Tubing SVBBV	2.750	4.500		3.60	7965.57
18.	3½" N-80 Pup JT. EUE	2.867	4.500		1.08	7966.65
19.	1-JT. 3½" N-80 Tubing EUE	2.867	4.500		31.40	7998.
20.	2.635 "XN" Nipple	2.635	4.500		1.35	7999.70
21.	1-JT. 3½" N-80 Tubing EUE	2.867	4.500		30.56	8028.96
22.	X-OVER 3½" EUE X 2⅞ EUE	2.441	4.500		1.64	8031.60
23.	"T"-LATCH ASSY. ABOVE	2.347	4.000		.40	8032.00
—	"T"-LATCH Assy in pkr	—	—		.75	8032.75
24.	SEAL ASSY. -2-	2.347	3.250		2.00	8034.75
25	45° Guide Shoe	2.347	3.200		.43	8035.18
A	7" 23-29# BWB Packer w/ 2 SBTB's @ 8032'.					

W/O WT. 96,000#
L/O WT. 84,000#

Tubing Landed w/ 10,000# on pkr.

Post-it" Fax Note 7671	Date	# of pages ▶
To DAN NEVILLE	From R. JACKSON	
Co./Dept. DRILLING	Co. ALISO	
Phone #	Phone #	
Fax # 213 244 8222	Fax #	

AC_CPUC_0118250

FORM 101
CALIFORNIA STATE PRINTING OFFICE

SUBMIT IN DUPLICATE

STATE OF CALIFORNIA
DEPARTMENT OF NATURAL RESOURCES

DIVISION OF OIL AND GAS

DIVISION OF OIL AND GAS
RECEIVED
FEB 17 1954
LOS ANGELES, CALIFORNIA

LOG AND CORE RECORD OF OIL OR GAS WELL

Operator TIDE WATER ASSOCIATED OIL COMPANY Field ALISO CANYON

Well No. Standard-Seamon 1-#29 Sec. 28, T. 3 N, R. 16 W, S.B. B. & M.

FORMATIONS PENETRATED BY WELL

DEPTH TO Top of Formation	DEPTH TO Bottom of Formation	Thickness	Drilled or Cored	Recovery	DESCRIPTION
SCHLUMBERGER SIDEWALL SAMPLES					
5750'				1/2"	Fine to medium grained, brown oil sand. Medium odor.
5553'				3/4"	Conglomeritic, light brown oil sand. Good petroleum odor.
5188'				1-1/2"	Gray with greenish cast, sandy shale.
5050'				3/4"	Fine to coarse grained, light brown unevenly saturated oil sand. Good petroleum odor.
4734'				1/2"	Conglomeritic, light brown, oil sand.
4660'				1/2"	As above.
4584'				3/4"	As above with pebbles 1/2" in diameter.
4510'				1"	As above.
4459'				No recovery.	
4410'				2"	Dark, greenish-brown shale with abundant foraminifers
4330'				No recovery.	
3590'				1-1/2"	Sandy, dark brown shale.
5778'				1/2"	Soft, medium grained, light brown oil sand. Good od or. (Looks wet.)
5633'				No recovery.	
5515'				1/4"	Hard fragments of dark brown silty shale.
4461'				1/2"	Firm, light gray sandy siltstone.
3764'				1/2"	Hard, brittle, dark gray, micaceous, silty limestone with free oil in fractures.
3350'				1/2"	Soft, coarse, poorly sorted, light brown, undersaturated oil sand. Good petroleum o
3255'				1/2"	Firm, medium grained, oil stained, gray sa Fair odor.
3189'				1/2"	Firm, fine grained, brown oil sand. Good petroleum odor.
3094'				No recovery.	
3037'				1/4"	Fragments to soft green siltstone.
2940'				2"	Firm, fine grained, greenish-brown, oil stained siltstone with occasional megafos Fair odor. (Looks tight.)
2185'				No recovery.	
2000'				2"	Soft, light green, sandy, siltstone with occasional dark spots possibly due to carb aceous material.
1420'				1/4"	Hard, gray, weathered granitic rock. May pebble or part of boulder. In area of hea lost circulation. Note thick mud cake.

2/10
S.M, SS 29 CORE DESCRIPTIONS. A COPY HAS BEEN FILED AT ALISO. S.C.

AC_CPUC_0118251

FORM 101
CALIFORNIA STATE PRINTING OFFICE

SUBMIT IN DUPLICATE

STATE OF CALIFORNIA
DEPARTMENT OF NATURAL RESOURCES

DIVISION OF OIL AND GAS

DIVISION OF OIL AND GAS
RECEIVED
FEB 17 1954
-2-
LOS ANGELES, CALIFORNIA

LOG AND CORE RECORD OF OIL OR GAS WELL

Operator TIDE WATER ASSOCIATED OIL COMPANY Field ALISO CANYON

Well No. Standard-Sesnon 1-#29 Sec. 28, T. 3 N, R. 16 W, S.B. B. & M.

FORMATIONS PENETRATED BY WELL

DEPTH TO Top of Formation	DEPTH TO Bottom of Formation	Thickness	Drilled or Cored	Recovery	DESCRIPTION
6" DIAMOND CORE BARREL					
8682'	8683'			No recovery.	
8683'	8686'			6"	Very hard Quartzite.
5-7/8" MERCURY CORE BARREL					
8810'	8824'			7'	Conglomerate with matrix of fine to medium oil sand. Good cut and odor.
8824'	8835'			No recovery.	
8835'	8836'			1'	Hard conglomerate with matrix of hard cemented gray sand and hard oil sand. No to fair cut and odor.
8836'	8856'			7'	Hard conglomerate with matrix of hard dark gray sand and hard oil sand. No to fair cut and odor.
8858'	8881'			19'	8' Hard conglomerate with matrix of hard cemented gray sand and hard oil sand. No to fair cut and odor. 4' Hard fine to medium oil sand. Fair t good cut and fair odor. 2' Shell. (Very hard, limey, gray sand. 2' Hard oil sand, as above. 1'6" Shell, as above. 1'6" Hard, medium oil sand and gray sand, possibly brecciated. No to fair cut and odor.
8881'	8905'			4'	2' Hard conglomerate with matrix of hard gray sand and hard oil sand. 2' As above, with more hard gray sand an firm oil sand than previous cores. I to good cut and no to fair odor. Had two 2" streaks of hard gray shale wit minor sheering evident.
8905'	8911'			No recovery	
8914'	8942'			1'	Very hard pieces of quartzite boulders.
5-7/8" REED CONVENTIONAL CORE BARREL					
8942'	8944'			0'3"	Three small pieces of quartzite.
9035'	9048'			0'6"	Fragments of granitic and gneissic boulder
9048'	9052'			1'0"	Hard, medium grained, micaceous gray sand. No cut, faint odor. One fragment of hard greenish-gray slickensided shale on botto

AC_CPUC_0118252

FORM 101
CALIFORNIA STATE PRINTING OFFICE

SUBMIT IN DUPLICATE

STATE OF CALIFORNIA
DEPARTMENT OF NATURAL RESOURCES

DIVISION OF OIL AND GAS

DIVISION OF OIL AND GAS
RECEIVED
FEB 17 1954
LOS ANGELES, CALIFORNIA

LOG AND CORE RECORD OF OIL OR GAS WELL

Operator TIDE WATER ASSOCIATED OIL COMPANY Field ALISO CANYON

Well No. Standard-Sesnon 1-#29 Sec. 28, T. 3 N, R. 16 W, S.B. B. & M.

FORMATIONS PENETRATED BY WELL

DEPTH TO Top of Formation	DEPTH TO Bottom of Formation	Thickness	Drilled or Cored	Recovery	DESCRIPTION
5-7/8" REED CONVENTIONAL CORE BARREL (cont.)					
9089'	9096'			5'	Hard, dark blue-gray shale with numerous light gray streaks and occasional slickensides. Good 10° dips.
9126'	9135'			5'	Hard, dark bluish-gray shale with numerous light gray streaks. Top 1' shows 75° dips and slickensiding. Remainder 10-20° dips.
9444'	9464'			15'	Hard, gray, medium to fine grained micaceous sand. Breaks readily into pieces 1/2" to 2" in length with muddy oil in partings. Faint cut indicating possible gas sand. Good gas showings recorded in mud ditch while coring. Possible 35-40° dip.
9464'	9484'			0'6"	As above. No cut or odor.
9484'	9504'			2'	Hard gray sand as above with possible 50-55° dips. Faint cut and shows fluorescence.
9770'	9790'			18'	Hard, medium grained, gray sand, with biscuit partings. No cut. Slight odor. Cut bottles shows slight fluorescence.

AC_CPUC_0118253

SC 1

FORM 101
CALIFORNIA STATE PRINTING OFFICE

To: Jim MANSDORFER

SUBMIT IN DUPLICATE

STATE OF CALIFORNIA
DEPARTMENT OF NATURAL RESOURCES

DIVISION OF OIL AND GAS

DIVISION OF OIL AND GAS
RECEIVED
FEB 17 1954
LOS ANGELES, CALIFORNIA

LOG AND CORE RECORD OF OIL OR GAS WELL

Operator TIDE WATER ASSOCIATED OIL COMPANY Field ALISO CANYON

Well No. Standard-Seaport 1-#29 Sec. 28, T. 3 N, R. 16 W, S.B. B. & M.

FORMATIONS PENETRATED BY WELL

DEPTH TO Top of Formation	DEPTH TO Bottom of Formation	Thickness	Drilled or Cored	Recovery	DESCRIPTION
SCHLUMBERGER SIDEWALL SAMPLES					
5750'				1/2"	Fine to medium grained, brown oil sand. Medium odor.
5553'				3/4"	Conglomeritic, light brown oil sand. Good petroleum odor.
5188'				1-1/2"	Gray with greenish cast, sandy shale.
4750'				3/4"	Fine to coarse grained, light brown unevenly saturated oil sand. Good petroleum odor.
4734'				1/2"	Conglomeritic, light brown, oil sand.
4660'				1/2"	As above.
4584'				3/4"	As above with pebbles 1/2" in diameter.
4520'				1"	As above.
4459'				No recovery.	
4410'				2"	Dark, greenish-brown shale with abundant foraminifers
4330'				No recovery.	
3590'				1-1/2"	Sandy, dark brown shale.
5778'				1/2"	Soft, medium grained, light brown oil sand. Good od or. (Looks wet.)
5633'				No recovery.	
5515'				1/4"	Hard fragments of dark brown silty shale.
4461'				1/2"	Firm, light gray sandy siltstone.
3764'				1/2"	Hard, brittle, dark gray, micaceous, silty limestone with free oil in fractures.
3350'				1/2"	Soft, coarse, poorly sorted, light brown, undersaturated oil sand. Good petroleum o
3255'				1/2"	Firm, medium grained, oil stained, gray sa Fair odor.
3189'				1/2"	Firm, fine grained, brown oil sand. Good petroleum odor.
3094'				No recovery.	
3037'				1/4"	Fragments to soft green siltstone.
2948'				2"	Firm, fine grained, greenish-brown, oil stained siltstone with occasional megafos Fair odor. (Looks tight.)
2185'				No recovery.	
2000'				2"	Soft, light green, sandy, siltstone with occasional dark spots possibly due to carb aceous material.
1420'				1/4"	Hard, gray, weathered granitic rock. May pebble or part of boulder. In area of hea lost circulation. Note thick mud cake.

AC_CPUC_0118254

FORM 101
CALIFORNIA STATE PRINTING OFFICE

SUBMIT IN DUPLICATE

STATE OF CALIFORNIA
DEPARTMENT OF NATURAL RESOURCES

DIVISION OF OIL AND GAS

DIVISION OF OIL AND GAS
RECEIVED
FEB 17 1954
-2-
LOS ANGELES, CALIFORNIA

LOG AND CORE RECORD OF OIL OR GAS WELL

Operator TIDE WATER ASSOCIATED OIL COMPANY Field ALISO CANYON

Well No. Standard-Sesnon 1-#29 Sec. 28, T. 3 N, R. 16 W, S.B. B. & M.

FORMATIONS PENETRATED BY WELL

DEPTH TO Top of Formation	DEPTH TO Bottom of Formation	Thickness	Drilled or Cored	Recovery	DESCRIPTION
6" DIAMOND CORE BARREL					
8682'	8683'			No recovery.	
8683'	8686'			6"	Very hard Quartzite.
5-7/8" MERCURY CORE BARREL					
8810'	8824'			7'	Conglomerate with matrix of fine to medium oil sand. Good cut and odor.
8824'	8835'			No recovery.	
8835'	8836'			1'	Hard conglomerate with matrix of hard cemented gray sand and hard oil sand. No to fair cut and odor.
8836'	8856'			7'	Hard conglomerate with matrix of hard dark gray sand and hard oil sand. No to fair cut and odor.
8858'	8881'			19'	8' Hard conglomerate with matrix of hard cemented gray sand and hard oil sand. No to fair cut and odor. 4' Hard fine to medium oil sand. Fair to good cut and fair odor. 2' Shell. (Very hard, limey, gray sand. 2' Hard oil sand, as above. 1'6" Shell, as above. 1'6" Hard, medium oil sand and gray sand, possibly brecciated. No to fair cut and odor.
8881'	8905'			4'	2' Hard conglomerate with matrix of hard gray sand and hard oil sand. 2' As above, with more hard gray sand an firm oil sand than previous cores. N to good cut and no to fair odor. Had two 2" streaks of hard gray shale wit minor shearing evident.
8905'	8911'			No recovery	
8911'	8942'			1'	Very hard pieces of quartzite boulders.
5-7/8" REED CONVENTIONAL CORE BARREL					
8942'	8944'			0'3"	Three small pieces of quartzite.
9035'	9048'			0'6"	Fragments of granitic and gneissic boulder
9048'	9052'			1'0"	Hard, medium grained, micaceous gray sand. No cut, faint odor. One fragment of hard greenish-gray slickensided shale on botton

AC_CPUC_0118255

FORM 101
CALIFORNIA STATE PRINTING OFFICE

SUBMIT IN DUPLICATE

STATE OF CALIFORNIA
DEPARTMENT OF NATURAL RESOURCES

DIVISION OF OIL AND GAS

DIVISION OF OIL AND GAS
RECEIVED
FEB 17 1954
LOS ANGELES, CALIFORNIA

LOG AND CORE RECORD OF OIL OR GAS WELL

Operator TIDE WATER ASSOCIATED OIL COMPANY Field ALISO CANYON

Well No. Standard-Sesnon 1-#29 Sec. 28, T. 3 N, R. 16 W, S.B. B. & M.

FORMATIONS PENETRATED BY WELL

DEPTH TO Top of Formation	DEPTH TO Bottom of Formation	Thickness	Drilled or Cored	Recovery	DESCRIPTION
5-7/8" REED CONVENTIONAL CORE BARREL (cont.)					
9089'	9096'			5'	Hard, dark blue-gray shale with numerous light gray streaks and occasional slickensides. Good 10° dips.
9126'	9135'			5'	Hard, dark bluish-gray shale with numerous light gray streaks. Top 1' shows 75° dips and slickensiding. Remainder 10-20° dips.
9444'	9464'			15'	Hard, gray, medium to fine grained micaceous sand. Breaks readily into pieces 1/2" to 2" in length with muddy oil in partings. Faint cut indicating possible gas sand. Good gas showings recorded in mud ditch while coring. Possible 35-40° dip.
9464'	9484'			0'6"	As above. No cut or odor.
9484'	9504'			2'	Hard gray sand as above with possible 50-55° dips. Faint cut and shows fluorescence.
9770'	9790'			18'	Hard, medium grained, gray sand, with biscuit partings. No cut. Slight odor. Cut bottles shows slight fluorescence.

AC_CPUC_0118256

STANDARD SESNON 29
ALISO CANYON

Surface Casing:
11-3/4"
0' - 999', 42# H40
999' - 1042', 47# K55

Production Casing:
7"
0' - 974' 23# N80
974' - 4454' 23# J55
4454' - 6494' 23# N80
6494' - 8170' 26# N80


7" Otis BWB packer at 8032'

Liner:
5" 18# Flushjoint
8075' - 9077'

Liner detail:
8075' - 8727': J55 Perforated 6, 1/2" spf; 8428' - 8436' 10, 1/2" spf; 8454' - 8502', 8528' - 8552', 8602' - 8638', 8658' - 8668', 8674' - 8694'.
8727' - 9077': N80 Slotted .012" x 12 rows x 6" centers
Perforated 6, 1/2" spf
8727' - 8737', 8750' - 8760', 8810' - 8820'.

Cement plug: 9094' - 9200'
9455' - 9650'

Original TD at 9790'



486' Baker Model T5 SCSSV

Tubing
0' - 490' (3-1/2" 9.3# N80 8rd EUE)
490' - 7887' (4-1/2" 11.6# N80 8rd EUE)
7887' - 8030' (3-1/2" 9.3# N80 8rd EUE)

7923' KBMG GLM w/ 1.0" latch
7962' Otis XD Sliding Sleeve (2.750")
7999' Otis XN Nipple (2.750" bore, 2.635" nogo)
8029' 3-1/2" x 2-7/8" crossover (2.441" ID)
8032' Otis J- latch and seal units (2)
8035' Otis guide shoe

Liner Squeezed
8330' - 8331' perforated w/ four 1/2" holes and squeeze cemented with 100 sx cement

Top of fish at 9074' which consists of two partially milled drillable retainers

Elevation (GRD):	2849' ASL
Elevation (KB):	2856' ASL
Elevation (KB):	7' AGL
Status:	Injection/Withdrawal
Flow Regime:	Tubing Flow
Surface Loc.:	750' S and 6100' W from station 84
Bottomhole Loc.:	At 7994' MD (7993' TVD), wellbore is 63' S and 58' W of surface location.

4/26/53 - 9/29/53: Well drilled and completed.

2/2/73 - 2/28/73: Converted well to gas storage by perforating in Sesnon zone. Pressure tested 7" casing. Cleaned out to 9074'. Ran tubing with SSSV.

8/27/77 - 9/9/77: Installed wireline SSSV. Cleaned out to 9077

3/5/79 - 3/10/79: Replaced SSSV.

9/20/91 - 11/6/91: Workover to repair shoe leak. Milled packer. Perforated four 1/2" holes 8330' - 8331'. Squeezed holes with 100 sx class G cement. Ran tubing conveyed perforating guns and shot various intervals at 6 spf with 1/2" holes. Ran Otis BWB packer at 8032' and 2-7/8" tubing without SSSV.

11/4/94 - 11/14/94: Converted well from casing flow to tubing flow. Installed SCSSV and ran large diameter tubing string.

	Well Volume Cu. Ft.	Bbl
Tubing	676	120
Casing	916	163
Csg/Lnr	109	19
Total	1701	302

Zone Tops		
MP	8150'	(8149')
S1	8346'	(8345')
S4	8428'	(8427')
S6	8452'	(8451')
S8	8522'	(8521')
Frew	8728'	(8727')

	Reviewed By	Date
Drilling:	DG Neville	5/17/95
Petroleum:	R Patterson	5/17/95
Region:	W Sweeney	5/19/95

Jim Dayton 11\14\94, DG Neville 5/15/95
W:\AC\SS29\\MEC_SS29.PUB

AC_CPUC_0118257

THE GAS COMPANY
PORTER,SS-29
ALISO CANYON,CALIFORNIA

SURVEY LISTING Page 1
Your ref : SEEKER GYRO
Last revised : 8-Nov-94

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	RECTANGULAR COORDINATES		Dogleg Deg/100Ft	Vert Sect
0.00	0.00	0.00	0.00	0.00 N	0.00 E	0.00	0.00
100.00	0.28	198.18	100.00	0.23 S	0.08 W	0.28	0.22
200.00	0.45	199.72	200.00	0.83 S	0.28 W	0.17	0.80
300.00	0.30	344.41	300.00	0.94 S	0.49 W	0.72	1.02
400.00	0.22	44.84	400.00	0.56 S	0.42 W	0.27	0.69
500.00	0.08	30.44	500.00	0.36 S	0.25 W	0.15	0.44
600.00	0.07	268.25	600.00	0.31 S	0.28 W	0.13	0.41
700.00	0.18	346.25	700.00	0.15 S	0.38 W	0.18	0.37
800.00	0.33	322.20	799.99	0.23 N	0.60 W	0.18	0.24
900.00	0.38	262.30	899.99	0.42 N	1.10 W	0.36	0.44
1000.00	0.72	266.70	999.99	0.34 N	2.06 W	0.35	1.15
1100.00	0.35	292.21	1099.98	0.41 N	2.97 W	0.44	1.72
1200.00	0.66	261.82	1199.98	0.45 N	3.82 W	0.40	2.28
1300.00	0.14	276.92	1299.98	0.38 N	4.52 W	0.52	2.80
1400.00	0.20	198.95	1399.98	0.22 N	4.70 W	0.22	3.04
1500.00	0.52	194.71	1499.97	0.39 S	4.88 W	0.32	3.60
1600.00	0.50	182.52	1599.97	1.27 S	5.01 W	0.11	4.34
1700.00	0.56	193.35	1699.96	2.18 S	5.14 W	0.12	5.10
1800.00	0.49	181.24	1799.96	3.09 S	5.27 W	0.13	5.85
1900.00	0.52	184.94	1899.96	3.97 S	5.31 W	0.04	6.53
2000.00	0.46	248.11	1999.95	4.57 S	5.72 W	0.52	7.25
2100.00	0.24	224.12	2099.95	4.87 S	6.24 W	0.26	7.82
2200.00	0.60	220.44	2199.95	5.42 S	6.73 W	0.36	8.56
2300.00	1.28	241.05	2299.94	6.36 S	8.05 W	0.74	10.14
2400.00	1.44	248.00	2399.91	7.37 S	10.19 W	0.23	12.34
2500.00	1.36	244.23	2499.88	8.36 S	12.43 W	0.12	14.59
2600.00	1.45	241.29	2599.85	9.49 S	14.61 W	0.11	16.90
2700.00	1.42	231.93	2699.82	10.86 S	16.70 W	0.24	19.32
2800.00	1.28	227.36	2799.79	12.38 S	18.50 W	0.17	21.66
2900.00	1.11	220.81	2899.77	13.87 S	19.95 W	0.22	23.75
3000.00	0.88	221.70	2999.75	15.18 S	21.10 W	0.23	25.48
3100.00	0.64	204.44	3099.74	16.26 S	21.83 W	0.33	26.77
3200.00	0.99	190.91	3199.73	17.61 S	22.23 W	0.40	28.04
3300.00	0.89	207.68	3299.72	19.16 S	22.76 W	0.29	29.52
3400.00	0.92	195.28	3399.71	20.62 S	23.33 W	0.20	30.98
3500.00	0.90	178.98	3499.69	22.18 S	23.52 W	0.26	32.26
3600.00	0.61	202.90	3599.69	23.46 S	23.72 W	0.42	33.33
3700.00	0.52	179.99	3699.68	24.41 S	23.93 W	0.24	34.17
3800.00	0.69	222.63	3799.68	25.31 S	24.34 W	0.47	35.10
3900.00	0.60	234.42	3899.67	26.06 S	25.18 W	0.16	36.23
4000.00	1.02	250.89	3999.66	26.66 S	26.44 W	0.47	37.53
4100.00	1.07	226.56	4099.64	27.59 S	27.96 W	0.44	39.25
4200.00	1.21	251.96	4199.62	28.56 S	29.64 W	0.52	41.10
4300.00	0.72	235.71	4299.61	29.24 S	31.16 W	0.55	42.64
4400.00	0.94	262.84	4399.60	29.70 S	32.50 W	0.44	43.88
4500.00	0.42	290.75	4499.59	29.67 S	33.65 W	0.60	44.64
4600.00	0.36	272.40	4599.59	29.53 S	34.31 W	0.14	44.99
4700.00	0.83	272.37	4699.58	29.48 S	35.35 W	0.47	45.66
4800.00	0.82	284.13	4799.57	29.28 S	36.76 W	0.17	46.48
4900.00	0.65	287.64	4899.57	28.93 S	38.00 W	0.17	47.07

All data is in feet unless otherwise stated
Coordinates from SS-29 and TVD from wellhead (2856.00 Ft above mean sea level).
Vertical section is from wellhead on azimuth 222.94 degrees.
Declination is 0.00 degrees, Convergence is 0.00 degrees.
Calculation uses the minimum curvature method.
Presented by Baker Hughes INTEQ

AC_CPUC_0118258

THE GAS COMPANY
PORTER,SS-29
ALISO CANYON,CALIFORNIA

SURVEY LISTING Page 2
Your ref : SEEKER GYRO
Last revised : 8-Nov-94

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	RECTANGULAR COORDINATES		Dogleg Deg/100Ft	Vert Sect	
5000.00	0.32	276.96	4999.56	28.73 S	38.81 W	0.34	47.47	
5100.00	0.10	229.66	5099.56	28.75 S	39.16 W	0.26	47.72	
5200.00	0.08	183.07	5199.56	28.88 S	39.23 W	0.08	47.87	
5300.00	0.38	163.63	5299.56	29.27 S	39.14 W	0.30	48.09	
5400.00	0.50	165.38	5399.56	30.01 S	38.94 W	0.12	48.49	
5500.00	0.61	173.06	5499.55	30.96 S	38.76 W	0.14	49.07	
5600.00	0.59	177.51	5599.55	32.00 S	38.68 W	0.05	49.78	
5700.00	0.46	193.35	5699.54	32.90 S	38.75 W	0.19	50.48	
5800.00	0.48	218.47	5799.54	33.62 S	39.10 W	0.20	51.24	
5900.00	0.62	225.51	5899.54	34.32 S	39.74 W	0.15	52.20	
6000.00	0.72	234.52	5999.53	35.06 S	40.64 W	0.15	53.35	
6100.00	0.84	229.08	6099.52	35.91 S	41.70 W	0.14	54.70	
6200.00	0.77	233.93	6199.51	36.78 S	42.80 W	0.10	56.08	
6300.00	0.86	224.09	6299.50	37.71 S	43.86 W	0.16	57.49	
6400.00	0.74	201.80	6399.49	38.85 S	44.62 W	0.33	58.84	
6500.00	1.05	229.58	6499.48	40.05 S	45.56 W	0.52	60.35	
6600.00	0.70	216.69	6599.47	41.13 S	46.62 W	0.40	61.87	
6700.00	1.21	205.43	6699.45	42.58 S	47.44 W	0.54	63.49	
6800.00	1.24	217.23	6799.43	44.39 S	48.55 W	0.25	65.57	
6900.00	1.15	230.45	6899.41	45.89 S	49.98 W	0.29	67.64	
7000.00	0.99	228.08	6999.39	47.11 S	51.40 W	0.17	69.50	
7100.00	1.02	196.78	7099.38	48.54 S	52.30 W	0.54	71.16	
7200.00	1.15	200.70	7199.36	50.33 S	52.91 W	0.15	72.89	
7300.00	0.54	192.82	7299.35	51.73 S	53.37 W	0.62	74.22	
7400.00	0.63	216.47	7399.34	52.63 S	53.80 W	0.25	75.18	
7500.00	0.73	188.46	7499.34	53.70 S	54.22 W	0.34	76.25	
7600.00	1.09	196.95	7599.32	55.24 S	54.59 W	0.39	77.63	
7700.00	0.84	209.94	7699.31	56.78 S	55.23 W	0.34	79.20	
7800.00	1.39	204.19	7799.29	58.53 S	56.10 W	0.57	81.06	
7900.00	1.60	209.76	7899.25	60.85 S	57.29 W	0.26	83.57	
7994.00	1.20	212.06	7993.23	62.83 S	58.46 W	0.43	85.82	
9077.00	1.20	212.06	9075.99	82.06 S	70.51 W	0.00	108.10	PROJECTED

DLS

All data is in feet unless otherwise stated
Coordinates from SS-29 and TVD from wellhead (2856.00 Ft above mean sea level).
Vertical section is from wellhead on azimuth 222.94 degrees.
Declination is 0.00 degrees, Convergence is 0.00 degrees.
Calculation uses the minimum curvature method.
Presented by Baker Hughes INTEQ

Comments in wellpath


MD	TVD	Rectangular Coords.		Comment
9077.00	9075.99	82.06 S	70.51 W	PROJECTED

All data is in feet unless otherwise stated
Coordinates from SS-29 and TVD from wellhead (2856.00 Ft above mean sea level).
Bottom hole distance is 108.19 on azimuth 220.67 degrees from wellhead.
Vertical section is from wellhead on azimuth 222.94 degrees.
Declination is 0.00 degrees, Convergence is 0.00 degrees.
Calculation uses the minimum curvature method.
Presented by Baker Hughes INTEQ

THE GAS COMPANY

Structure : PORTER Well : SS-29
Field : ALISO CANYON Location : CALIFORNIA

BAKER HUGHES INTEQ



PROJECTED SURVEY TO T.D.
9077.0'MD 9075.99'TVD
1.20-INCL 212.06-AZM
82.06'S 70.51'W
108.19' AT 220.67 AZM
FROM SURFACE LOCATION

Created by : planner
Date plotted : 12-Dec-94
Plot Reference is SEEKER GYRO.
Coordinates are in feet reference SS-29.
True Vertical Depths are reference wellhead.

--- Baker Hughes INTEQ ---

AC_CPUC_0118261

SCHLUMBERGER WELL SURVEYING CORPORATION

HOUSTON, TEXAS

SCHLUMBERGER

Electrical Log

COUNTY LOS ANGELES
FIELD ALISO CANYON
LOCATION 28 - 3N - 16W
WELL STANDARD SESNON NO. 1-29
COMPANY TIDE WATER ASSOC. OIL COMPANY

COMPANY TIDE WATER ASSOC OIL COMPANY
WELL STANDARD SESNON NO. 1-29
FIELD ALISO CANYON
LOCATION 28 - 3N - 16W
COUNTY LOS ANGELES
STATE CALIFORNIA

Location of Well

Elevation: D.F.:
K.B.: 2856
or G.L.:

FILING No.

RUN No.	1	2	3	4	5
Date	6-24-53	7-9-53	7-29-53	8-7-53	8-24-53
First Reading	5948	8183	8808	8940	9072
Last Reading	1040	6984 5948	8183	8808	8940
Feet Measured	4908	2235	625	132	132
Csg. Schlum.	1040	----	8180	----	----
Csg. Driller	1042	1042	8180	8180	8180
Depth Reached	5949	8184	8809	8941	9073
Bottom Driller	5948	8185	8810	8941	9072
Depth Datum	K.B.	K.B.	K.B.	K.B.	K.B.
Mud Nat.	Oil Emul	Carb+Lig	Oil Emul	Oil Emul	Carbono
" Density	76	77½	73	78	75
" Viscosity	39	55	44	42	30/500CC
" Resist.	2.3@ 94°F	3.3@ 80°F	1.9@ 94°F	2.0@ 85°F	1.8@ 74°F
" Res. BHT	1.8@127°F	2.0@139°F	1.2@161°F	1.1@163°F	.94@166°F
" pH	12 @ 94°F	11 @ 80°F	12 @ 94°F	12 @ 85°F	12 @ 74°F
" Wtr. Loss	-- CC 30 min.	-- CC 30 min.	-- CC 30 min.	-- CC 30 min.	-- CC 30 min.
Max. Temp. °F	127°F.	139°F.	161°F.	163°F.	166°F.
Bit Size	10⅝"	10⅝"	6¼"	6¼"	6¼"
Spcgs.—AM	16"-M	16"-M	16"-M	16"-M	16"-M
AO--	10	10	10	10	10
AO..	19	19	19	19	19
Opr. Rig Time	2 hrs.	2½ hrs.	2 hrs.	2 hrs.	2½ hrs.
Truck No.	NH-1733	NH-1720	NH-1732	NH-1720	NH-1732
Recorded By	Emesenbrink	Barbarick	Barbarick	Murphy	Barbarick
Witness By	Burns	Burns	Bowyer	Burns	Burns

RUN No.	6
Date	8-2[illegible]
First Reading	92
Last Reading	90
Feet Measured	1
Csg. Schlum.	--
Csg. Driller	81
Depth Reached	92
Bottom Driller	92
Depth Datum	K.
Mud Nat.	Carbon
" Density	76
" Viscosity	32
" Resist.	3.3@ 6
" Res. BHT	1.5@16
" pH	10 @
" Wtr. Loss	-- CC 30
Max. Temp. °F	169°
Bit Size	6¼"
Spcgs.—AM	16"
AO--	10
AO..	19
Opr. Rig Time	1½ hr
Truck No.	NH-17
Recorded By	Mesen
Witness By	Bowye

RUN No.	11
Date	9-13-
First Reading	97
Last Reading	86
Feet Measured	11
Csg. Schlum.	--
Csg. Driller	81
Depth Reached	97
Bottom Driller	97
Depth Datum	K.
Mud Nat.	Carb+
" Density	77
" Viscosity	31
" Resist.	2.0@
" Res. BHT	1.0@
" pH	12 @
" Wtr. Loss	-- CC
Max. Temp. °F	190
Bit Size	6¼"
Spcgs.—AM	16"
AO--	10
AO..	19
Opr. Rig Time	2½
Truck No.	NH-1
Recorded By	HBar
Witness By	Bowye

AC_CPUC_0118262

Run No.	6	7	8	9	10
	8-29-53	9-1-53	9-4-53	9-7-53	9-11-53
Reading	9202	9362	9503	9644	9787
Reading	9072	9202	9362	9503	9644
Measured	130	160	141	141	143
Schlum.	----	----	----	----	----
Driller	8180	8180	8180	8180	8180
Reached	9203	9363	9504	9645	9788
Driller	9202	9363	9504	9643	9790
Datum	K.B.	K.B.	K.B.	K.B.	K.B.
Mat.	Carbonox	Carbonox	Carbonox	Carbonox	Oil Emul
Density	76	77	75	76	78
Viscosity	34	50	42	45	40
Resist.	3.3@ 68 °F	1.5@ 97 °F	2.0@ 93 °F	2.5@ 85 °F	1.8@ 86 °F
Res. BHT	1.5@169 °F	@ °F	1.1@184 °F	1.3@184 °F	.94@184 °F
pH	10 @ 68 °F	12 @ 97 °F	12 @ 93 °F	12 @ 85 °F	12 @ 86 °F
Filtr. Loss	-- CC 30 min.	-- CC 30 min.	-- CC 30 min.	-- CC 30 min.	-- CC 30 min.
Temp. °F	160° F.		184° F.	184° F.	184° F.
	$6\frac{1}{8}$"	$6\frac{1}{8}$"	$6\frac{1}{8}$"+$5\frac{1}{8}$"	$6\frac{1}{8}$"+$5\frac{1}{8}$"	$6\frac{1}{8}$"+$5\frac{1}{8}$"
A-M	16"-M	16"-M	16"-M	16"-M	16"-M
A 0--	10	10	10	10	10
A O..	19	19	19	19	19
Log Time	$1\frac{3}{4}$ hrs.	$1\frac{3}{4}$ hrs.	$2\frac{1}{2}$ hrs.	$2\frac{1}{2}$ hrs.	2 hrs.
No.	NH-1720	NH-1732	NH-1720	NH-1720	NH-1733
Rec'd By	Mesenbrink	Barbarick	Murphy	Murphy	CGibson
Op. By	Bovyer	Burns	Burns	Burns	Burns

Run No.	11
	9-13-53
Reading	9790
Reading	8650
Measured	1140
Schlum.	----
Driller	8180
Reached	9791
Driller	9790
Datum	K.B.
Mat.	Carb+Oil Emul
Density	77
Viscosity	31
Resist.	2.0@ 90 F
Res. BHT	1.0@190 F
pH	12 @ 90 F
Filtr. Loss	-- CC 30 min.
Temp. F	190° F.
	$6\frac{1}{8}$"
A-M	16"-M
A 0--	10
A O...	19
Log Time	$2\frac{1}{4}$ hrs.
No.	NH-1732
Rec'd By	HBarbarick
Op. By	Bovyer

Films Used:
Run 1 1040 - 5942
Run 2 5942 - 8182
Run 3 8182 - 8642
Run 4 8642 - 8892
Run 5 and Run 7 Omitted
Run 6 8892 - 9164
Run 8 9164 - 9418
Run 9 9418 - 9634
Run 10 9634 - 9787

REMARKS: Hole Size: Run 1 $10\frac{1}{4}$" - 1040; Run 2 $10\frac{1}{4}$" - 8185; Run 3 $6\frac{1}{8}$" - 8810; Run 4 $6\frac{1}{8}$" - 8941; Run 5 $6\frac{1}{8}$" - 9072; Run 6 $6\frac{1}{8}$" - 9202; Run 7 $6\frac{1}{8}$" - 9363; Run 8 $6\frac{1}{8}$" - 9444+$5\frac{1}{8}$" - 9444; Run 9 $6\frac{1}{8}$" - 9629+$5\frac{1}{8}$" - 9643; Run 10 $6\frac{1}{8}$" - 9770+$5\frac{1}{8}$" - 9790; Run 11 $6\frac{1}{8}$" - 9790


REMARKS: Run No. 11 16 5" Balloon Scale only.

AC_CPUC_0118263

Run 7 6¼" - 9363

Run 6 8892 - 9164
Run 8 9164 - 9418
Run 9 9418 - 9634
Run 10 9634 - 9787

REMARKS
Run No. 11 is 5" Balloon Scale only.



AC_CPUC_0118264




AC_CPUC_0118265




AC_CPUC_0118266



AC_CPUC_0118267




AC_CPUC_0118268



AC_CPUC_0118269

AC_CPUC_0118270



AC_CPUC_0118271

SCHLUMBERGER WELL SURVEYING CORPORATION

HOUSTON, TEXAS

SCHLUMBERGER

Electrical Log

COMPANY TIDE WATER ASSOC OIL COMPANY

WELL STANDARD SESNON NO. 1-29

FIELD ALISO CANYON

LOCATION 26 - 3N - 16W

COUNTY LOS ANGELES

STATE CALIFORNIA

Location of Well

Elevation: D.F.:
K.B.: 2856
or G.L.:

FILING No.:

COUNTY LOS ANGELES
FIELD or ALISO CANYON
LOCATION 26 - 3N - 16W
WELL STANDARD SESNON NO. 1-29
COMPANY TIDE WATER ASSOC. OIL COMPANY

RUN No.	1	2	3	4	5
Date	6-24-53	7-9-53	7-29-53	8-7-53	8-24-53
First Reading	5948	8163	8808	8940	9072
Last Reading	1040	5984 5772	8163	8808	8940
Feet Measured	4908	2235	625	132	132
Csg. Schlum.	1040	----	8180	----	----
Csg. Driller	1042	1042	8180	8180	8180
Depth Reached	5949	8184	8809	8941	9073
Bottom Driller	5948	8185	8810	8941	9072
Depth Datum	K.B.	K.B.	K.B.	K.B.	K.B.
Mud Nat.	Oil Emul	Carb+Lig	Oil Emul	Oil Emul	Carbonox
" Density	76	77½	73	78	75
" Viscosity	39	55	44	42	30/500CC
" Resist.	2.3@ 94°F	3.3@ 80°F	1.9@ 94°F	2.0@ 85°F	1.8@ 74°F
" Res. BHT	1.8@127°F	2.0@139°F	1.2@161°F	1.1@163°F	.94@166°F
" pH	12 @ 94°F	11 @ 80°F	12 @ 94°F	12 @ 85°F	12 @ 74°F
" Wtr. Loss	-- CC 30 min.	-- CC 30 min.	-- CC 30 min.	-- CC 30 min.	-- CC 30 min.
Max. Temp. °F	127°F.	139°F.	161°F.	163°F.	166°F.
Bit Size	10"	10"	6¼"	6¼"	6¼"
Spcgs.—AM	16"-M	16"-M	16"-M	16"-M	16"-M
AO—	10	10	10	10	10
AO..	19	19	19	19	19
Opr. Rig Time	2 hrs.	2½ hrs.	2 hrs.	2 hrs.	2½ hrs.
Truck No.	NH-1733	NH-1720	NH-1732	NH-1720	NH-1732
Recorded By	Mesenbrink	Barbarick	Barbarick	Murphy	Barbarick
Witness By	Burns	Burns	Bovyer	Burns	Burns

RUN No.	6	7	8	9	10
Date	8-25-53	9-1-53	9-4-53	9-7-53	9-11-53
First Reading	9202	9362	9503	9644	9787
Last Reading	9072	9202	9362	9503	9644
Feet Measured	130	160	141	141	143
Csg. Schlum.	----	----	----	----	----
Csg. Driller	8180	8180	8180	8180	8180
Depth Reached	9203	9363	9504	9645	9788
Bottom Driller	9202	9363	9504	9643	9790
Depth Datum	K.B.	K.B.	K.B.	K.B.	K.B.
Mud Nat.	Carbonox	Carbonox	Carbonox	Carbonox	Oil Emul
" Density	76	77	75	76	78
" Viscosity	34	50	42	45	40
" Resist.	3.3@ 68°F	1.6@ 97°F	2.0@ 93°F	2.5@ 85°F	1.8@ 86°F
" Res. BHT	1.5@169°F	@ °F	1.1@184°F	1.3@184°F	.94@184°F
" pH	10 @ 68°F	12 @ 97°F	12 @ 93°F	12 @ 85°F	12 @ 86°F
" Wtr. Loss	-- CC 30 min.	-- CC 30 min.	-- CC 30 min.	-- CC 30 min.	-- CC 30 min.
Max. Temp. °F	169°F.		184°F.	184°F.	184°F.
Bit Size	6¾"	6¼"	6¾"+5⅞"	6¾"+5⅞"	6¾"+5⅞"
Spcgs.—AM	16"-M	16"-M	16"-M	16"-M	16"-M
AO—	10	10	10	10	10
AO..	19	19	19	19	19
Opr. Rig Time	1½ hrs.	1¾ hrs.	2½ hrs.	2½ hrs.	2 hrs.
Truck No.	NH-1720	NH-1732	NH-1720	NH-1720	NH-1733
Recorded By	Mesenbrink	Barbarick	Murphy	Murphy	CGibson
Witness By	Bovyer	Burns	Burns	Burns	Burns


RUN No.	11
Date	9-13-53
First Reading	9790
Last Reading	8650
Feet Measured	1140
Csg. Schlum.	----
Csg. Driller	8180
Depth Reached	9791
Bottom Driller	9790
Depth Datum	K.B.
Mud Nat.	Carb+Oil Emul
" Density	77
" Viscosity	31
" Resist.	2.0@ 90°F
" Res. BHT	1.0@190°F
" pH	12 @ 90°F
" Wtr. Loss	-- CC 30 min.
Max. Temp. °F	190°F.
Bit Size	6¾"
Spcgs.—AM	16"-M
AO—	10
AO..	19
Opr. Rig Time	2¼ hrs.
Truck No.	NH-1732
Recorded By	Barbarick
Witness By	Bovyer

REMARKS: Hole Size: Run 1 10¼" - 5948 - 1040, Run 2 10¼" - 8185 - 5942, Run 3 6¾" - 8810 - 8182, Run 4 6¾" - 8941 - 8642, Run 5 6¾" - 9202 - 8892, Run 6 6¾" - 9444 - 9202, Run 7 6¾" - 9629 - 9362, Run 8 6¾" - 9643 - 9503, Run 9 6¾" - 9770 - 9644, Run 10 6¾" - 9790 - 9787, Run 11 6¾" - 9790 - 9644. Films Used: Run 1 Omitted, Run 2 and Run 3 Omitted, Run 4 Omitted, Run 5 and Run 6 Omitted, Run 7 Omitted, Run 8 Omitted, Run 9 Omitted, Run 10 Omitted, Run 11 Omitted

AC_CPUC_0118272

AC_CPUC_0118273

| | | |



AC_CPUC_0118274

WORKOVER PROGRAM

OPERATOR: Southern California Gas Company

FIELD: Aliso Canyon

WELL: Standard Sesnon #29

CONTRACTOR: CPS D-7

OBJECTIVE: Repair shoe leak

APPROXIMATE LOCATION: 750' South and 6100' West from Station #84.

ELEVATION: Ground level 2848.77 feet. Take all measurements from original derrick floor 6.92' above ground level.

SAFETY: Hard hats are to be worn by all personnel on or near a rig. No smoking is permitted within 100' of the wellhead or near any other flammable material.

PRESENT CONDITIONS:

11-3/4"	0'-1042'	42# H-40 to 999'
		47# J-55 to 1042'
7"	0'-8180'	23# N-80 to 974'
		23# J-55 to 4452'
		23# N-80 to 6494'
		26# N-80 to 8180', packer at 8040', 3.25" ID
5" Liner		
8075'-9077'		18# N-80 FJ
		Perforations four .31" holes per foot.
		8456'-8502' 8658'-8668'
		8528'-8552' 8674'-8694'
		8602'-8638'
		8727'-9077' 120 mesh

2-7/8" Tubing Detail

Otis guide shoe
Otis production tube
Otis seal assembly 3.29" OD, 2.38" ID
Otis J-latch locator
Otis blast joint 3.668" OD 2.375" ID
Otis "XN" No-Go Nipple 2.205" ID
Otis blast joint with 4 centralizers 5.50" OD, 2.375" ID
Otis annular flow safety system 4.88" OD, 2.313" ID
Otis "X" Nipple 2.350" ID
Pup joint 6.5# N-80 8rd EUE
243 joints 6.5# J-55 8rd EUE tubing
16 joints 6.5# N-80 8rd EUE tubing
Pups 6.5# N-80 8rd EUE to surface

WORK CATEGORY:

PR

- o Prepare surface as required.
- o Perform any required piano wire work.
- o Spot open top storage tank on location.
- o Check with Resident Reservoir Engineer to determine any changes and condition of the well since writing of this program and current bottom-hole pressure in the vicinity of the well.
- o Kill well if necessary.
- o Well Kill Requirements:
  - a. Top of storage zone = 8428' M.D. 8422' T.V.D.
  - b. Estimated bottom-hole pressure = 3450 psig.
  - c. Calculated fluid density to provide 500 psi overbalance = 67.54 lb./cu.ft. Use 68 lb./cu.ft. fluid to kill well.
  - d. Hydrostatic pressure of calculated fluid density (c) = 3950 psig.
  - e. Overbalance = 500 psi.
  - f. Wellbore fluid volumes:

Tubing	=	47 bbls.
Annulus	=	250 bbls.
Casing Liner	=	19 bbls.
		316 bbls. Total

Note:

- * Pump filtered workover fluid down tubing at 3 bbls/min. through sliding sleeve at 8002'.
- * Bleed off any gas to Gas Company system.
- * Obtain assistance from Aliso Canyon shift supervisor when killing well.

* Be sure to bleed off surface string annulus.

* Maintain surface volume equal to or greater than well volume during workover.

PROGRAM

MI 1. Move in and rig up.

- o Bleed off all casing annuli to zero pressure.
- o Be sure well will stand full of fluid before proceeding. Notify the Sr. Drilling Engineer if well is not in this condition. Dike area as necessary for spill control.
- o Set equalizing back pressure valve in doughnut.
- o Remove xmas tree. Send xmas tree in for repairs as required.

WW 2. Install 9" Class III 5000 psi BOPE.

- o Include Hydril bag and double gate with 2-7/8" pipe rams and blind rams.
- o Bag and both sets of rams are to be actuated hydraulically by a 3000 psi, minimum 60 gallon accumulator with dual remote controls and auxiliary nitrogen. Accumulator fluid should have sufficient antifreeze added to sustain -20°F ambient temperature.
- o Install 5000 psi spool with choke and kill lines as well as check valve.
- o Choke manifold to have discharge to Gas Company system, with block valve and bleeder as well as connections to Baker tank.
- o Inspect Hydril bag when installing BOPE.
- o Use new Rx API rings on all untested BOPE connections.

WW 3. Pressure test BOPE.

- o Blind rams, 2-7/8" pipe rams and choke

manifold are to be tested to 4000 psi with water.

- o Test Hydril bag to 2850 psig with water.
- o Division of Oil and Gas to be given sufficient notice to allow a witness to be present.

CO 4. Pull tubing.

- o Remove back pressure valve.
- o Release tubing from seals.
- o Pull and lay down 2-7/8" tubing and production equipment. (If unable to release from packer, contact the Sr. Drilling Engineer).
- o Send tubing in to West Coast for inspection.
- o Send safety system to salvage. Send No-Go, latch and seals for inspection.

CO 5. Clean out well.

- o Pick up 2-7/8" drill pipe.
- o Run 6-1/8" bit, 7" casing scraper on 2-7/8" drill pipe and clean out to top of packer at 8040'.

CO 6. Retrieve 7" Permatrieve packer.

- o Run in with Otis pulling tool on 2-7/8" drill pipe and make a straight pull of 30,000# over tubing weight to release packer.
- o Pull packer and send to Otis stock.

CO 7. Clean out to TD.

- o Run 4-1/8" bit and 5" casing scraper on 1050' of 2-3/8" 8rd tubing and 2-7/8" drill pipe and clean out from 8075' to 9077'.

FF 8. Perforate 500 psig underbalanced in fluid with eight 1/2" diameter holes per foot and at 45° spiral phasing.

- o Filter workover fluid using DE filter and a 2-micron nominal cartridge filter in series.

- Run Gamma Ray log with collar locator and use for depth correlation.
- Run in with tubing conveyed perforation guns and position guns to perforate the following intervals:

8428'-8436'	8660'-8668'
8454'-8502'	8674'-8694'
8522'-8560'	8727'-8737'
8602'-8636'	8750'-8760'
	8810'-8820'

- If well will flow, allow flow for two hours before pulling perforating assembly.
- Pull perforating assembly from hole.

LR 9. Run Bridge Plug and cap with sand.

- Review guidelines in Company job instruction #224.6005.
- Run and set drillable bridge plug with top at 8345'.
- Cap plug with 8-12 sand to about 10' above top of plug using a dump bailer.

PF 10. Shoot WSO holes.

- Shoot four 1/2" holes at 8330'.

LR 11. Establish Injectivity.

- Change over to clean 2% KCl water.
- Run a 5" retrievable squeeze packer and set at 8240' with a 90' tail. Pump clean KCl water and attempt to establish an injection rate of at least 5 cu.ft./min.
- If established injection rate is below 5 cu.ft./min., spot 50 cu.ft. of 12% HCL/3% HF acid at the 2-3/8" 8rd tubing tail and squeeze it. Do not exceed a surface pressure of 2200 psig or a fracture gradiant of 0.7.
- If unable to establish injectivity, contact the Sr. Drilling Engineer.

LK 12. Squeeze Cement.

- o Pressure test lines and surface connections to 3000 psig, then unset packer.
- o Batch mix 50 cu.ft. of cement slurry.
- o Check makeup water volumes and slurry density prior to pumping.
- o Pump 25 cu.ft. of 6% HCL/1.5% HF acid pre-flush down tubing.
- o Pump 50 cu.ft. batch mixed slurry behind pre-flush. Maintain pressure equal to differential hydrostatic of the tubing and annulus on the annulus with a choke valve on the squeeze manifold.
- o Displace cement slurry with KCl water.
- o When pre-flush is about 10' from the squeeze tool, set packer and proceed to squeeze cement away.
- o When pressure build-up and lock-up is obtained, clear tool, shut down pump and W.O.C. for at least four hours.
- o If no pressure build-up is obtained, pull up and backscuttle 150% of work string volume and repeat Step 13.

LR 13. Clean out cement and pressure test.

- o Pull and lay down squeeze tools.
- o Drill out cement to top of cement plug at ±8335'.
- o Using the rig pump, pressure test squeeze job to surface pressure of 1500 psig but not more than o.70 psi/ft. pressure gradient of TVD for 15 minutes. If unsuccessful, repeat from Step 11.

CO 14. Clean out.

- o Run with 2-3/8" tubing x-over to 2-7/8" drill pipe, 5" casing scraper and 4-1/8" bit, and

clean out to bottom at 9077'.

LR 15. Flow test and noise log.

- o Notify station 24 hours in advance prior to flowing well. Well is to be manned at all times while flowing.
- o Run pressure control valve above packer and set test packer at approximately 8050' in 7" casing.
- o Run 2-7/8" drill pipe with circulating point at about 8040' and land in packer.
- o Unload and flow well for 12 hours.
- o Shut in well for 12 hours.
- o Noise log well and determine if leak has been repaired.
- o If noise log shows anomaly, repeat from Step 11. Do not shoot new holes unless authorized by the Sr. Drilling Engineer.
- o Pull out of hole and lay down tools.

TP 16. Install 7" packer.

- o Using reference collars, set Otis 7" 26# BWB packer on wireline at approximately 8030', but do not set packer in a collar.

CO 17. Run and land tubing.

- o Pick up and run 2-7/8" 6.5# J-55 tubing, drifting and hydrotesting to 4000 psi.

Tubing to Include:

Otis guide shoe
Otis production tube
Otis seal element with two seals
Otis J-latch locator
One joint of 2-7/8" tubing
Otis 2.205" XN No-Go nipple
One joint 2-7/8" tubing
Otis 2-7/8" XD sliding sleeve 2.313" ID. (closed)

One joint 2-7/8" tubing
GLM with 1-1/2" Pump-out valve set at 2700 psig differential
2-7/8" tubing with pups to surface

- o Pressure test packer to 1500 psig using a chart recorder.
- o Keep drill pipe full and observe for returns.
- o Circulate polymer completion fluid out of well with clean, double inhibited 2% KCl water with coat 7726.
- o Pull 20,000# over weight of tubing to check latch.
- o Space out and land tubing with 6,000# on packer.

WW 18. Remove BOPE and install xmas tree.

- o Install equalizing back pressure valve in doughnut.
- o Remove BOPE.
- o Install xmas tree.
- o Tighten all wellhead bolts.
- o Pressure test seals, xmas tree, innerstring spool, seal flange and tubing head to 5000 psig with oil for 20 minutes.
- o Check and close all wellhead valves.
- o Install tapped flanges with bleeder valves on all wellhead valves.
- o Open sliding sleeve.

MO 20. Rig down and move out rig.

- o Inform Resident Engineer and Station Supervisor before moving off wellsite so proper wellsite safety protection can be arranged.
- o Release rig.

- Clean up well site. All trash, debris, equipment and materials to be removed from site.

- Conduct walk-through with a Drilling department representative and a designee from the station after the site is cleaned up.

E. S. Sinclair
September 10, 1991

Approved: _____ 9-24-91
J. B. Lane

cc: C. C. Affelt
R. M. Dowell
J. A. Hemmerly
J. B. Lane
T. D. McMahon
M. E. Melton
R. L. Patterson
R. D. Phillips
J. P. Wesson
P. D. Yu
Rig Supervisor
Contract Tool Pusher (2)

NOTE: Filing of "Notice" and well history not required by D.O.G.

SUBMIT IN DUPLICATE

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION

DIVISION OF OIL AND GAS

History of Oil or Gas Well

Operator Southern California Gas Co. Field or County Aliso Canyon
Well S.S. #29, Sec. 28, T 3N, R 16W, SB B. & M.
A.P.I. No. Name P.S. Magruder Jr. (Person submitting report) Title Agent (President, Secretary or Agent)
Date March 13, 1979, 19

Signature P.S. Magruder Jr.

P.O. Box 3249 Terminal Annex, Los Angeles, Ca. 90051 (Address)
P.S. Magruder Jr. (213) 689-3561 (Telephone Number)

History must be complete in all detail. Use this form to report all operations during drilling and testing of the well or during redrilling or altering the casing, plugging, or abandonment with the dates thereof. Include such items as hole size, formation test details, amounts of cement used, top and bottom of plugs, perforation details, sidetracked junk, bailing tests and initial production data.

Date

GWO 98480

1979

Program: Remove 2 3/8" safety system and 5" packer from 5" liner at 8,420'. Set a packer in the 7" casing near 8,040' and install an Otis 2 7/8" annular flow safety system. Return the well to gas storage service.

3-5 0 Day. Killed well with 350 barrels of 63# brine-polymer completion fluid

3-6 1st Day. Moved California Production Service Co. rig #D-4 onto wellsite and rigged up. Mixed a total of 260 barrels of polymer completion fluid and obtained full circulation. Removed xmas tree and installed BOPE.

3-7 2nd Day. Tested BOPE, blind rams, 2 7/8" pipe rams and choke manifold to 3,000 psi, Hydril "GK" to 2,000 psi with water and nitrogen. Released from 5" Otis "Permatrieve" packer at 8,420'. Circulated gas cut mud from well. Pulled out of hole measuring tubing. Ran in with Otis retrieving tool and released packer. Pulling out of well.

3-8 3rd Day. Recovered 5" Otis "Permatrieve" packer from 8,420'. Ran in well with 7" casing scraper and cleaned out to 8,075'. Pulled out and ran in well with 5" casing scraper and cleaned out to 9,071'. Pulling out of well.

3-9 4th Day. Finished pulling out of well. Ran 7" Otis "Permatrieve" packer and set at 8,040'. Ran in well with Otis Latch-in Locator and 2 seals, changing tubing collars. Latched into packer and pulled 30,000# to check latch. Set 10,000# on packer and tested annulus to 1,500 psi. Pulling out of well.

3-10 5th Day. Finished pulling out of well. Ran Otis annular flow safety system. Hydrotested tubing to 5,000 psi. Landed tubing on packer at 8,040' with 10,000#. Pulled up 30,000# over weight of string to check packer and latch. String weight 53,000# on hook. Removed BOPE. Installed xmas tree and tested to 5,000 psi. Displaced brine-polymer completion fluid from well with 350 barrels of waste lease water. Released rig at 10:00 p.m., 3-10-79.

AC_CPUC_0118284

10/5/77

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION

DIVISION OF OIL AND GAS

History of Oil or Gas Well

Operator Southern California Gas Company Field or County Aliso Canyon
Well name and No. STANDARD SESNON #29, Sec. 28, T 3N, R 16W, S.B.B. & M.
A.P.I. well No. 037-00041 Name P. S. Magruder, Jr. (Person submitting report) Title Agent (President, Secretary or Agent)
Date September 24, 19 77.

Signature P. S. Magruder Jr.

P.O. Box 3249 Terminal Annex, Los Angeles, Ca., 90051 (Address) (213) 689-3561 (Telephone Number)

History must be complete in all detail. Use this form to report all operations during drilling and testing of the well or during redrilling or altering the casing, plugging, or abandonment with the dates thereof. Include such items as hole size, formation test details, amounts of cement used, top and bottom of plugs, perforation details, sidetracked junk, bailing tests and initial production data.

Date	
8-27-77	Moved California Production Service Rig #M 28 from Standard Sesnon #24 location. Circulated hole volume to work gas out of drilling fluid.
8-28-77	Rig and crew idle.
8-29-77	Installed plug in doughnut; removed tree; installed 8" Class III B.O.P.E. and tested with water and nitrogen as follows: Hydril 3000 psi 20 minutes - O.K. Pipe Rams 4000 psi 20 minutes - O.K. Blind Rams " " " " - O.K.
8-30-77	Released Camco hydrostatic packer and Baker locator seal assembly. Pulled out of well tallying tubing. Started back into well. Took gas kick. Killed well. Made up Baker milling tool on Baker junk basket, Bowen hydraulic jars and three 20' 2 3/8" drill collars. Ran tubing to top of liner. NOTE: There was 40' of fine sand inside the tubing string above tubing plug at base of S4 sand.
8-31-77	Milled over and recovered Baker 5" Model "D" packer. Mde up Robison 7" casing scraper and 6 1/8" bit and ran to 8075'. Started out of hole.
9-1-77	Pulled 7" casing scraper and 6 1/8" bit out of well. Ran 5" scraper and 4 1/8" bit to 9072'. (Cleaned out hard asphalt foundation from 9026' -9072'). Started out of well with 4 1/8" bit and scraper. Power tongs broke down - ordered set from H. & H. Started out of well again and their power tongs failed.
9-2-77	Finished pulling 4 1/8" bit and 5" scraper out of well. Ran Johnston 5" Retrievable bridge plug and set at 8425'. Pressured plug and pumped fluid away under 1450 psi. Pulled Retrieving tool. Ran Johnston 5" 18# Bob Cat packer to 8375'. Set and pressured 5" bridge plug to 1500 psi 10 minutes; held O.K.

AC_CPUC_0118285

9-3-77 Pressure tested annulus...(retainer at 8425') to 2500 psi - held O.K. Released retrievable retainer and pressured casing to 2500 psi - held O.K. Displaced polymer mud from well with fresh water treated with surface tension agent. Pulled 5" retrievable retainer out of well - ran 7" retainer to 3800' and pressure tested as follows:

3800'	to	8425'	at 2500 psi	for 60	minutes
3800'	"	Surface	" 2700 psi	" 60	"
3300'	"	"	" 2900 psi	" 60	"
2900'	"	"	" 3100 psi	" 60	"

All above tests O.K.

9-4-77 Rig and crew idle.

9-5-77 (Holiday) Rig and crew idle.

9-6-77 Continued pressure testing casing, as follows:

2500'	to	Surface	with 3300 psi	for 60	minutes
2000'	"	"	" 3700 psi	" 60	"
1100'	"	"	" 4000 psi	" 60	"

Above tests O.K.
Pulled out of well with 7" retainer. Ran tubing in hole to retrieve 5" 18# bridge plug.

9-7-77 Retrieved Johnston 5" 18# retrievable bridge plug. Changed out tubing collars and Baker sealed tubing pins. Using GO-International, set Otis 5" Permatrieve wireline packer at 8415'.

9-8-77 Made up Otis seal assembly; 2 3/8" x 10' blast joint; 2 3/8" x 1.56" NO-GO nipple; 2 3/8" x 20' blast joint; Otis annular flow safety system and tested to 5000 psi. Ran tubing to 8415' hydrotesting to 5000 psi and latched into Otis packer. Pulled 25,000# over tubing weight on packer (67,000# gross weight) and landed with 7000# set-down weight on packer. Installed back-pressure valve in doughnut. Removed B.O.P.E. and installed Christmas tree.

9-9-77 Tested Xmas tree to 5000 psi. Displaced polymer drilling fluid with lease salt water. Set Otis 1.56" blanking plug in "NO-GO" nipple at 9405'. Pressure tested packer and seals under 2000 psi. (Held O.K.). Released rig.

GCA/nd

AC_CPUC_0118286

FORM 103 SUBMIT IN DUPLICATE Δ OSP

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION

DIVISION OF OIL AND GAS

History of Oil or Gas Well

OPERATOR Pacific Lighting Service Company FIELD Aliso Canyon

Well No. SS-29, Sec. 28, T. 3N, R. 16W, S.B. B. & M.

Date ____, 19____ Signed ____

P. O. Box 54790, Terminal Annex
Los Angeles, California 90054 (213) 689-3561 Title Agent
(Address) (Telephone Number) (President, Secretary or Agent)

It is of the greatest importance to have a complete history of the well. Use this form to report a full account of all important operations during the drilling and testing of the well or during re-drilling, altering of casing, plugging, or abandonment with the dates thereof. Be sure to include such items as hole size, formation test details, amounts of cement used, top and bottom of plugs, perforation details, sidetracked junk, bailing tests, shooting and initial production data.

Date	
1973	The following is for the well file only. It does not have to be submitted to the Division of Oil & Gas.
7-31	PROGRAM: (1) Pull tubing and remove 1/4" control line and tubing safety valve. (2) Install nipples for wireline safety valve. (3) Install slotted tubing for sand control.
7-31	Pulled Camco "CA" blanking plug from 8520' and confirmed that sleeves at 8348' and 8488' were open in order to kill well. Moved in California Production Service rig with pump and shaker tank at 2:00 PM and began rigging up.
8-1	Killed and circulated well with 332 barrels brine-polymer workover fluid. Installed and tested Class III B.O.P.E. Pulled 8000' tubing and 1/4" control line.
8-2	Filled hole with 8 barrels. Completed pulling tubing. Lost 12 1/2" x 16" steel banding clamps and top rubber off Camco HRP-1-SP 5" packer. Laid down Camco packer and Page safety valve. Ran 2-1/4" O.D. sawtooth collar and 665' of 1-1/4" Hydrill drill rod on 2-7/8" tubing. Sat down on Model "D" packer at 8520' tubing measurements but rotated through OK. Hit top of fill at 9035'.
8-3	Circulated out soft fill of mud and a small amount of sand from 9035 to bottom at 9077'. Pulled tubing and laid down 665' of 1-1/4" drill rod. Made up and ran completion tubing to 6000' then shut down for the week-end.
8-4&5	Idle.
8-6	Completed running tubing. Hung tubing above packer at 8518' and circulated out mud with salt water, using 310 barrels. Landed tubing with 4000 pounds on Model "D" packer at 8518'. Ran Camco type "CA" 2-3/8" blanking plug and set in Camco "D" nipple at 8517' to isolate S-8 zone. Ran Otis type "X" 2-3/8" plug and set in Otis "X" nipple at 8455'. Pressured tubing to 3500 psi with hot oil truck

AC_CPUC_0118287

1973

8-6 con't. and set Camco HRP-1 2-3/8" x 5" packer at 8420'. Tested packer at 1500 psi for 5 minutes--Ok. Removed B.O.P.E. and installed and tested production head at 4500 psi for 20 minutes--Ok. Started rigging out.

8-7 Completed moving out and released rig at 10:00 AM. Fluid will be unloaded with nitrogen to top gas lift valve at 5690' and the tubing plug will be pulled from 8455' to make well ready for production.

AC_CPUC_0118288

FORM 103 SUBMIT IN DUPLICATE Δ OSP

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION

DIVISION OF OIL AND GAS

History of Oil or Gas Well

OPERATOR Pacific Lighting Service Co. FIELD Aliso Canyon

Well No. SFZU SS-29, Sec. 28, T. 3N, R. 16W, SB B. & M.

Date October 19, 1973 Signed P. S. Magruder, Jr.

P.O. Box 54790, Terminal Annex
Los Angeles, CA 90054 (213) 689-3561 Title Agent

(Address) (Telephone Number) (President, Secretary or Agent)

It is of the greatest importance to have a complete history of the well. Use this form to report a full account of all important operations during the drilling and testing of the well or during re-drilling, altering of casing, plugging, or abandonment with the dates thereof. Be sure to include such items as hole size, formation test details, amounts of cement used, top and bottom of plugs, perforation details, sidetracked junk, bailing tests, shooting and initial production data.

Date 1973	
2-2 to 2-5	Moved in California Production Service and rigged up. Mixed Brine Polymer workover fluid and killed well. Installed and tested Class III BOPE.
2-6	Pulled tubing and packer. Ran 4-1/8" bit and 5" casing scraper. Hit fill at 8970'. Cleaned out sand bridges and tagged bottom at 9074'. Circulated on bottom for 2 hours.
2-7	Ran 7" casing scraper and tagged top of liner at 8082'. Rigged up Dresser Atlas. Ran Cement Bond log 7950-9056', Densilog 8294-8788', and Neutron Lifetime/Gamma Ray logs 8280-9050'.
2-8	Made up and ran Baker model "C" bridge plug on fullbore packer, set bridge plug at 8065'. Set fullbore at 8025' and tested bridge plug with 1910 psi for 15 minutes, OK. Pulled up and set fullbore at 3444'. Tested 3444-8065' with 2060 psi for 15 minutes, OK. Tested from surface to 3444' with 2550 psi for 15 minutes, OK. Pulled up and set fullbore at 2341'. Tested from surface to 2341' with 3000 psi for 15 minutes, OK. Set fullbore packer at 1180' and tested from surface to 1180' with 3550 psi for 15 minutes, OK. 7" casing, OK. Ran in from 1180' and retrieved bridge plug. Rigged up Dresser Atlas. Jet perforated four 0.31" holes per foot 8528-8552', 8602-8638', 8658-8668', and 8674-8694'. Used 11 gram charges and 3-1/2" hollow carriers.
2-9	Made up and ran Johnston tester and bridge plug. Set bridge plug at 8715'. Pulled up and set test tool at 8486' with tail to 8511'. Opened tool at 11:12 a.m. Strong blow building to 142 psi at end of test. Closed tool at 12:32 p.m. Recovered bridge plug and reset same at 8580'. Set test tool at 8480' with tail to 8505'. Opened tool at 1:10 p.m. Light to medium blow throughout one hour test.

AC_CPUC_0118289

1973

Reset bridge plug at 8515'. Started out of hole with tester. Fluid heading out of tubing 5918' above tester. Dropped bar but backscuttle valve failed to open. Continued pulling tester and turning heading fluid to tanks. Total fluid rise approximately 300' of thin, oily, gas cut workover fluid and 5600' of gas cut oil. Recovered fine sand in test tool. Charts showed first test OK; IH 3773 psi, IF 511 psi, FF 1113 psi, FH 3763 psi. Plugged tool on second test. Rigged up Dresser Atlas and jet perforated four 0.31" holes per foot 8456-8502'. Used charges and carriers as above.

2-10 Made up and ran Johnston tester. Set packer at 8436' with tail to 8454'. Opened tool at 10:37 a.m. Shut in at surface after 5 hour clean up flow.

2-11 Idle

2-12 Opened surface valve for final flow at 6:20 a.m. Flowed S-4 zone for 12 hours. Maximum rate 2.7 M^2cf/D. Shut in at tool at 6:20 p.m.

2-13 Pulled tester loose. Ran in to retrieve and relocate bridge plug in preparation to retest perforations 8528-8552'. Could feel no fill and had no apparent difficulty latching onto bridge plug. Could not pull plug loose and could not back tester off of plug. Jarred for 5 hours with no results. Dropped bar. Backscuttled and conditioned mud above 8305'. Rigged up McCullough and made chemical cut at 8297'. Pulled out leaving 213' of fish and bridge plug in hole.

2-14 Made up fishing tools consisting of overshot for 2-3/8" tubing, four 3-3/4" drill collars, bumper sub, and jars. Ran in to 8297' and latched onto fish. Jarred loose. Pulled out of hole with tubing and test tools leaving bridge plug only in hole. Sand in Tester. Charts OK. IH 3729 psi, IF 1305 psi, FF 1425 psi, ISI 1471 psi, FSI 1476 psi, FH 3754 psi.

2-15 Ran overshot for bridge plug retrieving neck. Circulated out small amount of sand on top of plug but could make no hole with overshot. Pulled out and ran Johnston tungsten carbide toothed retrieving tool. Circulated and drilled with tongs. Latched onto and released bridge plug. Pulled out without plug.

2-16 Ran overshot, bumper sub, and jars. Found bridge plug at 9039'. Latched onto and recovered plug. Changed tubing line.

2-17 Made up and ran Johnston bridge plug and tester. Set bridge plug at 8578'. Pulled up and set tester at 8516' with tail to 8535'. Opened tool at 1:00 p.m. Shut in at surface during entire test. Closed tool at 3:00 p.m. Dropped bar and backscuttled approximately 10 bbls. of gas cut oil. Estimated fluid rise 2076'. Pulled tester. Sanded up but charts OK. IH 3728 psi, IF 231 psi, FF 776 psi, FH 3739 psi.

2-18 Idle

AC_CPUC_0118290

1973

2-19 Ran 7" bridge plug to 8065'. Closed rams and tested plug with 1050 psi for 10 minutes. Removed BOPE and tubing head. Rigged up casing jacks and 7" spear. Unlanded 7" casing. Cut and removed 11-3/4" casing head. Welded extension on 7" casing.

2-20 X-rayed 7" weld, OK. Welded on new 11-3/4" 5000 psi casing head. X-rayed OK. Relanded 7" casing with 171,000 lbs. Installed new seal flange and tubing head. Tested seals with 3500 psi.

2-21 Re-installed BOPE and tested with 1250 psi. Retrieved 7" bridge plug from 8065'. Ran 5" bridge plug and squeeze packer.

2-22 Set bridge plug at 8525' and packer at 8436'. Pumped 276 bbls. Halliburton Claylok and 276 bbls. KCl through perforations 8456-8502'. Pulled tools. Retrieved 5" Johnston bridge plug from 8578'. Ran 5" bridge plug and squeeze packer.

2-23 Set bridge plug at 8659' and packer at 8525'. Pumped 360 bbls. Halliburton Claylok and 360 bbls. KCl through perforations 8528-8552' and 8602-8638'. Attempted to treat perforations 8658-8668' and 8674-8694'. Unable to pump into formation with 3500 psi.

2-24 Ran Baker model "D" packer on wireline and set same at 8517'. Started in hole with completion string including 2-3/8" x 5" Camco HRP-1-SP packer, 2-3/8" Page RTL safety valve, and 1/4" control line.

2-25 Idle

2-26 Continued running completion string. Hydro-Tested 2-7/8" tubing to 5000 psi. Spaced out and landed tubing with 9000 lbs. on model "D". Tested 1/4" control line through doughnut with 5000 psi.

2-27 Removed BOPE and installed production head. Tested seals with 5000 psi. Displaced 310 bbls. workover fluid with lease salt water through circulating sleeve. Ran No-Go plug into Camco landing nipple at 8517' and closed circulating sleeve. Pressured tubing to set Camco packer at 8422'. Opened S-4 production sleeve.

2-28 Unloaded 200 bbls. salt water with nitrogen. Blew down tubing and casing. Tore out CPS. Well ready for gas lift and production line hookups.

CALIFORNIA STATE PRINTING OFFICE

SUBMIT IN DUPLICATE

STATE OF CALIFORNIA
DEPARTMENT OF NATURAL RESOURCES

DIVISION OF OIL AND GAS

History of Oil or Gas Well

OPERATOR TIDE WATER ASSOCIATED OIL COMPANY FIELD ALISO CANYON

Well No. Standard-Gesnon 1-#29, Sec. 28, T. 3 N, R. 16 W, S.B. B. & M.

Signed J. E. Weaver Jr.

Date February 11, 1953 Title Agent (President, Secretary or Agent)

It is of the greatest importance to have a complete history of the well. Use this form in reporting the history of all important operations at the well, together with the dates thereof, prior to the first production. Include in your report such information as size of hole drilled to cementing or landing depth of casings, number of sacks of cement used in the plugging, number of sacks or number of feet of cement drilled out of casing, depth at which cement plugs started, and depth at which hard cement encountered. If the well was dynamited, give date, size, position and number of shots. If plugs or bridges were put in to test for water, state kind of material used, position and results of pumping or bailing.

Date

1953

LOCATION: 750' South and 6100' West of Station #84 (From Gas Unit)

1953

ELEVATION: 2848.77' Mat
2855.69' Derrick Floor

3/3-4/25 Surveying location, moved in equipment to start grading, graded road and rig site, dug rat hole and cellar, built foundation forms, oil roads, poured foundation concrete, erected derrick, installed sub-base, rigged up rotary.

4/26 Spudded 15" hole at 5:00 AM and drilled to 201'.

4/27-5/1 Drilled 15" hole from 201' to 1006'. Reduced size of hole to 10-5/8" and drilled to 1115'.

5/2 Drilled 10-5/8" hole from 1115' to 1234'.

5/3 Reamed and opened hole to 1042'.

5/4 Ran and cemented 11-3/4" T & C Youngstown casing at 1042' with 550 sacks Colton construction cement; first and last 100 sacks treated with quick setting chemical. Bottom 43' is 47# J-55 and remainder is 42# H-40. Pressure rose from 200-400# when plugs bumped. Time 5:15 AM. No circulation in latter stages of operation. Pumped in 100 sacks around outside of casing which filled to surface. B.J. Service.

5/5 Installed cellar connections. Cleaned out cement from 1042' to 1234'.

5/6 Drilled 10-5/8" hole from 1234' to 1387'. Lost circulation while drilling at 1285'. Regained with hulls and gel.

5/7 Drilled 10-5/8" hole from 1387' to 1394'. Lost circulation while drilling at 1394'. Hung drill pipe at 1380' and pumped in 150 sacks Colton construction cement. Went in with bit and found no cement. Hung drill pipe at 1380' and pumped in 100 sacks Colton construction cement. Found top of cement at 1325'.

5/8 Drilled 10-5/8" hole from 1394' to 1520'. Lost circulation at 1394'. Regained with hulls and gel.

5/9 Drilled 10-5/8" hole from 1520' to 1725'. Lost circulation at 1725'. Regained with hulls and gel.

5/10-5/11 Drilled 10-5/8" hole from 1725' to 2384'. Lost circulation while drilling at 2350'. After 9-1/2" hours recovered circulation with hulls and gel.

5/12-5/14 Drilled 10-5/8" hole from 2384' to 3398'. Lost circulation while drillin at 3398' Hung drill pipe at 1217' and pumped in 100 sacks Colton construction cement. Found top of cement at 1320'. Hung drill pipe at 1217' and pumped in 100 sacks Colton construction cement.

5/15 Attempting to regain lost circulation.

5/16 Drilled 10-5/8" hole from 3398' to 3504'.

AC_CPUC_0118292

OPERATOR: TIDE WATER ASSOCIATED OIL COMPANY

WELL NO.: Standard-Gesnon 1-#29, Aliso Canyon Field

1953

5/17 Lost circulation. With drill pipe hanging at 1400', pumped in four batches (100 sacks each) Colton construction cement.

5/18 Lost circulation. Hung drill pipe at 1407' and pumped in 100 sacks Colton construction cement. Found top of cement at 1320'. Hung drill pipe at 1314' and pumped in 100 sacks Colton construction cement. Found top of cement at 1240'.

5/19 Drilled 10-5/8" hole from 3504' to 3566'. Lost circulation and stuck drill pipe at 1658'. Spotting oil.

5/20 Backed off drill pipe at 1158'. Washing over at 1206'.

5/21 Washing over fish at 1445'.

5/22 Made cut at 1536' and recovered 187' of fish.

5/23 Washed over fish at 1616' which fell down hole. Located top at 2046'.

5/24 Recovered fish. Unable to maintain circulation. Hung drill pipe at 1470'. Pumped in 100 sacks Colton Hi-temperature cement. Found top of cement at 1460'. Hung drill pipe at 1314'. Pumped in 150 sacks Colton construction cement. Found top at 1254'. Hung drill pipe at 1232' and pumped in 75 sacks Colton construction cement. Found top at 1232'. Hung drill pipe at 1232' and pumped in 75 sacks Colton construction cement. Found top of cement at 1198'.

5/25 Cleaned out cement from 1198' to 1397' when lost circulation. In six operations, by hanging drill pipe from 1397' to 1520', pumped in 600 s acks Colton construction cement. After last cement job, found top of cement at 1061'. Lost circulation while drilling out at 1450'.

5/26 Pumped in 900 sacks treated construction cement in stages from 1520' to shoe. With cement cleaned out 1' below shoe, 1043', hung drill pipe at 1029' and pumped in 100 sacks treated construction cement. Closed rams and squeezed. Final pressure 1000#. Located top of cement at 1043'. Held 950# pressure O.K.

5/27 Cleaned out cement from 1043' to 1350' in 50' stages, which held 500# O.K. until lost circulation at 1350'. Hung drill pipe at 1350' and pumped in 150 sacks treated Colton construction cement. Found top of cement at 1050'. Drilled out cement to 1359' when lost circulation. Hung drill pipe at 1350' and pumped in 50 sac sacks treated Colton construction cement. Found top of cement at 1310'.

5/28 Cleaned out cement from 1310' to 1600'. Cleaned out at 3200' with full circulation

5/29 Cleaned out to 3567'. Started out of hole to 3350', then backed down to 3417' and circulated. Lost circulation and stuck drill pipe. Spotted 110 barrels of oil but could not work pipe free.

5/30 Ran Magnatector and backed off 4" drill pipe at 1262'.

5/31 Top of 4-1/2" drill pipe at 1262'. Washed over drill pipe to 1383'. Cut and recovered 98' of drill pipe. Top of fish at 1360'. Washed over to 1410' and lost circulation.

6/1 Top of 4-1/2" drill pipe fish at 1360'. With drill pipe hanging at 1337', pumped in a mixture of 25 sacks Bentonite, 28 sacks Aquagel and 25 barrels Diesel oil. Final pressure 200#. Cleaned out to top of fish with bit. Washed over fish to 1437' when lost circulation.

6/2 Regained circulation with Kellseal, rice hulls and feathers. Washed over drill pipe fish from 1360' to 1563' and made cut #2 at 1548'. Recovered 188' of fish.

6/3 Washed over drill pipe fish to 1862'. Cut and recovered 313'.

6/4 Cut and recovered 315' of drill pipe fish. Top now at 2176'.

6/5 Washed over drill pipe fish to 2504'. Cut and recovered 308'. Top of fish at 2484'. Washed over drill pipe fish at 2815'. Cut and recovered 317'. Top of fish at 2801'.

6/6 Washed over drill pipe fish to 3120'. Cut and recovered 310'. Top of fish at 3111'.

AC_CPUC_0118293

OPERATOR: TIDE WATER ASSOCIATED OIL COMPANY

WELL NO.: Standard-Sesnon 1-#29, Aliso Canyon Field

1953

6/7 Washed over drill pipe fish to 3300'. Cut and recovered 189'. Top of fish at 3300'. Remainder of fish in hole, a single and two drill collars.

6/8 Washed over drill collars to 3342'.

6/9 Recovered remainder of fish. Cleaning up fish and tools.

6/10 Drilled 10-5/8" hole from 3566' to 3605'.

6/11-22 Drilled 10-5/8" hole from 3605' to 5672'. Repaired brake.

6/23-24 Drilled 10-5/8" hole from 5672' to 6008'. Ran Schlumberger electric log at 5948' and took sidewall samples at 5750', 5553', 5188', 4850', 4734', 4660', 4584', 4510', 4459', 4410', 4330' and 3590'.

6/25-7/8 Drilled 10-5/8" hole from 6008' to 8173'.

7/9 Drilled 10-5/8" hole from 8173' to 8185'. Ran Schlumberger electric log and took sidewall samples.

7/10 Ran and cemented 7" 23 & 26# T & C Youngstown and Japanese casing at 8170' with 550 sacks Colton Hi-temperature cement. Pressure increased from 900-1600# when plugs bumped. Time 3:00 PM. B.J. Service. Used two pump trucks. Casing detail is as follows: 1676' 26# N-80 Japanese casing on bottom; balance is all Youngstown casing: 2042' 23# N-80; 3478' 23# J-55; 974' 23# N-80. Had full circulation while cementing.

7/11 Standing cemented. Laying down drill pipe.

7/12 Standing cemented. Making up 2-7/8" drill pipe.

7/13 Found top of cement at 8145' and shoe of 7" casing at 8180'. Drilled 6-1/8" hole to 8186'.

7/14 Ran Johnston tester on 2-7/8" drill pipe and set packer at 8160' with tailpipe to 8175'. Used 600' of water cushion. Opened tester at 2:25 PM. Had light, steady blow for 3 minutes, then dead for balance of 1 hour test. Closed tester at 3:25 PM. Recovered water cushion and 30' net rise of drilling mud. Pressure bomb charts checked details of test. Water shutoff witnessed and approved by Division of Oil and Gas. Drilled 6-1/8" hole from 8186' to 8196'.

7/15-20 Drilled 6-1/8" hole from 8196' to 8682'.

7/21 Recovered cone with magnetic basket. Reamed 6-1/8" hole from 8170' to 8682'.

7/22 Cored with 6" Diamond core barrel from 8682' to 8686'.

7/23-29 Drilled 6-1/8" hole from 8686' to 8810'. Ran Schlumberger electric log at 8810'.

7/30 Cored 5-7/8" hole from 8810' to 8824' with Mercury Diamond Head bit. Ran Johnston formation tester on 2-7/8" drill pipe with 115' of perforated tailpipe. Set packers at 8709' and 8698'. Used 575' water cushion. Opened tester at 4:45 PM. Packers failed.

7/31 Drilled 6-1/8" hole from 8824' to 8825'. Ran Johnston formation tester on 2-7/8" drill pipe and set dual packers at 8638' and 8695' with 129' of perforated tailpipe. Used 575' water cushion. Opened tester at 1:55 PM. Had faint, steady blow to end of test at 3:05 PM. Had net rise of 4460' of oil, most of which blew from drill pipe. During test, pressure charts increased from 700-1775# and were still rising. Sample at 3977' off bottom packer tested 12.0 wet gravity, cut 42% mud and emulsion, 4% silt. Sample at 1975' off bottom packer tested 16.5 wet gravity, cut 20% muc and emulsion, 4% silt. Sample at 1055' off bottom packer tested 17.6 wet gravity, cut 16% emulsion 2% silt and sand. Sample at 515' off bottom packer tested 17.9 wet gravity, cut 3% water, 2.8% emulsion and 1% mud. Sample at 124' off bottom packer tested 13.7 wet gravity, cut 14% water and 1% mud.

8/1-5 Cored 5-7/8" hole from 8825' to 8911' with Mercury Diamond Head bit.

8/6 Drilled 6-1/8" hole from 8911' to 8914'. Cored 5-7/8" hole from 8914' to 8921'.

8/7 Cored 5-7/8" hole from 8921' to 8942'.

AC_CPUC_0118294

OPERATOR: TIDE WATER ASSOCIATED OIL COMPANY

WELL NO.: Standard-Sesnon 1-#29, Aliso Canyon Field

1953

8/8 Ran Schlumberger electric log at 8942'. Ran Johnston formation tester on 2-7/8" drill pipe and set packers at 8825' and 8816' with perforated tailpipe to 8942'. Used 1000' water cushion. Opened valve at 8:55 AM. Had light, steady blow for 15 minutes, decreasing to faint steady blow at end of 1 hour test. Recovered cushion and 660' net rise of gas-cut drilling mud with scum of oil. Filtered fresh water sample with difficulty. Unable to determine exact salinity due to extremely dark color. Pressure bomb charts indicated a pressure rise from 600# (cushion) to 900# during test. Reaming 5-7/8" hole to 6-1/4" hole.

8/9 Reamed 5-7/8" hole to 6-1/4". Cored 5-7/8" hole with Reed conventional bit from 8942' to 8944'. Ran Magnetic junk basket and recovered iron from bit.

8/10 Milled on iron.

8/11-14 Drilled 6-1/8" hole from 8944' to 8974'. Milling on iron.

8/15 Milled on iron.

8/16 Milled on cone. Drilled 6-1/8" hole from 8974' to 8980'.

8/17-21 Drilled 6-1/8" hole from 8980' to 9043'.

8/22-24 Cored 5-7/8" hole from 9043' to 9052'. Opened 5-7/8" hole to 6-1/8" from 9035' to 9072'. Reamed hole from 8914' to 9072'. Ran Schlumberger electric log at 9072'. Reamed hole from 8914' to 9072'.

8/25 Ran Johnston formation tester on 2-7/8" drill pipe and set packers at 8932' and 8943' with tailpipe to 9072'. Used 1000' water cushion. Opened tester at 5:45 AM. Had light, steady blow throughout 1 hour and 30 minute test. Recovered 665' net rise of gassy drilling mud. No free water or oil. Pressure bomb charts increased from 550-800# during test. Drilled 6-1/8" hole from 9072' to 9074'.

8/26 Drilled 6-1/8" hole from 9074' to 9089'. Cored 5-7/8" hole from 9089' to 9092'.

8/27 Cored 5-7/8" hole from 9092' to 9096'. Drilled 6-1/8" hole from 9096' to 9126'.

8/28 Cored 5-7/8" hole from 9126' to 9135'; opened hole to 6-1/8" then drilled ahead to 9165' with 6-1/8" bit.

8/29 Drilled 6-1/8" hole from 9165' to 9212'. Ran Schlumberger electric log at 9202'.

8/30-9/1 Drilled 6-1/8" hole from 9212' to 9388'. Ran Schlumberger electric log and Dipmeter at 9363'.

9/2-3 Drilled 6-1/8" hole from 9388' to 9484'.

9/4 Cored 5-7/8" hole from 9484' to 9504'. Ran Schlumberger electric log at 9504'. Opened 5-7/8" hole to 6-1/8" to 9504'.

9/5 Ran Johnston formation tester on 2-7/8" drill pipe and set packers at 9375' and 9365' with perforated tailpipe to 9504'. Used 1000' water cushion. Opened tester at 12:55 PM. Had medium, steady blow for 5 minutes, increasing to strong, steady blow for next 7 minutes, at which time gas surfaced; 2 minutes later water cushion surfaced (14 minutes). Well blew water cushion for 45 minutes and drilling mud for 50 minutes with gas at 1113 MCF/day rate. Closed tester at 2:35 PM after 1 hour and 35 minute test. Recovered 540' rise of gas cut drilling fluid. No free oil or water. Pressure bomb charts indicated a decrease from 1100-980# during period of test.

9/6-9/7 Drilled 6-1/8" hole from 9504' to 9629'. Cored 5-7/8" hole from 9629' to 9643'. Ran Schlumberger electric log at 9643'.

9/8 Reamed 6-1/8" hole from 9420' to 9643'. Ran Johnston tester on 2-7/8" drill pipe with packers set at 9523' and 9514' and bottom of perforated tailpipe at 9643'. Used 1000' water cushion. Opened valve at 9:00 PM and had faint blow of air for 15 minutes, then died. Closed valve at 10:00 PM after being open 1 hour. Recovered 260' gas cut drilling mud. No free water. Charts checked details of test.

9/9-10 Drilled 6-1/8" hole from 9643' to 9770'. Cored with 5-7/8" Reed Conventional Barrel from 9770' to 9775'.

9/11 Cored 5-7/8" hole from 9775' to 9790'. Ran Schlumberger electric log at 9790' and opened 5-7/8" hole to 6-1/8" from 9770' to 9790'.

AC_CPUC_0118295

OPERATOR: TIDE WATER ASSOCIATED OIL COMPANY

WELL NO.: Standard-Sesnon 1-#29, Aliso Canyon Field

1953

9/12 Ran Johnston tester on 2-7/8" drill pipe and set packers at 9652' and 9659' with tailpipe to 9790'. Used 1000' water cushion. Opened tester at 3:30 AM but packers failed. Reran Johnston tester and set packers at 9664' and 9671' with tailpipe to 9790'. Used 1000' water cushion. Opened tester at 11:00 PM but packers failed.

9/13 Cleaned out to bottom with 6-1/8" bit. Ran Johnston tester on 2-7/8" drill pipe and set packers at 9696' and 9687' with tailpipe to 9790'. Used 1000' water cushion. Opened tester at 5:00 PM but packers failed. Running Schlumberger electric log, Dipmeter, Caliper and Microlog.

9/14 Completed Schlumberger services. Cleaned out to bottom with 6-1/8" bit and reamed tight spots.

9/15 Ran Johnston forma tion tester on 2-7/8" drill pipe with bottom of perforated tailpipe at 9790'. Set top packer at 9693' and lower packer at 9700'. Opened valve at 6:00 AM but packers failed. Making up tubing.

9/16 Hung 2-7/8" tubing at 9650'. Pumped in 35 sacks Colton Hi-temperature cement. Final pressure 1300#. Time 9:35 AM. B.J. Service. Found top of cement at 9455'. Hung 2-7/8" tubing at 9200' and pumped in 35 sacks Colton Hi-temperature cement. Final pressure 1300#. Time 7:20 PM. B.J. Service. Found top of cement at 9094'.

9/17 Reamed 6-1/8" hole.

9/18 Landed 1002' 5" 18# F.J. liner at 9077' including 350' of perforations from 8727' to 9077'. Top of Burns liner hanger at 8075'. Perforations are N-80, 120 mesh, 12 rows, 6" centers, 6° undercut, by Pacific. Blank is J-55. Hung 2-7/8" drill pipe at 8104' and cemented 5" liner through Baker C.P. collar at 8725' with 100 s acks Colton Hi-temperature cement. Final pressure 1700#. Time 11:30 AM. B.J. Service.

9/19 Standing cemented.

9/20 Ran Johnston tester on 2-7/8" drill pipe to test 5" to 7" casing splice. Set packer at 8070' with perforated tailpipe to 8085'. Used 500' water cushion. Opened tester at 10:20 AM. Had one puff, then dead for duration of 1 hour 5 minute test. Recovered 90' net rise of drilling mud. No free water. Charts checked details of test. Found top of hard cement in 5" liner at 8122'. Drilled out cement from 8157' to 8366' and drilled out cement from 8366' to 8720'.

WSO splice

9/21 Conditioned mud. Running Johnston formation tester.

9/22 Ran Johnston combination gun and tester on 2-7/8" drill pipe. Shot four jet holes at 8710'. Used 500' water cushion. Opened valve at 1:15 AM. Had medium, steady blow for 45 minutes, then dead for balance of 1 hour test. Recovered 1450' net rise of oil. Average of four samples: gravity 16.2; cut 40% water; 133 grains per gallon. Believe oil to be from Frew Zone. Water shutoff witnessed but not approved by Division of Oil and Gas. Scraped 5" liner and ran Baker Model "K" retainer on 2-7/8" drill pipe and tubing. Attempted to set retainer at 6850' but ball would not seat. Time 3:30 AM 9-23-53.

9/23 Ran Baker Model "K" retainer on 2-7/8" tubing and drill pipe and set retainer at 8650'. Applied pressure to holes at 8710'. Formation broke down at 6000# and took fluid at rate of 4 cu. ft. per minute at 3300#. Opened circulating ports and mixed 50 sacks Colton Hi-temperature cement preceeded by 15 cu. ft. of water and followed by 251 cu. ft. of water. Closed circulating ports. Squeezed 34 sacks below retainer. Final pressure 7200#. Time 10:50 AM. B.J. Service. Backed off retainer and backscuttled an estimated 16 sacks of cement. Drilled up retainer and hard cement from 8647' to 8720'.

Cmt. 4 H.S. 8710

9/24 Ran Johnston combination gun and tester on 2-7/8" drill pipe and shot four holes at 8705'. Set packer at 8666' with perforated tailpipe to 8687'. Used 700' water cushion Opened tester at 1:35 PM. Had light steady blow for 2 minutes, then dead for balance of 1 hour and 10 minute test. Recovered 20' net rise of drilling fluid. Charts confirmed results of test. Water shutoff witnessed and approved by Division of Oil and Gas. Drilled out hard cement from 8720' to 8725'. Cleaned out to 9077'.

WSO # 8705

OPERATOR: TIDE WATER ASSOCIATED OIL COMPANY

WELL NO.: Standard-Seanon 1-#29, Aliso Canyon Field

1953

9/25 Displaced mud in liner with oil. Laid down 2-7/8" drill pipe. Tore out cellar connections. Running 2-7/8" tubing with Guiberson packer on bottom, [illegible]

9/26 Finished running 2-7/8" tubing and set packer at 8043'. Connected up Christmas tree. Started swabbing.

9/27 Swabbed. Fluid level at 3400'.

9/28 Swabbed well to 3600' fluid level when fluid started rising at approximately 8:00 PM. Continued swabbing and well started flowing at 3:00 AM 9-29-53. Well swabbed and flowed 188 barrels of circulating oil to 6:00 AM 9-29-53; 48/64" bean; no tubing or casing pressures. Total circulating oil recovered 293 barrels of 360 originally put in

9/29 In 24 hours well flowed 260 barrels gross fluid; 20.0% water, 7.0% mud, 27.0% total cut; 190 barrels net oil, of which 123 barrels is formation oil; 17.5 gravity; 40/64" bean; 50# tubing pressure; 150# casing pressure; 449 MCF gas.

9/30 Tearing out rotary. In 24 hours well flowed 146 barrels gross fluid; 9.8% water, 0.2% sand; 10.0% total cut; 131 barrels net oil; 18.6 wet gravity; 48/64" bean; 50# tubing pressure; 150# casing pressure.

	Gross	Net	Cut	Wet Gravity	Bean	Tubing Pressure	Casing Pressure	MCF Gas		
10/1	141	127	10.0%	18.6	48/64	50#	150#	381		
	Cut includes 9.0% water and 1.0% mud.									
10/2	125	116	7.0%	19.5	48/64	50#	150#	348		
10/3	124	115	7.0%	19.8	48/64	50#	250#	288		
10/4	123	117	4.7%	19.2	48/64	50#	225#	273		
10/5	125	115	8.0%	19.0	48/64	50#	250#	248		
10/6	124	114	8.4%	19.1	48/64	150#	225#	231		
10/7	124	122	1.8%	20.0	48/64	75#	225#	230		
10/8	123	122	1.0%	19.5	48/64	50#	225#	44	193	Inj
10/9	104	93	10.6%	19.5	48/64	50#	925#	117	132	"
10/10	104	100	4.0%	19.8	64/64	50#	900#	102	180	"
10/11	113	110	3.2%	19.5	64/64	50#	900#	112	176	"
10/12	111	103	7.2%	19.2	64/64	100#	900#	269	179	"
10/13	98	93	5.1%	20.0	64/64	75#	900#	132	144	"
	Injection line froze.									
10/14	59	57	4.0%	19.1	64/64	50#	900#	101		
	Well stopped producing on gas lift at 4:00 PM.									

10/15 In 8 hours well flowed 17 barrels gross fluid, then died. Shut in for 16 hours to build up pressures.

10/16 Shut in.

10/17 In 3 hours well flowed 11 barrels gross fluid, then died. Shut in for 21 hours.

10/18 Well would not flow. Shut in to build up pressures. 600# tubing pressure; 900# casing

10/19 In 16 hours well flowed on gas lift 92 barrels gross fluid, 90 barrels net oil, 2.0% cut, 20.9 gravity, 600# tubing pressure, 900# casing pressure.

10/20 In 24 hours well flowed on gas lift 92 barrels gross fluid, 88 barrels net oil, 4.0% cut, 19.8 gravity, 50# tubing pressure, 900# casing pressure, 64/64" bean.

10/21 In 19 hours well flowed on gas lift 65 barrels gross fluid, 62 barrels net oil, 4.0% cut, 19.4 gravity, 50# tubing pressure, 925# casing pressure, 64/64" bean. Injection line froze.

								MCF Inj.	MCF Net
10/22	86	84	3.1%	19.7	64/64	50#	925#	29	65
	Gas lift line froze. Off 2 hours.								
10/23	22	20	10.0%	19.5	64/64	50#	925#	30	33
	Gas lift line froze. Off 18 hours.								
10/24	114	85	25.0%	17.2	64/64	50#	900#	85	82
10/25	170	165	3.0%	20.0	64/64	50#	900#	200	131
10/26	125	120	3.5%	19.5	64/64	50#	900#	40	141

OPERATOR: TIDE WATER ASSOCIATED OIL COMPANY

WELL NO.: Standard-Seanon 1-#29, Aliso Canyon Field

1953	Gross	Net	Cut	Gravity	Bean	Tubing Pressure	Casing Pressure	MCF Inj.	MCF Net
10/27	140	115	18.0%	19.0	64/64	50#	925#	50	130
10/28	110	83	25.0%	19.0	64/64	50#	925#	40	127
10/29	93	82	12.0%	18.8	64/64	50#	900#	37	95
10/30	103	96	7.3%	19.2	64/64	50#	900#	66	136
10/31	103	75	28.0%	18.5	64/64	150#	900#	55	177
11/1	92	82	11.0%	19.8	64/64	100#	900#	48	182
11/2	93	78	14.0%	19.0	64/64	100#	900#	26	156
11/3	63	59	7.0%	19.0	64/64	100#	900#	26	138
11/4	90	81	10.0%	19.0	64/64	100#	900#	21	137
11/5	65	60	7.0%	19.0	64/64	100#	900#	10	0
11/6	100	93	7.0%	19.0	64/64	100#	900#	0	90
11/7	95	88	7.0%	19.0	64/64	100#	900#	40	84
11/8	95	88	7.0%	19.0	64/64	100#	900#	93	117
11/9	134	125	7.0%	19.0	64/64	100#	900#	57	148
11/10	87	81	7.0%	19.0	64/64	100#	900#	43	84
11/11	97	89	7.0%	19.0	64/64	100#	900#	52	96
11/12	76	71	7.0%	19.0	64/64	100#	950#	39	122
11/13	76	71	7.0%	19.5	64/64	100#	925#	59	128
11/14	76	71	7.0%	19.5	64/64	100#	925#	30	150
11/15	129	120	7.0%	19.5	64/64	100#	925#	200	79
11/16	72	67	7.0%	19.5	64/64	100#	925#	90	169
11/17	60	56	7.0%	19.5	64/64	100#	925#	56	80
11/18	53	49	7.0%	19.5	64/64	100#	925#	17	45

CASING RECORD

11-3/4" 42 & 47# C 1042'
7" 23 & 26# C 8180'
1002' 5" 18# L 9077' inc. 350' pfs. Top 8075'

TUBING RECORD

2-7/8" L w/packer 8043' 5" values

AC_CPUC_0118298

SUBMIT LOG IN DUPLICATE

FILL T... IN WITH TYPEWRITER. WRITE ON ONE SIDE OF P...

STATE OF CALIFORNIA
DEPARTMENT OF NATURAL RESOURCES

DIVISION OF OIL AND GAS

WELL SUMMARY REPORT

Operator TIDE WATER ASSOCIATED OIL COMPANY Field ALISO CANYON

Well No. Standard-Suman 1-29 Sec. 29, T. 3 N, R. 15 W S.B. B. & M.

Location 750' South and 620' West of Station #84 Elevation of ground above sea level 2018.77 feet.

All depth measurements taken from top of derrick floor which is 6.92 feet above ground.

In compliance with the provisions of Chapter 93, Statutes of 1939, the information given herewith is a complete and correct record of the present condition of the well and all work done thereon, so far as can be determined from all available records.

Date February 21, 1954 Signed J. E. Weaver

J. L. Berger (Engineer or Geologist) O. O. Suman (Superintendent) Title Agent (President, Secretary or Agent)

Commenced drilling April 25, 1953 Completed drilling September 24, 1953 Drilling tools Cable Rotary

Total depth 9790' Plugged depth 9058'

Junk

GEOLOGICAL MARKERS — DEPTH

Commenced producing September 29, 1953 (date) Flowing/gas lift/pumping (cross out unnecessary words)

On gas lift 20/8/53

20/25/53 production

Production after 30 days

Clean Oil bbl. per day	Gravity Clean Oil	Per Cent Water including emulsion	Gas Mcf. per day	Tubing Pressure	Casing Pressure
165	20.0	3.0%	131	50#	930#
49	19.5	7.0%	45	100#	525#


CASING RECORD (Present Hole)

Size of Casing (A. P. I.)	Depth of Shoe	Top of Casing	Weight of Casing	New or Second Hand	Seamless or Lapweld	Grade of Casing	Size of Hole Drilled	Number of Sacks of Cement	Depth of Cement if through perfs
12-3/4"	2082'	0'	42 & 47#	New	Seamless	H-40, J-55	15"	850	
7"	8160'	0'	23 & 26#	New	Seamless	J-55, N-80	10-1/2"	500	
5"	9077'	8075'	18#	New	Seamless	N-80 FJ	6-3/8"	100	8178

PERFORATIONS

Size of Casing	From	To	Size of Perforations	No. of Rows	Distance Between Centers	Method of Perforations
5"	8727 ft.	9077 ft.	180 Holes	12	6"	60° Oriented by Gun
	ft.	ft.				
	ft.	ft.				
	ft.	ft.				
	ft.	ft.				

AC_CPUC_0118299



Tubing:
0' - 8035':
2-7/8", 6.5#, J55
8rd EUE Tbg.
(2.441" I.D.)

7919' Camco 'MMA' GLM w/ 1.5" S.O.V. on 'RA' latch

7964' Otis 2.313" 'XD' SSD (opens down)

7999' Otis 2.205" 'XN' No-Go nipple

8031' Otis J-latch and 2 seal units (2.441" I.D.)

8035' Otis Mule shoe guide (2.441" I.D.)

5" Liner Detail:
18#, Flushjoint, 8075' - 9077'
(4.276" I.D.)

8075' - 8727': J55, Perforated 6, 1/2" SPF 8428'-8436',

10, 1/2" SPF 8454'-8502', 8528'-8552', 8602'-8638', 8658'-8668', 8674'-8694'.

8727' - 9077': N80 slotted, .012" gauge, 12 rows, 6" centers, 6 deg. undercut. Perforated 6, 1/2" SPF 8727'-8737', 8750'-8760', 8810'-8820'.

Note: Fish consists of 2 partially milled Robison 5" drillable retainers.

Standard Sesnon #29

Aliso Canyon

Status: Injection/Withdrawal

Flow Regime: Casing Flow

Elevation: 2849' G.L.
7' K.B.
KB to MV: 6'

Surface Location: Approximately 750'S & 6100'W of Station 84, T3N, R16W, Sec. 28

Btm. Hole Loc: Straight Hole at effective TVD of 9077'.

4/26/53 - 9/29/53: Well spudded and completed.

2/2/73 - 2/28/73: Pressure tested 7" casing, converted to gas storage by perforation in Sesnon zone. Cleaned out to 9074'. Ran tubing with SSSV.

7/31/73 - 8/7/73: Installed wireline SSSV. Cleaned out to 9077'.

8/27/77 - 9/9/77: Cleaned out to 9072'. Pressure tested casing. Reran tubing with SSSV.

3/5/79 - 3/10/79: Replaced safety system. Set packer at 8040'.

9/20/91 - 11/6/91: Milled packer. Shot 4, 1/2" SPF at 8330' - 8331'. Squeezed shoe leak with 100 sx class "G" cement. Ran tubing conveyed perforation guns and shot 6, 1/2" SPF at: 8428'-8436', 8454'-8502', 8522'-8560', 8602'-8636', 8660'-8668', 8674'-8694', 8727'-8737', 8750'-8760', 8810'-8820'. Completed with 7" Otis "BWB" packer and 2-7/8" tubing.

Volume	Cu.Ft.	Bbls.
Tubing	261	46.5
Annulus	1427	254
Casing/Liner	109	19
Total	1797	319.5

Top Of Zones

	M.D.
MP	8150'
S1	8346'
S2	8382'
S4	8428'
S8	8522'
Frew	8728'

Reviewed

Department	By:	Date
Drilling	R.M. Duell	9/1/92
Petroleum Eng.		9/1/92
Division		9/1/92


AC_CPUC_0118300

TUBING DETAIL

WELL: STANDARD SESNON #29
FIELD: ALISO CANYON

STATUS: Injection/Withdrawal
DATE: 11-6-91

DIAGRAM



	TUBING	TUBING	TUBING	
SIZE	2 7/8"			
WEIGHT	6.5			
GRADE	J55			
THREAD	8RD EUE			
DEPTH	8035'			
I.D.	2.441			
DRIFT ID	2.347			
O.D.	3.668 TJ			

ITEM #	DESCRIPTION	LENGTH	DEPTH
1.	KB	6.92	6.92
2.	G.L. TO TBG HEAD	-.14	6.78
3.	HANGER 7" 2 7/8" EUE X 2 7/8" EUE BOX	.60	7.38
4.	FATIGUE NIPPLE 2 7/8 EUE PIN X PIN	.68	8.06
5.	PUP JT 2 7/8" 6.5# NBO EUE	4.09	12.15
6.	250 JTS. 2 7/8" 6.5# J55 EUE	7907.35	7919.50
7.	BST 'MMA' GLM W/ 1 1/2" RA LATCH	12.92	7932.42
8.	1 JT. 2 7/8 EUE J55 TBG.	31.49	7963.91
9.	OTIS 2.313" 'XD' SSD	3.21	7967.12
10.	1 JT 2 7/8" EUE J55" TBG	31.55	7998.67
11.	OTIS 2.205" 'XN' NO-GO NIPPLE	1.28	7999.50
12.	1 JT. 2 7/8" EUE J55 TBG	31.55	8031.50
13.	OTIS J-LATCH & 2 SEAL UNITS	1.50 / 2.49	8032
14.	OTIS MULE SHOE GUIDE	.60	
15.			
16.			
17.			
18.	A. OTIS 7" 23-29# 'BWB' PKR		
19.	3.25" I.D. SET AT:		8032'
20.			
	TUBING LANDED W/ 8000#		
	DOWN ON PACKER		

AC_CPUC_0118301

8-6-73

TUBING DETAIL

No. Jts.	Item	Length	Depth
	Below K. B.	6.90	
	2-7/8" donut and pup joint	6.00	
	2-7/8" EU 8 thd. pup jt.	3.95	
184	2-7/8" EU 8 thd. J-55 tubing	5668.65	
	2-7/8" EU 8 thd. pup jt.	4.05	5689.55
	2-1/2" Camco KBMG mandrel w/1/4" BK 925# valve	7.35	5696.90
40	2-7/8" EU 8 thd. J-55	1224.08	
	2-7/8" EU 8 thd. pup jt.	4.03	6925.01
	2-1/2" Camco KBMG mandrel w/1/4" BK 915# valve	7.35	6932.36
34	2-7/8" EU 8 thd. J-55 tubing	1041.10	
	2-7/8" EU 8 thd. pup jt.	4.08	7977.54
	2-1/2" Camco KBMG mandrel w/1/4" BK 905# valve	7.35	7984.89
1	2-7/8" EU 8 thd. J-55 tubing	31.37	
	2-7/8" x 2.313" Otis "X" landing nipple	1.00	8017.26
1	2-7/8" EU 8 thd. J-55 tubing	30.23	
	2-7/8" x 2-3/8" EU 8 thd. crossover	1.15	8048.64
9	2-3/8" EU 8 thd. J-55 tubing	273.63	
	2-3/8" Camco B mandrel w/1/4" J-40 895# valve	4.10	8326.37
1	2-3/8" EU 8 thd. J-55 tubing	30.15	
	2-3/8" x 1.93 Camco sliding sleeve	2.70	8359.22
1	2-3/8" EU 8 thd. J-55 tubing	29.97	
	2-3/8" x 1.875 Otis "X" landing nipple	.95	8390.14
1	2-3/8" EU 8 thd. J-55 tubing	29.98	
	2-3/8" x 5" 18# Camco Hydrostatic set packer HRP-1 16 turns right to release	5.65	
1	2-3/8" EU 8 thd. J-55 tubing	29.73	
	2-3/8" x 1.875 Otis "X" landing nipple	.95	8456.45
	2-3/8" EU 8 thd. pup jt. w/20 mesh slots	10.00	8466.45
	2-3/8" EU 8 thd. pup jt. w/20 mesh slots	10.00	8476.45
	2-3/8" Otis polish nipple	1.50	8477.95
	2-3/8" EU 8 thd. pup jt.	4.20	
	2-3/8" x 1.875 Otis "X" landing nipple	.95	8483.10
	2-3/8" EU 8 thd. pup jt. w/20 mesh slots	10.20	8493.30
	2-3/8" EU 8 thd. pup jt. w/20 mesh slots	10.00	8503.30
	2-3/8" Otis polish nipple	1.50	8504.80
	2-3/8" EU 8 thd. pup jt.	4.05	
	2-3/8" EU 8 thd. pup jt.	8.00	
	2-3/8" x 1.81 Camco type "D" seating nipple	.95	8517.80
	2-3/8" Baker locator sub for Model "D" packer @ 8517'	.40	8518.20
	Baker seals 5 sets for Model "D" packer	4.60	8522.22

NOTE: The slotted tubing above is J-55 with special clearance N-80 collars slotted 20M, 12 rows, 1-1/2" slots on 6" centers.

AC_CPUC_0118302

SUBMIT IN DUPLICATE

STATE OF CALIFORNIA
DEPARTMENT OF NATURAL RESOURCES

DIVISION OF OIL AND GAS

History of Oil or Gas Well

OPERATOR TIDE WATER ASSOCIATED OIL COMPANY FIELD ALISO CANYON

Well No. Standard-Gesmon 1-#29, Sec. 28, T. 3 N, R. 16 W, S.B. B. & M.

Signed J. E. Weaver Jr.

Date February 11, 1953 Title Agent (President, Secretary or Agent)

It is of the greatest importance to have a complete history of the well. Use this form in reporting the history of all important operations at the well, together with the dates thereof, prior to the first production. Include in your report such information as size of hole drilled to cementing or landing depth of casings, number of sacks of cement used in the plugging, number of sacks or number of feet of cement drilled out of casing, depth at which cement plugs started, and depth at which hard cement encountered. If the well was dynamited, give date, size, position and number of shots. If plugs or bridges were put in to test for water, state kind of material used, position and results of pumping or bailing.

Date

1953

LOCATION: 750' South and 6100' West of Station #84 (From Gyro Test)

ELEVATION: 2848.77' Mat
2855.69' Derrick Floor

1953

3/3-4/25 Surveying location, moved in equipment to start grading, graded road and rig site, dug rat hole and cellar, built foundation forms, oil roads, poured foundation concrete, erected derrick, installed sub-base, rigged up rotary.

4/26 Spudded 15" hole at 5:00 AM and drilled to 201'.

4/27-5/1 Drilled 15" hole from 201' to 1005'. Reduced size of hole to 10-5/8" and drilled to 1115'.

5/2 Drilled 10-5/8" hole from 1115' to 1234'.

5/3 Reamed and opened hole to 1042'.

5/4 Ran and cemented 11-3/4" T & C Youngstown casing at 1042' with 550 sacks Colton construction cement; first and last 100 sacks treated with quick setting chemical. Bottom 43' is 47# J-55 and remainder is 42# H-40. Pressure rose from 200-400# when plugs bumped. Time 5:15 AM. No circulation in latter stages of operation. Pumped in 100 sacks around outside of casing which filled to surface. B.J. Service

5/5 Installed cellar connections. Cleaned out cement from 1042' to 1234'.

5/6 Drilled 10-5/8" hole from 1234' to 1387'. Lost circulation while drilling at 1285'. Regained with hulls and gel.

5/7 Drilled 10-5/8" hole from 1387' to 1394'. Lost circulation while drilling at 1394'. Hung drill pipe at 1380' and pumped in 150 sacks Colton construction cement. Went in with bit and found no cement. Hung drill pipe at 1380' and pumped in 100 sacks Colton construction cement. Found top of cement at 1325'.

5/8 Drilled 10-5/8" hole from 1394' to 1520'. Lost circulation at 1394'. Regained with hulls and gel.

5/9 Drilled 10-5/8" hole from 1520' to 1725'. Lost circulation at 1725'. Regained with hulls and gel.

5/10-5/11 Drilled 10-5/8" hole from 1725' to 2384'. Lost circulation while drilling at 2350'. After 9-1/2" hours recovered circulation with hulls and gel.

5/12-5/14 Drilled 10-5/8" hole from 2384' to 3398'. Lost circulation while drilling at 3398. Hung drill pipe at 1217' and pumped in 100 sacks Colton construction cement. Found top of cement at 1320'. Hung drill pipe at 1217' and pumped in 100 sacks Colton construction cement.

5/15 Attempting to regain lost circulation.

5/16 Drilled 10-5/8" hole from 3398' to 3504'.

AC_CPUC_0118303

OPERATOR: TIDE WATER ASSOCIATED OIL COMPANY

WELL NO.: Standard-Gesnon 1-#29, Aliso Canyon Field

1953

5/17 Lost circulation. With drill pipe hanging at 1400', pumped in four batches (100 sacks each) Colton construction cement.

5/18 Lost circulation. Hung drill pipe at 1407' and pumped in 100 sacks Colton construction cement. Found top of cement at 1320'. Hung drill pipe at 1314' and pumped in 100 sacks Colton construction cement. Found top of cement at 1240'.

5/19 Drilled 10-5/8" hole from 3504' to 3566'. Lost circulation and stuck drill pipe at 1658'. Spotting oil.

5/20 Backed off drill pipe at 1158'. Washing over at 1206'.

5/21 Washing over fish at 1445'.

5/22 Made cut at 1536' and recovered 187' of fish.

5/23 Washed over fish at 1616' which fell down hole. Located top at 2046'.

5/24 Recovered fish. Unable to maintain circulation. Hung drill pipe at 1470'. Pumped in 100 sacks Colton Hi-temperature cement. Found top of cement at 1460'. Hung drill pipe at 1314'. Pumped in 150 sacks Colton construction cement. Found top at 1254'. Hung drill pipe at 1232' and pumped in 75 sacks Colton construction cement. Found top at 1232'. Hung drill pipe at 1232' and pumped in 75 sacks Colton construction cement. Found top of cement at 1198'.

5/25 Cleaned out cement from 1198' to 1397' when lost circulation. In six operations, by hanging drill pipe from 1397' to 1520', pumped in 600 sacks Colton construction cement. After last cement job, found top of cement at 1061'. Lost circulation while drilling out at 1450'.

5/26 Pumped in 900 sacks treated construction cement in stages from 1520' to shoe. With cement cleaned out 1' below shoe, 1043', hung drill pipe at 1029' and pumped in 100 sacks treated construction cement. Closed rams and squeezed. Final pressure 1000#. Located top of cement at 1043'. Held 950# pressure O.K.

5/27 Cleaned out cement from 1043' to 1350' in 50' stages, which held 500# O.K. until lost circulation at 1350'. Hung drill pipe at 1350' and pumped in 150 sacks treated Colton construction cement. Found top of cement at 1050'. Drilled out cement to 1359' when lost circulation. Hung drill pipe at 1350' and pumped in 50 sacks treated Colton construction cement. Found top of cement at 1310'.

5/28 Cleaned out cement from 1310' to 1600'. Cleaned out at 3200' with full circulation

5/29 Cleaned out to 3567'. Started out of hole to 3350', then backed down to 3417' and circulated. Lost circulation and stuck drill pipe. Spotted 110 barrels of oil but could not work pipe free.

5/30 Ran Magnatector and backed off 4" drill pipe at 1262'.

5/31 Top of 4-1/2" drill pipe at 1262'. Washed over drill pipe to 1383'. Cut and recovered 98' of drill pipe. Top of fish at 1360'. Washed over to 1410' and lost circulation.

6/1 Top of 4-1/2" drill pipe fish at 1360'. With drill pipe hanging at 1337', pumped in a mixture of 25 sacks Bentonite, 28 sacks Aquagel and 25 barrels Diesel oil. Final pressure 200#. Cleaned out to top of fish with bit. Washed over fish to 1437' when lost circulation.

6/2 Regained circulation with Kellseal, rice hulls and feathers. Washed over drill pipe fish from 1360' to 1563' and made cut #2 at 1548'. Recovered 188' of fish.

6/3 Washed over drill pipe fish to 1862'. Cut and recovered 313'.

6/4 Cut and recovered 315' of drill pipe fish. Top now at 2176'.

6/5 Washed over drill pipe fish to 2504'. Cut and recovered 308'. Top of fish at 2484'. Washed over drill pipe fish at 2815'. Cut and recovered 317'. Top of fish at 2801'.

6/6 Washed over drill pipe fish to 3120'. Cut and recovered 310'. Top of fish at 3111'.

AC_CPUC_0118304

OPERATOR: TIDE WATER ASSOCIATED OIL COMPANY

WELL NO.: Standard-Sesnon 1-#29, Aliso Canyon Field

1953

6/7 Washed over drill pipe fish to 3300'. Cut and recovered 189'. Top of fish at 3300'. Remainder of fish in hole, a single and two drill collars.

6/8 Washed over drill collars to 3342'.

6/9 Recovered remainder of fish. Cleaning up fish and tools.

6/10 Drilled 10-5/8" hole from 3566' to 3605'.

6/11-22 Drilled 10-5/8" hole from 3605' to 5672'. Repaired brake.

6/23-24 Drilled 10-5/8" hole from 5672' to 6008'. Ran Schlumberger electric log at 5948' and took sidewall samples at 5750', 5553', 5188', 4850', 4734', 4660', 4584', 4510', 4459', 4410', 4330' and 3590'.

6/25-7/8 Drilled 10-5/8" hole from 6008' to 8173'.

7/9 Drilled 10-5/8" hole from 8173' to 8185'. Ran Schlumberger electric log and took sidewall samples.

7/10 Ran and cemented 7" 23 & 26# T & C Youngstown and Japanese casing at 8170' with 550 sacks Colton Hi-temperature cement. Pressure increased from 900-1600# when plugs bumped. Time 3:00 PM. B.J. Service. Used two pump trucks. Casing detail is as follows: 1676' 26# N-80 Japanese casing on bottom; balance is all Youngstown casing: 2042' 23# N-80; 3478' 23# J-55; 974' 23# N-80. Had full circulation while cementing.

7/11 Standing cemented. Laying down drill pipe.

7/12 Standing cemented. Making up 2-7/8" drill pipe.

7/13 Found top of cement at 8145' and shoe of 7" casing at 8180'. Drilled 6-1/8" hole to 8186'.

7/14 Ran Johnston tester on 2-7/8" drill pipe and set packer at 8160' with tailpipe to 8175'. Used 600' of water cushion. Opened tester at 2:25 PM. Had light, steady blow for 3 minutes, then dead for balance of 1 hour test. Closed tester at 3:25 PM. Recovered water cushion and 30' net rise of drilling mud. Pressure bomb charts checked details of test. Water shutoff witnessed and approved by Division of Oil and Gas. Drilled 6-1/8" hole from 8186' to 8196'.

7/15-20 Drilled 6-1/8" hole from 8196' to 8682'.

7/21 Recovered cone with magnetic basket. Reamed 6-1/8" hole from 8170' to 8682'.

7/22 Cored with 6" Diamond core barrel from 8682' to 8686'.

7/23-29 Drilled 6-1/8" hole from 8686' to 8810'. Ran Schlumberger electric log at 8810'.

7/30 Cored 5-7/8" hole from 8810' to 8824' with Mercury Diamond Head bit. Ran Johnston formation tester on 2-7/8" drill pipe with 115' of perforated tailpipe. Set packers at 8709' and 8698'. Used 575' water cushion. Opened tester at 4:45 PM. Packers failed.

7/31 Drilled 6-1/8" hole from 8824' to 8825'. Ran Johnston formation tester on 2-7/8" drill pipe and set dual packers at 8688' and 8695' with 129' of perforated tailpipe. Used 575' water cushion. Opened tester at 1:55 PM. Had faint, steady blow to end of test at 3:05 PM. Had net rise of 4460' of oil, most of which blew from drill pipe During test, pressure charts increased from 700-1775# and were still rising. Sample at 3977' off bottom packer tested 12.0 wet gravity, cut 42% mud and emulsion, 4% sil Sample at 1975' off bottom packer tested 16.5 wet gravity, cut 20% muc and emulsion, 4% silt. Sample at 1055' off bottom packer tested 17.6 wet gravity, cut 16% emulsi 2% silt and sand. Sample at 515' off bottom packer tested 17.9 wet gravity, cut 3% water, 2.8% emulsion and 1% mud. Sample at 124' off bottom packer tested 13.7 wet gravity, cut 14% water and 1% mud.

8/1-5 Cored 5-7/8" hole from 8825' to 8911' with Mercury Diamond Head bit.

8/6 Drilled 6-1/8" hole from 8911' to 8914'. Cored 5-7/8" hole from 8914' to 8921'.

8/7 Cored 5-7/8" hole from 8921' to 8942'.

AC_CPUC_0118305

OPERATOR: TIDE WATER ASSOCIATED OIL COMPANY

WELL NO.: Standard-Sesnon 1-#29, Aliso Canyon Field

1953

8/8 Ran Schlumberger electric log at 8942'. Ran Johnston formation tester on 2-7/8" drill pipe and set packers at 8825' and 8816' with perforated tailpipe to 8942'. Used 1000' water cushion. Opened valve at 8:55 AM. Had light, steady blow for 15 minutes, decreasing to faint steady blow at end of 1 hour test. Recovered cushion and 660' net rise of gas-cut drilling mud with scum of oil. Filtered fresh water sample with difficulty. Unable to determine exact salinity due to extremely dark color. Pressure bomb charts indicated a pressure rise from 600# (cushion) to 900# during test. Reaming 5-7/8" hole to 6-1/4" hole.

8/9 Reamed 5-7/8" hole to 6-1/4". Cored 5-7/8" hole with Reed conventional bit from 8942 to 8944'. Ran Magnetic junk basket and recovered iron from bit.

8/10 Milled on iron.

8/11-14 Drilled 6-1/8" hole from 8944' to 8974'. Milling on iron.

8/15 Milled on iron.

8/16 Milled on cone. Drilled 6-1/8" hole from 8974' to 8980'.

8/17-21 Drilled 6-1/8" hole from 8980' to 9043'.

8/22-24 Cored 5-7/8" hole from 9043' to 9052'. Opened 5-7/8" hole to 6-1/8" from 9035' to 9072'. Reamed hole from 8914' to 9072'. Ran Schlumberger electric log at 9072'. Reamed hole from 8914' to 9072'.

8/25 Ran Johnston formation tester on 2-7/8" drill pipe and set packers at 8932' and 8943' with tailpipe to 9072'. Used 1000' water cushion. Opened tester at 5:45 AM. Had light, steady blow throughout 1 hour and 30 minute test. Recovered 665' net rise of gassy drilling mud. No free water or oil. Pressure bomb charts increased from 550-800# during test. Drilled 6-1/8" hole from 9072' to 9074'.

8/26 Drilled 6-1/8" hole from 9074' to 9089'. Cored 5-7/8" hole from 9089' to 9092'.

8/27 Cored 5-7/8" hole from 9092' to 9096'. Drilled 6-1/8" hole from 9096' to 9126'.

8/28 Cored 5-7/8" hole from 9126' to 9135'; opened hole to 6-1/8" then drilled ahead to 9165' with 6-1/8" bit.

8/29 Drilled 6-1/8" hole from 9165' to 9212'. Ran Schlumberger electric log at 9202'.

8/30-9/1 Drilled 6-1/8" hole from 9212' to 9388'. Ran Schlumberger electric log and Dipmeter at 9363'.

9/2-3 Drilled 6-1/8" hole from 9388' to 9484'.

9/4 Cored 5-7/8" hole from 9484' to 9504'. Ran Schlumberger electric log at 9504'. Open 5-7/8" hole to 6-1/8" to 9504'.

9/5 Ran Johnston formation tester on 2-7/8" drill pipe and set packers at 9375' and 9365' with perforated tailpipe to 9504'. Used 1000' water cushion. Opened tester at 12:55 PM. Had medium, steady blow for 5 minutes, increasing to strong, steady blow for nex 7 minutes, at which time gas surfaced; 2 minutes later water cushion surfaced (14 min utes). Well blew water cushion for 45 minutes and drilling mud for 50 minutes with g at 1113 MCF/day rate. Closed tester at 2:35 PM after 1 hour and 35 minute test. Re covered 540' rise of gas cut drilling fluid. No free oil or water. Pressure bomb charts indicated a decrease from 1100-980# during period of test.

9/6-9/7 Drilled 6-1/8" hole from 9504' to 9629'. Cored 5-7/8" hole from 9629' to 9643'. Ran Schlumberger electric log at 9643'.

9/8 Reamed 6-1/8" hole from 9420' to 9643'. Ran Johnston tester on 2-7/8" drill pipe wit packers set at 9523' and 9514' and bottom of perforated tailpipe at 9643'. Used 1000 water cushion. Opened valve at 9:00 PM and had faint blow of air for 15 minutes, the died. Closed valve at 10:00 PM after being open 1 hour. Recovered 260' gas cut dril ing mud. No free water. Charts checked details of test.

9/9-10 Drilled 6-1/8" hole from 9643' to 9770'. Cored with 5-7/8" Reed Conventional Barrel 9770' to 9775'.

9/11 Cored 5-7/8" hole from 9775' to 9790'. Ran Schlumberger electric log at 9790' and opened 5-7/8" hole to 6-1/8" from 9770' to 9790'.

AC_CPUC_0118306

OPERATOR: TIDE WATER ASSOCIATED OIL COMPANY

WELL NO.: Standard-Seamon 1-#29, Aliso Canyon Field

1953

9/12 Ran Johnston tester on 2-7/8" drill pipe and set packers at 9652' and 9659' with tailpipe to 9790'. Used 1000' water cushion. Opened tester at 3:30 AM but packers failed. Reran Johnston tester and set packers at 9664' and 9671' with tailpipe to 9790'. Used 1000' water cushion. Opened tester at 11:00 PM but packers failed.

9/13 Cleaned out to bottom with 6-1/8" bit. Ran Johnston tester on 2-7/8" drill pipe and set packers at 9696' and 9687' with tailpipe to 9790'. Used 1000' water cushion. Opened tester at 5:00 PM but packers failed. Running Schlumberger electric log, Dipmeter, Caliper and Microlog.

9/14 Completed Schlumberger services. Cleaned out to bottom with 6-1/8" bit and reamed tight spots.

9/15 Ran Johnston forma tion tester on 2-7/8" drill pipe with bottom of perforated tailpipe at 9790'. Set top packer at 9693' and lower packer at 9700'. Opened valve at 6:00 AM but packers failed. Making up tubing.

9/16 Hung 2-7/8" tubing at 9650'. Pumped in 35 sacks Colton Hi-temperature cement. Final pressure 1300#. Time 9:35 AM. B.J. Service. Found top of cement at 9455'. Hung 2-7/8" tubing at 9200' and pumped in 35 sacks Colton Hi-temperature cement. Final pressure 1300#. Time 7:20 PM. B.J. Service. Found top of cement at 9094'.

9/17 Reamed 6-1/8" hole.

9/18 Landed 1002' 5" 18# F.J. liner at 9077' including 350' of perforations from 8727' to 9077'. Top of Burns liner hanger at 8075'. Perforations are N-80, 120 mesh, 12 rows, 6" centers, 6° undercut, by Pacific. Blank is J-55. Hung 2-7/8" drill pipe at 8104' and cemented 5" liner through Baker C.P. collar at 8725' with 100 s acks Colton Hi-temperature cement. Final pressure 1700#. Time 11:30 AM. B.J. Service.

9/19 Standing cemented.

9/20 Ran Johnston tester on 2-7/8" drill pipe to test 5" to 7" casing splice. Set packer at 8070' with perforated tailpipe to 8085'. Used 500' water cushion. Opened tester at 10:20 AM. Had one puff, then dead for duration of 1 hour 5 minute test. Recovered 90' net rise of drilling mud. No free water. Charts checked details of test. Found top of hard cement in 5" liner at 8122'. Drilled out cement from 8157' to 8366' and drilled out cement from 8366' to 8720'.

9/21 Conditioned mud. Running Johnston formation tester.

9/22 Ran Johnston combination gun and tester on 2-7/8" drill pipe. Shot four jet holes at 8710'. Used 500' water cushion. Opened valve at 1:15 AM. Had medium, steady blow for 45 minutes, then dead for balance of 1 hour test. Recovered 1450' net rise of oil. Average of four samples: gravity 16.2; cut 40% water; 133 grains per gallon. Believe oil to be from Frew Zone. Water shutoff witnessed but not approved by Division of Oil and Gas. Scraped 5" liner and ran Baker Model "K" retainer on 2-7/8" drill pipe and tubing. Attempted to set retainer at 6850' but ball would not seat. Time 3:30 AM 9-23-53.

9/23 Ran Baker Model "K" retainer on 2-7/8" tubing and drill pipe and set retainer at 8650' Applied pressure to holes at 8710'. Formation broke down at 6000# and took fluid at rate of 4 cu. ft. per minute at 3300#. Opened circulating ports and mixed 50 sacks Colton Hi-temperature cement preceeded by 15 cu. ft. of water and followed by 251 cu. ft. of water. Closed circulating ports. Squeezed 34 sacks below retainer. Final pressure 7200#. Time 10:50 AM. B.J. Service. Backed off retainer and backscuttled an estimated 16 sacks of cement. Drilled up retainer and hard cement from 8647' to 8720'.

9/24 Ran Johnston combination gun and tester on 2-7/8" drill pipe and shot four holes at 8705'. Set packer at 8666' with perforated tailpipe to 8687'. Used 700' water cushic Opened tester at 1:35 PM. Had light steady blow for 2 minutes, then dead for balance of 1 hour and 10 minute test. Recovered 20' net rise of drilling fluid. Charts confirmed results of test. Water shutoff witnessed and approved by Division of Oil and Gas. Drilled out hard cement from 8720' to 8725'. Cleaned out to 9077'.

AC_CPUC_0118307

OPERATOR: TIDE WATER ASSOCIATED OIL COMPANY

WELL NO.: Standard-Seanon 1-#29, Aliso Canyon Field

1953

9/25 Displaced mud in liner with oil. Laid down 2-7/8" drill pipe. Tore out cellar connections. Running 2-7/8" tubing with Guiberson packer on bottom, [illegible]

9/26 Finished running 2-7/8" tubing and set packer at 8043'. Connected up Christmas tree. Started swabbing.

9/27 Swabbed. Fluid level at 3400'.

9/28 Swabbed well to 3600' fluid level when fluid started rising at approximately 8:00 PM. Continued swabbing and well started flowing at 3:00 AM 9-29-53. Well swabbed and flowed 188 barrels of circulating oil to 6:00 AM 9-29-53; 48/64" bean; no tubing or casing pressures. Total circulating oil recovered 293 barrels of 360 originally put i

9/29 In 24 hours well flowed 260 barrels gross fluid; 20.0% water, 7.0% mud, 27.0% total cut; 190 barrels net oil, of which 123 barrels is formation oil; 17.5 gravity; 40/64" bean; 50# tubing pressure; 150# casing pressure; 449 MCF gas.

9/30 Tearing out rotary. In 24 hours well flowed 146 barrels gross fluid; 9.8% water, 0.2% sand; 10.0% total cut; 131 barrels net oil; 18.6 wet gravity; 48/64" bean; 50# tubing pressure; 150# casing pressure.

	Gross	Net	Cut	Wet Gravity	Bean	Tubing Pressure	Casing Pressure	MCF Gas	
10/1	141	127	10.0%	18.6	48/64	50#	150#	381	
	Cut includes 9.0% water and 1.0% mud.								
10/2	125	116	7.0%	19.5	48/64	50#	150#	348	
10/3	124	115	7.0%	19.8	48/64	50#	250#	288	
10/4	123	117	4.7%	19.2	48/64	50#	225#	273	
10/5	125	115	8.0%	19.0	48/64	50#	250#	248	
10/6	124	114	8.4%	19.1	48/64	150#	225#	231	
10/7	124	122	1.8%	20.0	48/64	75#	225#	230	
10/8	123	122	1.0%	19.5	48/64	50#	225#	44	193
10/9	104	93	10.6%	19.5	48/64	50#	925#	117	132
10/10	104	100	4.0%	19.8	64/64	50#	900#	102	180
10/11	113	110	3.2%	19.5	64/64	50#	900#	112	176
10/12	111	103	7.2%	19.2	64/64	100#	900#	269	179
10/13	98	93	5.1%	20.0	64/64	75#	900#	132	144
	Injection line froze.								
10/14	59	57	4.0%	19.1	64/64	50#	900#	101	
	Well stopped producing on gas lift at 4:00 PM.								
10/15	In 8 hours well flowed 17 barrels gross fluid, then died. Shut in for 16 hours to build up pressures.								
10/16	Shut in.								
10/17	In 3 hours well flowed 11 barrels gross fluid, then died. Shut in for 21 hours.								
10/18	Well would not flow. Shut in to build up pressures. 600# tubing pressure; 900# casi								
10/19	In 16 hours well flowed on gas lift 92 barrels gross fluid, 90 barrels net oil, 2.0% cut, 20.9 gravity, 600# tubing pressure, 900# casing pressure.								
10/20	In 24 hours well flowed on gas lift 92 barrels gross fluid, 88 barrels net oil, 4.0% cut, 19.8 gravity, 50# tubing pressure, 900# casing pressure, 64/64" bean.								
10/21	In 19 hours well flowed on gas lift 65 barrels gross fluid, 62 barrels net oil, 4.0% cut, 19.4 gravity, 50# tubing pressure, 925# casing pressure, 64/64" bean. Injection line froze.							MCF Inj.	MCF N
10/22	86	84	3.1%	19.7	64/64	50#	925#	29	65
	Gas lift line froze. Off 2 hours.								
10/23	22	20	10.0%	19.5	64/64	50#	925#	30	33
	Gas lift line froze. Off 18 hours.								
10/24	114	85	25.0%	17.2	64/64	50#	900#	85	82
10/25	170	165	3.0%	20.0	64/64	50#	900#	200	131
10/26	125	120	3.5%	19.5	64/64	50#	900#	40	141

AC_CPUC_0118308

OPERATOR: TIDE WATER ASSOCIATED OIL COMPANY

WELL NO.: Standard-Sesnon 1-#29, Aliso Canyon Field

1953	Gross	Net	Cut	Gravity	Bean	Tubing Pressure	Casing Pressure	MCF Inj.	MCF Net
10/27	140	115	18.0%	19.0	64/64	50#	925#	50	130
10/28	110	83	25.0%	19.0	64/64	50#	925#	40	127
10/29	93	82	12.0%	18.8	64/64	50#	900#	37	95
10/30	103	96	7.3%	19.2	64/64	50#	900#	66	136
10/31	103	75	28.0%	18.5	64/64	150#	900#	55	177
11/1	92	82	11.0%	19.8	64/64	100#	900#	48	182
11/2	93	78	14.0%	19.0	64/64	100#	900#	26	156
11/3	63	59	7.0%	19.0	64/64	100#	900#	26	138
11/4	90	81	10.0%	19.0	64/64	100#	900#	21	137
11/5	65	60	7.0%	19.0	64/64	100#	900#	10	0
11/6	100	93	7.0%	19.0	64/64	100#	900#	0	90
11/7	95	88	7.0%	19.0	64/64	100#	900#	40	84
11/8	95	88	7.0%	19.0	64/64	100#	900#	93	117
11/9	134	125	7.0%	19.0	64/64	100#	900#	57	148
11/10	87	81	7.0%	19.0	64/64	100#	900#	43	84
11/11	97	89	7.0%	19.0	64/64	100#	900#	52	96
11/12	76	71	7.0%	19.0	64/64	100#	950#	39	122
11/13	76	71	7.0%	19.5	64/64	100#	925#	59	128
11/14	76	71	7.0%	19.5	64/64	100#	925#	30	150
11/15	129	120	7.0%	19.5	64/64	100#	925#	200	79
11/16	72	67	7.0%	19.5	64/64	100#	925#	90	169
11/17	60	56	7.0%	19.5	64/64	100#	925#	56	80
11/18	53	49	7.0%	19.5	64/64	100#	925#	17	45

CASING RECORD

11-3/4" 42 & 47# C 1042'
7" 23 & 26# C 8180'
10021' 5" 18# L 9077' inc. 350' pfs. Top 8075'

TUBING RECORD

2-7/8" L w/packer 8043' 5 5 values

AC_CPUC_0118309

FORM 100
Approved, State printing office

SUBMIT LOG IN DUPLICATE
FILL THIS IN WITH TYPEWRITER. WRITE ON ONE SIDE OF PAPER

STATE OF CALIFORNIA
DEPARTMENT OF NATURAL RESOURCES

DIVISION OF OIL AND GAS

WELL SUMMARY REPORT

Operator TIDE WATER ASSOCIATED OIL COMPANY Field ALISO CANYON

Well No. Standard-Semmon 1-A29 Sec. 28, T. 3 N, R. 16 W S.B. B. & M.

Location 750' South and 6100' West of Station #84 Elevation of ground above sea level 2048.77 feet.

All depth measurements taken from top of derrick floor which is 6.92 feet above ground.

In compliance with the provisions of Chapter 93, Statutes of 1939, the information given herewith is a complete and correct record of the present condition of the well and all work done thereon, so far as can be determined from all available records.

Date February 21, 1954 Signed J. E. Weaver

J. R. Berger (Engineer or Geologist) O. O. Suman (Superintendent) Title Agent (President, Secretary or Agent)

Commenced drilling April 25, 1953 Completed drilling September 24, 1953 Drilling tools Cable Rotary

Total depth 9790' Plugged depth 9054'

Junk

GEOLOGICAL MARKERS — DEPTH

Commenced producing September 29, 1953 (date) Flowing/gas lift/pumping (cross out unnecessary words)

On gas lift 10/8/53

10/25/53 ~~Initial~~ production

Production after 30 days

Clean Oil bbl. per day	Gravity Clean Oil	Per Cent Water including emulsion	Gas Mcf. per day	Tubing Pressure	Casing Pressure
165	20.0	3.0%	131	50#	930
49	19.5	7.0%	45	100#	925

CASING RECORD (Present Hole)

Size of Casing (A. P. I.)	Depth of Shoe	Top of Casing	Weight of Casing	New or Second Hand	Seamless or Lapweld	Grade of Casing	Size of Hole Drilled	Number of Sacks of Cement	Depth of Cem if through perf.
12-3/4"	1042'	0'	42 & 47#	New	Seamless	H-40, J-55	15"	650	
7"	8160'	0'	23 & 26#	New	Seamless	J-55, S-95	10-5/8"	500	
5"	9077'	8075'	18#	New	Seamless	J-55 N-80 S.J.	6-3/8"	100	872

PERFORATIONS

Size of Casing	From	To	Size of Perforations	Number of Rows	Distance Between Centers	Method of Perforations
5"	8727 ft.	9077 ft.	120 Mesh	12	6"	60° Undercut by Pac
	ft.	ft.				
	ft.	ft.				
	ft.	ft.				

AC_CPUC_0118310

FORM 103 SUBMIT IN DUPLICATE Δ OSP

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION

DIVISION OF OIL AND GAS

History of Oil or Gas Well

OPERATOR Pacific Lighting Service Co. FIELD Aliso Canyon

Well No. SFZU SS-29, Sec. 28, T. 3N, R. 16W, SB B. & M.

Date October 19, 1973 Signed P. S. Magruder, Jr.

P.O. Box 54790, Terminal Annex
Los Angeles, CA 90054 (213) 689-3561 Title Agent

(Address) (Telephone Number) (President, Secretary or Agent)

It is of the greatest importance to have a complete history of the well. Use this form to report a full account of all important operations during the drilling and testing of the well or during re-drilling, altering of casing, plugging, or abandonment with the dates thereof. Be sure to include such items as hole size, formation test details, amounts of cement used, top and bottom of plugs, perforation details, sidetracked junk, bailing tests, shooting and initial production data.

Date	
1973	
2-2 to 2-5	Moved in California Production Service and rigged up. Mixed Brine Polymer workover fluid and killed well. Installed and tested Class III BOPE.
2-6	Pulled tubing and packer. Ran 4-1/8" bit and 5" casing scraper. Hit fill at 8970'. Cleaned out sand bridges and tagged bottom at 9074'. Circulated on bottom for 2 hours.
2-7	Ran 7" casing scraper and tagged top of liner at 8082'. Rigged up Dresser Atlas. Ran Cement Bond log 7950-9056', Densilog 8294-8788', and Neutron Lifetime/Gamma Ray logs 8280-9050'.
2-8	Made up and ran Baker model "C" bridge plug on fullbore packer, set bridge plug at 8065'. Set fullbore at 8025' and tested bridge plug with 1910 psi for 15 minutes, OK. Pulled up and set fullbore at 3444'. Tested 3444-8065' with 2060 psi for 15 minutes, OK. Tested from surface to 3444' with 2550 psi for 15 minutes, OK. Pulled up and set fullbore at 2341'. Tested from surface to 2341' with 3000 psi for 15 minutes, OK. Set fullbore packer at 1180' and tested from surface to 1180' with 3550 psi for 15 minutes, OK. 7" casing, OK. Ran in from 1180' and retrieved bridge plug. Rigged up Dresser Atlas. Jet perforated four 0.31" holes per foot 8528-8552', 8602-8638', 8658-8668', and 8674-8694'. Used 11 gram charges and 3-1/2" hollow carriers.
2-9	Made up and ran Johnston tester and bridge plug. Set bridge plug at 8715'. Pulled up and set test tool at 8486' with tail to 8511'. Opened tool at 11:12 a.m. Strong blow building to 142 psi at end of test. Closed tool at 12:32 p.m. Recovered bridge plug and reset same at 8580'. Set test tool at 8480' with tail to 8505'. Opened tool at 1:10 p.m. Light to medium blow throughout one hour test.

AC_CPUC_0118311

1973

Reset bridge plug at 8515'. Started out of hole with tester. Fluid heading out of tubing 5918' above tester. Dropped bar but backscuttle valve failed to open. Continued pulling tester and turning heading fluid to tanks. Total fluid rise approximately 300' of thin, oily, gas cut workover fluid and 5600' of gas cut oil. Recovered fine sand in test tool. Charts showed first test OK; IH 3773 psi, IF 511 psi, FF 1113 psi, FH 3763 psi. Plugged tool on second test. Rigged up Dresser Atlas and jet perforated four 0.31" holes per foot 8456-8502'. Used charges and carriers as above.

2-10 Made up and ran Johnston tester. Set packer at 8436' with tail to 8454'. Opened tool at 10:37 a.m. Shut in at surface after 5 hour clean up flow.

2-11 Idle

2-12 Opened surface valve for final flow at 6:20 a.m. Flowed S-4 zone for 12 hours. Maximum rate 2.7 M^2cf/D. Shut in at tool at 6:20 p.m.

2-13 Pulled tester loose. Ran in to retrieve and relocate bridge plug in preparation to retest perforations 8528-8552'. Could feel no fill and had no apparent difficulty latching onto bridge plug. Could not pull plug loose and could not back tester off of plug. Jarred for 5 hours with no results. Dropped bar. Backscuttled and conditioned mud above 8305'. Rigged up McCullough and made chemical cut at 8297'. Pulled out leaving 213' of fish and bridge plug in hole.

2-14 Made up fishing tools consisting of overshot for 2-3/8" tubing, four 3-3/4" drill collars, bumper sub, and jars. Ran in to 8297' and latched onto fish. Jarred loose. Pulled out of hole with tubing and test tools leaving bridge plug only in hole. Sand in Tester. Charts OK. IH 3729 psi, IF 1305 psi, FF 1425 psi, ISI 1471 psi, FSI 1476 psi, FH 3754 psi.

2-15 Ran overshot for bridge plug retrieving neck. Circulated out small amount of sand on top of plug but could make no hole with overshot. Pulled out and ran Johnston tungsten carbide toothed retrieving tool. Circulated and drilled with tongs. Latched onto and released bridge plug. Pulled out without plug.

2-16 Ran overshot, bumper sub, and jars. Found bridge plug at 9039'. Latched onto and recovered plug. Changed tubing line.

2-17 Made up and ran Johnston bridge plug and tester. Set bridge plug at 8578'. Pulled up and set tester at 8516' with tail to 8535'. Opened tool at 1:00 p.m. Shut in at surface during entire test. Closed tool at 3:00 p.m. Dropped bar and backscuttled approximately 10 bbls. of gas cut oil. Estimated fluid rise 2076'. Pulled tester. Sanded up but charts OK. IH 3728 psi, IF 231 psi, FF 776 psi, FH 3739 psi.

2-18 Idle

1973

2-19 Ran 7" bridge plug to 8065'. Closed rams and tested plug with 1050 psi for 10 minutes. Removed BOPE and tubing head. Rigged up casing jacks and 7" spear. Unlanded 7" casing. Cut and removed 11-3/4" casing head. Welded extension on 7" casing.

2-20 X-rayed 7" weld, OK. Welded on new 11-3/4" 5000 psi casing head. X-rayed OK. Relanded 7" casing with 171,000 lbs. Installed new seal flange and tubing head. Tested seals with 3500 psi.

2-21 Re-installed BOPE and tested with 1250 psi. Retrieved 7" bridge plug from 8065'. Ran 5" bridge plug and squeeze packer.

2-22 Set bridge plug at 8525' and packer at 8436'. Pumped 276 bbls. Halliburton Claylok and 276 bbls. KCl through perforations 8456-8502'. Pulled tools. Retrieved 5" Johnston bridge plug from 8578'. Ran 5" bridge plug and squeeze packer.

2-23 Set bridge plug at 8659' and packer at 8525'. Pumped 360 bbls. Halliburton Claylok and 360 bbls. KCl through perforations 8528-8552' and 8602-8638'. Attempted to treat perforations 8658-8668' and 8674-8694'. Unable to pump into formation with 3500 psi.

2-24 Ran Baker model "D" packer on wireline and set same at 8517'. Started in hole with completion string including 2-3/8" x 5" Camco HRP-1-SP packer, 2-3/8" Page RTL safety valve, and 1/4" control line.

2-25 Idle

2-26 Continued running completion string. Hydro-Tested 2-7/8" tubing to 5000 psi. Spaced out and landed tubing with 9000 lbs. on model "D". Tested 1/4" control line through doughnut with 5000 psi.

2-27 Removed BOPE and installed production head. Tested seals with 5000 psi. Displaced 310 bbls. workover fluid with lease salt water through circulating sleeve. Ran No-Go plug into Camco landing nipple at 8517' and closed circulating sleeve. Pressured tubing to set Camco packer at 8422'. Opened S-4 production sleeve.

2-28 Unloaded 200 bbls. salt water with nitrogen. Blew down tubing and casing. Tore out CPS. Well ready for gas lift and production line hookups.

NOTE: Filing of "Notice" and well history not required by D.O.G.

SUBMIT IN DUPLICATE

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION

DIVISION OF OIL AND GAS

History of Oil or Gas Well

Operator Southern California Gas Co. Field or County Aliso Canyon
Well S.S. #29, Sec. 28, T 3N, R 16W, SB B. & M.
A.P.I. No. Name P.S. Magruder Jr. (Person submitting report) Title Agent (President, Secretary or Agent)
Date March 13, 1979, 19

Signature P.S. Magruder Jr.
P.S. Magruder Jr.

P.O. Box 3249 Terminal Annex, Los Angeles, Ca. 90051 (Address)
(213) 689-3561 (Telephone Number)

History must be complete in all detail. Use this form to report all operations during drilling and testing of the well or during redrilling or altering the casing, plugging, or abandonment with the dates thereof. Include such items as hole size, formation test details, amounts of cement used, top and bottom of plugs, perforation details, sidetracked junk, bailing tests and initial production data.

Date	
1979	GWO 98480 Program: Remove 2 3/8" safety system and 5" packer from 5" liner at 8,420'. Set a packer in the 7" casing near 8,040' and install an Otis 2 7/8" annular flow safety system. Return the well to gas storage service.
3-5	0 Day. Killed well with 350 barrels of 63# brine-polymer completion fluid
3-6	1st Day. Moved California Production Service Co. rig #D-4 onto wellsite and rigged up. Mixed a total of 260 barrels of polymer completion fluid and obtained full circulation. Removed xmas tree and installed BOPE.
3-7	2nd Day. Tested BOPE, blind rams, 2 7/8" pipe rams and choke manifold to 3,000 psi, Hydril "GK" to 2,000 psi with water and nitrogen. Released from 5" Otis "Permatrieve" packer at 8,420'. Circulated gas cut mud from well. Pulled out of hole measuring tubing. Ran in with Otis retrieving tool and released packer. Pulling out of well.
3-8	3rd Day. Recovered 5" Otis "Permatrieve" packer from 8,420'. Ran in well with 7" casing scraper and cleaned out to 8,075'. Pulled out and ran in well with 5" casing scraper and cleaned out to 9,071'. Pulling out of well.
3-9	4th Day. Finished pulling out of well. Ran 7" Otis "Permatrieve" packer and set at 8,040'. Ran in well with Otis Latch-in Locator and 2 seals, changing tubing collars. Latched into packer and pulled 30,000# to check latch. Set 10,000# on packer and tested annulus to 1,500 psi. Pulling out of well.
3-10	5th Day. Finished pulling out of well. Ran Otis annular flow safety system. Hydrotested tubing to 5,000 psi. Landed tubing on packer at 8,040' with 10,000#. Pulled up 30,000# over weight of string to check packer and latch. String weight 53,000# on hook. Removed BOPE. Installed xmas tree and tested to 5,000 psi. Displaced brine-polymer completion fluid from well with 350 barrels of waste lease water. Released rig at 10:00 p.m., 3-10-79.

AC_CPUC_0118314

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION

DIVISION OF OIL AND GAS

History of Oil or Gas Well

Operator Southern California Gas Company Field or County Aliso Canyon
Well name and No. STANDARD SESNON #29, Sec. 28, T 3N, R 16W, S.B.B. & M.
A.P.I. well No. 037-00041 Name P. S. Magruder, Jr. (Person submitting report) Title Agent (President, Secretary or Agent)
Date September 24, 19 77

Signature P S Magruder Jr.

P.O. Box 3249 Terminal Annex, Los Angeles, Ca., 90051 (Address) (213) 689-3561 (Telephone Number)

History must be complete in all detail. Use this form to report all operations during drilling and testing of the well or during redrilling or altering the casing, plugging, or abandonment with the dates thereof. Include such items as hole size, formation test details, amounts of cement used, top and bottom of plugs, perforation details, sidetracked junk, bailing tests and initial production data.

Date	
8-27-77	Moved California Production Service Rig #M 28 from Standard Sesnon #24 location. Circulated hole volume to work gas out of drilling fluid.
8-28-77	Rig and crew idle.
8-29-77	Installed plug in doughnut; removed tree; installed 8" Class III B.O.P.E. and tested with water and nitrogen as follows: Hydril 3000 psi 20 minutes - O.K. Pipe Rams 4000 psi 20 minutes - O.K. Blind Rams " " " " - O.K.
8-30-77	Released Camco hydrostatic packer and Baker locator seal assembly. Pulled out of well tallying tubing. Started back into well. Took gas kick. Killed well. Made up Baker milling tool on Baker junk basket, Bowen hydraulic jars and three 20' 2 3/8" drill collars. Ran tubing to top of liner. NOTE: There was 40' of fine sand inside the tubing string above tubing plug at base of S4 sand.
8-31-77	Milled over and recovered Baker 5" Model "D" packer. Mde up Robison 7" casing scraper and 6 1/8" bit and ran to 8075'. Started out of hole.
9-1-77	Pulled 7" casing scraper and 6 1/8" bit out of well. Ran 5" scraper and 4 1/8" bit to 9072'. (Cleaned out hard asphalt foundation from 9026' -9072'). Started out of well with 4 1/8" bit and scraper. Power tongs broke down - ordered set from H. & H. Started out of well again and their power tongs failed.
9-2-77	Finished pulling 4 1/8" bit and 5" scraper out of well. Ran Johnston 5" Retrievable bridge plug and set at 8425'. Pressured plug and pumped fluid away under 1450 psi. Pulled Retrieving tool. Ran Johnston 5" 18# Bob Cat packer to 8375'. Set and pressured 5" bridge plug to 1500 psi 10 minutes; held O.K.

AC_CPUC_0118315

9-3-77 Pressure tested annulus...(retainer at 8425') to 2500 psi - held O.K. Released retrievable retainer and pressured casing to 2500 psi - held O.K. Displaced polymer mud from well with fresh water treated with surface tension agent. Pulled 5" retrievable retainer out of well - ran 7" retainer to 3800' and pressure tested as follows:

3800'	to	8425'	at 2500 psi	for 60	minutes
3800'	"	Surface	" 2700 psi	" 60	"
3300'	"	"	" 2900 psi	" 60	"
2900'	"	"	" 3100 psi	" 60	"

All above tests O.K.

9-4-77 Rig and crew idle.

9-5-77 (Holiday) Rig and crew idle.

9-6-77 Continued pressure testing casing, as follows:

2500'	to	Surface	with 3300 psi	for 60	minutes
2000'	"	"	" 3700 psi	" 60	"
1100'	"	"	" 4000 psi	" 60	"

Above tests O.K.
Pulled out of well with 7" retainer. Ran tubing in hole to retrieve 5" 18# bridge plug.

9-7-77 Retrieved Johnston 5" 18# retrievable bridge plug. Changed out tubing collars and Baker sealed tubing pins. Using GO-International, set Otis 5" Permatrieve wireline packer at 8415'.

9-8-77 Made up Otis seal assembly; 2 3/8" x 10' blast joint; 2 3/8" x 1.56" NO-GO nipple; 2 3/8" x 20' blast joint; Otis annular flow safety system and tested to 5000 psi. Ran tubing to 8415' hydrotesting to 5000 psi and latched into Otis packer. Pulled 25,000# over tubing weight on packer (67,000# gross weight) and landed with 7000# set-down weight on packer. Installed back-pressure valve in doughnut. Removed B.O.P.E. and installed Christmas tree.

9-9-77 Tested Xmas tree to 5000 psi. Displaced polymer drilling fluid with lease salt water. Set Otis 1.56" blanking plug in "NO-GO" nipple at 9405'. Pressure tested packer and seals under 2000 psi. (Held O.K.). Released rig.

GCA/nd

AC_CPUC_0118316

FORM 103

SUBMIT IN DUPLICATE

Δ OSP

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION

DIVISION OF OIL AND GAS

History of Oil or Gas Well

OPERATOR Pacific Lighting Service Company FIELD Aliso Canyon

Well No. SS-29, Sec. 28, T. 3N, R. 16W, S.B. B. & M.


Date ____, 19____ Signed ____

P. O. Box 54790, Terminal Annex
Los Angeles, California 90054 (213) 689-3561 Title Agent
(Address) (Telephone Number) (President, Secretary or Agent)

It is of the greatest importance to have a complete history of the well. Use this form to report a full account of all important operations during the drilling and testing of the well or during re-drilling, altering of casing, plugging, or abandonment with the dates thereof. Be sure to include such items as hole size, formation test details, amounts of cement used, top and bottom of plugs, perforation details, sidetracked junk, bailing tests, shooting and initial production data.

Date	
1973	The following is for the well file only. It does not have to be submitted to the Division of Oil & Gas.
7-31	PROGRAM: (1) Pull tubing and remove 1/4" control line and tubing safety valve. (2) Install nipples for wireline safety valve. (3) Install slotted tubing for sand control.
7-31	Pulled Camco "CA" blanking plug from 8520' and confirmed that sleeves at 8348' and 8488' were open in order to kill well. Moved in California Production Service rig with pump and shaker tank at 2:00 PM and began rigging up.
8-1	Killed and circulated well with 332 barrels brine-polymer workover fluid. Installed and tested Class III B.O.P.E. Pulled 8000' tubing and 1/4" control line.
8-2	Filled hole with 8 barrels. Completed pulling tubing. Lost 12 1/2" x 16" steel banding clamps and top rubber off Camco HRP-1-SP 5" packer. Laid down Camco packer and Page safety valve. Ran 2-1/4" O.D. sawtooth collar and 665' of 1-1/4" Hydrill drill rod on 2-7/8" tubing. Sat down on Model "D" packer at 8520' tubing measurements but rotated through OK. Hit top of fill at 9035'.
8-3	Circulated out soft fill of mud and a small amount of sand from 9035 to bottom at 9077'. Pulled tubing and laid down 665' of 1-1/4" drill rod. Made up and ran completion tubing to 6000' then shut down for the week-end.
8-4&5	Idle.
8-6	Completed running tubing. Hung tubing above packer at 8518' and circulated out mud with salt water, using 310 barrels. Landed tubing with 4000 pounds on Model "D" packer at 8518'. Ran Camco type "CA" 2-3/8" blanking plug and set in Camco "D" nipple at 8517' to isolate S-8 zone. Ran Otis type "X" 2-3/8" plug and set in Otis "X" nipple at 8455'. Pressured tubing to 3500 psi with hot oil truck


AC_CPUC_0118317



WELL VOLUME	Cu.Ft.	Bbl.
Tubing	262	47
Csg/Lnr.	105	19
Annulus	1405	250

AC_CPUC_0118318

WELL PROFILE



Southern California Gas Co.
OPERATOR

WELL S.S. #29

FIELD Aliso Canyon

COUNTY Los Angeles

STATE California

DATE March 13, 1979

☐ NEW COMPLETION ☐ WORKOVER

	CASING	LINER	TUBING 1	TUBING 2	TUBING 3
SIZE					
WEIGHT					
GRADE					
THREAD					
DEPTH					

ITEM NO.	TUBING DETAILS	LENGTH	DEPTH
1.	Kelly Bushing	6.92	-
2.	Tubing Hanger	.30	6.92
3.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	1.18	7.72
4.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	3.15	8.90
5.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	10.25	12.05
6.	16 joints 2 7/8" 6.5# N-80 8rd EUE	500.84	22.30
7.	243 Joints 2 7/8" 6.5# J-55 8rd EUE	7473.19	523.14
8.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	4.09	7996.33
9.	Otis "X" nipple 2.350" I.D.	1.13	8000.42
10.	Otis Annular Flow Safety System 4.88" O.D., 2.313" I.D.	7.66	8001.55
11.	Otis blast joint with 4 centralizers 5.50" O.D., 2.375" I.D.	19.82	8009.21
12.	Otis "XN" No-Go Nipple 2.205" I.D.	1.17	8029.03
13.	Otis Blast Joint 3.668" O.D. 2.375" I.D.	9.80	8030.20
14.	Otis "J" latch locator	1.16	8040.00
15.	Otis "Permatrieve" 7" packer (new) (20-26#) 5.87" O.D. 3.25" I.D.	4.16	8040.00
16.	Otis seal assembly (4) 3.29" O.D., 2.38" I.D.	4.05	8041.16
17.	Otis Production Tube	2.96	8045.21
18	Otis Guide Shoe	.42	8048.17
	End of Tubing		8048.59

NOTES

Side door choke in safety system

Tubing landed with 10,000X compression on packer

Corrected tubing measurments (7,482.13) to meet wireline measurments.

COMMENTS:

AC_CPUC_0118319

8-6-73

TUBING DETAIL

No. Jts.	Item	Length	Depth
	Below K. B.	6.90	
	2-7/8" donut and pup joint	6.00	
	2-7/8" EU 8 thd. pup jt.	3.95	
184	2-7/8" EU 8 thd. J-55 tubing	5668.65	
	2-7/8" EU 8 thd. pup jt.	4.05	5689.55
	2-1/2" Camco KBMG mandrel w/1/4" BK 925# valve	7.35	5696.90
40	2-7/8" EU 8 thd. J-55	1224.08	
	2-7/8" EU 8 thd. pup jt.	4.03	6925.01
	2-1/2" Camco KBMG mandrel w/1/4" BK 915# valve	7.35	6932.36
34	2-7/8" EU 8 thd. J-55 tubing	1041.10	
	2-7/8" EU 8 thd. pup jt.	4.08	7977.54
	2-1/2" Camco KBMG mandrel w/1/4" BK 905# valve	7.35	7984.89
1	2-7/8" EU 8 thd. J-55 tubing	31.37	
	2-7/8" x 2.313" Otis "X" landing nipple	1.00	8017.26
1	2-7/8" EU 8 thd. J-55 tubing	30.23	
	2-7/8" x 2-3/8" EU 8 thd. crossover	1.15	8048.64
9	2-3/8" EU 8 thd. J-55 tubing	273.63	
	2-3/8" Camco B mandrel w/1/4" J-40 895# valve	4.10	8326.37
1	2-3/8" EU 8 thd. J-55 tubing	30.15	
	2-3/8" x 1.93 Camco sliding sleeve	2.70	8359.22
1	2-3/8" EU 8 thd. J-55 tubing	29.97	
	2-3/8" x 1.875 Otis "X" landing nipple	.95	8390.14
1	2-3/8" EU 8 thd. J-55 tubing	29.98	
	2-3/8" x 5" 18# Camco Hydrostatic set packer HRP-1 16 turns right to release	5.65	
1	2-3/8" EU 8 thd. J-55 tubing	29.73	
	2-3/8" x 1.875 Otis "X" landing nipple	.95	8456.45
	2-3/8" EU 8 thd. pup jt. w/20 mesh slots	10.00	8466.45
	2-3/8" EU 8 thd. pup jt. w/20 mesh slots	10.00	8476.45
	2-3/8" Otis polish nipple	1.50	8477.95
	2-3/8" EU 8 thd. pup jt.	4.20	
	2-3/8" x 1.875 Otis "X" landing nipple	.95	8483.10
	2-3/8" EU 8 thd. pup jt. w/20 mesh slots	10.20	8493.30
	2-3/8" EU 8 thd. pup jt. w/20 mesh slots	10.00	8503.30
	2-3/8" Otis polish nipple	1.50	8504.80
	2-3/8" EU 8 thd. pup jt.	4.05	
	2-3/8" EU 8 thd. pup jt.	8.00	
	2-3/8" x 1.81 Camco type "D" seating nipple	.95	8517.80
	2-3/8" Baker locator sub for Model "D" packer @ 8517'	.40	8518.20
	Baker seals 5 sets for Model "D" packer	4.60	8522.22

NOTE: The slotted tubing above is J-55 with special clearance N-80 collars slotted 20M, 12 rows, 1-1/2" slots on 6" centers.

AC_CPUC_0118320

TEL NO. Sep 11,91 8:10 P.15

FORM 109-A (10-48)

STATE OF CALIFORNIA
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL AND GAS

SEP 30 1953
LOS NIETOS

Report on Test of Water Shut-off
(FORMATION TESTER)

No. T 153-1158

Los Angeles 15, Calif. September 29, 1953

Mr F C Foster
Box Y
Los Nietos, Calif.
Agent for TIDE WATER ASSOCIATED OIL CO

DEAR SIR:

Your well No. Standard-Vesnon 1-A 29, Sec. 28, T 3 N, R 16 W, S B B & M.
Aliso Canyon Field, in Los Angeles County, was tested for water shut-off on September 22, 1953. Mr. O. J. Horkovich, Inspector, designated by the supervisor, was present as prescribed in Secs. 3222 and 3223, Ch. 93, Stat. 1939; there were also present J. Poyner, Engineer; H. N. Frantz, Drilling Foreman.

Shut-off data: 5 in. 18 lb. casing was cemented through perforations at 8731 ft. on September 18, 1953 in 6 in. hole with 100 sacks of cement XXXXX of which 30 sacks was left in casing.

Casing record of well: 11-3/4" cem. 1042'; 7" cem. 8180', W.S.O.; 5" ld. 9083', top at 8681', C.P. 8731', perf. 8731'-9083', four 1/2" holes 8710', W.S.O. Plugged with cement 9450'-9455' and 9200'-9094'.

Present depth 9790 ft. / Bridged with cement from 8731 ft. to 8720 ft. Cleaned out to 8720 ft. for test.
A pressure of XXX lb. was applied to the inside of casing for XXX min. without loss after cleaning out to XXX ft.
A Johnston gun and tester was run into the hole on 2-7/8 & 2- in. drill pipe-tubing, with 750 ft. of water-XXX cushion, and packer set at 8668 ft. with tailpiece to 8725 ft.
Tester valve, with 3/8 in. bean, was opened at 1120 a.m. and remained open for 1 hr. and XXX min. During this interval there was a medium steady blow for 45 min., no blow for 5 min., then a faint blow for 10 min.

THE INSPECTOR ARRIVED AT THE WELL AT 8150 A.M. AND MR. POYNER REPORTED:

1. A 6" rotary hole was drilled from 8185' to 9790'.
2. On September 16, 1953, 35 sacks of cement was pumped into the hole through 2-7/8" drill pipe hanging at 9650', filling to 9455'.
3. On September 16, 1953, 35 sacks of cement was pumped into the hole through 2-7/8" drill pipe hanging at 9200', filling to 9094'.
4. The 5" casing was cemented as noted above.
5. A Johnston tester was run into the hole and the test indicated that no fluid has access to the well between the 7" and 5" casings.
6. Cement was drilled out of the 5" casing from 8355' to 8720' (equivalent to 23 sacks), and the hole was cleaned out to 8720'.
7. The 5" casing was shot-perforated with four 1/2" holes at 8710'.

THE INSPECTOR REPORTED:

1. When the drill pipe was removed, 1729' net rise consisting of 1000' of gas-cut, thin drilling fluid, grading to 729' of oil, was found in the drill pipe above the tester.
2. The recording pressure bomb chart showed that the tester valve was open 1 hr.

The test was completed at 7105 a.m.

THE 5" SHUT-OFF AT 8710' IS APPROVED.

DIVISION

cc T L Park
Jos Jensen
J R Poyner (2)

R. D. BUSH, State Oil and Gas Supervisor

By [signature], Deputy

AC_CPUC_0118321

SOUTHERN CALIFORNIA gas COMPANY

INTEROFFICE CORRESPONDENCE

TO R. D. Phillips
J. B. Lane

FROM P. D. Yu

DATE July 19, 1991

SUBJECT Workover Recommendation for SS 29 at Aliso Canyon

We recommend that SS 29 be worked over. The proposed work is to repair the shoe leak and reperforate the Sesnon, HZ and Upper Frew zones. Our analysis indicates that all these zones are gas productive.

Temperature, noise and tracer surveys demonstrate that this well has a shoe leak. A shoe leak investigation history is summarized in Appendix I. Reperforating will increase gas deliverability. To evaluate the current status of the producing zones, a spinner survey (spinner, temperature and capacitance) was run on 7/25/90. It was discovered that most of the gas was flowing from a 9' interval (8456' to 8465' ELM) in the S-6. The capacitance tool detected no liquid level in the wellbore.

Based on an examination of recent sand test data, this well is capable of producing approximately 40 MMCF/D at 35 Bcf inventory and approximately 20 MMCF/D at 10 Bcf inventory. After reperforating, it is estimated that it will produce at least 55 MMCF/D at 35 Bcf inventory and at least 30 MMCF/D at 10 Bcf inventory.

WORKOVER RECOMMENDATIONS

In conjunction with standard operating practices employed in the Drilling Department, the following items are emphasized and recommended.

1) In the process of killing the well, spearhead the kill fluid with 0.5% PQA for clay stabilization.

2) Pull the 2-7/8" tubing string.

3) Clean out wellbore to PBTD of 9077' MD.

4) Make a bit and casing scrapper run. Run a casing inspection log in the 7" casing from 8075' MD to the surface.

5) Cut the 5" liner at approximately 8160' MD. After perforating the 7" casing, repair the shoe leak by squeeze cementing. Pressure test the casing. Dress off top of liner. Run in with lead seal drive-over adapter.

6) Prior to zone perforating, filter the completion fluid in order to maximize well productivity. Utilize a plate and frame diatomaceous earth (DE) filter and a 2-micron nominal cartridge filter in series.

AC_CPUC_0118322

7) Perforate the following intervals underbalanced at 8 SPF with tubing conveyed guns. Surge the perforations.

S-4:	8428' - 8436'	ELM
S-6:	8454' - 8502'	ELM
S-8:	8522' - 8560'	ELM
	8602' - 8636'	ELM
	8660' - 8668'	ELM
HZ:	8674' - 8694'	ELM
FREW:	8727' - 8737'	ELM
	8750' - 8760'	ELM
	8810' - 8820'	ELM

8) Rerun the 2-7/8" tubing string. Equip the tubing string with a No-Go nipple, sliding sleeve and gas lift mandrel equipped with pump-out plug.

If you have any questions, please advise.

Original Request Submitted by: Steve Robinson

Prepared by: R. L. Adamczyk
R. L. Adamczyk

Reviewed by: M. E. Melton
M. E. Melton

RLA:bb
Attachments
(WOSSREV)

cc: R. L. Adamczyk
M. E. Melton
R. L. Patterson
R. W. Weibel

APPENDIX I

SS 29 Shoe Leak Investigation History

In his memo dated 11/14/89, Steve Robinson recommended a shoe leak repair for this well. In his memo dated 11/29/89, Richard Adamczyk concurred with the shoe leak repair since temperature, noise and tracer surveys demonstrated that the well had a shoe leak.

In September of 1990, it was decided to defer the SS 29 workover after an 8/30/90 noise log indicated that the suspected leak did not warrant remedial action at that time. Plans were made to closely monitor the well over the next year.

The temperature survey run on 10/11/90 (Inventory = 48.5 Bcf) shows a temperature break at 8350' MD. The noise/temperature survey run on 12/5/90 (Inventory = 56.0 Bcf) shows a temperature break at 8150' MD (or 30' above the 7" casing shoe) and very high noise levels in the vicinity of the shoe. These two surveys are attached.

The magnitude of leakage is further emphasized by Thermo's concern that their nearby well, DA 2, was starting to produce an increased amount of gas. And helium counts increased to 49 PPM in October, 1990 from 2 PPM in May, 1990. Historically the helium in DA 2 has fluctuated with inventory, but the October level of 49 PPM is twice as high as it has ever been at previous high inventories. It appears that work on this well should not be further delayed.

AC_CPUC_0118324

ALISO CANYON

SS 29

3.

SS-29 Orig. TD

TCP 0

0

1

2

3

4

5

6

7

8

9

1000

2000

3000

4000

5000

6000

7000

8000

9000

16 1512

cooling: 4500'-6000'

No. Temp. break @ Shoe


11/10/89: RA tag movement to MP ± ↑

11/11/89: noise in zone @ shoe. CONTINUE TO MONITOR.

Will N.L./inTracer @ '90 Hi-INV. to Verify S.L.


AC_CPUC_0118325

(4.)



SS 29
NOISE / TEMP.
SURVEY
12/5/90
INV. = 56.0 BCF

(5.)



SS 29
SPINNER
SURVEY
7/25/90
INV. = 44.3 BCF
RATE =
15 MMCF/D

SOUTHERN CALIFORNIA gas COMPANY

INTEROFFICE CORRESPONDENCE

TO N. W. Buss
M. E. Melton

FROM S. P. Robinson

DATE 11/14/89

SUBJECT Shoe Leak Repair for SS-29 - Aliso Canyon

Repair the shut-off leak on SS-29 and plug back the HZ and Frew intervals.

The radioactive tracer survey run on 11/10/89 verified the shoe leak that the 11/87 and 10/89 noise logs showed. Gas is moving up past the top of the Sesnon zone to the MP sand and above (See Figure 1).

While working on SS-29, we should take advantage of an opportunity to improve the well low inventory deliverability. We can do this by plugging back the HZ and Frew intervals. Fluids from these intervals load up the well at low inventories.


Include the following in the rework:

- Cement squeeze to shut off the leak between the sesnon and MP.
- Plug back the well at the base of the Sesnon (approximately 8695').
- Run a casing inspection log to 8075'.
- Complete the well with Otis 2.205 XN, 2-7/8 XD SSD, 2-7/8 GLM
- Rebuild the master valve and casing wing valves.


The Division pre and post rig cost should be $10,000 ($2000 labor; $3000 non-labor; $5000 contract).

SPR:db


cc: N. D. Stevenson




AC_CPUC_0118329



AC_CPUC_0118330



AC_CPUC_0118331



AC_CPUC_0118332

Southern California Gas Company
Cost Estimating Sheet

WELLNAME: SS 29
MWO Account Number:99412 GWO Account Number:
Begin Date: 09/10/91 End Date: 10/05/91 PPP#:
Job Category: SL Shoe leak repair

Date: 07/24/91
Field:ALISO CANYON
Rig Code: CPS D-7

Pr St	M/ G	FI	WC	Description of Expenditure	Rig Hrs	Serv. Contr	Purch Mater	Store Mater	Co Labor	Sub-total	Total Cost
1	M	01	PR	Pre-rig work, well kill	0	0	11000	0	0	11000	
	M	49		Tank rental,misc. rental.		4000	0	0	0	4000	15000
2	M	01	RM	RIG MOVE	12	4800	0	0	0	4800	
	M	44		Trucking,hauling		5000	0	0	0	5000	
	M	45		Cranes		5000	0	0	0	5000	14800
3	M	01	MI	Rig up, install & test BOPE	24	9600	0	0	0	9600	
	M	04		BOPE svcs,API rings		1000	0	0	0	1000	
	M	12		Wellhead equip. & svcs.		1000	0	0	0	1000	
	M	44		Trucking,hauling		2500	0	0	0	2500	
	M	45		Cranes		2500	0	0	0	2500	16600
4	M	01	PT	Recover tubing	24	9600	0	0	0	9600	
	M	31		Fishing tools & svcs.		10000	0	0	0	10000	19600
5	M	01	LT	Lay down tubing	12	4800	0	0	0	4800	4800
6	M	01	PD	Pick up drillpipe	12	4800	0	0	0	4800	4800
7	M	01	Pk	Retrieve packer	36	14400	0	0	0	14400	
	M	31		Fishing tools & svcs.		10000	0	0	0	10000	
	M	77		Mill		5000	0	0	0	5000	
	M	41		Other Wireline svcs.		2000	0	0	0	2000	31400
8	M	01	CS	Scrape csg/clean out	12	4800	0	0	0	4800	
	M	20		Bits		1500	0	0	0	1500	
	M	69		SCRAPER		2000	0	0	0	2000	
	M	24		Filtering and solids control		4000	0	0	0	4000	
	M	44		Trucking,hauling		2500	0	0	0	2500	14800
9	M	01	LL	Log well	12	4800	0	0	0	4800	
	M	16		Run logs(vertilog,caliper,etc)		9500	0	0	0	9500	14300
10	M	01	Pf	Re/Perforation	12	4800	0	0	0	4800	
	M	30		Service tools		30000	0	0	0	30000	34800
11	M	01	LR	LEAK REPEAR CMT. SQZ. CASING	42	16800	0	0	0	16800	
	M	11		Tubing accessories,packers		10000	0	0	0	10000	
	M	22		Cement,acid,sand,chemicals		22000	0	0	0	22000	
	M	47		Pumping svcs		12000	0	0	0	12000	
	M	41		Other Wireline svcs.		3000	0	0	0	3000	63800
12	M	01	CO	Initial/final clean out	24	9600	0	0	0	9600	
	M	20		Bits		1500	0	0	0	1500	
	M	06		Pressure test		1500	0	0	0	1500	
	M	09		Install Lead Seal		4500	0	0	0	4500	17100
13	M	01	IP	INSTALL PACKER	12	4800	0	0	0	4800	
	M	78		Prod. Packer		0	8000	0	0	8000	
	M	06		Pressure test		1500	0	0	0	1500	
	M	41		Other Wireline svcs.		3500	0	0	0	3500	17800
14	M	01	TP	Run tbg. & prod. equip.	12	4800	0	0	0	4800	
	M	10		Tubular goods		0	5000	0	0	5000	
	M	52		hydrotest		550	0	0	0	550	

Southern California Gas Company
Cost Estimating Sheet

WELLNAME: SS 29 Date: 07/24/91
MWO Account Number:99412 GWO Account Number: Field:ALISO CANYON
Begin Date: 09/10/91 End Date: 10/05/91 PPP#: Rig Code: CPS D-7
Job Category: SL Shoe leak repair

Pr St	M/ G	FI	WC	Description of Expenditure		Rig Hrs	Serv. Contr	Purch Mater	Store Mater	Co Labor	Sub-total	Total Cost
	M	44		Trucking,hauling			1500	0	0	0	1500	11850
15	M	01	WW	Wellhead work		12	4800	0	0	0	4800	
	M	12		Wellhead equip. & svcs.			1500	0	0	0	1500	
	M	51		Xmas tree scvs			1500	0	0	0	1500	7800
16	M	01	MO	Rig down-move out		6	2400	0	0	0	2400	2400
				MWO Cost Estimate =>		264	267650	24000	0	0	291650	
				GWO Cost Estimate =>		0	0	0	0	0		0
				Total Estimate =>	291650	264	267650	24000	0	0	291650	0
				20% Contingency	53530	53	53530					
				Division Pre/Post-Rig	15000		9000	2500	0	3500		
				GRAND TOTALS =>	360180	317	330180	26500	0	3500		
				Estimate days =>		26						

PRE/POST WELLSITE REVIEW

WELL: _____ FIELD: _____ RIG: _____

I PRE RIG WALKTHROUGH

A. SURFACE AREA:

B. WELL CELLAR:

C. WELLHEAD:

D. WELLHEAD MODIFICATIONS:

DATE: _____ DRILLING DEPARTMENT: _____ STATION SUPERVISOR: _____ RESIDENT ENGINEER: _____

II POST RIG WALKTHROUGH

DATE RIG MOVED OFF WELL: _____

A. SURFACE AREA:

B. WELL CELLAR:

C. WELLHEAD:

WELL RELEASED TO STATION: YES ____ NO ____ DATE: _____

DRILLING DEPARTMENT: _____ STATION SUPERVISOR: _____ RESIDENT ENGINEER: _____

AC_CPUC_0118335

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION
DIVISION OF OIL AND GAS

Notice of Intention to Rework Well

This notice and indemnity or cash bond shall be filed, and approval given, before rework begins. If operations have not commenced within one year of receipt of the notice, this notice will be considered cancelled.

FOR DIVISION USE ONLY		
BOND	FORMS	
	OGD 114	OGD 121

DIVISION OF OIL AND GAS

In compliance with Section 3203, Division 3, Public Resources Code, notice is hereby given that it is our intention to rework well Standard Sesnon #29 (Well designation), API No. 037-00041

Sec. 29, T. 35, R. 16W, S.B. B. & M., Aliso Canyon Field, Los Angeles County.

The present condition of the well is as follows:

1. Total depth 9790', plug at 9094'.

2. Complete casing record, including plugs and perforations (present hole)

0'-1042'	11-3/4"	Cemented 1042'
0'-8180'	7"	Cemented 8180' WSO at shoe
8075'-9077'	5"	Landed 9077' top 8075' cemented 8725', Slotted 120 mesh, 9077'-8727' Squeezed 8700'-8705' (WSO). Perforation Intervals: 8456'-8502', 8528'-8552', 8602'-8638', 8658'-8668', 8674'-8694'

3. Present producing zone name Sesnon ; Zone in which well is to be recompleted _____

4. Present zone pressure 3450 psig ; New zone pressure _____

5. Last produced Gas Storage Operation (Date) _____ (Oil, B/D) _____ (Water, B/D) _____ (Gas, Mcf/D)

(or)

Last injected Gas Storage Operation (Date) _____ (Water, B/D) _____ (Gas, Mcf/D) _____ (Surface pressure, psig)

6. Is this a critical well according to the definition on the reverse side of this form? ☐ (Yes) ☒ (No)

The proposed work is as follows:

1. Move in, rig up, kill well and, install and pressure test BOPE.
2. Pull and lay down 2-7/8" tubing.
3. Retrieve 7" packer.
4. Clean out well and run casing inspection log.
5. Perforate intervals: 8428'-8436', 8454'-8502', 8522'-8560', 8602'-8636', 8660'-8668', 8674'-8694', 8727'-8737', 8750'-8760', 8810'-8820'.
6. Shoot holes and cement squeeze casing shoe leak.
7. Flow and noise log well.

Note: If well is to be redrilled, show proposed new bottom-hole coordinates and true vertical depth.

It is understood that if changes in this plan become necessary, we are to notify you immediately.

Address P. O. Box 3249, Terminal Annex (Street)

Los Angeles, California 90051 (City) (State) (Zip)

Telephone Number (213) 689-3925

Southern California Gas Company (Name of Operator)

By J. B. Lane for R. D. Phillips (Agent) (Name-Printed)

J. B. Lane 11 SEP 91 (Name-Signature) (Date)

Type of Organization Corporation (Corporation, Partnership, Individual, etc.)

OG107 (2/86/DWRR/5M)

AC_CPUC_0118336

NOTICE OF INTENTION TO REWORK WELL
DIVISION OF OIL AND GAS
Supplemental page
Well Name: Standard Sesnon #29
API. NO.: 037-00041

The proposed work is as follows (con'd):

8. Install 7" packer.
9. Install 2-7/8" tubing, remove BOPE and install wellhead.
10. Return well to service.

AC_CPUC_0118337

FORM 100-A (10-48)

STATE OF CALIFORNIA
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL AND GAS

SEP 30 1953
LOS NIETOS

Report on Test of Water Shut-off
(FORMATION TESTER)

No. T 153-1158

Los Angeles 15, Calif. September 29, 1953

Mr P C Foster
xxx Box X
Los Nietos, Calif.
Agent for TIDE WATER ASSOCIATED OIL CO

DEAR SIR:

Your well No. "Standard-Seaboard 1" 29, Sec. 28, T 2 S, R 16 W, S B B & M.
Aliso Canyon Field, in Los Angeles County, was tested for water shut-off on September 22, 1953. Mr. O. J. Markovich, Inspector, designated by the supervisor, was present as prescribed in Secs. 3222 and 3223, Ch. 93, Stat. 1939; there were also present J. Poyer, Engineer; R. N. Frantz, Drilling Foreman.

Shut-off data: 5 in. 18 lb. casing was cemented through perforations at 8731 ft. on September 18, 1953 in 6 in. hole with 100 sacks of cement xxxxx of which 30 sacks was left in casing.

Casing record of well: 11-3/4" cem. 1042'; 7" cem. 8180', W.S.O.; 5" ld. 9063', top at 8081', O.D. 8731', perf. 8731'-9063', four 1/2" holes 8710', W.S.O. Plugged with cement 9450'-9455' and 9200'-9004'.

Present depth 9790 ft. / Bridged with cement from 8731 ft. to 8720 ft. Cleaned out to 8720 ft. for test.
A pressure of xxx lb. was applied to the inside of casing for xxx min. without loss after cleaning out to xxx ft.
A Johnston gun and tester was run into the hole on 2-7/8 & 2-3/8 in. drill pipe-tubing, xxxxx with 750 ft. of water-xxx cushion, and packer set at 8668 ft. with tailpiece to 8720 ft.
Tester valve, with 3/8 in. bean, was opened at 1120 a.m. and remained open for 1 hr. and xxx min. During this interval there was a medium steady blow for 45 min., no blow for 5 min., then a faint blow for 10 min.

THE INSPECTOR ARRIVED AT THE WELL AT 0130 A.M. AND MR. POYER REPORTED:

1. A 6" rotary hole was drilled from 8185' to 9790'.
2. On September 16, 1953, 35 sacks of cement was pumped into the hole through 2-7/8" drill pipe hanging at 9550', filling to 9455'.
3. On September 16, 1953, 35 sacks of cement was pumped into the hole through 2-7/8" drill pipe hanging at 9200', filling to 9004'.
4. The 5" casing was cemented as noted above.
5. A Johnston tester was run into the hole and the test indicated that no fluid has access to the well between the 7" and 5" casings.
6. Cement was drilled out of the 5" casing from 8355' to 8720' (equivalent to 23 sacks), and the hole was cleaned out to 8720'.
7. The 5" casing was shot-perforated with four 1/2" holes at 8710'.

THE INSPECTOR REPORTED:

1. When the drill pipe was removed, 1729' net rise consisting of 1000' of mud-cut, thin drilling fluid, grading to 729' of oil, was found in the drill pipe above the tester.
2. The recording pressure bomb chart showed that the tester valve was open 1 hr.

The test was completed at 7105 a.m.

THE 5" SHUT-OFF AT 8710' IS APPROVED.

DIVISION

cc T L Park
Jos Jensen
J R Poyer (2)

R. D. BUSH, State Oil and Gas Supervisor
By O. J. Markovich, Deputy

AC_CPUC_0118338

Recld 8-31-77
GSD

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION

DIVISION OF OIL AND GAS

Notice of Intention to Rework Well

This notice and indemnity or cash bond shall be filed, and approval given, before rework begins. If operations have not commenced within one year of receipt of the notice, this notice will be considered cancelled.

FOR DIVISION USE ONLY		
BOND		
	OGD114	OGD121

DIVISION OF OIL AND GAS

In compliance with Section 3203, Division 3, Public Resources Code, notice is hereby given that it is our intention to rework well No. STANDARD SESNON #29, API No. -,

Sec. 29, T. 3S, R. 16W, S.B. B. & M., Aliso Canyon Field, Los Angeles County.

The present condition of the well is as follows:

1. Total depth. 9790' - plug at 9094'

2. Complete casing record, including plugs and perforations:

11 3/4" cemented 1042'

7" cemented 8170', WSO on shoe

1002' 5" landed 9077', top 8075', cp'd 8725', WSO on lap
slotted 9077'-8727'
squeezed 8700' - WSO 8705'
perforated at intervals 8694'-8456'

3. Present producing zone name SESNON & FREW Zone in which well is to be recompleted -

4. Present zone pressure 3650 psi New zone pressure -

5. Last produced Gas Storage Well
(Date) (Oil, B/D) (Water, B/D) (Gas, Mcf/D)

or

6. Last injected
(Date) (Water, B/D) (Gas, Mcf) (Surface pressure, psig.)

The proposed work is as follows:

1. Move in and rig up. Kill well. Install B.O.P.E. and pressure test.
2. Pull tubing and packer. Mill over and recover packer.
3. Clean out to 9077'. Pressure test 5" and 7" casings.
4. Perform any remedial work indicated by pressure testing.
5. Ran packer. Run tubing with down-hole safety system.
6. Return well to gas storage service.

It is understood that if changes in this plan become necessary we are to notify you immediately.

Address P.O. Box 3249, Terminal Annex
(Street)
Los Angeles, California 90051
(City) (State) (Zip)
Telephone Number (213) 689-3561

SOUTHERN CALIFORNIA GAS COMPANY
(Name of Operator)
By P. S. Magruder Jr
(Name) P. S. Magruder, Jr. (Date) 8-25-77
Type of Organization Corporation
(Corporation, Partnership, Individual, etc.)

OG107 (8-75—GSRI—15M)

AC_CPUC_0118339

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION

DIVISION OF OIL AND GAS

Report on Operations

No. T 277-235

Mr. P. S. Magruder, Jr., Agent
So. Calif. Gas Co.
P.O. Box 54790 Terminal Annex
Los Angeles, Calif. 90024

Santa Paula, Calif.
Sept. 12, 1977

DEAR SIR:

Operations at well No. "SFZU" SS-29, API No. 037-00041, Sec. 28, T. 3N, R. 16W, S.B., B & M. Aliso Canyon Field, in Los Angeles County, were witnessed on 8/29/77. Mr. T. M. Callaway, representative of the supervisor was present from 1630 to 2100. There were also present E. Bradbury, engr.

Present condition of well: No additions to the casing record since proposal dated 1/19/73.

The operations were performed for the purpose of Testing the blowout prevention equipment and installation

DECISION:

THE BLOWOUT PREVENTION EQUIPMENT AND INSTALLATION ARE APPROVED.

b

M. G. MEFFERD
~~JOHN F. MATTHEWS, JR.~~
State Oil and Gas Supervisor

By John L Gordon Deputy

OG109 (2-75—OSP-20M)

30986-705 2-75 20M ① ◊ OSP

AC_CPUC_0118340

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION
DIVISION OF OIL AND GAS

No. P 277-320

REPORT ON PROPOSED OPERATIONS

Santa Paula, California

Mr. P. S. Magruder, Jr., Agent
So. Calif. Gas Co.
P.O. Box 54790 Terminal Annex
Los Angeles, Calif. 90024

Sept. 1, 1977

Your rework proposal to gas storage well "SFZU" SS-29 (Name and number)

, A.P.I. No. 037-00041, Section 28, T. 3N, R. 16W,

S.B. B. & M., Aliso Canyon field, Los Angeles County,

dated 8-25-77, received 8-31-77, has been examined in conjunction with records filed in this office.

THE PROPOSAL IS APPROVED PROVIDED THAT:

1. The drilling fluid used shall be of a quality and in sufficient quantity to control all subsurface conditions in order to prevent blowouts; and a reserve supply of this material shall be kept on hand to meet any emergency.
2. Blowout prevention equipment, at least of theDivision of Oil and Gas Class III,3M rating, shall be installed and maintained in operating condition at all times. The BOPE and choke system shall be tested under a pressure of at least 1500 psi.
3. THIS DIVISION SHALL BE NOTIFIED TO WITNESS A PRESSURE TEST OF THE BLOWOUT PREVENTION EQUIPMENT BEFORE COMMENCING DOWNHOLE OPERATIONS.

NOTE: A COPY OF THIS APPROVAL SHALL BE POSTED AT THE WELL SITE PRIOR TO COMMENCING OPERATIONS.

Blanket Bond
MD:b

3 copies - Blue
Pink - Gray
xc - Pink - Back
xc -

M. G. MEFFERD
State Oil and Gas Supervisor

By John L. Hardoin
Deputy Supervisor

John L. Hardoin

OG111 (11-76-GSR1-30M)

AC_CPUC_0118341

INTEROFFICE SOUTHERN CALIFORNIA gas COMPANY CORRESPONDENCE

TO Mr. L. K. Harrington FROM A. E. Russell DATE

SUBJECT Approval of MWO for Wellwork on Standard Sesnon #29 - Aliso Canyon

Attached for your approval is MWO No. 99412 for $361,000 to repair a casing shoe leak in well SS #29.

SS #29 is a withdrawal well in the Aliso Canyon Storage Field. The well recently developed a casing shoe leak thus creating a potential for gas to migrate outside the wellbore. The leak will have to be repaired to ensure well integrity and to prevent gas from migrating outside the wellbore.

If you agree with this proposal please approve the attached MWO.

Funds for this project are available in the 1991 Storage Operations Operating and Maintenance Plan.

JUL 26 1991

MISCELLANEOUS WORK ORDER

M.W.O. NO. 99412

DIVISION North Basin DEPT. Storage Operations ORG. CODE KZ DATE 7-24-91

THIS M.W.O., WHEN PROPERLY APPROVED, WILL AUTHORIZE A DIRECT EXPENDITURE OF $

To repair casing shoe leak in well SS #29.

REASON FOR REQUEST

To repair well casing leak and to ensure well integrity.

ESTIMATE OF DIRECT COST	AMOUNT
Labor	4,000 00
Non-Labor	27,000 00
Contract	330,000 00
TOTAL ESTIMATED DIRECT COSTS	361,000 00

%	ACCOUNT	AMOUNT
	352	
	108.11	
	108.14	

TO BE BILLED TO: (INCLUDE ADDRESS OF BILLEE)

PLANT ACCOUNTING APPROVAL:

REMARKS: The total cost includes $15,000 for Division pre/post well work.

REQUESTED BY:	PREPARED BY:	EXAMINED & APPROVED BY:		
J. B. Lane	E. S. S.	R. D. Phillips	J. F. Guy	R. L. Rudzik

MANAGEMENT APPROVALS L. K. Harrington L. M. Stewart A. E. Russell

AC_CPUC_0118343

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION
DIVISION OF OIL AND GAS

Notice of Intention to Rework Well

This notice and indemnity or cash bond shall be filed, and approval given, before rework begins. If operations have not commenced within one year of receipt of the notice, this notice will be considered cancelled.

FOR DIVISION USE ONLY		
BOND	FORMS	
	OGD 114	OGD 121

DIVISION OF OIL AND GAS

In compliance with Section 3203, Division 3, Public Resources Code, notice is hereby given that it is our intention

to rework well Standard Sesnon #29 (Well designation), API No. 037-00041

Sec. 29, T. 35, R. 16W, S.B. B. & M., Aliso Canyon Field, Los Angeles County.

The present condition of the well is as follows:

1. Total depth 9790', plug at 9094'.

2. Complete casing record, including plugs and perforations (present hole)

0'-1042'	11-3/4"	Cemented 1042'
0'-8180'	7"	Cemented 8180' WSO at shoe
8075'-9077'	5"	Landed 9077' top 8075' cemented 8725', Slotted 120 mesh, 9077'-8727' Squeezed 8700'-8705' (WSO). Perforation Intervals: 8456'-8502', 8528'-8552', 8602'-8638', 8658'-8668', 8674'-8694'

3. Present producing zone name Sesnon ; Zone in which well is to be recompleted _____

4. Present zone pressure 3450 psig ; New zone pressure _____

5. Last produced Gas Storage Operation (Date) _____ (Oil, B/D) _____ (Water, B/D) _____ (Gas, Mcf/D)

(or)

Last injected Gas Storage Operation (Date) _____ (Water, B/D) _____ (Gas, Mcf/D) _____ (Surface pressure, psig)

6. Is this a critical well according to the definition on the reverse side of this form? ☐ (Yes) ☒ (No)

The proposed work is as follows:

1. Move in, rig up, kill well and, install and pressure test BOPE.
2. Pull and lay down 2-7/8" tubing.
3. Retrieve 7" packer.
4. Clean out well and run casing inspection log.
5. Perforate intervals: 8428'-8436', 8454'-8502', 8522'-8560', 8602'-8636', 8660'-8668', 8674'-8694', 8727'-8737', 8750'-8760', 8810'-8820'.
6. Shoot holes and cement squeeze casing shoe leak.
7. Flow and noise log well.

Note: If well is to be redrilled, show proposed new bottom-hole coordinates and true vertical depth.

It is understood that if changes in this plan become necessary, we are to notify you immediately.

Address P. O. Box 3249, Terminal Annex (Street)

Los Angeles, California 90051 (City) (State) (Zip)

Telephone Number (213) 689-3925

Southern California Gas Company (Name of Operator)

By J. B. Lane for R. D. Phillips (Agent) (Name - Printed)

J. B. Lane 11 SEP 91 (Name - Signature) (Date)

Type of Organization Corporation (Corporation, Partnership, Individual, etc.)

AC_CPUC_0118344

NOTICE OF INTENTION TO REWORK WELL
DIVISION OF OIL AND GAS
Supplemental page
Well Name: Standard Sesnon #29
API. NO.: 037-00041

The proposed work is as follows (con'd):

8. Install 7" packer.
9. Install 2-7/8" tubing, remove BOPE and install wellhead.
10. Return well to service.

AC_CPUC_0118345

OUG-JBL
cc: HR
RP

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION
DIVISION OF OIL AND GAS

No.P291- 389
Field Code 010
Area Code 00
New Pool Code 30
Old Pool Code 30

PERMIT TO CONDUCT WELL OPERATIONS
GAS STORAGE

R.D. Phillips, Agent
Southern Calif. Gas Company
810 S. Flower St.
Los Angeles, CA. 90017

Ventura, California
September 17, 1991

Your proposal to rework well "SFZU" SS-29, A.P.I. No. 037-00041, Section 28, T. 3 N, R. 16W, S.B. B.&M., Aliso Canyon field, any area, Sesnon pool, Los Angeles County, dated 9/11/91, received 9/12/91, has been examined in conjunction with records filed in this office.

THE PROPOSAL IS APPROVED PROVIDED THAT:

1. Blowout prevention equipment conforming to DOG Class III 5M requirements shall be installed and maintained in operating condition at all times.
2. Hole fluid of a quality and in sufficient quantity is used to control all subsurface conditions in order to prevent blowouts.
3. Wire line operations are conducted through at least a 5M lubricator.
4. This office shall be consulted before initiating any changes or additions to this proposed operation, or if operations are to be suspended.
5. THIS DIVISION SHALL BE NOTIFIED:
   a. To inspect the installed blowout prevention equipment before commencing downhole operations.
   b. Witness Noise Log after remedial work.

Blanket Bond
SF:ljg

Engineer Steve Fields

Phone (805) 654-4761

M.G. MEFFERD, State Oil and Gas Supervisor

By Patrick J. Kinnear
Deputy Supervisor

A copy of this permit and the proposal must be posted at the well site prior to commencing operations. Records for work done under this permit are due within 60 days after the work has been completed or the operations have been suspended.
OGIII

AC_CPUC_0118346

OTIS

GENERAL PRODUCT INFORMATION

212.1.1.2A


Product Code

Date: 11-4-91

Product Name: 'WE' Permanent Packer

Page: 1

SOU CAL GAS CO.
ALISO CANYON
SS#29



PACKER - OTIS BWB (212BWB 70700-A) 3.25" I.D.

23-29#


Note: These instructions describe desired results from use of Otis equipment, but such results are not guaranteed. Operation of equipment is subject to mechanical limitations and Otis shall only be liable for its merchandise and service as set forth in its general terms and conditions.

Otis Engineering Corporation • Dallas, Texas, U.S.A.

AC_CPUC_0118347

Elevation: 2849'
: 7'

Standard Sesnon 29



Surface Choke: _____
Casing flow string

--8002' Otis 2-1/2" SSSV
(8002') 2.313"ID

--8029' Otis "XN" No-Go Nipple
(8029') 2.205"

--8049'

--(8256') (-5400)

--S4 8428'

--S8 8520' (8520')

--HZ 8682'

--Frew 8727'

9077'

(SS - 6941')

4/26/53 Well spud
9/29/53 Well completed
2/2/73-2/28/73 Pressure tested 7" casing, converted to gas store by perforating in Sesnon Zone, cleaned out to 9074', ran tubing with SSSV
7/31/73-8/7/73 Installed wirelin SSSV, cleaned out to 9077'
8/27/77-9/9/77 Cleaned out to 9072', pressure tested casing, reran tubing with SSSV
3/5/79-3/10/79 Replaced safety system, set packer at 8040'

WELL VOLUME

	Cu.Ft.	Bbl.
Tubing	262	47
Csg/Lnr.	105	19
Annulus	1405	250

6-16-86


AC_CPUC_0118348

TUBING DETAIL

WELL: STANDARD SESNON #29
FIELD: ALISO CANYON

STATUS: Injection/Withdrawal
DATE: 11-6-91

DIAGRAM



	TUBING	TUBING	TUBING	
SIZE	2 7/8			
WEIGHT	6.5			
GRADE	J55			
THREAD	8RD EUE			
DEPTH	8035'			
I.D.	2.441			
DRIFT ID	2.347			
O.D.	3.668 JT			

ITEM #	DESCRIPTION	LENGTH	DEPTH
1.	KB	6.92	6.92
2.	G.L. TO TBG HEAD	-.14	6.78
3.	HANGER 7" 2 7/8" EUE X 2 7/8" EUE BOX	.60	7.38
4.	FATIGUE NIPPLE 2 7/8 EUE PIN X PIN	.68	8.06
5.	PUP JT 2 7/8" 6.5# N80 EUE	4.09	12.15
6.	250 JTS. 2 7/8" 6.5# J55 EUE	7907.35	7919.50
7.	BST 'MMA' GLM W/ 1 1/2" RA LATCH	12.92	7932.42
8.	1 JT. 2 7/8 EUE J55 TBG.	31.49	7963.91
9.	OTIS 2.313" 'XD' SSD	3.21	7967.12
10.	1 JT 2 7/8" EUE J55" TBG	31.55	7998.67
11.	OTIS 2.205" 'XN' NO-GO NIPPLE	1.28	7999.50
12.	1 JT. 2 7/8" EUE J55 TBG	31.55	8031.50
13.	OTIS J-LATCH W/ 2 SEAL UNITS	1.50 / 2.49	8032
14.	OTIS MULE SHOE GUIDE	.60	
15.			
16.			
17.			
18.	A. OTIS 7" 23-29# 'BWB' PKR		
19.	3.25" I.D. SET AT:		8032'
20.			
	TUBING LANDED W/ 8000#		
	DOWN ON PACKER		

AC_CPUC_0118349

OTIS

GENERAL PRODUCT INFORMATION

N 212.1.1.2A


Product Code:

Date: 11-4-91

Product Name: 'HE' Permanent Packer

Page: 1

SOU CAL GAS CO.
ALISO CANYON
SS#29



PACKER - OTIS BWB (212BWB 70700-A) 3.25" I.D.
23-29#

Note: These instructions describe desired results from use of Otis equipment but such results are not guaranteed. Operation of equipment is subject to mechanical limitations and Otis shall only be liable for its merchandise and service as set forth in its general terms and conditions.

Otis Engineering Corporation • Dallas, Texas, U.S.A.

AC_CPUC_0118350

Orig-JRL
cc: FK
RP

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION
DIVISION OF OIL AND GAS

No. P291- 389
Field Code 010
Area Code 00
New Pool Code 30
Old Pool Code 30

PERMIT TO CONDUCT WELL OPERATIONS
GAS STORAGE

R.D. Phillips, Agent
Southern Calif. Gas Company
810 S. Flower St.
Los Angeles, CA. 90017

Ventura, California
September 17, 1991

Your proposal to rework well "SFZU" SS-29, A.P.I. No. 037-00041, Section 28, T. 3 N, R. 16W, S.B. B.&M., Aliso Canyon field, any area, Sesnon pool, Los Angeles County, dated 9/11/91, received 9/12/91, has been examined in conjunction with records filed in this office.

THE PROPOSAL IS APPROVED PROVIDED THAT:

1. Blowout prevention equipment conforming to DOG Class III 5M requirements shall be installed and maintained in operating condition at all times.
2. Hole fluid of a quality and in sufficient quantity is used to control all subsurface conditions in order to prevent blowouts.
3. Wire line operations are conducted through at least a 5M lubricator.
4. This office shall be consulted before initiating any changes or additions to this proposed operation, or if operations are to be suspended.
5. THIS DIVISION SHALL BE NOTIFIED:
   a. To inspect the installed blowout prevention equipment before commencing downhole operations.
   b. Witness Noise Log after remedial work.

Blanket Bond
SF:ljg

Engineer Steve Fields

Phone (805) 654-4761

M.G. MEFFERD, State Oil and Gas Supervisor

By Patrick J. Kinnear
Patrick J. Kinnear
Deputy Supervisor

A copy of this permit and the proposal must be posted at the well site prior to commencing operations. Records for work done under this permit are due within 60 days after the work has been completed or the operations have been suspended.
OG111

AC_CPUC_0118351

RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION
DIVISION OF OIL AND GAS

No. P 277-320

REPORT ON PROPOSED OPERATIONS

Santa Paula, California

Mr. P. S. Magruder, Jr., Agent
So. Calif. Gas Co.
P.O. Box 54790 Terminal Annex
Los Angeles, Calif. 90024

Sept. 1, 1977

Your rework proposal to gas storage well "SFZU" SS-29 (Name and number), A.P.I. No. 037-00041, Section 28, T. 3N, R. 16W, S.B. B. & M., Aliso Canyon field, Los Angeles County, dated 8-25-77, received 8-31-77, has been examined in conjunction with records filed in this office.

THE PROPOSAL IS APPROVED PROVIDED THAT:

1. The drilling fluid used shall be of a quality and in sufficient quantity to control all subsurface conditions in order to prevent blowouts; and a reserve supply of this material shall be kept on hand to meet any emergency.
2. Blowout prevention equipment, at least of theDivision of Oil and Gas Class III, 3M rating, shall be installed and maintained in operating condition at all times. The BOPE and choke system shall be tested under a pressure of at least 1500 psi.
3. THIS DIVISION SHALL BE NOTIFIED TO WITNESS A PRESSURE TEST OF THE BLOWOUT PREVENTION EQUIPMENT BEFORE COMMENCING DOWNHOLE OPERATIONS.

NOTE: A COPY OF THIS APPROVAL SHALL BE POSTED AT THE WELL SITE PRIOR TO COMMENCING OPERATIONS.

Blanket Bond
MD:b

3 Copies
- Buff
Pink - Buff
xc - Blue-Back
xc - Blue-Back


M. G. MEFFERD
State Oil and Gas Supervisor

By John L. Hardoin
Deputy Supervisor

John L. Hardoin

OG111 (11-76—GSR1—30M)

AC_CPUC_0118352



AC_CPUC_0118353

SOUTHERN CALIFORNIA GAS COMPANY
SUB-SURFACE PRESSURE SURVEY

FIELD ALISO WELL SS-29 DATE

RECORDER NO. RUN NO. SHEET NO. OF SHEETS BY

CLOCK HOURS TIME CLOCK STARTED TIME RUN COMPLETED

WELL CONDITION DURING RUN, SHUT-IN FLOWING INJECTION

HOURS WELL, SHUT-IN FLOWING INJECTION BEFORE RUN

WELL HEAD PRESSURE

TUBING

CASING

FLOW RATE

GAS MCF/D

OIL BBL'S/D

WATER BBL'S/D

GOR

MAXIMUM TEMPERATURE

ZERO POINT 5½ @ M/V

PICK-UP

DATUM 8256 (-5400)

	SIZE	DEPTH
TUBING	2 7/8	8049
CASING	7	8180
CASING SHOE		
LINER	5	
TOP		8075
BOTTOM		9077

PERFORATION

TOP

BOTTOM

SURVEY DATA

DEPTH		STYLUS DEFLECTION	PRESSURE	GRADIENT PSI/100 FT
VERTICAL	MEASURED			
0	0			
5000	5000			
6000	6000			
7000	7000			
8000	8000			
8256	8256 DAT			
8428	8428 S-4			
8520	8520 S-8			
8700	8700			
8900	8900			
9000	9000			

SPECIAL INSTRUCTIONS: TBG TAIL 8049
TD 9077

BY

REMARKS:

NOTE: REVISED PRESSURE SURVEY SHEET, BASED ON TEMPERATURE SURVEY
MOVED UP SOME BOTTOM STOPS, ADDED A COUPLE STOPS NEAR BOTTOM (JDM: 6/86)

FIELD OPERATOR

CHART READ BY

SOUTHERN CALIFORNIA GAS CO.—4296

AC_CPUC_0118354

PRUETT WIRELINE SERVICE


8915 Rosedale Hwy, Bakersfield, Ca. 93308
(805) 589-2768

SUB—SURFACE PRESSURE SURVEY

COMPANY Southern California Gas FIELD Aliso Canyon WELL NAME SS 29

TOTAL DEPTH	--	WELL STATUS	Static	BOMB HUNG @	none
CASING	--	CASING PRESSURE	--	TIME ON BOTTOM	11:38am
LINER	--	TUBING PRESSURE	--	TIME OFF BOTTOM	11:40am
PERFORATIONS	--	ZONE	none	SHUT IN	none
MPP	--	MAX °F	190.4°	ON PRODUCTION	none
TUBING DETAIL	2 7/8" @ 8048' **			PURPOSE	Pressure Gradient Survey

DATE	3-23-79		
ELEMENT RANGE	5350 PSI		
ZERO POINT	6.92'		
ELEVATION	none		
PICKUP	none made		



MEASURED DEPTH	PRESSURE
0	1833
5000	2094
6000	2148
7000	2199
8249	2263
8520	2293
Measured MPP 8520	2293

SURVEY DATA

** Safety @ 8001'

VERTICAL DEPTH	GRADIENT
	.052
	.054
	.051
	.051
	.111

M. McShane
3-31-79

S Wilson


AC_CPUC_0118355

TECHNICAL SERVICE CO.
801 West 14th Street
Long Beach, California 90813

Phones: 24 Hours
Long Beach - 436-9901

SUB-SURFACE PRESSURE DATA

Company: So. California Gas Co. Field: Aliso Date: 5-2-75 Run No.:
Well: S. S. 29 Zone: Elev.:
Purpose: Static Pressure Gradient Survey Status: Shut In
Total Depth: Effect. Depth:
Casing Size: Depth: Liner Size: Top: Bottom:
Perforations:
Tubing: 2-7/8" & 2-3/8" to 8518' (plug), G. L. Valves @ 5697', 6932', 7985', 8326', "X" Nipple @ 8017', 8390', 8456', 8483', Sliding Sleeve @ 8359', Packer @ 8420', 8518'



OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas-Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	1910
Casing Fluid Level - Ft.	

RESULTS

Gross Productivity Index	B/D PSI
Net Productivity Index	B/D PSI
Static M.E.P. - Run No.	PSI
Static M.E.P. - Projected	PSI
Gross Absolute Potential	B/D
Net Absolute Potential	B/D
Datum Pressures:	

Traverse Depth MD Feet	VD	Pressure PSIG	Gradient PSI/FT
0	0	1910	
5000	5000	2175	0.053
6000	6000	2225	0.050
7000	7000	2269	0.044
8000	8000	2325	0.050
8500	8500	2358	0.066

COMMENTS: Zero: Mat + 7.0'. Maximum temperature not recorded.

AC_CPUC_0118356

PACIFIC LIGHTING SERVICE COMPANY

SUB-SURFACE PRESSURE SURVEY

FIELD Aliso Canyon WELL S. S. 29 DATE 5-2-75

RECORDER No. 2900 RUN No. ____ SHEET No. ____ OF ____ SHEETS BY ____

CLOCK HOURS 3 TIME CLOCK STARTED ____ TIME RUN COMPLETED ____

WELL CONDITION DURING RUN, SHUT IN ____ FLOWING ____ INJECTION ____

HOURS WELL, SHUT-IN ____ FLOWING ____ INJECTION ____ BEFORE RUN ____

WELL HEAD PRESSURE

TUBING 1910

CASING ____

FLOW RATE

GAS MCF/D ____

OIL BBL'S/D ____

WATER BBL'S/D ____

GOR ____

MAXIMUM TEMPERATURE --

ZERO POINT 7.0'

PICK-UP ____

DATUM 8524'

	SIZE	DEPTH
TUBING		
CASING		
CASING SHOE		
LINER		
TOP		
BOTTOM		
PERFORATION		
TOP		
BOTTOM		

SURVEY DATA

DEPTH		STYLUS DEFLECTION	PRESSURE	GRADIENT PSI/100 F
MEASURED	VERTICAL			
0	0	1.030	1910	
5000	5000	1.174	2175	0.053
6000	6000	1.201	2225	0.050
7000	7000	1.225	2269	0.044
8000	8000	1.255	2325	0.056
8500	8500	1.273	2358	0.066

SPECIAL INSTRUCTIONS: ____

BY ____

REMARKS: ____

FIELD OPERATOR Harlan

CHART READ BY Smith

PLS FORM 501


AC_CPUC_0118357

TECHNICAL SERVICE CO.
801 West 14th Street
Long Beach, California 90813

Phones: 24 Hours
Long Beach - 436-9901

SUB-SURFACE PRESSURE DATA

Company: So. California Gas Co. Field: Aliso Date: 4-23-75 Run No.:
Well: S. S. 29 Zone: Elev.:
Purpose: Static Pressure Gradient Survey Status: Shut In
Total Depth: Effect. Depth:
Casing Size: Depth: Liner Size: Top: Bottom:
Perforations:
Tubing: 2-7/8" & 2-3/8" to 8518' (plug), G. L. Valves @ 5697', 6932', 7985', 8326', "X" Nipple @ 8017', 8390', 8456', 8483', Sliding Sleeve @ 8359', Packer @ 8420', 8518'



OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas-Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	1899
Casing Fluid Level - Ft.	

RESULTS

Gross Productivity Index	B/D PSI
Net Productivity Index	B/D PSI
Static M.E.P. - Run No.	PSI
Static M.E.P. - Projected	PSI
Gross Absolute Potential	B/D
Net Absolute Potential	B/D
Datum Pressures:	

Traverse Depth Feet MD	VD	Pressure PSIG	Gradient PSI/FT
0	0	1899	
5000	5000	2164	0.053
6000	6000	2208	0.044
7000	7000	2253	0.045
8000	8000	2304	0.051
8500	8500	2338	0.068

COMMENTS: Zero: Mat + 6.92'. Maximum temperature 182° F. .

AC_CPUC_0118358

PACIFIC LIGHTING SERVICE COMPANY

SUB-SURFACE PRESSURE SURVEY

FIELD Aliso Canyon WELL S. S. 29 DATE 4-23-75

RECORDER No. 2900 RUN No. ____ SHEET No. ____ OF ____ SHEETS BY ____

CLOCK HOURS 3 TIME CLOCK STARTED ____ TIME RUN COMPLETED ____

WELL CONDITION DURING RUN, SHUT IN ____ FLOWING ____ INJECTION ____

HOURS WELL, SHUT-IN ____ FLOWING ____ INJECTION ____ BEFORE RUN ____

WELL HEAD PRESSURE

TUBING 1899

CASING ____

FLOW RATE

GAS MCF/D ____

OIL BBL'S/D ____

WATER BBL'S/D ____

GOR ____

MAXIMUM TEMPERATURE 182° F.

ZERO POINT 7.0'

PICK-UP ____

DATUM 8524'

	SIZE	DEPTH
TUBING	2-3/8"	8522'
CASING		
CASING SHOE		
LINER		
TOP		
BOTTOM		
PERFORATION		
TOP		
BOTTOM		

SURVEY DATA

DEPTH		STYLUS DEFLECTION	PRESSURE	GRADIENT PSI/100 FT
MEASURED	VERTICAL			
0	0	1.024	1899	
5000	5000	1.168	2164	0.053
6000	6000	1.192	2208	0.044
7000	7000	1.216	2253	0.045
8000	8000	1.244	2304	0.051
8500	8500	1.262	2338	0.068

SPECIAL INSTRUCTIONS: ____

BY ____

REMARKS: Unit 1 Survey sequence #3

FIELD OPERATOR Harlan

CHART READ BY Robinson - Smith

PLS FORM 501


AC_CPUC_0118359

TECHNICAL SERVICE CO
801 West 14th Street
Long Beach, California 90813

Phones: 24 Hours
Long Beach - 436-9901

SUB-SURFACE PRESSURE DATA

Company So. California Gas Co. Field Aliso Canyon Date 4-11-75 Run No.
Well Standard Sesnon 29 Zone Elev.
Purpose Static Pressure Gradient Survey Status Shut In
Total Depth Effect. Depth
Casing Size Depth Liner Size Top Bottom
Perforations
Tubing 2-7/8" & 2-3/8" to 8518' (plug), G. L. Valves @ 5697', 6932', 7985', 8326', "X" Nipple @ 8017', 8390', 8456', 8483', Sliding Sleeve @ 8359', Packer @ 8420', 8518'



OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas-Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	1860
Casing Fluid Level - Ft.	

RESULTS

Gross Productivity Index	B/D PSI
Net Productivity Index	B/D PSI
Static M.E.P. - Run No.	PSI
Static M.E.P. - Projected	PSI
Gross Absolute Potential	B/D
Net Absolute Potential	B/D
Datum Pressures:	

Traverse Depth Feet MD	VD	Pressure PSIG	Gradient PSI/FT
0	0	1860	
5000	5000	2116	0.051
6000	6000	2164	0.048
7000	7000	2212	0.048
8000	8000	2262	0.050
8500	8500	2292	0.060

Datum 8522 P=2293

COMMENTS Zero: K. B. 6.92'. Maximum temperature 170° F.

AC_CPUC_0118360

PACIFIC LIGHTING SERVICE COMPANY

SUB-SURFACE PRESSURE SURVEY

FIELD Aliso Canyon WELL S. S. 29 DATE 4-11-75

RECORDER NO. 2900 RUN NO. ____ SHEET NO. ____ OF ____ SHEETS BY ____

CLOCK HOURS 3 TIME CLOCK STARTED ____ TIME RUN COMPLETED ____

WELL CONDITION DURING RUN, SHUT IN ____ FLOWING ____ INJECTION ____

HOURS WELL, SHUT-IN ____ FLOWING ____ INJECTION ____ BEFORE RUN ____

WELL HEAD PRESSURE

TUBING 1860

CASING ____

FLOW RATE

GAS MCF/D ____

OIL BBL'S/D ____

WATER BBL'S/D ____

GOR ____

MAXIMUM TEMPERATURE 170° F.

ZERO POINT 7.0'

PICK-UP ____

DATUM 8524'

	SIZE	DEPTH
TUBING		
CASING		
CASING SHOE		
LINER		
TOP		
BOTTOM		
PERFORATION		
TOP		
BOTTOM		

SURVEY DATA

DEPTH		STYLUS DEFLECTION	PRESSURE	GRADIENT PSI/100 FT
MEASURED	VERTICAL			
0	0	1.003	1860	
5000	5000	1.142	2116	0.051
6000	6000	1.168	2164	0.048
7000	7000	1.194	2212	0.048
8000	8000	1.221	2262	0.050
8500	8500	1.237	2292	0.060

SPECIAL INSTRUCTIONS: ____

BY ____

REMARKS: Survey sequence #2 - Unit 2

FIELD OPERATOR Harlan

CHART READ BY Robinson - Smith

PLS FORM 501


AC_CPUC_0118361

TECHNICAL SERVICE CO
801 West 14th Street
Long Beach, California 90813

Phones: 24 Hours
Long Beach - 436-9901

SUB-SURFACE PRESSURE DATA

Company So. California Gas Co. Field Aliso Canyon Date 4-11-75 Run No.
Well Standard Sesnon 29 Zone Elev.
Purpose Static Pressure Gradient Survey Status Shut In
Total Depth Effect. Depth
Casing Size Depth Liner Size Top Bottom
Perforations
Tubing 2-7/8" & 2-3/8" to 8518' (plug), G. L. Valves @ 5697', 6932', 7985', 8326', "X" Nipple @ 8017', 8390', 8456', 8483', Sliding Sleeve @ 8359', Packer @ 8420', 8518'



OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas-Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	1860
Casing Fluid Level - Ft.	

RESULTS

Gross Productivity Index	B/D PSI
Net Productivity Index	B/D PSI
Static M.E.P. - Run No.	PSI
Static M.E.P. - Projected	PSI
Gross Absolute Potential	B/D
Net Absolute Potential	B/D
Datum Pressures:	

Traverse Depth MD Feet	VD	Pressure PSIG	Gradient PSI/FT
0	0	1860	
5000	5000	2116	0.051
6000	6000	2164	0.048
7000	7000	2212	0.048
8000	8000	2262	0.050
8500	8500	2292	0.060

COMMENTS Zero: K. B. 6.92'. Maximum temperature 170° F.

AC_CPUC_0118362

PACIFIC LIGHTING SERVICE COMPANY

SUB-SURFACE PRESSURE SURVEY

FIELD Aliso Cyn WELL SS 29 DATE 12-20-74

RECORDER NO. 12327 RUN NO. ___ SHEET NO. ___ OF ___ SHEETS BY Wilson

CLOCK HOURS 1½ TIME CLOCK STARTED 1.04 TIME RUN COMPLETED ___

WELL CONDITION DURING RUN, SHUT IN ___ FLOWING ___ INJECTION ___

HOURS WELL, SHUT-IN ___ FLOWING ___ INJECTION ___ BEFORE RUN ___

WELL HEAD PRESSURE

TUBING ___

CASING ___

FLOW RATE

GAS MCF/D ___

OIL BBL'S/D ___

WATER BBL'S/D ___

GOR ___

MAXIMUM TEMPERATURE 194°

ZERO POINT 7'

PICK-UP ___

DATUM 8524 *

	SIZE	DEPTH
TUBING	2 3/8"	8522'
CASING	___	___
CASING SHOE		___
LINER	___	
TOP		___
BOTTOM		___
PERFORATION		
TOP		___
BOTTOM		___

SURVEY DATA

DEPTH MEASURED	DEPTH VERTICAL	STYLUS DEFLECTION	PRESSURE	GRADIENT PSI/~~100~~ FT
0	0	1.362	2189.19	
5000	5000	1.551	2998.07	0.1618
6000	6000	1.587	3067.57	0.0695
7000	7000	1.622	3135.14	0.0676
8000	8000	1.657	3202.70	0.0676
8500	8500	1.675	3237.45	0.0695
	(Calc.)	Datum	3239.1	

SPECIAL INSTRUCTIONS: Plug @ 5517

BY ___

REMARKS: Extrapolate to datum, DO Not Go To NO-GO
Plug at 8517'.

FIELD OPERATOR ___

CHART READ BY


AC_CPUC_0118363

TECHNICAL SERVICE CO.
801 West 14th Street
Long Beach, California 90813

Phones: 24 Hours
Long Beach - 436-9901

SUB-SURFACE PRESSURE DATA

Company: So. California Gas Co. Field: Aliso Canyon Date: 11-20-74 Run No.:
Well: S. S. #29 Zone: Elev.: Mat + 7'
Purpose: Static Pressure Survey Status: Shut In
Total Depth: Effect. Depth:
Casing Size: Depth: Liner Size: Top: Bottom:
Tubing: 2-7/8" to 8049', 2-3/8" to 8522', "KBMG" Mandrels @ 5697', 6933', 7985', 8326', 2-3/8" Sliding Sleeve @ 8359', Camco HRP-1 Packer @ 8426', 2-3/8" Plugged @ 8518', Baker Model "D" Packer @ 8522'



OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas-Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	2756
Casing Fluid Level - Ft.	

RESULTS

Gross Productivity Index	B/D PSI
Net Productivity Index	B/D PSI
Static M.E.P. - Run No.	PSI
Static M.E.P. - Projected	PSI
Gross Absolute Potential	B/D
Net Absolute Potential	B/D
Datum Pressures:	

Traverse Depth Feet MD	VD	Pressure PSIG	Gradient PSI/FT
0	0	2756	
5000	5000	3141	.077
6000	6000	3218	.077
7000	7000	3290	.072
8000	8000	3365	.075
8500	8500	3401	.072

COMMENTS: Zero: 7.0' above mat. Maximum temperature 156° F.
Survey sequence #3

AC_CPUC_0118364

PACIFIC LIGHTING SERVICE COMPANY

SUB-SURFACE PRESSURE SURVEY

FIELD Aliso Canyon WELL S. S. 29 DATE 11-20-74

RECORDER NO. 4770 RUN NO. ____ SHEET NO. ____ OF ____ SHEETS BY ____

CLOCK HOURS 3 TIME CLOCK STARTED ____ TIME RUN COMPLETED ____

WELL CONDITION DURING RUN, SHUT IN ____ FLOWING ____ INJECTION ____

HOURS WELL, SHUT-IN ____ FLOWING ____ INJECTION ____ BEFORE RUN ____

WELL HEAD PRESSURE

TUBING 2756

CASING ____

FLOW RATE

GAS MCF/D ____

OIL BBL'S/D ____

WATER BBL'S/D ____

GOR ____

MAXIMUM TEMPERATURE 156° F.

ZERO POINT 7.0'

PICK-UP ____

DATUM 8524'

	SIZE	DEPTH
TUBING	____	____
CASING	____	____
CASING SHOE		____
LINER	____	
TOP		____
BOTTOM		____
PERFORATION		
TOP		____
BOTTOM		____

SURVEY DATA

DEPTH		STYLUS DEFLECTION	PRESSURE	GRADIENT PSI/100 F
MEASURED	VERTICAL			
0	0	1.441	2756	
5000	5000	1.642	3141	.077
6000	6000	1.682	3218	.077
7000	7000	1.720	3290	.072
8000	8000	1.759	3365	.075
8500	8500	1.778	3401	.072

SPECIAL INSTRUCTIONS: ____

BY ____

REMARKS: Survey sequence #3

FIELD OPERATOR Baker

CHART READ BY Smith

PLS FORM 501


AC_CPUC_0118365

TECHNICAL SERVICE CO.
801 West 14th Street
Long Beach, California 90813

Phones: 24 Hours
Long Beach - 436-9901

SUB-SURFACE PRESSURE DATA

Company: So. California Gas Co. Field: Aliso Canyon Date: 1-15-74 Run No.:
Well: S. S. #29 Zone: Elev.: Mat + 7'
Purpose: Static Pressure Gradient Survey Status: Shut In
Total Depth: Effect. Depth:
Casing Size: Depth: Liner Size: Top: Bottom:
Tubing: 2-7/8" to 8049'. 2-3/8" to 8522'. "KBMG" Mandrels @ 5697', 6933', 7985', & 8326'. 2-3/8" Sliding Sleeve @ 8359'. Camco HRP-1 Packer @ 8426' 2-3/8" Plugged @ 8518'. Baker Model "D" Packer @ 8522'



OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas-Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	1638
Casing Fluid Level - Ft.	

RESULTS

Gross Productivity Index	B/D PSI
Net Productivity Index	B/D PSI
Static M.E.P. - Run No.	PSI
Static M.E.P. - Projected	PSI
Gross Absolute Potential	B/D
Net Absolute Potential	B/D
Datum Pressures:	

Traverse Depth MD Feet	VD	Pressure PSIG	Gradient PSI/FT MD
0	0	1638	
5000	5000	1883	0.049
6000	6000	1928	0.045
7000	7000	1980	0.052
8000	8000	2023	0.049
Datum			
8500	8500	2046	0.046

COMMENTS: Maximum Temperature 218° F.
Zero: Mat + 7'

By: Pate - Snider - Homer

AC_CPUC_0118366

SS 29
5-1-73

K&E 10 X 10 TO THE CENTIMETER 46 1510
18 X 25 CM. MADE IN U.S.A.
KEUFFEL & ESSER CO.

AC_CPUC_0118367

O.K.

PACIFIC LIGHTING SERVICE COMPANY

SUB-SURFACE PRESSURE SURVEY

FIELD Aliso Canyon WELL SS 29 DATE 6-1-73

RECORDER NO. _____ RUN NO. ____ SHEET NO. ____ OF ____ SHEETS BY _____

CLOCK HOURS _____ TIME CLOCK STARTED _____ TIME RUN COMPLETED _____

WELL CONDITION DURING RUN, SHUT IN _____ FLOWING _____ INJECTION _____

HOURS WELL, SHUT-IN _____ FLOWING _____ INJECTION _____ BEFORE RUN _____

WELL HEAD PRESSURE

TUBING _____

CASING _____

FLOW RATE

GAS MCF/D _____

OIL BBL'S/D _____

WATER BBL'S/D _____

GOR _____

MAXIMUM TEMPERATURE _____

ZERO POINT 7'

PICK-UP _____

DATUM 8521'

	SIZE	DEPTH
TUBING		
CASING		
CASING SHOE		
LINER		
TOP		
BOTTOM		
PERFORATION		
TOP		
BOTTOM		

SURVEY DATA

DEPTH		STYLUS DEFLECTION	PRESSURE	GRADIENT PSI/100 FT
MEASURED	VERTICAL			
0	0		1168	
5000	5000		1328	.032
6000	6000		1356	.028
7000	7000		1388	.032
8000	8000		1425	.037
8500	8500		1442	.034
8521*	8521		1443	.048

SPECIAL INSTRUCTIONS: * EXTRAPOLATE TO DATUM. DO NOT GO TO NO-GO PLUG AT 8521'.

BY _____

REMARKS: _____

FIELD OPERATOR _____

CHART READ BY _____

PLS FORM 501

AC_CPUC_0118368

Archer - Reed

WIRE LINE SERVICE

205 Baldwin Ave. Ventura, Calif. 93030

VENTURA 642-7061
LONG BEACH 591-0921

SUB-SURFACE DATA

Company Southern Calif. Gas Co. Field Date 5-1-73 Run No. 1

Well Std. Sessnon #29 Zone Elev.

Purpose Status

Total Depth Effect. Depth

Casing Size Depth Liner Size Top Bottom

Perforations

Tubing

Company	Southern Calif. Gas Co.		
Well	Std. Sessnon #29		
Date		Date	
Arrive	A P	Arrive	A P
Leave	A P	Leave	A P
Inst.	No. 6788 Size 3450		
	No. 7580 Size 43-270		
Clock	No. Hrs. 3		
	No. Hrs. 3		
Stylus Marked	12:21 PM		A P
Pressure On	12:25 PM		A P
Depth	8500 Zero KB		
At Depth Date	5-1-73 Time 1:08 PM		A P
Off Depth Date	5-1-73 Time 1:23 PM		A P
Shut In Date	unknown Time		A P
Start Press Tbg.	Csg.		#
Final Press Tbg.	Csg.		#
Pick-up	8500 Temp. 177		F

OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas - Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	
Casing Fluid Level - Ft.	

TIME	DEPTH	SCALE	PSI or °F	TIME	DEPTH	SCALE	PSI or °F
/	PRESSURE			/TEMPERATURE			
1225 /1230	0	.678	1168	1225/1230	0	.050	68
1240 /1245	5000	.769	1328	1240/1245	5000	.245	118
1247 /1252	6000	.785	1356	1247/1252	6000	.345	135
1255 /100	7000	.803	1388	1255/ 100	7000	.446	151
102 /107	8000	.824	1425	102/ 107	8000	.512	160
108 /	8500	.834	1442	108/	8500	.647	177
113 /	8500	.834	1442	113/	8500	.647	177
118 /	8500	.834	1442	118/	8500	.647	177
123 /	8500	.834	1442	123/	8500	.647	177
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			

COMMENTS

By

AC_CPUC_0118369

ALISO CANYON

SS 29

SS29 9-19-91

80 100 120 140 160 180

Cooling above S1.
Rig moving in
ASAP to correct
shoe leak.

T.D. 9025'
T 2810
C 2810

RUN DEAD PLOT

INV. 630 Out of Service: 5 DAYS

100 FT/MIN

4-25-84

46 1512

10 X 10 TO THE CENTIMETER 18 X 25 CM.
KEUFFEL & ESSER CO. MADE IN U.S.A.

AC_CPUC_0118370

ALISO CANYON
R 3/25/92
SS 29

SS 29 5-7-91

70 90 110 130 150 170

0 1 2 3 4 5 6 7 8 9

0 1000 2000 3000 4000 5000 6000 7000 8000 9000

Some cooling above S1. Well scheduled for workover to repair shoe leak.

Stop 8200'
T 2210
C 2210
RUN DEAD PLOT: 7hr

Out of Service: 5 DAYS

100 FT/MIN

H-25-84

46 1512

10 X 10 TO THE CENTIMETER 18 X 25 CM.
KEUFFEL & ESSER CO. MADE IN U.S.A.

AC_CPUC_0118371

SHUT IN 5 DAYS PRIOR TO SURVEY. 5529 11-28-90

INJ WD 1.75 HOURS PRIOR TO SHUT IN.

SS-29

SS-29 11-28-90

149 153 157 161 165 169

7500 7700 7900 8100 8300 8500 8700 8900 9100

Shoe appears ok
Disregard gradient
7500' - 7840'
Will run Noise Log

PKR 8040'
LNR 8075'
SHOE 8180'
PERFS 8456

9077'

TBG 3880
CSG 3880
P.U. 9024'

RUN C.V. AREA PLOT > RM

46 1512

10 X 10 TO THE CENTIMETER 18 X 25 CM.
KEUFFEL & ESSER CO. MADE IN U.S.A.


AC_CPUC_0118372

ALISO CANYON

SS 29

SS-29 10-11-90

TEMP



SHUT IN 5 days + PRIOR TO SURVEY.

INJ/WD _____ HOURS PRIOR TO SHUT IN.

4-25-84


KE 10 X 10 TO THE CENTIMETER 18 X 25 CM. KEUFFEL & ESSER CO. MADE IN U.S.A.

46 1512

AC_CPUC_0118373

ALISO CANYON


SS 29



46 1512
10 X 10 TO THE CENTIMETER 18 X 25 CM.
KEUFFEL & ESSER CO. MADE IN U.S.A.

SHUT IN 14 days PRIOR SURVEY.
INJ/WD HOURS PRIOR TO SHUT IN.

ALISO CANYON
SS 29



46 1512

10 X 10 TO THE CENTIMETER
KEUFFEL & ESSER CO. MADE IN U.S.A.

4-25-84

AC_CPUC_0118375

ALISO CANYON

SS 29

SS-29

4-21-89

70 90 110 130 150 170 190

0 1000 2000 3000 4000 5000 6000 7000 8000 9000

TBG 1740
CSG 1740
T.D. 9024'

OK

PKR 8040
SHOE 8180'

100 FT/MIN

RUN SDC
READ
PLOT RM

SS-29

4-21-89

AC_CPUC_0118376

SHUT IN 30+ DAY PRIOR SURVEY.

INJ/WD _____ HOURS PRIOR SHUT IN.

ALISO CANYON

SS 29

SS29 10-14-88

90 110 130 150 170 190

0 1000 2000 3000 4000 5000 6000 7000 8000 9000

S-1

OK

T 2 8S

C 2 8S

RUN, TEXD, PLOT, ETC

4-25-84

46 1512

10 X 10 TO THE CENTIMETER
KEUFFEL & ESSER CO. MADE IN U.S.A.

AC_CPUC_0118377

ALISO CANYON

SS 29

IN 16 DAYS PRIOR TO

INJWD 12 HRS HOURS PRIOR TO STOP IN

SS 29 3-16-88

50 60 70 80 90 100 110 120 130 140 150 160 170 180

0 1 2 3 4 5 6 7 8 9

0 1000 2000 3000 4000 5000 6000 7000 8000 9000

OK

T 1570
C 1575

RUN, READ, PLOT

RCS/4/20/88 4-25-84

46 1510


10 X 10 TO THE CENTIMETER 18 X 25 CM
KEUFFEL & ESSER CO. MADE IN U.S.A.

AC_CPUC_0118378

10 DAYS

ALISO CANYON

SS 29



46 1510

10 X 10 TO THE CENTIMETER 18 X 25 CM.
KEUFFEL & ESSER CO. MADE IN U.S.A.

4-25-84

RCSP 12/17/87

AC_CPUC_0118379

ALISO CANYON

SS 29

SHUT IN 5 DAYS PRIOR TO SURVEY.

INJ/WD 323 INJ [illegible] TO SHUT IN

SS-29 9-24-87

80 100 120 140 160 180

0 1000 2000 3000 4000 5000 6000 7000 8000 9000

461510

ANOMALY ABOVE SHOE POSSIBLY DUE TO INADEQUATE SHUT-IN. WILL RERUN.

TBG 2180

CSG 2180

T.D. 9021'

PKR 8940

SHOE 9180'

PERFS 8956

9094'

9144'

100 FT/MIN

RUN 9-25-87

SS-29


RCP 10/16/87

10 X 10 TO THE CENTIMETER 18 X 25 CM.
KEUFFEL & ESSER CO. MADE IN U.S.A.

AC_CPUC_0118380

SHUT IN 23 days PRIOR SURVEY.
INJ WD HOURS PRIOR TO SHUT IN.

SS 29



46 1512


10 X 10 TO THE CENTIMETER 10 X 25 CM.
KEUFFEL & ESSER CO. MADE IN U.S.A.

REC'D 4-25-84
4-7157

AC_CPUC_0118381

SHUT IN 4 days PRIOR TO SURVEY.
IN 98.2 HOURS PRIOR TO SHUT IN.

55-29
9-16-86



46 1512

10 X 10 TO THE CENTIMETER IN A
KEUFFEL & ESSER CO MADE IN U.S.A.

AC_CPUC_0118382

SS 29

SS 29
9-4-86

80 100 120 140 160 180


SLIGHT ANOMALY ABOVE S-1
WILL RUN DETAIL

T- 2330
C- 2330
TIO 9033

100 FT/MIN

HFJ

- AP
- S1



SS-29
9-5-86

H-25-84


46 1512

KE 10 X 10 TO THE CENTIMETER
KEUFFEL & ESSER CO MADE IN U.S.A.

AC_CPUC_0118383

SHUT-IN 12 days PRIOR TO SURVEY.
FOUND ____ HOURS PRIOR TO SHUT IN.

SS 29



46 1512

K+E 10 X 10 TO THE CENTIMETER 25 X 25 CM
KEUFFEL & ESSER CO. MADE IN U.S.A.

AC_CPUC_0118384

SHUT IN 5 days PRIOR TO SURVEY.

WD 6.3 HOURS P[illegible] TO SHUT IN.

SS 29

SS-29 8-12-85

50 70 90 110 130 150 170 190

0 1 2 3 4 5 6 7 8 9

0 1000 2000 3000 4000 5000 6000 7000 8000 9000

T- 1940
C- 1940
TD- 9030

RUN RENO H.S. PLOT R.M. 8-13-85

SS-29

4-25-84

AC_CPUC_0118385

SS-29 4-29-85


80 100 120 140 160 180 200

INSUFFICIENT SHUT IN PRIOR TO SURVEY, NO APPARENT ANOMALIES

TBG 1590 PSI

CSG 1560 PSI


RUN #1
RUN #2
Plot 7Q




4-25-84

46 1512
KEUFFEL & ESSER CO. MADE IN U.S.A.

AC_CPUC_0118386



AC_CPUC_0118387




46 1512
KE 10 X 10 TO THE CENTIMETER 18 X 25 CM.
KEUFFEL & ESSER CO. MADE IN U.S.A.

AC_CPUC_0118388

SS 29

SS 29 3-20-81

60 80 100 120 140 160 180



RED-PLOT 7.6

REW RM


T 1600

C

46 1512

10 X 10 TO THE CENTIMETER 18 X 25 CM.
KEUFFEL & ESSER CO. MADE IN U.S.A.

AC_CPUC_0118389



46 1512
10 X 10 TO THE CENTIMETER
KEUFFEL & ESSER CO. MADE IN U.S.A.

AC_CPUC_0118390


SS-29 5-26-83

80 100 120 140 160

0 1 2 3 4 5 6 7 8

T-195.0
C-NIL

RUN-SP. MCDONALD
PLOT-P. MCDONALD
READ-H. SHEDTKE
5-31-83



46 1512
K+E 10 X 10 TO THE CENTIMETER 10 X 25 CM.
KEUFFEL & ESSER CO. MADE IN U.S.A.


AC_CPUC_0118391

SS-29 10-18-82

80 100 120 140 160


T- 2880
C- 2880

RUN-PLOT H JAECKE
READ R. McDONALD



46 1512
10 X 10 TO THE CENTIMETER 18 X 25 CM.
KEUFFEL & ESSER CO. MADE IN U.S.A.
K+E

AC_CPUC_0118392



46 1512
10 X 10 TO THE CENTIMETER
KEUFFEL & ESSER CO. MADE IN U.S.A.
X 25 CM.

AC_CPUC_0118393

SS-29
9-21-81
OFF INJ. 9-17-81

80 100 120 140 160

0 1 2 3 4 5 6 7 8

T - 2780
C - 2780

9-25-81 Harry Jacobs

46 1512
K+E 10 X 10 TO THE CENTIMETER 18 X 25 CM
KEUFFEL & ESSER CO. MADE IN U.S.A.

RCS/9-30-81

AC_CPUC_0118394

SS-29 4-29-81

3 DAYS SINCE WELL ON

70 90 110 130 150 170

0 1 2 3 4 5 6 7 8

0 1000 2000 3000 4000 5000 6000 7000 8000

10941

SHOE 8210'
PKR 8431'
PERFS 8456'

CP 8078'
SLIP 8191'
SN 8428'
SB 8450'
PERF 8454'

9094'
9456'

PBTD 9077'
TD 9790'

TUBING - 2150

CASING - 2780

READ BY GUREVICH
PLOT BY M. NELSON

46 1512

K+E 10 X 10 TO THE CENTIMETER 18 X 25 CM.
KEUFFEL & ESSER CO. MADE IN U.S.A.

AC_CPUC_0118395

Southern California Gas Company
Aliso Canyon

Well SS-29 Date 4-27-81 Element No 39138 Clock Hours _____

Tubing Press. 2750 Status _____ Time Clock Started _____ Time Clock Off _____

Casing Press. 2780 Pick-Up _____ Operator JA _____ ' per Minute

Time Press. on _____ Time Start Down _____ Zero Point -7

Depth	Elapse Time	Deflection	Temp.	Depth	Elapse Time	Deflection	Temp.
0	5[illegible]	OVER .136	73.4	5000 ✓	55.0	.365	117.0
250	7.5	.128	71.5	5250	57.5	.377	118.9
500	10.	.138	73.8	5500	60.	.396	121.9
750	12.5	.146	75.7	5750	62.5	OVER .420	125.1
1000 ✓	15.0	.158	78.5	6000 ✓	65.0	.455	129.7
1250	17.5	.168	80.8	6250	67.5	.464	130.9
1500	20.	.176	82.6	6500	70.	.487	133.9
1750	22.5	.185	84.7	6750	72.5	.519	137.8
2000 ✓	25.0	.195	87.0	7000 ✓	75.0	.537	139.9
2250	27.5	.205	89.1	7250	77.5	.560	142.6
2500	30.	.215	91.0	7500	80.	.585	145.6
2750	32.5	.226	93.1	7750	82.5	.615	148.8
3000 ✓	35.0	.235	94.8	8000	85.0	.645	151.8
3250	37.5	.248	97.2				
3500	40.	.262	99.8		87.5		
3750	42.5	.275	102.2				
4000 ✓	45.	.284	103.9				
4250	47.5	.302	107.2				
4500	50.	.329	111.4				
4750	52.5	.350	114.7				

AC_CPUC_0118396

50	5.5	.101	65.2
100	6.0	.115	68.5
150	6.5	.123	70.3
200	7.0	.124	70.6
5800	63.0	.427	126.0
5850	63.5	.431	126.6
5900	64.0	.433	126.8
5950	64.5	.435	127.1


AC_CPUC_0118397

SS29

SS 2

SS-29 9-8-80

100 120 140 160




46 1512

AC_CPUC_0118398

SS 2


SS-29 6-27-20

90 110 130 150 170




46 1512
K&E 10 X 10 TO THE CENTIMETER 18 X 25 CM.
KEUFFEL & ESSER CO. MADE IN U.S.A.

AC_CPUC_0118399



46 1512
10 X 10 TO THE CENTIMETER 18 X 25 CM
KEUFFEL & ESSER CO MADE IN USA

5-5-79
5-23-79
Replot from Page 4



AC_CPUC_0118401

PRUETT WIRELINE SERVICE


8915 Rosedale Hwy, Bakersfield, Ca. 93308
(805) 589-2768

SUB—SURFACE TEMPERATURE SURVEY

COMPANY Southern California Gas FIELD Aliso Canyon WELL NAME SS 29

TOTAL DEPTH ---	WELL STATUS Static	BOMB HUNG @ none	DATE 3-23-79
CASING --	CASING PRESSURE --	TIME ON BOTTOM 10:30am	ELEMENT RANGE 60-200°
LINER ---	TUBING PRESSURE --	TIME OFF BOTTOM 10:35am	ZERO POINT 6.92'
PERFORATIONS ---	ZONE none	SHUT IN none	ELEVATION none
MPP --	MAX. °F 190.4°	ON PRODUCTION none	PICKUP 9038'
TUBING DETAIL 2 7/8" @ 8048' **		PURPOSE Traverse Temperature Survey	

TEMPERATURE



SURVEY DATA

SEE ATTACHED

** Safety @ 8001'

S Wilson

AC_CPUC_0118402

PRUETT WIRELINE SERVICE

8915 Rosedale Hwy, Bakersfield, Ca. 93308
(805) 589-2768

SUB—SURFACE TEMPERATURE SURVEY

COMPANY Southern California Gas FIELD Aliso Canyon WELL NAME SS 29

TOTAL DEPTH --	WELL STATUS Static	BOMB HUNG @ none	DATE 3-23-79
CASING --	CASING PRESSURE --	TIME ON BOTTOM 10:30am	ELEMENT RANGE 60-200°
LINER --	TUBING PRESSURE --	TIME OFF BOTTOM 10:35am	ZERO POINT 6.92'
PERFORATIONS --	ZONE none	SHUT IN none	ELEVATION none
MPP --	MAX. °F. 190.4°	ON PRODUCTION none	PICKUP 9038'
TUBING DETAIL 2 7/8" @ 8048'		PURPOSE Traverse Temperature Survey	

SURVEY DATA


DEPTH	TEMPERATURE	DEPTH	TEMPERATURE	DEPTH	TEMPERATURE
0	72.6	3100	99.4	6200	137.8
100	60.9	3200	100.6	6300	138.9
200	70.8	3300	101.7	6400	140.1
300	72.9	3400	102.8	6500	141.3
400	73.8	3500	103.8	6600	142.6
500	74.7	3600	105.0	6700	143.8
600	75.4	3700	106.2	6800	145.0
700	76.2	3800	107.4	6900	146.2
800	77.2	3900	108.5	7000	147.4
900	78.4	4000	109.6	7100	148.5
1000	79.8	4100	111.0	7200	149.7
1100	81.2	4200	112.3	7300	150.9
1200	82.5	4300	113.6	7400	152.1
1300	83.4	4400	114.9	7500	153.3
1400	84.2	4500	116.2	7600	154.4
1500	84.9	4600	117.5	7700	155.5
1600	85.6	4700	118.8	7800	156.7
1700	86.4	4800	120.2	7900	158.0
1800	87.0	4900	121.5	8000	159.1
1900	87.7	5000	122.6	8100	160.3
2000	88.5	5100	124.0	8200	161.5
2100	89.4	5200	125.3	8300	162.7
2200	90.5	5300	126.6	8400	163.7
2300	91.5	5400	127.9	8450	164.1
2400	92.5	5500	129.2	8500	155.5
2500	93.5	5600	130.4	8600	162.3
2600	94.4	5700	131.7	8700	170.0
2700	95.4	5800	132.8	8800	175.9
2800	96.4	5900	134.1	8900	184.2
2900	97.3	6000	135.3	9000	186.2
3000	98.3	6100	136.6	9038	190.4

Instrument Serial No. 41724, calibrated 11-15-77.
Survey traversed 100' per minute.

S Wilson

AC_CPUC_0118403

5-7-29
3-23-79
Exploit Room Page #



46 1512
KEUFFEL & ESSER CO MADE IN U.S.A.

AC_CPUC_0118404

SS-29 2-23-78 R Cann


60 80 100 120 140 160 180

T- 1980 (S. VALVE etc)
C- 2250

B.H.T. 100' min to 8385'
B.H. SAFETY VALVE BELOW

A.C. SS-29 (2-23-78)


AC_CPUC_0118405



SS-29 10-26-77

AC_CPUC_0118406

55-29 4-13-77 R2



PICK-UP 8380'
B.H. CHOKE BELOW

SS#29


AC_CPUC_0118407

TECHNICAL SERVICE CO.
801 West 14th Street
Long Beach, California 90813

Phones: 24 Hours
Long Beach - 436-9901

SUB-SURFACE TEMPERATURE DATA

Company So. California Gas Co. Field Aliso Canyon Date 9-24-76 Run No.
Well S. S. 29 Zone Elev.
Purpose Static Temperature Survey Status Shut In
Total Depth Effect. Depth
Casing Size Depth Liner Size Top Bottom
Perforations
Tubing 2-7/8" & 2-3/8" to 8522', G. L. Valves @ 5697', 6932', 7985', 8326', "X" Nipple @ 8017', 8390', 8456', 8483', Sliding Sleeve @ 8359', Packer @ 8420', 8518'



OBSERVATIONS	
Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas-Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	
Casing Fluid Level - Ft.	

Traverse Depth Feet	Temperature °F	Traverse Depth Feet	Temperature °F
0	89.1	5000	121.2
100	81.0	5100	122.6
200	79.5	5200	123.7
300	79.3	5300	124.9
400	79.3	5400	126.1
500	79.5	5500	127.7
600	80.6	5600	129.5
700	81.4	5700	130.6
800	82.5	5800	131.6
900	83.4	5900	133.8
1000	83.8	6000	134.5
1100	84.4	6100	135.7
1200	84.8	6200	137.3
1300	85.0	6300	138.2
1400	85.5	6400	139.2
1500	86.3	6500	139.7
1600	86.7	6600	141.3
1700	87.2	6700	142.8
1800	88.2	6800	143.6
1900	88.9	6900	144.5
2000	89.9	7000	145.5
2100	90.8	7100	146.7
2200	91.6	7200	147.0
2300	92.4	7300	148.2
2400	93.3	7400	149.4
2500	94.1	7500	150.9
2600	95.1	7600	152.0
2700	95.8	7700	153.6
2800	96.6	7800	155.0
2900	97.6	7900	156.5
3000	98.7	8000	157.5
3100	99.5	8100	159.3
3200	100.3	8200	160.3
3300	101.4	8300	161.5
3400	102.3	8400	163.7
3500	103.2	8500	141.7
3600	104.3		
3700	105.3		
3800	106.0		
3900	107.3		
4000	108.8		
4100	110.1		
4200	112.9		
4300	114.0		
4400	115.6		
4500	116.3		
4600	117.5		
4700	118.3		
4800	119.2		
4900	120.2		

COMMENTS Zero: Mat + 7.0'


AC_CPUC_0118408

TECHNICAL SERVICE CO.
801 West 14th Street
Long Beach, California 90813

Phones: 24 Hours
Long Beach - 436-9901

SUB-SURFACE TEMPERATURE DATA

Company: So. California Gas Co. Field: Aliso Canyon Date: 3-18-76 Run No.:
Well: S. S. 29 Zone: Elev.:
Purpose: Static Temperature Survey Status: Shut In
Total Depth: Effect. Depth:
Casing Size: Depth: Liner Size: Top: Bottom:
Perforations:
Tubing: 2-7/8" & 2-3/8" to 8522', G. L. Valves @ 5697', 6932', 7985', 8326', "X" Nipple @ 8017', 8390', 8456', 8483', Sliding Sleeve @ 8359', Packer @ 8420', 8518'



OBSERVATIONS	
Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas-Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	
Casing Fluid Level - Ft.	

Traverse Depth Feet	Temperature °F	Traverse Depth Feet	Temperature °F
0	75.1	5000	127.3
100	75.1	5100	128.3
200	75.1	5200	129.6
300	75.3	5300	131.0
400	75.6	5400	132.2
500	76.5	5500	133.6
600	77.2	5600	134.9
700	78.4	5700	136.1
800	81.7	5800	137.2
900	84.6	5900	138.1
1000	85.9	6000	139.6
1100	86.7	6100	140.2
1200	87.7	6200	141.3
1300	88.1	6300	142.8
1400	89.1	6400	143.8
1500	89.7	6500	144.8
1600	89.9	6600	145.9
1700	90.8	6700	147.7
1800	91.6	6800	148.8
1900	93.2	6900	149.2
2000	94.2	7000	150.3
2100	95.0	7100	151.4
2200	95.9	7200	152.3
2300	96.7	7300	153.3
2400	97.2	7400	154.4
2500	98.0	7500	155.4
2600	98.9	7600	156.5
2700	100.0	7700	157.5
2800	101.4	7800	159.1
2900	102.8	7900	160.0
3000	103.8	8000	161.2
3100	105.0	8100	162.6
3200	106.1	8200	163.6
3300	107.1	8300	164.6
3400	108.4	8400	167.5
3500	109.5	8425	168.5
3600	110.8		
3700	111.9		
3800	113.4		
3900	114.9		
4000	116.4		
4100	117.6		
4200	119.0		
4300	120.1		
4400	121.1		
4500	121.8		
4600	123.0		
4700	124.0		
4800	125.2		
4900	126.2		

COMMENTS: Zero: Mat + 7.0'


AC_CPUC_0118409

TECHNICAL SERVICE CO
801 West 14th Street
Long Beach, California 90813

Phones: 24 Hours
Long Beach - 436-9901
Ventura - - 642-3794

SUB-SURFACE TEMPERATURE DATA

Company: So. California Gas Co. Field: Aliso Canyon Date: 3-18-75 Run No.:
Well: S. S. 29 Zone: Elev.:
Purpose: Sub-Surface Temperature Survey Status: Flowing from Casing
Total Depth: Effect. Depth:
Casing Size: Depth: Liner Size: Top: Bottom:
Perforations:
Tubing: 2-7/8" to 8049', 2-3/8" to 8522', KBMG Mandrels @ 5697', 6933', 7985', 8326', 2-3/8" Sliding sleeve @ 8359', Camco HRP-1 Packer @ 8426', 2-3/8" Plugged @ 8518', Baker Model "D" Packer @ 8522'




OBSERVATIONS	
Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas-Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	
Casing Fluid Level - Ft.	

Traverse Depth Feet	Temperature °F	Traverse Depth Feet	Temperature °F
0	91.4	5000	145.7
100	94.8	5100	146.3
200	100.4	5200	146.8
300	107.9	5300	147.4
400	110.4	5400	147.8
500	113.6	5500	148.4
600	115.3	5600	148.7
700	116.9	5700	149.2
800	118.3	5800	149.7
900	119.1	5900	150.0
1000	119.9	6000	150.4
1100	120.9	6100	150.9
1200	121.7	6200	151.4
1300	122.8	6300	152.0
1400	123.6	6400	152.3
1500	124.4	6500	152.8
1600	125.2	6600	153.2
1700	126.2	6700	153.6
1800	126.6	6800	154.1
1900	127.5	6900	154.5
2000	128.1	7000	155.0
2100	128.8	7100	155.3
2200	129.4	7200	155.7
2300	129.9	7300	155.9
2400	130.6	7400	156.3
2500	131.2	7500	156.6
2600	132.0	7600	157.1
2700	132.5	7700	157.5
2800	133.5	7800	158.0
2900	133.8	7900	158.2
3000	134.6	8000	158.5
3100	135.3	8100	158.8
3200	135.9	8200	159.1
3300	136.6	8300	159.4
3400	137.4	8329	159.6
3500	138.0		
3600	138.7		
3700	139.3		
3800	140.0		
3900	140.5		
4000	141.0		
4100	141.6		
4200	142.0		
4300	142.6		
4400	143.0		
4500	143.4		
4600	144.0		
4700	144.4		
4800	144.8		
4900	145.4		

COMMENTS

AC_CPUC_0118410



AC_CPUC_0118411

PACIFIC LIGHTING SERVICE COMPANY
SUB-SURFACE TEMPERATURE SURVEY

FIELD Aliso Canyon WELL SS-29 DATE 3-18-74

RECORDER NO. 13440 RUN NO. ___ SHEET NO. 2 OF 2 SHEETS BY R. Hazel

CLOCK HOURS 3 TIME CLOCK STARTED 1244P TIME RUN COMPLETED ___

WELL CONDITION DURING RUN, SHUT-IN ___ FLOWING ___ INJECTION ___

HOURS WELL, SHUT-IN ___ FLOWING ___ INJECTION ___ BEFORE RUN ___

WELL HEAD PRESSURE

TUBING 1780#

CASING ___

FLOW RATE

GAS MCF/D ___

OIL BBL'S/D ___

WATER BBL'S/D ___

GOR ___

AMBIENT TEMPERATURE ___

ZERO POINT 6.9' above donut

PICK-UP ___

DATUM ___

FLUID LEVEL ___

	SIZE	DEPTH
TUBING	2 7/8	8048
	2 3/8	8522
CASING	No Go plug	8517.8'
CASHING SHOE		
LINER		
TOP		
BOTTOM		
PERFORATION		
TOP		
BOTTOM		

SPECIAL INSTRUCTIONS

Traverse from 4200' to 8500' @ 30'/min. Stop at 4200' for 15 min. Stop line sum 300'

BY ___

REMARKS - USE REVERSE SIDE

R. Hazel (R. Bu)

FIELD OPERATOR

CHART READ BY ___

PLSS FORM 500

SURVEY DATA

DEPTH MEASURED	DEPTH VERTICAL	Lapsed Time	STYLUS DEFLECTION	TEMPERATURE
4200		24	.081	116.2
4350			.089	118.7
4500		34	.096	120.8
4650			.103	122.7
4800		44	.110	124.3
4950			.117	125.9
5100		54	.125	127.7
5250			.136	130.3
5400		64	.145	132.3
5550			.156	134.9
5700		74	.165	136.9
5850			.174	139.0
6000		84 (14)	.186	141.8
6150			.197	144.3
6300		96	.209	146.6
6450			.220	148.7
6600		106	.232	150.9
6750			.244	153.1
6900 20.		116	.259	155.8
7050			.272	158.2
7200		126	.285	160.6
7350			.296	162.6
7500		136	.312	165.2
7650			.323	166.9
7800		146	.339	169.4
7950			.352	171.5
8100 *		156	.363	173.2
8250			.387	177.0
8400		168	.412	180.6
8500'	351		.424	182.2
8524'				182.6
8210			.375	175.1

AC_CPUC_0118412

PACIFIC LIGHTING SERVICE COMPANY
SUB-SURFACE TEMPERATURE SURVEY

FIELD Aliso Canyon WELL SS-29 DATE 3-18-74

RECORDER NO. 1853 RUN NO. ___ SHEET NO. 1 OF 2 SHEETS BY R. Hazel

CLOCK HOURS 8 TIME CLOCK STARTED 927 Am TIME RUN COMPLETED ___

WELL CONDITION DURING RUN, SHUT-IN ___ FLOWING ___ INJECTION ___

HOURS WELL, SHUT-IN ___ FLOWING ___ INJECTION ___ BEFORE RUN ___

WELL HEAD PRESSURE

TUBING 1780#

CASING ___

FLOW RATE

GAS MCF/D ___

OIL BBL'S/D ___

WATER BBL'S/D ___

GOR ___

AMBIENT TEMPERATURE ___

ZERO POINT 6.9' above ground

PICK-UP ___

DATUM ___

FLUID LEVEL ___

	SIZE	DEPTH
TUBING	___	___
CASING	___	___
CASHING SHOE		___
LINER	___	
TOP		___
BOTTOM		___
PERFORATION		
TOP		___
BOTTOM		___

SPECIAL INSTRUCTIONS ___

Traverse from 0' to 4500' @ 30'/min. Stopped at 0' for 10 min. Swab line down 200'.

BY ___

REMARKS - USE REVERSE SIDE

R. Hazel (Ron G.)
FIELD OPERATOR

CHART READ BY

SURVEY DATA

DEPTH MEASURED	DEPTH VERTICAL	Lapsed TIME	STYLUS DEFLECTION	TEMPERATURE
0		17	.258	71.7
150			.227	69.5
300		27	.227	69.5
450			.249	71.0
600		37	.273	72.7
750			.314	75.5
900		47	.339	77.1
1050			.365	78.9
1200		54 (7)	.390	80.6
1350			.404	81.4
1500		64	.420	82.4
1650			.445	83.9
1800		74	.470	85.4
1950			.505	87.4
2100		84	.534	89.2
2250			.567	91.0
2400		94	.595	92.4
2550			.621	94.0
2700		104	.650	95.6
2850			.687	97.5
3000		114	.730	100.0
3150			.767	101.8
3300		124	.801	103.5
3450			.852	106.0
3600		134	.905	108.6
3750			.952	110.8
3900		144	.998	112.8
4050			1.065	115.9
4200		154	1.116	118.0
4350		159 (5)	1.160	120.1
4500		167 (13)	1.209	122.1
40'			.178	65.6
75'			.220	68.9
90'			.227	69.5
160			.282	73.3
190			.303	74.8

PLSS FORM 500

AC_CPUC_0118413

Archer - Reed

WIRE LINE SERVICE

205 Baldwin Ave. Ventura, Calif. 93030

VENTURA 642-7061
LONG BEACH 591-0921

SUB-SURFACE DATA

Company Southern Calif. Gas Co. Field Date 5-1-73 Run No. 1

Well Std. Sessnon #29 Zone Elev.

Purpose Status

Total Depth Effect. Depth

Casing Size Depth Liner Size Top Bottom

Perforations

Tubing

Company	Southern Calif. Gas Co.
Well	Std. Sessnon #29
Date	Date
Arrive A P	Arrive A P
Leave A P	Leave A P
Inst. No.	6788 Size 3450
Inst. No.	7580 Size 43-270
Clock No.	Hrs. 3
Clock No.	Hrs. 3
Stylus Marked	12:21 PM A P
Pressure On	12:25 PM A P
Depth	8500 Zero KB
At Depth Date	5-1-73 Time 1:08 PM A P
Off Depth Date	5-1-73 Time 1:23 PM A P
Shut In Date	unknown Time A P
Start Press Tbg.	Csg. #
Final Press Tbg.	Csg. #
Pick-up	8500 Temp. 177 F

OBSERVATIONS


Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas - Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	
Casing Fluid Level - Ft.	

TIME	DEPTH	SCALE	PSI or °F	TIME	DEPTH	SCALE	PSI or °F
/	PRESSURE			/TEMPERATURE			
1225 /1230	0	.678	1168	1225/1230	0	.050	68
1240 /1245	5000	.769	1328	1240/1245	5000	.245	118
1247 /1252	6000	.785	1356	1247/1252	6000	.345	135
1255 /100	7000	.803	1388	1255/ 100	7000	.446	151
102 /107	8000	.824	1425	102/ 107	8000	.512	160
108 /	8500	.834	1442	108/	8500	.647	177
113 /	8500	.834	1442	113/	8500	.647	177
118 /	8500	.834	1442	118/	8500	.647	177
123 /	8500	.834	1442	123/	8500	.647	177
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			

COMMENTS

Ru

AC_CPUC_0118414




AC_CPUC_0118415

Standard Sesnon 29 Aliso Cyn.
Well Test File

AC_CPUC_0118416

WELL: SS-29


MARKER	TD	LENGTH	D	CSG ID
7" 23#	6494	6494	"	6.366"
26#	8002	1508	D x 5.37"	6.276"
			"	"
			"	"
			"	"
SSSV	8002	0	2.313"	
TBG Pt 1	8029	27	2.441"	
TBG Pt 2			"	
TBG Pt 3			"	
BHC	8029	0	2.205"	
TBG TAIL	8049	20	2.441"	
CSG Pt 1			"	
CSG Pt 2			"	
LNR TOP	8075	26	6.276"	
S8 / MPP	8520	445	4.276"	




DATE	SIWHP	Q	ΔP^2	P/Z
① 12-14-81	2200	31000	4.31	317
② 1-27-82	1360	12000	2.30	182
③ 11-9-82	2400	57000	1.29	352
④ 12-20-82	1620	34000	2.45	247

C = .02447

n = .9128



AC_CPUC_0118417




FIELD: ALISO


WELL: SS 29

DATE: 10/17/78


TEST NO.	Q	ΔP^2	DATE
L1	23.5	1.7	
L2	32.5	2.2	
L3	35.2	3.38	



AC_CPUC_0118418



AC_CPUC_0118419



AC_CPUC_0118420

SOUTHERN CALIFORNIA GAS COMPANY

Compiled 9.16.85 Date JB

Checked ..... Checked .....

Approved ..... Job No. .....

WELL NAME: SS-29 workovers; 3.79 repl. SSSV

WELL TEST INFORMATION

16 hr flow test values unless noted – erosion rates on 6" pipe

	DATE	SIWHP (psig)	FWHP (psig)	FW TEMP. (°F)	RATE (MMcf/d)	ΔP^2 (x 10^6 psia)	P/Z (psia)	CHOKE (in.) BHC	CHOKE (in.) SFC	INVENTORY (Bcf)	P_{DS}/T_{DS} (psig/°F)	EROSION (%)	
1	7.11.78	2535	1925	93	23.7				0.74		590 25		1
2	9.5.78	2680	1300	74	36.5				1.10		620 44		2
3	12.14.81	2200	580	68	31			0.86	—		—		3
4	1.27.82	1360	560	86	12			suspect BHC still in well	⊖		—	⊖	4
5	11.9.82	2440	600	52	48			0.85			—	8.46	5
6	12.20.82	1620	525	75	34			0.85			—	1.72	6
7	1.30.85	1330	530	—	30				⊖		— 97	2.38	7


AC_CPUC_0118421

K+E 10 X 10 TO THE CENTIMETER 18 X 25 CM.
KEUFFEL & ESSER CO. MADE IN U.S.A.

461510

SS-29 date of test 4-19-76 current rate = 21 MMCFD

Test rate 23.1 - 21.4 MMSCFD,



AC_CPUC_0118422

CALCULATION SHEET

REF. Also

BY MEM - BEJ


CHECKED -

DATE March 1973

SHEET NO. ____ OF ____ SHEETS

TITLE SS-29 well test

Possible interpretations of fault plane from well test data



PLS FORM 19

AC_CPUC_0118423

JOHNSTON

P. O. BOX 36369 ■ HOUSTON, TEXAS

A Division of Schlumberger Technology Corporation

SERVICE CONTRACT & FIELD REPORT

20090 B

SURFACE DATA

Description (Rate of Flow)	Time Date	Pressure P.S.I.G.	Surface Choke
Set Packer 2-10-73	1035		
Opened Tool	1037		
SHUT IN @ SURFACE TO	1047	980	1/8
OPEN TO FLOW - 1047	1055	1039	1/8
~~Closed for Initial Shut-in~~	1110	921	1/2
	1140	668	1/2
Finished Shut-in	1240	730	1/2
~~Re-opened Tool~~	1340	747	1/2
	1440	757	1/2
	1537	762	1/2
CLOSED IN @ SURFACE 2-10-73	1537		
P.S.I. AT SURFACE 2-12-73	0620	1180	
OPEN WELL TO TANK - 2-12-73	0620		
	0700	779	1/2
	0800	810	1/2
	0930	827	1/2
	1030	807	1/2
	1130	767	1/2
	1230	777	1/2
	1330	767	1/2
6300	1430	767	1/2
	1630	765	1/2
	1730	765	1/2
	1820	765	1/2
Closed for Final Shut-in 2-12-73	1823	765	
Pulled Packer Loose 2-13-73	0640		

Cushion Type	Amount	Pressure
	0	

Bottom Choke Size 1/2

HOLE DATA

Conventional ☐ Straddle ☐ MFE ☒

Formation Tested		Elevation	Ft.
Net Productive Interval	46 Ft.	Est. Porosity	%
All Depths Measured From	KB	Total Depth	9077 Ft.
Open Hole Size		Rat Hole Size	
Casing Size	7"	Liner Size	5"

MUD DATA

Mud Type	WATER & GEL		
Weight	63	Viscosity	Water Loss C.C.
Resist: of Mud	@ °F; of Filtrate	@ °F	Chloride PPM

EQUIPMENT SEQUENCE

Show Price* or Indicate X For Extra Services To Be Charged	Code	Components	Type	Size	Length-Depth	I. D.
		TUBING	EUE	2 1/16		
		TUBING	EUE	2 3/8		
41.00	137	REV. CIRC VALVE	K-0	2 3/8	.85	
		LIFT NIPPLE		2 3/8	4.60	
609.00	101	MFE TOOL		3 1/16	10.05	
		MFE BIAS		3 1/16	1.77	
160.00	117	JARS	FJ	3 1/16	6.40	
		PACKER	MST	5"	5.35	8423
		PERFS	Slot	2 1/8	8.00	
		RECORDER	T	3 1/8	5.05	84.
		RECORDER	T	3 1/8	5.05	8443
		RUNNING CAP		5"	3.70	8446
192.00	102	24 HR CLOCK				
246.00	103	24 HR CLOCK				
1248.00						

RECOVERY DESCRIPTION	FEET	BARRELS	% OIL	% WATER	% OTHERS	API GRAV.	RESIST.	CHL. PPM
						@ °F	@ °F	
						@ °F	@ °F	
						@ °F	@ °F	
						@ °F	@ °F	
						@ °F	@ °F	
						@ °F	@ °F	

Reversed Out: Time Started: Time Finished: Pump Pressure P.S.I.G.

Remarks:

To: JOHNSTON: You are hereby requested to perform or attempt to perform the following service(s) or furnish the following equipment, on a rental or purchase basis, as indicated:

WELL IDENTIFICATION

Well Owner: SOUTHERN CALIF GAS Co. Reports Address: AT DON SMILEY 1200 W. LINCOLN MONTEBELLO, CALIF

Well & No. SS # 29 Field: ALISO CAN County: LOS ANGELES State: CALIF

Tested Interval: 8456 Ft. To 8502 Ft. Test No. 2 Location:

Said well has been drilled to 9077 - WORKOVER ft. and is in good condition.

The undersigned, hereinafter referred to as customer, agrees to pay you for the above specified service(s) or equipment (leased or purchased), and any additional service(s) or equipment requested, at Johnston's office in Houston, Harris County, Texas, in accordance with the provisions of your current applicable price schedule.

In consideration of the prices as are set out in your current applicable price schedule, we choose to be bound by the terms and conditions set out on the reverse side hereof, including the assumption by us of the liabilities and responsibilities contained in the hold harmless and exculpatory clauses, rather than enter into a different contract and furnish you insurance against the liabilities and responsibilities herein assumed by us.

If signed by an agent on behalf of customer, said agent represents that he has full authority from his principal to execute same; in the absence of authority, the signer agrees that he shall be obligated hereunder as Customer.

Customer's Name SOUTHERN CALIF GAS Co (PRINT) Address 1200 W LINCOLN MONTEBELLO, CALIF

Invoice Mailing Address SAME

X By D. A. Smiley

(SIGNATURE OF CUSTOMER OR AUTHORIZED REPRESENTATIVE) (TITLE AND ADDRESS IF EXECUTED BY CUSTOMER'S REPRESENTATIVE)

M.F.E. SAMPLER DATA

Sampler Drained: ☐ on location ☐ service center ☐ other

☐ laboratory - Name

Address

Recovery		Resistivity	Chl. Content
Cu. Ft. Gas	Recovered Water @ °F		PPM
C.C. Oil	Recovered Mud @ °F		
C.C. Water	Rec. Mud Filtrate @ °F		PPM
C.C. Mud	Pit Mud @ °F		
Gravity °API °F	Pit Mud Filtrate @ °F		PPM
Gas/Oil Ratio			Cu. Ft./Bbl.
Sampler Pressure			P.S.I.G. at Surface

I certify that the above ordered services and/or equipment have been performed or furnished.

By J. N. Bugg, Johnston Operator

Test Accepted as ☐ Successful ☐ Unsuccessful Johnston District 315

X By D. A. Smiley Date

(Signature of Customer or His Authorized Representative)

By

(Please Print the Above Signature)

B 20090 Customer Purchase Order No.

INSTRUMENT DATA

Instrument No.	T-159	T 217			
Capacity (P.S.I.G.)	7000	7000			
Depth	8438	8443			
Inside-outside	IN	IN			
Clock Cap. Hr.	60	96			
Temperature °F.	183	183			
I. Hyd. P.S.I.G.					
I. Flow P.S.I.G.					
I.S.I. P.S.I.G.					
2nd Flow P.S.I.G.					
2nd S.I. P.S.I.G.					
F. Flow P.S.I.G.					
F.S.I. P.S.I.G.					
F. Hyd. P.S.I.G.					

Extra Technical Reports

Marine Operations: Inland ☒ Offshore ☐

Tool Rental Time Hours

Operator's Time Hours

Mileage Miles

Special Data Analysis ☐ Breakdown ☐

Make of Gun Used: Jet Bullet

No. of Shots Intervals Perforated

Total *All prices estimated and subject to correction.

	Date	Time
On Location	2-10	0630
Started Operations	2-10	0700
Ceased Operations	2-14	1700
Off Location	2-14	1800

FORM J-184 (REV. 6-66)

AC_CPUC_0118424

WELL TEST FILE

STAND OESNO 29 GI[illegible]

1/64

1000" TUB- 1050" CHS.

DATE	24 HR GAS RATE	FLUID GROSS	FLUID NET
MARCH 18	1836 MCF	18.0	12.0
MARCH 23	1964 MCF	12.0	8.0
APRIL 2	2483 MCF	16.0	12.0
APRIL 6	2361 MCF	13.0	11.0

AC_CPUC_0118425

JOHNSTON

P. O. BOX 36369 ■ HOUSTON, TEXAS

A Division of Schlumberger Technology Corporation

SERVICE CONTRACT & FIELD REPORT

20090 B

SURFACE DATA

Description (Rate of Flow)	Time / Date	Pressure P.S.I.G.	Surface Choke
Set Packer 2-10-73	1035		
Opened Tool	1037		
SHUT IN @ SURFACE TO	1047	980	1/8
OPEN TO TANK - 1047.	1055	1039	1/8
~~Closed for Initial Shut-in~~	1110	921	1/2
	1140	668	1/2
Finished ~~Shut-in~~	1240	730	1/2
Re-opened Tool	1340	707	1/2
	1440	757	1/2
	1537	762	1/2
CLOSED IN @ SURFACE 2-10-73	1537		
P.S.I. AT SURFACE 2-12-73	0620	1180	
OPEN WELL TO TRAP - 2-12-73	0620		
	0700	779	1/2
	0800	810	1/2
	0935	827	1/2
	1030	807	1/2
	1132	767	1/2
	1232	777	1/2
	1330	767	1/2
1530	1430	767	1/2
	1630	765	1/2
	1730	765	1/2
	1820	765	1/2
Closed for Final Shut-in 2-12-73	1823	765	
Pulled Packer Loose 2-13-73	0640		

Cushion Type	Amount	Pressure
	0	

Bottom Choke Size 1/2

HOLE DATA

Conventional ☐ Straddle ☐ MFE ☒

Formation Tested — Elevation — Ft.

Net Productive Interval 46 Ft. — Est. Porosity — %

All Depths Measured From K.B. — Total Depth 9077 Ft.

Open Hole Size 8 3/4 — Rat Hole Size

Casing Size 7" — Liner Size 5"

MUD DATA

Mud Type WATER & GEL

Weight 63 — Viscosity — Water Loss — C.C.

Resist. of Mud @ °F — Filtrate @ °F — Chloride PPM

Show Price* or Indicate X For Extra Services To Be Charged: CODE

EQUIPMENT SEQUENCE

		Components	Type	Size	Length-Depth	I.D.
		TUBING	EUE	2 1/8		
		TUBING	EUE	2 1/8		
41.00	137	REC. CIRCULAR	KO	2 3/8	.85	
		LIFT NIPPLE		2 3/8	4.60	
609.00	101	MFE TOOL		3 1/8	10.05	
		MFE BIAS		3 1/8	1.77	
160.00	117	JARS	FJD	3 1/8	6.40	
		PACKER	HNT	5"	5.35	8423
		PERFS	Slot	2 7/8	8.00	
		REC CARRIER	T	3 1/8	5.05	84.
		REC CARRIER	T	3 1/8	5.05	84.3
		C TRP RUNNING		5"	3.70	84.15
192.00	102	2 JTS @ 600				
246.00	103	2 JTS @ 780				
1248.00						

RECOVERY DESCRIPTION	FEET	BARRELS	% OIL	% WATER	% OTHERS	API GRAV.	RESIST.	CHL. PPM
						@ °F	@ °F	
						@ °F	@ °F	
						@ °F	@ °F	
						@ °F	@ °F	
						@ °F	@ °F	
						@ °F	@ °F	

Reversed Out: Time Started: — Time Finished: — Pump Pressure — P.S.I.G.

Remarks:

To: JOHNSTON: You are hereby requested to perform or attempt to perform the following service(s) or furnish the following equipment, on a rental or purchase basis, as indicated:

WELL IDENTIFICATION

Well Owner: SOUTHERN CALIF GAS Co. — Reports Address: 1200 W. LINCOLN MONTEBELLO, CALIF — AT DON SMILEY

Well & No. S.S. # 29 — Field: ALISO CAN — County: LOS ANGELES — State: CALIF

Tested Interval: 8456 Ft. To 8502 Ft. — Test No. 2 — Location:

Said well has been drilled to 9077 - WORKED ft. and is in good condition.

The undersigned, hereinafter referred to as customer, agrees to pay you for the above specified service(s) or equipment (leased or purchased and any additional service(s) or equipment requested, at Johnston's office in Houston, Harris County, Texas, in accordance with the provisions of your current applicable price schedule.

In consideration of the prices as are set out in your current applicable price schedule, we choose to be bound by the terms and conditions set out on the reverse side hereof, including the assumption by us of the liabilities and responsibilities contained in the hold harmless and exculpatory clauses, rather than enter into a different contract and furnish you insurance against the liabilities and responsibilities herein assumed by us.

If signed by an agent on behalf of customer, said agent represents that he has full authority from his principal to execute same; in the absence of such authority, the signer agrees that he shall be obligated hereunder as Customer.

Customer's Name SOUTHERN CALIF GAS Co. (PRINT) — Address 1200 W LINCOLN MONTEBELLO, CALIF

Invoice Mailing Address SAME

X By W. S. Smiley (SIGNATURE OF CUSTOMER OR AUTHORIZED REPRESENTATIVE) (TITLE AND ADDRESS IF EXECUTED BY CUSTOMER'S REPRESENTATIVE)

M.F.E. SAMPLER DATA

Sampler Drained: ☐ on location ☐ service center ☐ other

☐ laboratory - Name

Address

Recovery		Resistivity	Chl. Content
Cu. Ft. Gas	Recovered Water	@ °F	PPM
C.C. Oil	Recovered Mud	@ °F	
C.C. Water	Rec. Mud Filtrate	@ °F	PPM
C.C. Mud	Pit Mud	@ °F	
Gravity °API °F	Pit Mud Filtrate	@ °F	PPM
Gas/Oil Ratio			Cu. Ft./Bbl.
Sampler Pressure			P.S.I.G. at Surface

INSTRUMENT DATA

Instrument No.	T-159	T-217				
Capacity (P.S.I.G.)	7000	7000				
Depth	8438	8443				
Inside-outside	IN	IN				
Clock Cap. Hr.	60	96				
Temperature °F.	183	183				
I. Hyd. P.S.I.G.						
I. Flow P.S.I.G.						
I.S.I. P.S.I.G.						
2nd Flow P.S.I.G.						
2nd S.I. P.S.I.G.						
F. Flow P.S.I.G.						
F.S.I. P.S.I.G.						
F. Hyd. P.S.I.G.						

I certify that the above ordered services and/or equipment have been performed or furnished.

By J. M. Boggs, Johnston Operator

Test Accepted as ☐ Successful ☐ Unsuccessful Johnston District 315

X By W. S. Smiley Date

(Signature of Customer or His Authorized Representative)

By

(Please Print the Above Signature)

B 20090 Customer Purchase Order No.

Extra Technical Reports

Marine Operations: Inland ☒ Offshore ☐

Tool Rental Time ____ Hours

Operator's Time ____ Hours

Mileage ____ Miles

Special Data Analysis ☐ Breakdown ☐

Make of Gun Used: Jet ____ Bullet ____

No. of Shots ____ Intervals Perforated ____

1248 Total

*All prices estimated and subject to correction.


	Date	Time
On Location	2-10	0630
Started Operations	2-10	0700
Ceased Operations	2-14	1700
Off Location	2-14	1900

FORM J-184 (REV. 6-66)

AC_CPUC_0118426


Day	Date	(T/C/D)	SIWHP	FWHP	Choke (in.)	DS	E (%)	Q (MMCFD)	(Pts^2-Ptf^2) x 10^6	"C"	Check
1	7/11/1978	C	2535	1925	0.74	590	3.5	23.7	2.738	0.028	24
56	9/5/1978	C	2680	1300	1.1	620		36.5	5.533	0.024	36
1235	12/14/1981	C	2200	580	0.86			31	4.551	0.024	31
1278	1/27/1982	C	1360	560				12	1.559	0.023	12
1560	11/9/1982	C	2440	600	0.85		8.5	48	5.648	0.031	48
1601	12/20/1982	C	1620	525	0.85		1.7	34	2.381	0.046	34
2361	1/30/1985	C	*1330*	530			2.4	30	1.511	0.060	30
4526	2/5/1991	C	1660	1505			0.1	25	0.495	0.128	25
4859	1/8/1992	C	1880	1320	0.80		1.3	18	1.808	0.031	18

Figure 1
SS-29
Wellhead Performance Curves



AC_CPUC_0118428

Figure 2
SS-29
"C" factor v. Time



AC_CPUC_0118429

NODAL ANALYSIS RESULTS
****

SS 29 SAND TEST 11/82

SUMMARY OF GENERAL INPUT DATA
****

GAS GRAVITY = .63
WELLHEAD PRESSURE,PSIG = 600.0

SUMMARY OF INPUT DATA FOR RESERVOIR MODULE
****

AVERAGE RESERVOIR PRESSURE,PSIG = 3032. Z=.8912

P/Z = 3402

INFLOW
******

CALCULATED AOF= 74259.05

FLOW RATE	NODE PRESSURE,PWF
57000.	1454.

SUMMARY OF INPUT DATA FOR WELL MODULE
****

WELL CONFIGURATION
****

DEPTH	TUBING DIA.	ANGLE	CASING DIA.	TUBING I.D.
8002.	2.875	.00	6.366	.000
8011.	2.205	.00	.000	.000
8049.	2.441	.00	.000	.000
8075.	.000	.00	6.366	.000
8575.	.000	.00	4.277	.000

PIPE ABS. ROUGHNESS,IN. = .00094
BOTTOM-HOLE TEMPERATURE,DEG-F = 158.
NUMBER OF LENGTH INCREMENTS = 10

PRESSURE DROP CORRELATION:
CULLENDER AND SMITH

OUTFLOW
****

FLOW RATE	PWH	NODE PRESSURE,PWF	WELLHEAD TEMP.
57000.	600.	1364.	52.

$\Delta P^2 = 7.33 \times 10^6$

AC_CPUC_0118430

WELL: SS 29

FLOW: CSG / ~~TBG~~

	TVD'
(1) SSSV:	8002'
(2) S8/~~MPP~~:	8520'
(3) -5400:	8299'
(4) Gas Gr:	0.63
(6) T_{avg}:	119 °F
(5) T_{bh}:	169 °F

MD S8: 8250'

TVD' MARKER LLLL'. D.DDD"		
(20)	0.0	
(21)	0.0	
(22)	8002. 5137	
(23)	0.2313	
(24)	27.2491	
(25)	0.2205	
(26)	20.2941	
(27)	26.6276	
(28)	445.4276	
(29)	0.0	

	DATE: 12-14-81		DATE: 1-27-82		DATE: 11-9-82		DATE: 12-20-82		DATE:	
	TEST: 1		TEST: 2		TEST: 3		TEST: 4		TEST:	
	P_{up}.T_{up}: 580 .068		P_{up}.T_{up}: 560 .086		P_{up}.T_{up}: 600 .052		P_{up}.T_{up}: 525 .077		P_{up}.T_{up}: .	
	SIWHP: 2200 psi		SIWHP: 1360 psi		SIWHP: 2400 psi		SIWHP: 1900 psi		SIWHP: psi	
	SIBHP's		SIBHP's		SIBHP's		SIBHP's		SIBHP's	
	SSSV: 2700 psi		SSSV: 1656 psi		SSSV: 2992 psi		SSSV: 1990 psi		SSSV: psi	
	S8/MPP: 2736 psi		S8/MPP: 1677 psi		S8/MPP: 3022 psi		S8/MPP: 2007 psi		S8/MPP: psi	
	-5400: 2717 psi		-5400: 1666 psi		-5400: 3011 psi		-5400: 1993 psi		-5400: psi	
	P_{up}: 580 psi		P_{up}: 560 psi		P_{up}: 600 psi		P_{up}: 525 psi		P_{up}: psi	
	P_{dn}: 570 psi		P_{dn}: 560 psi		P_{dn}: psi		P_{dn}: psi		P_{dn}: psi	
	T_{up}: 68 °F		T_{up}: 86 °F		T_{up}: 0520 °F		T_{up}: 77.5 °F		T_{up}: °F	
	S. Chk: — "		S. Chk: — "		S. Chk: — "		S. Chk: "		S. Chk: "	
	Q: 31000 MCF/D		Q: 12000 MCF/D		Q: 57000 MCF/D		Q: 37000 MCF/D		Q: MCF/D	
	Erosion: 6.6 %		Erosion: 0 %		Erosion: 2.4%		Erosion: 1.7%		Erosion: %	
	Oil Prod: — B/D		Oil Prod: — B/D		Oil Prod: — B/D		Oil Prod: — B/D		Oil Prod: B/D	
	° API: —		° API: —		° API: —		° API: —		° API:	
	ANALYZE	DESIGN	ANALYZE	DESIGN	ANALYZE	DESIGN	ANALYZE	DESIGN	ANALYZE	DESIGN
(20)										
(21)										
(22)	580		560		600		525			
(23)	881		710		1199		962			
(24)	895		712		1233		879			
(25)	912		716		1275		901			
(26)	1752	[0.86 BHC]	719		1314		2026	[D...		
(27)	1759		722		1344		2035			
(28)	1761		723		1345		2036			
(29)	1789		734		1398		2066			
ΔP^2:	4.31 X 10^6		2.30 X 10^6		7.29 X 10^6		-2.45 X 10^6		X 10^6	
Design Q:	MCF/D		MCF/D		MCF/D		MCF/D		MCF/D	
DsgnΔP^2:	X 10^6		X 10^6		X 10^6		X 10^6		X 10^6	
Dsgn Chk:	"		"		"		"		"	
By:	JBL	$\frac{P}{Z}$ = 3175	JBL	$\frac{P}{Z}$ = 1823	DM	$\frac{P}{Z}$ = 3526	DM	$\frac{P}{Z}$ = 238		

AC_CPUC_0118431

WELL: 55-29

LOW: (CSG)/TBG


MARKER	TVD'
SG/ TBG	
P S.CHK	
SSSV	8390
8 / MFP	8520'
8 / MFP psia	
-5400'	8249'
SIBHPest	
Pavg ann	
Zavg ann	


No directional survey

	TEST #: 2-1	TEST #: 2-2	TEST #: 2-3	TEST #:
	DATE: 9-11-78	DATE: 8-29-78	DATE:	DATE:
S.I. PSIG GAUGE	2535	2600	2680	
S.I. PSIG BOMB	—	—	—	
FLOWING PSIG ANALYSE CALC	1920	1670	1280	
FLOWING PSIG ANALYSE MEAS	2780 / 1920	2330 / —	2520 / 1380	
FLOWING PSIG DESIGN PRED.		1678	1259	
	3130 / 2464	3209 / 2164	3306 / 2613	
	3140 / 2864	3220 / 2833	3316 / 2782	
	3155 / 2878	3234 / 2848	3331 / 2747	
	3119	3198	3294	
	3141	3220	3317	
	2838	2910	2999	
	.8160	.8174	.8200	
	Rec'md: — " Chk	Rec'md: .9 " Chk	Rec'md: 1.10" Chk	Rec'md: .750" Chk
	For: — MCF/D	For: 31M MCF/D	For: 36.11 MCF/D	For: 35.3 MCF/D
	By: — On: —	By: CJ On: 8/19/78	By: WLC On: 8-30-78	By: JWT On: 9/07/78
SHUT IN SURVEY BOMB	68 / —	72 / —	68 / —	— / —
FLOWING BOMB ESTIMATED	90 / —	100 / —	74 / —	— / —
	169 / — / 150	171 / — / 150	177 / — / —	— / — / —
	119 / — / 120	119 / — / 110	117 / — / —	— / — / —
CHK SIZE	SURFACE .741" SSSV .750" BHC NONE"	SURFACE .9" SSSV .750" BHC .750"	SURFACE 1.100" SSSV .750" BHC NONE"	SURFACE 1.0" SSSV .750" BHC NONE"
Pup, Tup sf chk	1920 psig, 89 F	1670 psig, 96 F	1280 psig, 74 F	____ psig, ____ F
Pdn, Tdn sf chk	580 psig, 24 F	620 psig, 30 F	620 psig, 85 F	____ psig, ____ F
Q, $\Delta(P_e^2-P_{wf}^2)$	23,515 MCF/D, 1.7 X10^6	32,196 MCF/D, 2.2 X10^6	35,201 MCF/D, 3.5 X10^6	____ MCF/D, ____ X10^6
OIL PRODUCTION	— °API @ 60°F, — % BS&W	— °API @ 60°F, — % BS&W	— °API @ 60°F, — % BS&W	— °API @ 60°F, — % BS&W

MARKER	TO	LENGTH	D	CSG ID	TBG OD
7" 23#	6494'	6494'	"	6.366"	2.875"
7" 26#	7990'	1500'	"	6.276"	2.875"
7" 26#	8075'	85'	5.137"	6.276"	2.375"
5" 18#	8400'	325'	3.1410"	4.276"	2.375"
			"		
SSSV	8400'	0	1.875"		
TBG Pt 1	8421'	21'	1.995"		
TBG Pt 2			"		
TBG Pt 3			"		
BHC	8421'	0	1.56"		
TBG TAIL	8438'	16'	1.995"		
CSG Pt 1			"		
CSG Pt 2			"		
LNR TOP			"		
S8 / MFP	8520'	82'	4.276"		

SSV is choke
No BHC n= C=





JWT:jwt (rev. 8/08/78) TEST WORKSHEET

AC_CPUC_0118432

WELL NO: 55-

CHOKE & PRESSURE WORKSHEET

ANALYSE	DESIGN	P_a	(00) T_a	(11) Z_a	(22) Q	(B) D''	(C) L'	(D) P_{wh}	(E) P_{bh}
		55V IS CHOKE				—	—	—	—
B		1525	120	.8349	33.200	5.137	3078	(1280)	1694
C		1700	140	.8476		3.14	325	1604	1730
D						.350	0	1730	2693
E		2700		.8366		1.995	21	2693	2711
F						1.56	0	2711	2791
G		2750		.8364		1.095	16	2741	2755
			↓		↓	4.276	12	2755	2761
	4B	2700	140	.8356	40.000	4.276	32	2705	2718
	C					1.095	16	2685	2703
	D	2615		.8353		1.56	0	2646	2687
	E	2650		.8349		1.995	21	2622	2646
	F					.350	0	39.041 ↓	2622
	G	2622	↓	.8344		3.14	325	* WELL CANNOT	
	H		120		↓	5.137	3078	FLOW 40 MCF/D. WILL	
								TRY 36 MCF	
	4H'	1700	120	.8476	↑	5.137	3078		
	G'	1650	↑	.8407		3.14	325		
	F'	↑		↑		.350	0	36.280	2715
	E'	2725		.8360		1.995	21	2715	2734
	D'	↑		↑		1.56	0	2734	2767
	C'					1.095	16	2767	2781
	B'	2735	140	.8364	36.400	4.276	32	2781	2788
					Q =	1.100			

9-6-78: FOR FINAL TEST BEAN WAS .750 SSV NO SURFACE CHOKE OR BHC FOR 36.3 MM²

WELL HAS SMALL FIELD PIPING & 1.1" CHK WILL REMAIN TO ASSIST FIELD OPERATORS IN PUTTING WELL ON.

AN.	DS.	(22) Q	(E') $\Delta(P_e^2-P_{wf}^2)$	(D') SIBHP psig	P_{wf} @S8 psig
3C		35.200	3.38×10^8	3316	2761
	4A	40.000	3.65×10^6	3316	2716
	4A'	36.400	3.24×10^6	3316	2788

NOTE: (D') must be hit before (E')

ANAL.	DSGN.	(00) T_{up}	(B) CHK''	(A') P_{up}	(B') P_{dn}	Q_{sub}	Q_{crit}	Q_{meas}
2A		[illegible]	1.100	[illegible]	[illegible]	—	39.232	35.2
	4I	100	1.100	1221	600	—	36.964	—

AC_CPUC_0118433

WELL NO: 55-

CHOKE & PRESSURE WORKSHEET

ANALYSE	DESIGN	P_a	(00) T_a	(11) Z_a	(22) D''	(33) Q	(C) L'	(D) P_{wh}	(E) P_{bh}
2B		1925	120	.8770	5.137	32.500	8075	(690)	2119
C		2150	140	.8352	3.14		325	2119	2164
D					.750		0	2164	2800
E		2825		.8379	1.995		21	2800	2815
F					1.56		0	2815	2840
G		2850		.8384	1.995		16	2840	2891
H			↓		4.276	↓	82	2891	2858
			55		15 CHOKE				
2G'		2925	140	.8379	1.995	32.500	16	2915	2827
H'		2850	↓	.8384	4.276	↓	82	2827	2733
	3B	2750	140	.8384	4.276	36.000	82	2757	2771
	C	2725		.8360	1.995		16	2743	2757
	D				1.995		21	2724	2743
	E				.750		0	1670	2724
	F	1650	↓	.9497	3.14		325	1654	1670
	G	1450	120	.8395	5.137	↓	8075	1259	1654
	H		100	–	1.1	37.689	0	600	1259

ANALYSE	DESIGN	P_a	(00) T_a	(11) Z_a	(22) D''	(33) Q	(C) L'	(D) P_{wh}	(E) P_{bh}

AN.	DS.	Q	$\Delta(P_e^2-P_{wf}^2)$	P_e psia	P_{wf} psia	P_{wf} psig
2I		32.5	2.2×10^6	3234	2873	2858
2I'		32.5	2.3×10^6	3234	2848	2833
	3A	36.0	2.7×10^6	3234	2785	2771

ANAL.	DSGN.	(44) T_{up}	(55) CHK''	(A) P_{up}	(B) P_{dn}	(A') Q_{sub}	(B') Q_{crit}	(C') T_{dn}	ΔT
2A		90	.9	1670	620		33.673	-19	52.5
2D		140	.750	2800	2164	32.5		106	
2E		140	.750	3296	2815	32.5		119	
	3E	140	.750	2724	1670	36.0		77	
	3H	100	1.1	1259	600		37.689	15	

JWT:cma (rev. 8/9/78

AC_CPUC_0118434

WELL NO: SS-29

CHOKE & PRESSURE WORKSHEET

ANALYSE	DESIGN	P_a	(A') T_a	(B') Z_a	(A) L'	(B) Q	(C) D''	(D) P_{wh}	(E) P_{bh}
1A		2200	100	.7845	8075	26,200	5.137	1920→	2128
1B			127		325		3.140	2928	2964
C			145		0		.750	2464	2823
D		2825	145	.8433	21		1.995	2823	2833
E			150		0		1.56	2833	2850
F		2875	150	.8497	16		1.995	2850	2858
G			150		82	↓	4.276	2858	2869
	2B	2750	150	.8472	82	30,000	4.276	2769	2770
	C		↓		16		1.995	2753	2769
	D				0		1.56	2730	2753
	E	2725	149	.8468	21		1.995	2716	2730
	F				0		.750	2170	2716
	G	2925	110	.8043	325		3.140	2129	2170
	H				8075	↓	5.137	1678	2129

AN.	DS.	Q	$\Delta(P_e^2-P_{wf}^2)$	P_e psia	P_{wf} psia	P_{wf} psig
1H		26,200	1.7×10^6	3155	2878	2864
	2A	30,000	2.2×10^6	3155	2785	2770

ANAL.	DSGN.	(A) P_{up}	(B) P_{dn}	(C) T_{up}	(D) CHK''	(E)	(A') Q_{sub}	(B') Q_{crit}	(C') T_{dn}
1A		1920	530	89	.174			26,237	
1G		2823	2464	145	.750		26,200	127°	
1E		2850	2833	150	1.56		26,600	149°	
	2D	2753	2730	150	1.56		30,402	149°	
	2F	2716	2170	149	.750		30,000	119°	
	2I	1678	580	100	.9		30,600	118°	

JWT:cma (rev. 8/9/78

AC_CPUC_0118435

WELL NO: SS-29 DATE: 1-30-85 OPERATOR: _____ TEST NO: _____

B. H. CHOKE: — " SURF. CHOKE: — " BOMBS RUN?: ~~YES~~ / NO

FLOWING STRING: CSG/~~TBG~~ . SAFETY VALVE ~~IN~~ / OUT? PROBE REMARKS. _____

LIQUIDS _____ bbls. WATER CUT (%BS&W): _____ OIL GRAVITY: _____ @ _____ °F

PROBE INFORMATION:

NUMBERS:	US#1	US#2	DS#1 89 ✓	DS#2 90 ✓
AVG. WT. BEFORE:			136.1555	136.1666
WT. AFTER.	#1		.1525	.1637
6" 60'	#2		.1523	1636
	#3			
EROSION AREA:	#1		0	0
EST. RATE	#2			
13 M²	#3		322	322
HOURS OF FLOW:			6.75	6.75
EROSION RATE:			2.38	2.26

ELAP TIME	TIME OF DAY	CSG PRESSURE	TBG PRESSURE	UPSTREAM SURFACE CHOKE PRESSURE	UPSTREAM SURFACE CHOKE TEMP.	DOWNSTREAM SURFACE CHOKE PRESSURE	DOWNSTREAM SURFACE CHOKE TEMP.	GAS FLOW RATE STATIC	DIFFERENTIAL	TEMPERATURE	COEFFICIENT	RATE
SEUT IN	8 00 A	1330	1330		37		37					
1/2	8 35 A	550	1090			550	83					
1 3/4	945	570	1100			570	93°					
3 3/4	11 45 A	555	1090			555	90°					
6 3/4	2 45 P	530	1080			530	97°					30 MM
						SS-29						JDM

AC_CPUC_0118436

WELL NO: 55-29 DATE: 12-[illegible]-82 OPERATOR: _____ TEST NO: _____

B. H. CHOKE: 0.85 " SURF.CHOKE: NO " BOMBS RUN?: YES / NO

FLOWING STRING: CSG/TBG . SAFETY VALVE IN / OUT? PROBE REMARKS. _____

LIQUIDS _____ bbls. WATER CUT (%BS&W): _____ OIL GRAVITY: _____ @ _____ °F

PROBE INFORMATION:

	US#1	US#2	DS#1	DS#2
NUMBERS:	40	41	42	43
AVG. WT. BEFORE:	136.5535	136.6339	136.6325	136.5789
WT. AFTER. #1	136.5516	136.6320	136.6309	136.5772
#2	136.5514	136.6320	136.6305	136.5771
C/W 6" #3				
EROSION AREA: #1				
#2	0	0	0	0
55-29 #3	3.22	3.22	3.22	3.22
HOURS OF FLOW:	6	6	6	6
EROSION RATE:	1.72	1.63	1.55	1.51

EST RATE 24 MZ

ELAPSED TIME	TIME OF DAY	CSG PRESSURE	TBG PRESSURE	UPSTREAM SURFACE CHOKE PRESSURE	UPSTREAM SURFACE CHOKE TEMP.	DOWNSTREAM SURFACE CHOKE PRESSURE	DOWNSTREAM SURFACE CHOKE TEMP.	GAS FLOW RATE STATIC	DIFFERENTIAL	TEMPERATURE	COEFFICIENT	RATE
SHUT IN	8 20 A	1620	1620	1620	65°	1620	65°					32 MZ
1/2	8 50 A	530	900	530	66°	530	66					
1 1/2	10 00 A	530	800	530	75°	530	75					
2 3/4	11 15 A	530	780	530	79°	530	79					
4 3/4	1 00 P	530	800	530	74°	530	74					
	2 20 P	525	800	525	75°	525	75					34 MZ

AC_CPUC_0118437

WELL NO: 5529 DATE: 11-0-82 OPERATOR: _____ TEST NO: _____

B. H. CHOKE: 0,85 " SURF.CHOKE: _____ " BOMBS RUN?: ~~YES~~ / NO

FLOWING STRING: CSG/~~TBG~~ SAFETY VALVE ~~NO~~ OUT? PROBE REMARKS.

5529 6"

LIQUIDS _____ bbls. WATER CUT (%BS&W): _____ OIL GRAVITY: _____ @ _____ °F

PROBE INFORMATION:



	US#1	US#2	DS#1	DS#2
NUMBERS:	77	81	92	99
AVG. WT. BEFORE:	137,2512	137,2876	137,3812	137,2348
WT. AFTER. #1	137,2481	137,2778	137,3783	137,2315
#2				
LOSS	0,0031	0,0098	0,0029	0,0033
EROSION AREA: #1	0	0	0	0
#2	322	322	322	322
#3				
HOURS OF FLOW:	6	6	6	6
EROSION RATE:	2,67 %	8,46 %	2,50 %	2,85 %

TIME ELA	TIME OF DAY	CSG PRESSURE	TBG PRESSURE	UPSTREAM SURFACE CHOKE PRESSURE	UPSTREAM SURFACE CHOKE TEMP.	DOWNSTREAM SURFACE CHOKE PRESSURE	DOWNSTREAM SURFACE CHOKE TEMP.	GAS FLOW RATE STATIC	DIFFERENTIAL	TEMPERATURE	COEFFICIENT	RATE
SHUT IN	8:45 AM	2440	2440	2440	42°	2440	42°					
30 MIN	9:15 AM	600	1100	600	57°	600	57°					57 m²
1 HR	9:45	600	1100	600	56°	600	56°					
2 HR	10:45	600	1100	600	56°	600	56°					
4 HR	12:45	600	1100	600	56	600	56°					
6 HR	2:45	600	1000	600	52°	600	52°					48 m²

PROBES SENT TO LAB 11-10-82

AC_CPUC_0118438

B. H. CHOKE: NO " SURF. CHOKE: NO " BOMBS DOWN?: [redacted] / NO

FLOWING STRING: CSG/[redacted] SAFETY VALVE [redacted] / OUT? PROBE REMARKS.

LIQUIDS _____ bbls. WATER CUT (%BS&W): _____ OIL GRAVITY: _____ @ _____ °F

PROBE INFORMATION:

	US#1	US#2	DS#1 #3	DS#2
NUMBERS:				
AVG. WT. BEFORE:			136.5146	
WT. AFTER.			136.5166	
	#1		136.5160	
	#2			
	#3			
EROSION AREA:	#1		3.22 in^2	
	#2			
	#3			
HOURS OF FLOW:			6.25 hrs	
EROSION RATE:			—	

6" CASING 60° LAT

SS 29

EST. RATE 19

ELAPSED TIME	TIME OF DAY	CSG PRESSURE	TBG PRESSURE	UPSTREAM SURFACE CHOKE PRESSURE	UPSTREAM SURFACE CHOKE TEMP.	DOWNSTREAM SURFACE CHOKE PRESSURE	DOWNSTREAM SURFACE CHOKE TEMP.	GAS FLOW RATE STATIC	DIFFERENTIAL	TEMPERATURE	COEFFICIENT	RATE
SHUT IN	7:40 A	1360	1360	1360	40°	1360	40°					16.3 M^2
1/2	8:15 A	570	810	570	72°	570	72°					
2 1/4	10:00 A	580	930	580	86°	580	86°					
3 1/4	11:00 A	570	930	570	87°	570	87°					
6 1/4	1:50 P	560	930	560	86°	560	86°					12 m^2

RETURNED TO SERVICE 1-27-82 [redacted]

AC_CPUC_0118439

WELL NO: SS 29 DATE: 12-14-81 OPERATOR: REX & R[illegible] TEST NO: _____

B. H. CHOKE 0.860 " SURF. CHOKE: NO " BOMBS RUN? ~~YES~~ / NO

FLOWING STRING: CSG/~~TBG~~ SAFETY VALVE ~~IN~~ / OUT? PROBE REMARKS. _____

LIQUIDS _____ bbls. WATER CUT (%BS&W): _____ OIL GRAVITY: _____ @ _____ °F

PROBE INFORMATION: 

	US#1	US#2	DS#1	DS#2
NUMBERS:	38			
AVG. WT. BEFORE:	134.1455			
WT. AFTER. #1	134.1363			
#2	134.1363			
#3				
EROSION AREA: #1	3.89 in²			
#2				
#3				
HOURS OF FLOW:	6			
EROSION RATE:	6.6 %			

6" c LATI

5529

(4.9 m²) 24 m²

CST DAILY

ELAPSED TIME	TIME OF DAY	CSG PRESSURE	TBG PRESSURE	UPSTREAM SURFACE CHOKE PRESSURE	UPSTREAM SURFACE CHOKE TEMP.	DOWNSTREAM SURFACE CHOKE PRESSURE	DOWNSTREAM SURFACE CHOKE TEMP.	GAS FLOW RATE STATIC	DIFFERENTIAL	TEMPERATURE	COEFFICIENT	RATE
SHUT IN	7:50 PM	2200	2200	2200	62°	2200	62°					
1/2 HR	8:15 PM	560	930	560	60°	560	60°					44 m²
2 HR	9:50	570	960	570	74°	570	74°					
3 HR	10:50	590	1010	590	68°	580	68°					
4 HR	12:50	580	960	580	70°	570	70°					
6 HR	2:50 PM	580	960	580	68°	570	68°					31 m²

LEFT OUT OF SERVICE FOR YOUR INSP. 12-15-81

AC_CPUC_0118440

NO:

TEST NO. & DATE	PROBE NO.	PROBE LOCATION	ERODED AREA (XXX)	AVERAGE INITIAL WEIGHT (gm)	WEIGHT AFTER TEST (gm)	CHANGE IN WEIGHT (mg)	ERODED AREA (sq In)	EROSION FACTOR	CHOKE & TEST Q	RECM'D NEXT CHOKE & TEST Q	
1, 7-11-78	83	[illegible]		[illegible]	[illegible]	2.0	3.24 *	.013	.241 54 [illegible]		
2, 8-29-78	338	DS #1		138.2576	138.2515	0.3	3.24 *	.0018	.1998 32.5		
3, 9-5-78	364	US #1	↗	[illegible]	144.5539	-0.0 *		.0	1.10 sort 35.2		* negative weight loss
	365	DS #1	↘	144.2455	144.2496	0.4	3.24 *	.0006			

AC_CPUC_0118441

RT: JW 7/3/78

WELL NO: 55-28 DATE: 8-5-78 OPERATOR: Summers TEST NO: L-3

B. H. CHOKE: _____" SURF. CHOKE: 1.100 " (LATERAL) / VESSEL TEST?

FLOWING STRING: (CSG) TBG SAFETY VALVE (IN) OUT ? BOMBS RUN?: YES / (NO)

PROBE ID NO'S--RISER: _____ US#1 #36d US#2 _____ DS#1 #365 DS#2 _____

PROBE AND BULL PLUG REMARKS: _____

WATER CUT (% BS & W): _____ OIL GRAVITY: _____ @ _____ °F

ELAPSED TIME	TIME OF DAY	AIR TEMPERATURE	CSG PRESSURE	TBG PRESSURE	UPSTREAM SURFACE CHOKE		DOWNSTREAM SURFACE CHOKE		GAS FLOW RATE				LIQUIDS
					PRESSURE	TEMPERATURE	PRESSURE	TEMPERATURE	STATIC	DIFFERENTIAL	TEMPERATURE	RATE	
SHUT IN	8:45A		2680	2665									
0:00	8:50A	START FLOW TEST											
0:05							↓						
0:10													
0:15													
0:25													
0:35													
0:45													
1:00	9:50A	71°		2500	1330	86°	630	58°	7.1	6.7	60°	36,762	
1:15													
1:30													
1:45													
2:00	10:50	64°		2380	1320	80°	620	54°	7.1	6.7	60°	36,762	
2:30													
3:00	11:50	63°		2320	1320	79°	610	53°	7.1	6.7	60°	36,762	
3:30													
4:00	12:50	70°		2250	1310	76°	620	47°	7.1	6.65	60°	36,488	
4:30													
5:00	1:50	62°		2200	1300	75°	620	45°	7.1	6.65	60°	36,488	
5:30													
6:00	2:50	61°		1520	1300	74°	620	44°	7.1	6.5	60°	36,488	
6:30													
7:00	3:50	60°		2620	1290	74°	620	45°	7.1	6.45	60°	35,390	
7:30													.7729
8:00	4:50	60°		2580	1280	74°	620	45°	7.1	6.45	60	35,390	

JWT/wlc (rev. 7/19/78) Field Test Data Sheet 7.09 6.43 39.201

AC_CPUC_0118442

API GRAVITY DETERMINATION WORKSHEET

WELL # _____

Hydrometer reads _____ ° API at _____ °F.

Go to API charts, find corrected reading for this temp. and the closest numbers either side of the hydrometer reading. (Example: Hydrometer reads 42.6, low is 42, high is 43.)

LOW

_____ . _____

+ . □

_____

_____ . _____

ACTUAL

_____ . □ → Put this number in all boxes. To calculate corrected reading use LOW if this number is less than or equal to 5, use HIGH if this number is greater than 5.

This is the corrected reading @ 60°

HIGH

_____ . _____

- 1 . 0

_____

_____ . _____

+ . □

_____

_____ . _____

EXAMPLE

Hydrometer reads 46.7 ° API at 97 °F.

Look at API chart under 46 & 47 next to 97°.

LOW

42 . 9

+ . 7

_____

_____ . _____

ACTUAL

46 . 7 → Put a 7 in all boxes.

Since 7 is greater than 5 do calculations in HIGH.

HIGH

43 . 9

-1 . 0

42 . 9

+ . 7

_____

43 . _____

Don't do anything here

This is your corrected reading at 60°F →

ORIFICE PLATE COEFFICIENTS

PLATE SIZE _____ " METER SIZE 100"/300" FIELD VESSEL # _____

TEMP.	100"/1000#	300"/1000#
10°		
20°		
30°		
40°		
50°		
60°		
70°		

AC_CPUC_0118443

WELL NO: SS-29 DATE: 8-29-78 OPERATOR: F. VALDEZ TEST NO: L-2

B. H. CHOKE: .750 " SURF CHOKE: .900 " (LATER) / VESSEL TEST?

FLOWING STRING: (CSG) / TBG SAFETY VALVE (IN) / OUT ? BOMBS RUN?: YES / (NO)

PROBE ID NO'S--RISER: _____ US#1 _____ US#2 _____ DS#1 338 DS#2 _____

PROBE AND BULL PLUG REMARKS: PROBE # 338 SHOW NO BUFFING

WATER CUT (% BS & W): _____ OIL GRAVITY: _____ @ _____ °F

ELAPSED TIME	TIME OF DAY	AIR TEMPERATURE	CSG PRESSURE	TBG PRESSURE	UPSTREAM SURFACE CHOKE		DOWNSTREAM SURFACE CHOKE		GAS FLOW RATE				LIQUIDS
					PRESSURE	TEMPERATURE	PRESSURE	TEMPERATURE	STATIC	DIFFERENTIAL	TEMPERATURE	RATE	
OUT IN	7:30A	83°	2600	26200									
0:00	7:45		BEGAN	FLOW	TEST								
0:05													
0:10													
0:15													
0:25													
0:35													
0:45													
1:00	8:45	90°		2560	1720	91°	610	33°	7.00	6.15	39°	33.269	
1:15													
0													
1:45													
2:00	9:45	88°		2480	1710	92°	615	34°	7.00	6.05	39°	32.728	
2:30													
3:00	10:45	90°		2430	1700	93°	610	32°	7.00	6.00	38°	32.458	
3:30													
4:00	11:45	91°		2380	1700	93°	620	32°	7.00	6.00	38°	32.458	
4:30													
5:00	12:45P	91°		2340	1695	93°	620	31°	7.00	6.00	37°	32.458	
5:30													
6:00	1:45	93°		2290	1680	92°	620	30°	7.00	6.00	36°	32.458	
6:30													
7:00	2:45	95°		2260	1680	92°	620	30°	7.00	6.00	36°	32.458	
7:30													
8:00	3:45	94°		2230	1670	90°	620	30°	7.00	6.00	36°	32.458	

AC_CPUC_0118444

AC_CPUC_0118445

Hydrometer reads _____° API at _____°F.

Go to API charts, find corrected readings for this temp. and the closest numbers either side of the hydrometer reading. (Example: Hydrometer reads 42.6, low is 42, high is 43.)

LOW

ACTUAL

HIGH

_____ . ☐ → Put this number in all boxes. To calculate corrected reading use LOW if this number is less than or equal to 5, use HIGH if this number is greater than 5.

_____ . 0

+ . ☐

This is the corrected reading @ 60°

Hydrometer reads 46.7° API at 97°F.

Look at API chart under 46 & 47 next to 97°.

LOW

ACTUAL

HIGH

42 . 9

46 . 7 → Put a 7 in all boxes.

Since 7 is greater than 5 do calculations in HIGH.

43 . 0

- 1 . 0

42 . 8

+ . 7

Don't do anything here

This is your corrected reading at 60°F → 42 . 7

CRUDE PLATE COEFFICIENTS

PLATE SIZE 8 X 4.375 " METER SIZE 100"/300" FIELD VESSEL #_____

TEMP.	100"/1000#	300"/1000#
10°		
20°		
30°		
40°		
50°		
60°		.772800
70°		

WELL NO: 55-29 DATE: 7-11-78 OPERATOR: Summers TEST NO: 4-1

B. H. CHOKE: _____" SURF. CHOKE: .94 " ORIFICE PLATE SIZE: _____"

FLOWING STRING: (CSG) TBG ORIFICE PLATE COEFF: 72800 @ 60° F

ROBE ID. NO'S: RISER: _____ US#1 _____ US#2 _____ DS#1 N 85 DS#2 _____

PROBE & BULL PLUG REMARKS: No marks —

WATER CUT (% BS & W): _____ OIL GRAVITY: _____ @ _____ F

ELASPED TIME	TIME OF DAY	AIR TEMPERATURE	CSG PRESSURE	TBG PRESSURE	UPSTREAM SURFACE CHOKE PRESSURE	UPSTREAM SURFACE CHOKE TEMPERATURE	DOWNSTREAM SURFACE CHOKE PRESSURE	DOWNSTREAM SURFACE CHOKE TEMPERATURE	GAS FLOW RATE STATIC	GAS FLOW RATE DIFFERENTIAL	GAS FLOW RATE RATE	LIQUIDS
shut in	9 15 A	78°	2535	2965								
0:00	9 30 A											
0:05												
0:10												
0:15												
0:25												
0:35												
0:45												
1:00	10 30 A	81°	300+		1920	85°	570	19°	7.18	4.5	23.522	
1:15												
1:30												
1:45												
2:00	11 30 A	80°		3000+	1930	91°	570	23°	7.18	4.5	23.522	
2:30												
3:00	12 30 P	80°		2950	1940	92°	585	25°	7.18	4.25	23.574	
3:30												
4:00	1 30 P	83°		2910	1940	93°	585	25°	7.24	4.5	23.718	
4:30												
5:00	2 30 P	85°		2875	1930	93°	590	25°	7.25	4.5	23.751	
5:30												
6:00	3 30 P	87		2845	1925	93°	590	25°	7.24	4.5	23.718	
6:30												
7:00	4 30 P	83.5		2815	1925	92°	580	24°	7.22	4.4	23.127	
7:30												
8:00	5 30 P	75°		2780	1920	89°	580	24°	7.21	4.48	23.515	

7/15/78

AC_CPUC_0118446

Compiled _____ Date _____

Checked _____ Checked _____

Approved _____ Job No. _____

~~#5~~

SOUTHERN CALIFORNIA GAS COMPANY

SS29

See Spot CHECKS by Meter DEPT.

SOUTHERN CALIFORNIA GAS CO.—1373

~~2-1/2 HOUR FLOW TEST~~

WELL NAME	SS29	17 m²
DATE		
BOTTOM HOLE CHOKE	.584	
SURFACE CHOKE	NONE	
FLOW T or C	C	
METER NO.	V-503	
INITIAL SHUT-IN PRESSURE T		PSIG
C		PSIG
TIME ON		
FINAL FLOWING PRESSURE T		PSIG
C		PSIG
TIME OFF		
FINAL RATE		MMCF/D

Flowing pressure must be upstream of surface choke, if any.

DATE	RATE
12-6-75	19.74 MMCF/D
12-21-75	16.56
1-13-76	13.74

AC_CPUC_0118447

Well No. 55-29 Test Rate = 26.1

Top @ 6X4.000 Type of Meas. Flu Orifice None

Date	Time	Casing Press.	Diff.	Flowing Temp.	Remarks
12-6-75	4:25 PM	547#	56"	76°	MCF 56.18 - site
12-7-75	9:35 PM	549#	53"	78°	"
12-8-75	1:15 PM	540#	54"	78°	"
12-12-75	2:00 PM	563#	53"	82°	"
12-13-75	1:50 P.M.	559#	48"	82°	"
12-17-75	2:40 P.M.	545#	41"	87°	"
12-18-75	3:25	543#	40"	87°	"
12-19-75	1:45	560	42"	87°	"
12-20-75	12:40	562#	40"	90	"
12-21-75	12	561#	40"	91°	"
12-22-75	1 P.M.	570#	28"	81°	"
12-23-75	3 P.M.	561#	31"	92°	"
12-24-75	11:30 A.M.	542#	36"	92°	"
12-25-75	10:30 A.M.	564	34"	93°	"
12-26-75	8 A.M.	562#	29"	92°	"
12-27-75	9 A.M.	543#	30"	93°	"
12-28-75	12:20 P.M.	550#	28"	94°	"

12-6-75		549# 7.50	56" 7.49	76°	56.18
12-21-75		561# 7.51	40" 6.31	90°	47.89
1-13-76		550# 7.51	28" 5.29	94°	39.73

AC_CPUC_0118448

Nov. 5,6, 1975

AC_CPUC_0118449

Compiled _____ Date _____

Checked _____ Checked _____

Approved _____ Job No. _____

SOUTHERN CALIFORNIA GAS COMPANY

Crew B

Zuniga, Rompel

SOUTHERN CALIFORNIA GAS CO.—1373

DATE 11-6-75

WELL NAME SS 29

B. H. CHOKE .584"

SURFACE CHOKE None

DESIGN RATE 25 MM

INITIAL SHUT-IN PRESSURE


Tubing 2660 CASING 2650

TIME	CASING PRESSURE	TUBING PRESS	TEMP.	GAS RATE	NOTES.
8 00 AM					START TEST
8 05 AM	2280	2320	73°	27.55	
8 10 A	2000	2090	72.5°	27.60	
8 15 A	1800	1910	74°	26.25	
8 20 A	1700	1810	75°	27.10	
8 25 A	1560	1680	76°	27.45	
8 30 A	1460	1600	77°	27.55	
8 35 A	1360	1525	77.5°	28.20	
8 40 A	1230	1400	78.5°	26.75	
8 45 A	1140	1330	79°	28.15	
8 50 A	1000	1200	79°	26.80	
8 55 A	920	1125	80°	27.30	
9 00 AM	960	1135	92°	24.60	
9 05 AM	860	1060	93°	27.30	
9 15 AM	760	975	84°	27.30	
9 18 A	620	930	84°	28.20	
9 30 A	570	830	85°	2640	
9 45 A	570	830	87.5°	26.21	
10 00 A	570	830	89°	26.21	
10 15 A	570	830	91.5°	26.21	
10 30 A	570	830	93°	26.54	
10 45 A	570	830	94°	26.54	
11 00 A	570	830	93°	26.54	
11 15 A	570	830	94°	26.12	

NO BUFFING

ADD TO READY

AC_CPUC_0118450



AC_CPUC_0118451

NODAL ANALYSIS RESULTS
****

SS 29 @ 0 INVENTORY

SUMMARY OF GENERAL INPUT DATA
****

GAS GRAVITY = .63
WELLHEAD PRESSURE,PSIG = 500.0

SUMMARY OF INPUT DATA FOR RESERVOIR MODULE
****

AVERAGE RESERVOIR PRESSURE,PSIG = 1667.

INFLOW
******

CALCULATED AOF= 22624.92

FLOW RATE	NODE PRESSURE,PWF
57000.	0.
28000.	0.
14000.	1024.

17940

SUMMARY OF INPUT DATA FOR WELL MODULE
****

WELL CONFIGURATION
****

DEPTH	TUBING DIA.	ANGLE	CASING DIA.	TUBING I.D.
8002.	2.875	.00	6.366	.000
8011.	2.205	.00	.000	.000
8049.	2.441	.00	.000	.000
8075.	.000	.00	6.366	.000
8575.	.000	.00	4.277	.000


PIPE ABS. ROUGHNESS,IN. = .00094
BOTTOM-HOLE TEMPERATURE,DEG-F = 158.
NUMBER OF LENGTH INCREMENTS = 10


PRESSURE DROP CORRELATION:
CULLENDER AND SMITH

OUTFLOW
****

FLOW RATE	PWH	NODE PRESSURE,PWF	WELLHEAD TEMP.
57000.	500.	1303.	52.
28000.	500.	840.	52.
14000.	500.	678.	52.

PRESSURE, PSIG vs GAS RATE





GAS RATE	NODE PRESSURES, PSIG				
(MSCF/DAY)	1	2	3	4	5
57000.	0.	1303.			
28000.	0.	840.			
14000.	1024.	678.			

NODAL ANALYSIS RESULTS

SS 29 @ -10 INVENTORY

SUMMARY OF GENERAL INPUT DATA

GAS GRAVITY = .63
WELLHEAD PRESSURE,PSIG = 500.0

SUMMARY OF INPUT DATA FOR RESERVOIR MODULE

AVERAGE RESERVOIR PRESSURE,PSIG = 1421.

INFLOW

CALCULATED AOF= 16489.88

FLOW RATE	NODE PRESSURE,PWF
57000.	0.
28000.	0.
1000.	1377.

13,755

SUMMARY OF INPUT DATA FOR WELL MODULE

WELL CONFIGURATION

DEPTH	TUBING DIA.	ANGLE	CASING DIA.	TUBING I.D.
8002.	2.875	.00	6.366	.000
8011.	2.205	.00	.000	.000
8049.	2.441	.00	.000	.000
8075.	.000	.00	6.366	.000
8575.	.000	.00	4.277	.000


PIPE ABS. ROUGHNESS,IN. = .00094
BOTTOM-HOLE TEMPERATURE,DEG-F = 158.
NUMBER OF LENGTH INCREMENTS = 10


PRESSURE DROP CORRELATION:
CULLENDER AND SMITH

OUTFLOW

FLOW RATE	PWH	NODE PRESSURE,PWF	WELLHEAD TEMP.
57000.	500.	1303.	52.
28000.	500.	840.	52.
1000.	500.	611.	52.

PRESSURE, PSIG vs GAS RATE





GAS RATE (MSCF/DAY)

GAS RATE (MSCF/DAY)	NODE PRESSURES, PSIG 1	2	3	4	5
57000.	0.	1303.			
28000.	0.	840.			
1000.	1377.	611.			

AC_CPUC_0118455

NODAL ANALYSIS RESULTS

SS 29 @ -20 INVENTORY

SUMMARY OF GENERAL INPUT DATA

GAS GRAVITY = .63
WELLHEAD PRESSURE,PSIG = 500.0

SUMMARY OF INPUT DATA FOR RESERVOIR MODULE

AVERAGE RESERVOIR PRESSURE,PSIG = 1163.

INFLOW

CALCULATED AOF= 11095.82

FLOW RATE	NODE PRESSURE,PWF
57000.	0.
28000.	0.
1000.	1109.

10,645

SUMMARY OF INPUT DATA FOR WELL MODULE

WELL CONFIGURATION

DEPTH	TUBING DIA.	ANGLE	CASING DIA.	TUBING I.D.
8002.	2.875	.00	6.366	.000
8011.	2.205	.00	.000	.000
8049.	2.441	.00	.000	.000
8075.	.000	.00	6.366	.000
8575.	.000	.00	4.277	.000


PIPE ABS. ROUGHNESS,IN. = .00094
BOTTOM-HOLE TEMPERATURE,DEG-F = 158.
NUMBER OF LENGTH INCREMENTS = 10


PRESSURE DROP CORRELATION:
CULLENDER AND SMITH

OUTFLOW


FLOW RATE	PWH	NODE PRESSURE,PWF	WELLHEAD TEMP.
57000.	500.	1303.	52.
28000.	500.	840.	52.
1000.	500.	611.	52.

PRESSURE, PSIG vs GAS RATE





GAS RATE (MSCF/DAY)	NODE PRESSURES, PSIG				
	1	2	3	4	5
57000.	0.	1303.			
28000.	0.	840.			
1000.	1109.	611.			



AC_CPUC_0118458

(B) after NOON

Compiled _____ Date _____ SOUTHERN CALIFORNIA GAS COMPANY

Checked _____ Checked _____

Approved _____ Job No. SS29

SOUTHERN CALIFORNIA GAS CO.—1373

DATE 11-5-75

WELL NAME SS29

B. H. CHOKE 0.584

SURFACE CHOKE 0.900

DESIGN RATE 25 m²

INITIAL SHUT-IN PRESSURE

TUBING 2660 CASING 2650


89° - 97°


TIME	CASING PRESSURE UP	CASING PRESSURE DOWN	TUBING PRESS	TEMP. UP	TEMP. DOWN	GAS RATE V-72		NOTES.	
1 55 PM	2650		2660					Start	Test
2 00 PM	2050	1730	2260	73.5°	83°	9.55	31.58		
2 05 PM	1850	1500	1920	73.5°	79.5°	9.0	29.76		
2 10 PM	1700	1240	1830	74.5°	79°	9.5	31.41		
2 15 PM	1550	1020	1720	75.5	77°	9.55	31.58		
2 20 PM	1420	850	1560	77°	72°	9.3	30.75		
2 25 PM	1350	640	1490	77°	70°	8.5	28.11		
2 30 PM	1260	590	1440	78°	65.5°	8.5	28.11	VALVE wide open	
2 35 PM	1240	580	1420	79°	64°	8.4	27.78		
2 40 PM	1280	580	1400	79.5°	64°	8.1	26.79		
2 45 PM	1270	580	1400	80°	64°	8.0	26.45		
3 00 PM	1270	580	1390	82°	64.5°	7.8	25.88		
3 15 PM	1270	580	1390	84.5°	65°	7.8	25.88		
3 30 PM	1270	580	1390	86°	64.5°	7.8	25.88		
3 45 PM	1270	580	1400	87°	63°	7.8	25.88		
4 00 PM	1270	580	1400	87°	61.5°	7.75	25.72		
4 30 PM	1275	580	1400	85°	57°	7.75	25.72	Well SI	

NO BUFFING - DOWNSTREAM Ø PLATE

AC_CPUC_0118459

AC_CPUC_0118460





AC_CPUC_0118461

Oct. 9, 1975

AC_CPUC_0118462

SS-29

10-9-75

G.A.R.

CHOKE TEST
(CASING WITHDRAWAL)

TIME	P_{CASING} (PSIG)	P_{TUBING} (PSIG)	T_{CASING} (°F)	Q_{GAS} ($M^2CF/D.$)	REMARKS
1:10 P.M.	2710	2750	73		SHUT-IN
1:15	2710	2750	73		ON FLOW
1:17	2300	2380	72		SAFETY VALVE CLOSED.
1:19	2500	2575	72		ON FLOW.
1:25	2175	2250	72		SAFETY VALVE CLOSED
1:27	2370	2425	72		ON FLOW
1:35	1940	2000	72		SAFETY VALVE CLOSED
1:36	1950	2050	72		ON FLOW
1:45	1600	1800	74		HEADER VALVE 50% OPEN
1:50	1440	1650	80		
2:00	1250	1475	81		HEADER VALVE 75% OPEN
2:15	1050	1275	85		
2:30	1060	1300	87		
2:45	940	1190	87		
3:00	680	1000	87	32.0	H. VALVE 100% OPEN.
3:15	630	925	84	31.1	
3:30	630	925	84	31.1	AVG. RATE = ± 30.7 $M^2CF/D.$
3:45	630	925	84	30.2	
4:00	630	925	84	30.7	SHUT-IN.

Closing Due to High Pressure Downstream of Valve.

Pinching Header Valve to Restrict Flow

DESIGNED RATE = 26 $M^2CF/D.$ (CASING WITHDRAWAL)


0.613" BOTTOM HOLE CHOKE INSTALLED ON 9-17-75

TEMPERATURE OF ENVIRONMENT – (70-75)°F.

NO SURFACE CHOKE.

INSPECTION OF BAR STOCK SHOWED VERY LIGHT BUFFING. BAR STOCK CLEAN

AC_CPUC_0118463



AC_CPUC_0118464

1-71
Printed in U. S. A.

GAS RESEARCH AND ENGINEERING SERVICE
5119 KINSIE STREET
LOS ANGELES, CALIFORNIA 90040
PHONE 261-9726

VICTOR F. GARMAN

ROBERT P. CHAFFEY

GAS ANALYSIS BY CHROMATOGRAPH

SOUTHERN CALIFORNIA GAS COMPANY

Sample Description: SS - 29 (8000') 1500 psig, 177°F.

Received
Date 5-4-73 Type 2 Area or/ Plant No. Aliso Canyon Meter No. or Sample No. SG-N113

ANALYSIS REPORT

1. ROYALTY GAS
2. OTHER GAS
3. L. P. G.
4. GASOLINE

1. BREA
2. LONG BEACH
3. VENTURA
4. TEN SECTIONS

5. MOLINO
6. SACRAMENTO RIVER GAS SYSTEM
7. ALASKA

NOTE: Water in sample tank.

	MOL. %		Mol. % w/Air		LIQUID VOL. %		B.T.U.	SPEC. GRAV.
O_2	.00		.090					
N_2	.37		.708					
Co_2	.16		.156					
H_2								
Air								
Methane	91.52		91.131					
Ethane	4.62		4.596					
Propane	1.78		1.769					
Iso - Butane	.27	+	.270	+				
N - Butane	.42		.419					
Iso - Pentane	.16	+	.159	+				
N - Pentane	.14		.139					
Hexane	.18		.184					
Heptane	.21		.212					
Octane	.11		.114					
Nonane	.05		.046					
Decane plus	.01		.007					
TOTAL	100.00		100.000				1119	.629

AIR FREE

AC_CPUC_0118465

```
DESTINATION CODE?
1108#?
JOB QUEUED  18:41:28  10/29/75
OUTPUT NAME:  NO2167 CO
>GU/L NO2167 CO
JOB # 2167 NOT FOUND
>DO R
FILE NOT FOUND
>OP NO2167 CO
>DO REPOT
FILE NOT FOUND
>DO REPORT
 ALISO CANYON SS #29 CHOKE ANALYSIS AT 3500 PSIA

 MAX RATE FOR BOTTOM HOLE CHOKE DESIGN... 25000.0 MCF/D
 FLOWING BOTTOM HOLE PRESS AT MAX RATE....  3033.0 PSIG
 FLOWING BOTTOM HOLE TEMP AT MAX RATE....   120.1 DEG F
 EST PRESS DROP (PBH-PWH) AT MAX RATE.....   648.6 PSI
 NORMAL RATE FOR SURFACE PLATE DESIGN.... 22500.0 MCF/D
 FLOWING BOTTOM HOLE PRESS AT NORM RATE...  3081.0 PSIG
 FLOWING BOTTOM HOLE TEMP AT NORM RATE...   124.3 DEG F
 EST PRESS DROP (PBH-PWH) AT NORM RATE.....   633.4 PSI
 GATHERING SYSTEM PRESSURE.................   550.0 PSIG
 GAS GRAVITY.....................................   .630
 BOTTOM HOLE SHUT-IN PRESSURE.............  3485.3 PSIG
 BOTTOM HOLE SHUT-IN TEMPERATURE.........   159.6 DEG F


 ID OF CASING.............................  6.2860 INCHES
 OD OF TUBING.............................  2.8580 INCHES
 FRICTION FACTOR CORRECTED FOR MEASURED DEPTH...  .0140
 MEASURED DEPTH..'........................  8331.0 FEET
 VERTICAL DEPTH...........................  8331.0 FEET
 MAX ALLOW BOTTOM HOLE CHOKE DIAMETER...  1.0000 INCHES
 ACTUAL BOTTOM HOLE CHOKE DIAMETER.....    .0000 INCHES
 ACTUAL SAFETY VALVE DIAMETER..........    .0000 INCHES
 ACTUAL SURFACE PLATE DIAMETER.........    .0000 INCHES


 MAX RATE= 25000.0 MCF/D AT 3033.0 PSIG AND 120.1 DEG F  (FLOWING AT VALVE LOCATION)

 DIAMETER OF BOTTOM HOLE CHOKE FOR MAX RATE=  .584 INCHES

 FLOWING WELLHEAD TEMP AT MAX RATE=  57.7 DEG F

 NORMAL RATE= 22500.0 MCF/D AT 3081.0 PSIG AND 124.3 DEG F  (FLOWING AT VALVE LOCATI

 DIAMETER OF SURFACE PLATE FOR NORMAL RATE =  .703 INCHES

 FLOWING TEMP UPSTREAM OF SURFACE PLATE=  74.5 DEG F

 FLOWING TEMP DOWNSTREAM OF SURFACE PLATE =   6.3 DEG F

  3047.7   829.9   829.9   564.7  3095.7  2344.1  2344.1  1820.6   564.7
   580.1   506.0   506.0   517.7   584.3   548.6   543.6   534.5   466.3



EXECUTION TERMINATED BY AN ATTEMPT TO READ THRU AN END OF FILE
  I/O  CALLED AT SEQUENCE NUMBER 00107 OF MAIN PROGRAM
 FORTRAN LIBRARY LEVEL: 10.5
* RUN,D   DSS09,LG2127,2,100                N BLG2DSS0                    2167
2167   29 OCT 75   18:41:22   IDENT DSS09     ACCOUNT LG2127   CARDS IN
```


AC_CPUC_0118466

Jan. 28, 1974

AC_CPUC_0118467

```
PRSS29 ED   04/11/74  16:19:08  LA

      10 @ RUN,D   DSS14,LG2127,3,100
      20 @ MSG PLEASE SEND TO D SMILEY, ML 1405
      30 @ XQT CUR
      40 FSTIN RADGAS/RDH
      50 @N XQT MAIN
      60  ALISO CANYON, SS29, PREDICTIONS BASED ON RZ MODEL OF FLOW TEST 1-27-74
      70    10    1   16    1    0    1    0
      80        .178         5.       750.      1707.      2050.       640.       520.
      90        .628       590.     3.878      .0140      8331.
     100        413.       .971      .0124
     110        615.       .947      .0129
     120        815.       .930      .0133
     130       1015.       .915      .0137
     140       1215.       .902      .0142
     150       1415.       .895      .0146
     160       1615.       .880      .0151
     170       1815.       .868      .0156
     180       2015.       .863      .0162
     190       2215.       .859      .0167
     200       2415.       .856      .0174
     210       2615.       .857      .0181
     220       2815.       .860      .0187
     230       3015.       .867      .0193
     240       3215.       .875      .0199
     250       3515.       .890      .0209
     260        43.0
     270       105.0
     280         0.0
     290         .13
     300       .0073
     310 0
     320           5        1.0     99    1    1    1    20000.
     330           2        5.0     99    0    0    1    20000.
     340           3       15.0     99    0    0    1    20000.
     350           2       60.0     99    0    0    1    20000.
     360           3      180.0     99    0    0    1    20000.
     370           1      720.0     99    0    0    1    20000.
     380           1     1440.0      1    0    0    1    20000.
     390 0
     400     1     1
     410        23.7
     420 0
     430 0
>
```



AC_CPUC_0118469

Compiled _____ Date _____

Checked _____ Checked _____

Approved _____ Job No. _____

SOUTHERN CALIFORNIA GAS COMPANY

SS-29 BUILDUP ANALYSIS

FLOW TEST 1-27-74

FINAL FLOWING PRESSURE 1403 PSIG

SOUTHERN CALIFORNIA GAS CO.—1973

t, min.	Δt, min.	t + Δt	(t+Δt)/Δt	P, PSIG
540	5	545	109	1822
	10	550	55	1963
	15	555	37	2008
	30	570	19	2017
	45	585	13	2019
	105	645	6.14	2019
	405	945	2.33	2019
	885	1425	1.61	2027

AC_CPUC_0118470

Compiled _____ Date 1-28-74

Approved _____ No _____

Pacific Lighting Service Company


WELL TEST DATA SHEET


WELL # SS-29

TIME	FLOW THRU	CHOKE SIZE	RATE MCFD	PRESS. UPSTREAM FR CHOKE	PRESS. DOWNSTREAM FR CHOKE	TUBING PRESSURE SHUT-IN	TEMP	BAR STK COND	FLUID RATES
8:10	—	INITAL PRESS		1600		1620			
8:15	CASING	32/64		1360	650	1420		OK	
8:30	"	"		1360	660	1420		OK	
8 55	"	"	8.8	1380	660	1440		OK	GR. 16 NT. 12
9 10	"	"		1380	650	1440		OK	
9 40	"	"		1400	650	1460		"	
10 10	"	"	9.4	1400	650	1470	38°	"	
10 40	"	"		1400	650	1480	39°	"	
11 10	"	"		1400	650	1480	39°	"	
11 15		48/64	CHANGE CHOKE SIZE						
11:30	"	"		1180	750	1320	54°	"	
11 40	"	"		1140	740	1300	58°	"	
11 55	"	"	14.3	1150	740	1310	60°	"	
12 30	"	"		1160	750	1320	64°	SLT Abrasion	
1 00	"	"		1160	740	1310	63.5°	"	GR. 27.1 NT. 20.5
1 30	"	"	15.2	1160	740	1310	64.3°	"	
2 00	"	"		1160	740	1310	70.5°	"	GR. 33.7 NT. 25.3
2 15	"	64/64	Change Choke Size						
2 30	"	"		960	810	1180	81°	SLT Abrasion	
2 45	"	"		950	800	1175	86°	"	
3 00	"	"	18.0	950	800	1180	86.1°	Light Abrasion	
3 30	"	"		950	800	1170	88°	"	44.9 G 33.5 N
4 00	"	"		940	800	1170	91°	"	
4 30	"	"		940	790	1170	91°	"	
5 00	"	"	17.6	930	790	1150	92°	"	
5 15	S/I								GR - 48.8 Net. - 36.4

PLS-307

AC_CPUC_0118471





Archer - Reed

WIRE LINE SERVICE

205 Baldwin Ave. Ventura, Calif. 93030

VENTURA 642-7061
LONG BEACH 591-0921

SUB-SURFACE DATA

Company Southern Calif. Gas Co. Field Aliso Date 1-27-74 Run No.

Well SS #29 Zone Elev.

Purpose Status

Total Depth Effect. Depth

Casing Size Depth Liner Size Top Bottom

Perforations

Tubing

Company Southern Calif. Gas Co.

Well SS #29

Date 1-27-74	Date 1-29-74
Arrive 12:00 PM A P	Arrive 8:00 AM A P
Leave 4:00 PM A P	Leave 12:00 PM A P

Inst. No. 5375 Size 3350 / No. Size

Clock No. 510 Hrs. 72 / No. Hrs.

Stylus Marked 3:05 PM A P

Pressure On 3:13 PM A P

Depth 8331 Zero KB

At Depth Date 1-27-74 Time 3:33 PM A P

Off Depth Date 1-29-74 Time 8:00 AM A P

Shut In Date 1-29-74 Time 8:15 AM A P

Start Press Tbg. 1645 Csg. #

Final Press Tbg. 1645 Csg. #

Pick-up Temp. 203 F

OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas - Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	
Casing Fluid Level - Ft.	

TIME	DEPTH	SCALE	PSI or °F	TIME	DEPTH	SCALE	PSI or °F
1-27-74	SHUT-IN			11:19 AM		1.019	1726
4:00 PM		1.203	2035	11:20		1.009	1709
1-28-74				11:25		.975	1652
12:00 AM		1.203	2035	11:30		.960	1626
8:00 AM		1.203	2035	11:45		.951	1611
FLOWING			32/64	12:00 PM		.951	1611
8:15 AM		1.203	2035	12:30		.948	1606
8:16		1.186	2007	1:00 PM		.946	1603
8:17		1.152	1950	1:30		.946	1603
8:18		1.123	1901	2:00 PM		.946	1603
8:19		1.107	1874	2:15		.946	1603
8:20		1.097	1857	CHANGE BEAN			64/64
8:25		1.067	1806	2:15		.946	1603
8:30		1.055	1786	2:16		.926	1569
8:35		1.053	1783	2:17		.911	1544
8:45		1.057	1790	2:18		.901	1527
8:55		1.060	1795	2:19		.890	1508
9:00 AM		1.063	1800	2:20		.884	1498
9:15		1.068	1808	2:25		.865	1466
9:30		1.073	1817	2:30		.857	1453
10:00 AM		1.081	1830	2:45		.853	1446
10:30		1.080	1828	3:00 PM		.852	1444
11:00 AM		1.083	1833	4:00 PM		.841	1425
11:15		1.086	1838	5:00 PM		.828	1403
CHANGE BEAN			48/64	5:15		.828	1403
11:15		1.086	1838	SHUT-IN	5:15 PM		
11:16		1.068	1808	5:15		.828	1403
11:17		1.047	1773	5:20		1.076	1822
11:18		1.032	1747	5:25		1.160	1963

COMMENTS

By

AC_CPUC_0118474

Archer - Reed

WIRE LINE SERVICE

205 Baldwin Ave. Ventura, Calif. 93030

VENTURA 642-7061
LONG BEACH 591-0921

SUB-SURFACE DATA

Company _____ Field _____ Date _____ Run No. _____

Well _____ Zone _____ Elev. _____

Purpose _____ Status _____

Total Depth _____ Effect. Depth _____

Casing Size _____ Depth _____ Liner Size _____ Top _____ Bottom _____

Perforations _____

Tubing _____

Company

Well

Date / Date

Arrive A P / Arrive A P

Leave A P / Leave A P

Inst. No. Size / No. Size

Clock No. Hrs. / No. Hrs.

Stylus Marked A P

Pressure On A P

Depth Zero

At Depth Date Time A P

Off Depth Date Time A P

Shut In Date Time A P

Start Press Tbg. Csg. #

Final Press Tbg. Csg. #

Pick-up Temp. F

OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas - Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	
Casing Fluid Level - Ft.	

TIME	DEPTH	SCALE	PSI or °F	TIME	DEPTH	SCALE	PSI or °F
5:30 PM		1.187	2008	/			
5:45		1.192	2017	/			
6:00 PM		1.193	2019	/			
7:00 PM		1.193	2019	/			
1-29-74				/			
12:00 AM		1.193	2019	/			
8:00 AM		1.198	2027	/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			

COMMENTS _____

By _____

AC_CPUC_0118475

Archer - Reed
WIRE LINE SERVICE

205 Baldwin Ave. Ventura, Calif. 93030

VENTURA 642-7061
LONG BEACH 591-0921

SUB-SURFACE DATA

Company Southern Calif. Gas Co. Field Aliso Date 1-27-74 Run No.
Well SS #29 Zone Elev.
Purpose Status
Total Depth Effect. Depth
Casing Size Depth Liner Size Top Bottom
Perforations
Tubing

Company Southern Calif. Gas Co.
Well SS #29

Date 1-27-74		Date 1-29-74	
Arrive 12:00 PM	A P	Arrive 8:00 AM	A P
Leave 4:00 PM	A P	Leave 12:00 PM	A P
Inst. No. 5375		Size 3350	
Inst. No.		Size	
Clock No. 510		Hrs. 72	
Clock No.		Hrs.	

Stylus Marked 3:05 PM A P
Pressure On 3:13 PM A P

Depth 8331 Zero KB
At Depth Date 1-27-74 Time 3:35 PM A P
Off Depth Date 1-29-74 Time 8:00 AM A P
Shut In Date 1-29-74 Time 8:15 AM A P
Start Press Tbg. 1645 Csg. #
Final Press Tbg. 1645 Csg. #

Pick-up Temp. 203 F

OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas - Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	
Casing Fluid Level - Ft.	

TIME	DEPTH	SCALE	PSI or °F
1-27-74	SHUT-IN		
4:00 PM		1.203	2035
1-28-74			
12:00 AM		1.203	2035
8:00 AM		1.203	2035
FLOWING			32/64
8:15 AM		1.203	2035
8:16		1.186	2007
8:17		1.152	1950
8:18		1.123	1901
8:19		1.107	1874
8:20		1.097	1857
8:25		1.067	1806
8:30		1.055	1786
8:35		1.053	1783
8:45		1.057	1790
8:55		1.060	1795
9:00 AM		1.063	1800
9:15		1.068	1808
9:30		1.073	1817
10:00 AM		1.081	1830
10:30		1.080	1828
11:00 AM		1.083	1833
11:15		1.086	1838
CHANGE BEAN			48/64
11:15		1.086	1838
11:16		1.068	1808
11:17		1.047	1773
11:18		1.032	1747
11:19 AM		1.019	1726
11:20		1.009	1709
11:25		.975	1652
11:30		.960	1626
11:45		.951	1611
12:00 PM		.951	1611
12:30		.948	1606
1:00 PM		.946	1603
1:30		.946	1603
2:00 PM		.946	1603
2:15		.946	1603
CHANGE BEAN			64/64
2:15		.946	1603
2:16		.926	1569
2:17		.911	1544
2:18		.901	1527
2:19		.890	1508
2:20		.884	1498
2:25		.865	1466
2:30		.857	1453
2:45		.853	1446
3:00 PM		.852	1444
4:00 PM		.841	1425
5:00 PM		.828	1403
5:15		.828	1403
SHUT-IN	5:15 PM		
5:15		.828	1403
5:20		1.076	1822
5:25		1.160	1963

COMMENTS

By

AC_CPUC_0118476

Archer - Reed
WIRE LINE SERVICE
205 Baldwin Ave. Ventura, Calif. 93030
VENTURA 642-7061
LONG BEACH 591-0921

SUB-SURFACE DATA

Company _____ Field _____ Date _____ Run No. _____
Well _____ Zone _____ Elev. _____
Purpose _____ Status _____
Total Depth _____ Effect. Depth _____
Casing Size _____ Depth _____ Liner Size _____ Top _____ Bottom _____
Perforations _____
Tubing _____

Company
Well
Date / Date
Arrive A P / Arrive A P
Leave A P / Leave A P
Inst. No. Size / No. Size
Clock No. Hrs. / No. Hrs.
Stylus Marked A P
Pressure On A P
Depth Zero
At Depth Date Time A P
Off Depth Date Time A P
Shut In Date Time A P
Start Press Tbg. Csg. #
Final Press Tbg. Csg. #
Pick-up Temp. F

OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas - Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	
Casing Fluid Level - Ft.	

TIME	DEPTH	SCALE	PSI or °F	TIME	DEPTH	SCALE	PSI or °F
5:30 PM		1.187	2008	/			
5:45		1.192	2017	/			
6:00 PM		1.193	2019	/			
7:00 PM		1.193	2019	/			
1-29-74				/			
12:00 AM		1.193	2019	/			
8:00 AM		1.198	2027	/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			
/				/			

COMMENTS _____

By _____

AC_CPUC_0118477

Archer - Reed

WIRE LINE SERVICE

205 Baldwin Ave. Ventura, Calif. 93030

VENTURA 642-7061
LONG BEACH 591-0921

SUB-SURFACE DATA

Company Southern Calif. Gas Co. Field Aliso Date 1-27-74 Run No.

Well SS #29 Zone Elev.

Purpose Status

Total Depth Effect. Depth

Casing Size Depth Liner Size Top Bottom

Perforations

Tubing

Company Southern Calif. Gas Co.

Well SS #29

Date 1-27-74		Date 1-29-74	
Arrive 12:00 PM	A P	Arrive 8:00 AM	A P
Leave 4:00 PM	A P	Leave 12:00 PM	A P
Inst. No. 5375	Size 3350		
No.	Size		
Clock No. 510	Hrs. 72		
No.	Hrs.		

Stylus Marked 3:05 PM A P

Pressure On 3:13 PM A P

Depth 8331 Zero KB

At Depth Date 1-27-74 Time 3:33 PM A P

Off Depth Date 1-29-74 Time 8:00 AM A P

Shut In Date 1-29-74 Time 8:15 AM A P

Start Press Tbg. 1645 Csg. #

Final Press Tbg. 1645 Csg. #

Pick-up Temp. 203 F

OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas - Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	
Casing Fluid Level - Ft.	

TIME	DEPTH	SCALE	PSI or °F
1-27-74	SHUT-IN		
4:00 PM		1.205	2035
1-28-74			
12:00 AM		1.203	2035
8:00 AM		1.203	2035
FLOWING			32/64
8:15 AM		1.203	2035
8:16		1.186	2007
8:17		1.152	1950
8:18		1.123	1901
8:19		1.107	1874
8:20		1.097	1857
8:25		1.067	1806
8:30		1.055	1786
8:35		1.053	1783
8:45		1.057	1790
8:55		1.060	1795
9:00 AM		1.063	1800
9:15		1.068	1808
9:30		1.073	1817
10:00 AM		1.081	1830
10:30		1.080	1828
11:00 AM		1.083	1833
11:15		1.086	1838
CHANGE BEAN			48/64
11:15		1.086	1838
11:16		1.068	1808
11:17		1.047	1773
11:18		1.032	1747

TIME	DEPTH	SCALE	PSI or °F
11:19 AM		1.019	1726
11:20		1.009	1709
11:25		.975	1652
11:30		.960	1626
11:45		.951	1611
12:00 PM		.951	1611
12:30		.948	1606
1:00 PM		.946	1603
1:30		.946	1603
2:00 PM		.946	1603
2:15		.946	1603
CHANGE BEAN			64/64
2:15		.946	1603
2:16		.926	1569
2:17		.911	1544
2:18		.901	1527
2:19		.890	1508
2:20		.884	1498
2:25		.865	1466
2:30		.857	1453
2:45		.853	1446
3:00 PM		.852	1444
4:00 PM		.841	1425
5:00 PM		.828	1403
5:15		.828	1403
SHUT-IN	5:15 PM		
5:15		.828	1403
5:20		1.076	1822
5:25		1.160	1963

COMMENTS

By

AC_CPUC_0118478

Archer - Reed

WIRE LINE SERVICE

205 Baldwin Ave. Ventura, Calif. 93030

VENTURA 642-7061
LONG BEACH 591-0921

SUB-SURFACE DATA

Company _____ Field _____ Date _____ Run No. _____

Well _____ Zone _____ Elev _____

Purpose _____ Status _____

Total Depth _____ Effect. Depth _____

Casing Size _____ Depth _____ Liner Size _____ Top _____ Bottom _____

Perforations _____

Tubing _____

Company

Well

Date / Date

Arrive A P / Arrive A P

Leave A P / Leave A P

Inst. No. Size / No. Size

Clock No. Hrs. / No. Hrs.

Stylus Marked A P

Pressure On A P

Depth Zero

At Depth Date Time A P

Off Depth Date Time A P

Shut In Date Time A P

Start Press Tbg. Csg. #

Final Press Tbg. Csg. #

Pick-up Temp. F

OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas - Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	
Casing Fluid Level - Ft.	

TIME	DEPTH	SCALE	PSI or °F	TIME	DEPTH	SCALE	PSI or °F
5:30 PM		1.187	2008	/			
5:45		1.192	2017	/			
6:00 PM		1.193	2019	/			
7:00 PM		1.193	2019	/			
1-29-74				/			
12:00 AM		1.193	2019	/			
8:00 AM		1.198	2027	/			
/				/			
/				/			
/		

Archer - Reed
WIRE LINE SERVICE
205 Baldwin Ave. Ventura, Calif. 93030
VENTURA 642-7061
LONG BEACH 591-0921

SUB-SURFACE DATA

Company Southern Calif. Gas Co. Field Aliso Date 1-27-74 Run No.
Well SS #29 Zone Elev.
Purpose Status
Total Depth Effect. Depth
Casing Size Depth Liner Size Top Bottom
Perforations
Tubing

Company Southern Calif. Gas Co.
Well SS #29

Date 1-27-74		Date 1-29-74	
Arrive 12:00 PM	A P	Arrive 8:00 AM	A P
Leave 4:00 PM	A P	Leave 12:00 PM	A P
Inst. No. 5375		Size 3350	
Inst. No.		Size	
Clock No. 510		Hrs. 72	
Clock No.		Hrs.	

Stylus Marked 3:05 PM A P
Pressure On 3:13 PM A P
Depth 8331 Zero KB
At Depth Date 1-27-74 Time 3:35 PM A P
Off Depth Date 1-29-74 Time 8:00 AM A P
Shut In Date 1-29-74 Time 8:15 AM A P
Start Press Tbg. 1645 Csg. #
Final Press Tbg. 1645 Csg. #
Pick-up Temp. 203 F

OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas - Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	
Casing Fluid Level - Ft.	

TIME	DEPTH	SCALE	PSI or °F
1-27-74	SHUT-IN		
4:00 PM		1.203	2035
1-28-74			
12:00 AM		1.203	2035
8:00 AM		1.203	2035
FLOWING			32/64
8:15 AM		1.203	2035
8:16		1.186	2007
8:17		1.152	1950
8:18		1.123	1901
8:19		1.107	1874
8:20		1.097	1857
8:25		1.067	1806
8:30		1.055	1786
8:35		1.053	1783
8:45		1.057	1790
8:55		1.060	1795
9:00 AM		1.063	1800
9:15		1.068	1808
9:30		1.073	1817
10:00 AM		1.081	1830
10:30		1.080	1828
11:00 AM		1.083	1833
11:15		1.086	1838
CHANGE BEAN			48/64
11:15		1.086	1838
11:16		1.068	1808
11:17		1.047	1773
11:18		1.032	1747

TIME	DEPTH	SCALE	PSI or °F
11:19 AM		1.019	1726
11:20		1.009	1709
11:25		.975	1652
11:30		.960	1626
11:45		.951	1611
12:00 PM		.951	1611
12:30		.948	1606
1:00 PM		.946	1603
1:30		.946	1603
2:00 PM		.946	1603
2:15		.946	1603
CHANGE BEAN			64/64
2:15		.946	1603
2:16		.926	1569
2:17		.911	1544
2:18		.901	1527
2:19		.890	1508
2:20		.884	1498
2:25		.865	1466
2:30		.857	1453
2:45		.853	1446
3:00 PM		.852	1444
4:00 PM		.841	1425
5:00 PM		.828	1403
5:15		.828	1403
SHUT-IN	5:15 PM		
5:15		.828	1403
5:20		1.076	1822
5:25		1.160	1963

COMMENTS

By

AC_CPUC_0118480

Archer - Reed
WIRE LINE SERVICE
205 Baldwin Ave. Ventura, Calif. 93030
VENTURA 642-7061
LONG BEACH 591-0921

SUB-SURFACE DATA


Company _____ Field _____ Date _____ Run No. _____
Well _____ Zone _____ Elev _____
Purpose _____ Status _____
Total Depth _____ Effect. Depth _____
Casing Size _____ Depth _____ Liner Size _____ Top _____ Bottom _____
Perforations _____
Tubing _____

Company			
Well			
Date		Date	
Arrive	A P	Arrive	A P
Leave	A P	Leave	A P
Inst.	No.	Size	
	No.	Size	
Clock	No.	Hrs.	
	No.	Hrs.	
Stylus Marked			A P
Pressure On			A P
Depth		Zero	
At Depth	Date	Time	A P
Off Depth	Date	Time	A P
Shut In	Date	Time	A P
Start Press	Tbg.	Csg.	#
Final Press	Tbg.	Csg.	#
Pick-up		Temp.	F


OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas - Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	
Tubinghead Pressure - PSIG	
Casing Fluid Level - Ft.	

TIME	DEPTH	SCALE	PSI or °F	TIME	DEPTH	SCALE	PSI or °F
5:30 PM		1.187	2008	/			
5:45		1.192	2017	/			
6:00 PM		1.193	2019	/			
7:00 PM		1.193	2019	/			
1-29-74				/			
12:00 AM		1.195	2019	/			
8:00 AM		1.198	2027	/			
/				/			
/				/			
/		



AC_CPUC_0118482


6 DAY
7 A.M.
8 A.M.
9 A.M.
10 A.M.
11 A.M.
NOON
1 P.M.
2 P.M.
3 P.M.
4 P.M.
5 P.M.
6 P.M.
7 P.M.
NIGHT
Coeff = 623712 F³/DAY
W-10
1000#
DISC. NO.
100"
METER 4375
TAKEN OFF
CHART PUT ON
6:30 A.M.
1-28 1974
LOCATION V-72
REMARKS ALISO CANYON
STATION 23

AC_CPUC_0118484

WELL TEST PRESSURE OBSERVATION CODING FORM

HEADER CARD #1

ALISO CANYON STORAGE FLD — CC 1-24 FIELD NAME

PRESSURE BUILD-UP TEST — CC 25-48 TYPE OF TEST

SS-29 U SESNON ZONE — CC 49-72 WELL IDENTIFICATION

HEADER CARD #2

4-6-73 TO 4-9-73 — CC 1-24 TEST DATE

44 — CC 25-29 NUMBER OF OBSERVATIONS

86400 — CC ~~25~~ 31-45 DELTA T

CC 46-60 DEPTH TO DATUM

1169 — CC 61-75 STARTING PRESSURE

DATA CARDS

TIME FROM START HOURS CC 7-9	TIME FROM START MIN CC 10-11	PRESSURE CC 16-21
	01	1264
	2	1315
	3	1334
	4	1345
	5	1348
	6	1349
	7	1350
	8	1350
	9	1350
	10	1353
	12	1353
	14	1354
	16	1355
	18	1355
	20	1356
	22	1356
	24	1356
	26	1357
	28	1357
	30	1360
	42	1362
	50	1357
→ 1	00	1366
1	10	1363
1	20	1409

TIME FROM START HOURS CC 7-9	TIME FROM START MIN CC 10-11	PRESSURE CC 16-21
2	00	1400
5	00	1400
10	00	1400
15	00	1401
20	00	1402
22	00	1402
22	30	1411
23	00	1410
25	00	1410
30	00	1413
35	00	1413
40	00	1415
45	00	1416
50	00	1418
55	00	1419
60	00	1420
65	00	1421
70	00	1418
72	00	1415

Inf-Sys 7 K.P.

Inf-Sys 7 K.P.

AC_CPUC_0118485

Compiled _____ Date _____

Approved _____ No. _____

Pacific Lighting Service and Supply Company

STO – SESNON Z9, V SESNON ZONE

Pressure build up test.

SI 4/6/73

DATUM = 8456

	Schedule Time After SI.	Actual Time	Pressure P.S.I. ΔP	BHP P + ΔP - 24			
PRIOR TO SI	0	1:00 PM	998 195	1169			
	1	1:01	1085 203	1264			
	2	1:02	1119 220	1315			
	3	1:03	1135 223	1334			
	4	1:04	1144 225	1345			
	5	1:05	1147 226	1348			
	6	1:06	1148 225	1349			
	7	1:07	1149 226	1350			
	8	1:08	1149 225	1350			
	9	1:09	1149 225	1350			
	10	1:10	1150 227	1353			
	12	1:12	1150 227	1353			
	14	1:14	1151 227	1354			
	16	1:16	1152 227	1355			
	18	1:18	1152 227	1355			
	20	1:20	1153 227	1356			
	22	1:22	1153 227	1356			
	24	1:24	1153 227	1356			
	26	1:26	1154 227	1357			
	28	1:28	1154 227	1357			
	30	1:30	1156 228	1360			
	42	1:42	1158 228	1362	Wire Going into hole		
	50	1:50	1154 227	1357	Bomb on bottom 1:52		
1	60	2:00	1161 229	1366	Lubricator leaking had to bring		
1 10	70	2:10	1159 228	1363	bomb back out of hole.		
1 21	81	2:21	1155 225		Bomb started back into		
1 30	90	2:30	1155		hole 2:12 bomb on bottom		
1 40	100	2:40	1153		2:18		
1 50	110	2:50	1152				

Form 307

AC_CPUC_0118486

SS-29 - S-4 zone (18/64)

Opened & production on 3/1/73

3/18	18 B/D gross	12 B/D net	1.836 Mcf
3/23	12 B/D gross	8 B/D net	1.964 Mcf
4/2	16 B/D gross	12 B/D net	2.483 Mcf
4/6	13 B/D gross	11 B/D net	2.361 Mcf

1000 tbg
1050 csg

Shut-in on 4/6/73 avg 2.40

AC_CPUC_0118487

TECHNICAL SERVICE CO.
801 West 14th Street
Long Beach, California 90813

Phones: 24 Hours
Long Beach - 436-9901
Ventura - - - 648-4888

SUB-SURFACE PRESSURE DATA

Company So. California Gas Company Field Aliso Canyon Date 4-(6-9)-73 Run No.
Well Standard Sesnon No. 29 Zone Elev. 2848.77'
Purpose Pressure Build-Up Survey Status Shut In
Total Depth 9790' Effect. Depth 9077'
Casing Size 7" Depth 8170' Liner Size 5" Top 8075' Bottom 9077'
Perforations 8502' - 9077' @ Intervals
Tubing 2-7/8" to 8028', 2-3/8" 8669'. G/L Mandrals @ 5684', 6919', 8002', 8385'.
Sleeves @ 8351', 8488'. Pkr. 8521'

DEPTH:


Time Hrs.	Pressure PSIG	Time Hrs.	Pressure PSIG	Time Hrs.	Pressure PSIG
1:20	1400	55:00	1419	Check	Instr.
2:00	1400	60:00	1420	1:20	1402
5:00	1400	65:00	1421	10:00	1400
10:00	1400	70:00	1418	22:00	1402
15:00	1401	72:00	1415	22:30	1412
20:00	1402			25:00	1412
22:00	1402			35:00	1413
22:30	1411			50:00	1417
23:00	1410			60:00	1419
25:00	1410			70:00	1417
30:00	1413			72:00	1415
35:00	1413				
40:00	1415				
45:00	1416				
50:00	1418				

OBSERVATIONS

Stabilization Period - Hrs. 72:00 | Shut-in 4/6 1:00 p.m.
Run No.
Time at Depth 4/6 2:20 p.m.
Time off Depth 4/9 1:00 p.m.
Csg. PSIG: Start - End 1050 - 1150
Tbg. PSIG: Start - End 1000 - 1138
Zero: K. B. 6.9'

Comments:
Maximum Temperature 182° F

By: Harlan - Snider - Homer



T-16—Pfanstiel Printing


AC_CPUC_0118488

TECHNICAL SERVICE CO.
801 West 14th Street
Long Beach, California 90813

Phones: 24 Hours
Long Beach - 436-9901

SUB-SURFACE PRESSURE DATA

Company So. California Gas Company Field Aliso Canyon Date 4-9-73 Run No.
Well Standard Sesnon No. 29 Zone Elev. 2848.77'
Purpose Static Pressure Survey Status Shut In
Total Depth 9790' Effect. Depth 9077'
Casing Size 7" Depth 8170' Liner Size 5" Top 8075' Bottom 9077'
Perforations 8502' - 9077' @ Intervals
Tubing 2-7/8" to 8028', 2-3/8" 8669'. G/L Mandrals @ 5684', 6919', 8002', 8385'. Sleeves @ 8351', 8488'. Pkr. 8521'



OBSERVATIONS

Stabilization Period - Hrs.	72:00
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas-Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	1150
Tubinghead Pressure - PSIG	1138
Casing Fluid Level - Ft.	

RESULTS

Gross Productivity Index	B/D PSI
Net Productivity Index	B/D PSI
Static M.E.P. - Run No.	PSI
Static M.E.P. - Projected	PSI
Gross Absolute Potential	B/D
Net Absolute Potential	B/D
Datum Pressures:	

Traverse Depth Feet	Pressure PSIG	Gradient PSI/FT
0	1138	
5000	1300	0.032
6000	1336	0.036
7000	1372	0.036
8000	1399	0.027
8456	1415	0.035
Check Instr.		
0	1139	
5000	1300	
6000	1334	
7000	1371	
8000	1398	
8456	1415	

COMMENTS Zero: K. B. 6.9'


By Worley - Homer

AC_CPUC_0118489


ALISO CANYON STORAGE FLD SS-29, U SESNON ZONE PRESSURE BUILD-UP TEST 4-6-73 TO 4-9-73

DELTA T	T + DT / DT	SURFACE PRESSURE	BOTTOM HOLE PRESSURE	PS - PWF
1.0	51841,000	1264,0	1264,0	95,0
2.0	25921,001	1315,0	1315,0	146,0
3.0	17281,000	1334,0	1334,0	165,0
4.0	12961,000	1345,0	1345,0	176,0
5.0	10369,000	1348,0	1348,0	179,0
6.0	8641,000	1349,0	1349,0	180,0
7.0	7406,714	1350,0	1350,0	181,0
8.0	6481,000	1350,0	1350,0	181,0
9.0	5761,000	1350,0	1350,0	181,0
10.0	5185,000	1353,0	1353,0	184,0
12.0	4321,000	1353,0	1353,0	184,0
14.0	3703,857	1354,0	1354,0	185,0
16.0	3241,000	1355,0	1355,0	186,0
18.0	2881,000	1355,0	1355,0	186,0
20.0	2593,000	1356,0	1356,0	187,0
22.0	2357,364	1356,0	1356,0	187,0
24.0	2161,000	1356,0	1356,0	187,0
26.0	1994,846	1357,0	1357,0	188,0
28.0	1852,429	1357,0	1357,0	188,0
30.0	1729,000	1360,0	1360,0	191,0
42.0	1235,286	1362,0	1362,0	193,0
50.0	1037,800	1357,0	1357,0	188,0
60.0	865,000	1366,0	1366,0	197,0
70.0	741,571	1363,0	1363,0	194,0
80.0	649,000	1400,0	1400,0	231,0
120.0	433,000	1400,0	1400,0	231,0
300.0	173,800	1400,0	1400,0	231,0
600.0	87,400	1400,0	1400,0	231,0
900.0	58,600	1401,0	1401,0	232,0
1200.0	44,200	1402,0	1402,0	233,0
1320.0	40,273	1402,0	1402,0	233,0
1350.0	39,400	1411,0	1411,0	242,0
1380.0	38,565	1410,0	1410,0	241,0
1500.0	35,560	1410,0	1410,0	241,0
1800.0	29,800	1413,0	1413,0	244,0
2100.0	25,686	1413,0	1413,0	244,0
2400.0	22,600	1415,0	1415,0	246,0
2700.0	20,200	1416,0	1416,0	247,0
3000.0	18,280	1418,0	1418,0	249,0
3300.0	16,709	1419,0	1419,0	250,0
3600.0	15,400	1420,0	1420,0	251,0
3900.0	14,292	1421,0	1421,0	252,0
4200.0	13,343	1418,0	1418,0	249,0
4320.0	13,000	1415,0	1415,0	246,0

AC_CPUC_0118490



AC_CPUC_0118491



AC_CPUC_0118492

ALISO CANYON FIELD
STORAGE FIELD

WELL NO, SS 29, U SESNON ZONE TEST DATES 4- 6-73 THROUGH 4- 9-73

BASIC DATA

NET HYDROCARBON THICKNESS	= 46,00	OIL SATURATION	= ,230	WELLBORE RADIUS	= ,204
NET GAS SAND THICKNESS	= 46,00	GAS SATURATION	= ,300	WITHDRAWAL RATE	= 2,40
POROSITY, PHI	= ,080	WATER SATURATION	= ,470		

DATA FROM TESTS

PRESSURE BUILDUP

VOLUME FACTOR, BG	,01244
COMPRESSIBILITY, CT	,00031
VISCOSITY, MU	,01433
SLOPE, M	15,800
P(I) = P AT SHUT-IN	1169,
P* = EXTRAPOLATED P	1394,
P(1 HR)	1364,
P-BAR AVERAGE P	1418,
BOUNDARY TIME-LAG	1,70
BOUNDARY SLOPE	610,000

AC_CPUC_0118493

ALISO CANYON FIELD
STORAGE FIELD

WELL NO. SS 29, U SESNON ZONE TEST DATES 4- 6-73 THROUGH 4- 9-73

TEST RESULTS

PRESSURE BUILDUP

CONDUCTANCE, KH	785.36
PERMEABILITY, K	17.07
SKIN EFFECT, S	7.50
PRESSURE LOSS, DELP	103.
PRODUCTIVITY INDEX ACTUAL	1901.4
PRODUCTIVITY INDEX IDEAL	3507.6
FLOW EFFICIENCY	.542
DISTANCE TO NEAREST BOUNDARY	291.874*

* INDICATES MORE THAN ONE BOUNDARY

AC_CPUC_0118494

FEB 12-13, 1973

AC_CPUC_0118495

Compiled _____ Date _____

Approved _____ No. _____

Pacific Lighting Service Company

SS 29

CLEANUP FLOW

	ΔT	PRESS		DT	PRESS		
				init dwgd	3729.3		
10:47 1/8"	0			0	1304.6		
	2	1304.6		2	1321.2		
	4			4	1344.7		
	6			6	1364.1		
10:55	8			8	1397.3		
3/8"	10			10	1426.3		
	12			12	1444.3		
	14			14	1452.6		
	16			16	1456.7		
	18			18	↓		
	20			20	↓		
	22			22	1448.4		
11:10	23			24	1447.1		
1/2"	25			26	1444.3		
	27			28	1444.3		
	29			30	1442.9		
	31			32	1441.5		
11:20	33			34	1441.5		
	43			36	1427.7		
11:40	53			38	1422.2		
	1hr 23			40	1419.4		
12:40	1hr 53			42	1419.4		
	2hr 53			44	1418.0		
	3 hr 53			46	1418.0		
	4 hr 50			48	1418.0		
				50	1419.4		
				↓	↓		
				4 hr 50	↓		
				303 min			

PLS-307

AC_CPUC_0118496

Compiled _____ Date _____

Approved _____ No. _____

Pacific Lighting Service Company

SS 29

T 159 7000 psi T: 183°

SHUT-IN After Cooling

INSIDE INST

	ΔT	PRESS
15:37	0	1419.4
	2	1442.9
	4	1462.3
	6	1467.8
	8	1469.2
	10	1470.6
	12	
	14	
	16	
	18	
	20	
	22	
16:00	23	
	33	
	45	
	53	
	1hr 3 min	
	1 13	
17:00	1 23	
	1 53	
18:00	2 23	
	3 23	
	4 23	
	5 23	
	6 23	
	7 23	
24:00	8 23	
6	14 23	
12	20 23	
18	26 23	
24	32 23	
3/12 6:20 AM	38 N 43	


PLS-307

AC_CPUC_0118497


ALISO CANYON STORAGE FLD SS 29, U SESNON ZONE PRESSURE DRAWDOWN TEST FEB 12, 1973

DELTA T	T + DT / DT	SURFACE PRESSURE	BOTTOM HOLE PRESSURE	PS - PWF
1.0	1,000	1443,0	1443,0	33,0
2.0	1,000	1436,0	1436,0	40,0
3.0	1,000	1432,0	1432,0	44,0
4.0	1,000	1429,0	1429,0	47,0
7.0	1,000	1429,0	1429,0	47,0
10.0	1,000	1429,0	1429,0	47,0
30.0	1,000	~~1429,0~~ 1428.	~~1429,0~~ 1428.	47,0
40.0	1,000	1428,0	1428,0	48,0
50.0	1,000	~~1428,0~~ 1426.	~~1428,0~~ 1426.	48,0
60.0	1,000	1426,0	1426,0	50,0
90.0	1,000	1425,0	1425,0	51,0
723.0	1,000	1425,0	1425,0	51,0


AC_CPUC_0118498



AC_CPUC_0118499



AC_CPUC_0118500



AC_CPUC_0118501

Compiled _____ Date _____

Approved _____ No. _____

Pacific Lighting Service Company

SS 29

FINAL FLOW

	ΔT	PRESS
	0	1470.6
	~~0~~	~~1447.1~~
(10b)	1	1442.9
	2	1436.0
	3	1431.8
	4	1429.1
	~~5~~	
	~~6~~	
	7	1429.
	~~8~~	
	~~9~~	
6:30 (9b)	10	1429.
	~~20~~	↓
	30	1427.7 ←
7:00	40	1427.7
	~~1 hr 50 min~~	1426.3 ←
8:00 (8b)	1 hr 0	1426.3
		↓
	1 hr 30 min	1424.9
	~~2 hr 0~~	
12:00	~~5 hr 0~~	
	~~8 hr 40~~	
18:23 (7b)	12 03	14.25

721

PLS-307

AC_CPUC_0118502

Compiled _____ Date _____

Approved _____ No. _____

Pacific Lighting Service Company

SS 29

FINAL SHUT-IN

	ΔT	PRESS
18:23	0	~~1424.9~~
	1 min	1459.5
	2	1466.4
	3	1469.2
	4	1472.0
	5	1474.7
	6	1476.1
	7	
	8	
	9	
	10	
	11	
18:35	12	
	22	
	32	
19:00	47	
	1 hr 17 min	
20:00	1 hr 47 min	
	2 | 47	
	3 | 47	
	4 | 47	
24:00	5 | 47	
	8 | 47	
6:40	12 ↓ | 27 ↓	1476

737

PLS-307

AC_CPUC_0118503

1424.9


ALISO CANYON STORAGE FLD SS 29, U SESNON ZONE PRESSURE BUILDUP TEST FEB 12 AND 13, 1973

DELTA T	T + DT / DT	SURFACE PRESSURE		BOTTOM HOLE PRESSURE	PS - PWF
1.0 .5	724,000 → 1447	1459,5	1456.7	1459,5	34,5
2.0 1.5	362,500 → 483	1466,4	1469.9	1466,4	41,4
3.0 2.5	242,000 → 290.2	1469,2	1469.2	1469,2	44,2
4.0 3.5	181,750 → 207.6	1472,0	1470.6	1472,0	47,0
5.0 4.5	145,600 → 161.7	1474,7	1473.3	1474,7	49,7
6.0 5.5	121,500 → 132.5	1476,1	1476.1	1476,1	51,1
747.0 6.5	1,968 → 112.2	1476,1	(6½=7.0 same)	1476,1	51,1
7.0	104.3				


Note:

6.1
9.7
T.9

AC_CPUC_0118504



AC_CPUC_0118505



AC_CPUC_0118506

INDIVIDUAL WELL PERFORMANCE TESTS
ALISO CANYON FIELD
STORAGE FIELD

WELL NO, SS 29, U SESNON ZONE TEST DATES 2-12-73 THROUGH 2-13-73

BASIC DATA

NET HYDROCARBON THICKNESS	= 46,00	OIL SATURATION	= ,230	WELLBORE RADIUS	= ,204
NET GAS SAND THICKNESS	= 46,00	GAS SATURATION	= ,300	WITHDRAWAL RATE	= 2,70
POROSITY, PHI	= ,080	WATER SATURATION	= ,470		

DATA FROM TESTS

	PRESSURE DRAWDOWN	PRESSURE BUILDUP
VOLUME FACTOR, BG	,02226	,01089
COMPRESSIBILITY, CT	,00054	,00028
VISCOSITY, MU	,01329	,01463
SLOPE, M	8,800	8,600
P(I) = P AT SHUT-IN	1476,	1425,
P* = EXTRAPOLATED P		1484,
P(1 HR)	1426,	1469,
P-BAR AVERAGE P	1425,	1476,
BOUNDARY TIME-LAG		,00
BOUNDARY SLOPE		27,000

AC_CPUC_0118507

ALISO CANYON FIELD
STORAGE FIELD

WELL NO. SS 29, U SESNON ZONE

TEST DATES 2-12-73 THROUGH 2-13-73

TEST RESULTS

	PRESSURE DRAWDOWN TRANSIENT	PRESSURE DRAWDOWN LATE TRANSIENT	PRESSURE BUILDUP
CONDUCTANCE, KH	2630.30	.00	1449.90
PERMEABILITY, K	57.18	.00	31.52
SKIN EFFECT, S	-.54	.00	-1.18
PRESSURE LOSS, DELP	-4.	0.	-9.
PRODUCTIVITY INDEX ACTUAL			8157.3
PRODUCTIVITY INDEX IDEAL			7097.1
FLOW EFFICIENCY			1.149
DISTANCE TO NEAREST BOUNDARY			15.998*

* INDICATES MORE THAN ONE BOUNDARY

AC_CPUC_0118508

ALISO CANYON FIELD
STORAGE FIELD

WELL NO; SS 29, U SESNON ZONE

TEST DATES 2-12-73 THROUGH 2-13-73

BASIC DATA

NET HYDROCARBON THICKNESS	= 46,00	OIL SATURATION	= ,230	WELLBORE RADIUS	= ,204
NET GAS SAND THICKNESS	= 46,00	GAS SATURATION	= ,300	WITHDRAWAL RATE	= 2,70
POROSITY, PHI	= ,080	WATER SATURATION	= ,470		

DATA FROM TESTS

	PRESSURE DRAWDOWN	PRESSURE BUILDUP
VOLUME FACTOR, BG	,02226	,01089
COMPRESSIBILITY, CT	,00054	,00028
VISCOSITY, MU	,01329	,01463
SLOPE, M	8,800	8,600
P(I) = P AT SHUT-IN	1476,	1425,
P* = EXTRAPOLATED P		1484,
P(1 HR)	1426,	1469,
P-BAR AVERAGE P	1425,	1476,
BOUNDARY TIME-LAG		,00
BOUNDARY SLOPE		27,000

AC_CPUC_0118509

ALISO CANYON FIELD
STORAGE FIELD

WELL NO, SS 29, U SESNON ZONE

TEST DATES 2-12-73 THROUGH 2-13-73

TEST RESULTS

	PRESSURE DRAWDOWN TRANSIENT	PRESSURE DRAWDOWN LATE TRANSIENT	PRESSURE BUILDUP
CONDUCTANCE, KH	2630,30	,00	1449,90
PERMEABILITY, K	57,18	,00	31,52
SKIN EFFECT, S	-,54	,00	-1,18
PRESSURE LOSS, DELP	-4,	0,	-9,

PRODUCTIVITY INDEX ACTUAL	8157,3
PRODUCTIVITY INDEX IDEAL	7097,1
FLOW EFFICIENCY	1,149

DISTANCE TO NEAREST BOUNDARY	15,998*

* INDICATES MORE THAN ONE BOUNDARY

AC_CPUC_0118510

SS-29
UPPER SESNOM

FINAL FLOW
PERF'D 4 HPF
8456 - 8502
BRIDGE PLUG 8515

Shut in press - 1180

SS# 29

6:20 AM open 1180 37/64 bean
6:21 - 950
6:22 - 890
6:23 - 859
6:24 - 830
6:25 - 810
6:26 - 790
6:27 - 785
6:28 - 775
6:29 - 772
6:30 - 775
6:31 - 775
6:32 - 775
6:33 - 770
6:34 - 765
6:35 - 762
6:36 - 760
6:37 - 763
6:38 - 763
6:39 - 763
6:40 - 763
6:45 - 767
6:50 - 767
6:55 - 775
7:00 - 779
7:10 - 810
7:20 - 830
7:30 - 855
7:40 - 870
7:50 - 850
8:00 - 810
8:10 - 817
8:20 - 820
8:30 - 820
9:30 - 827
10:30 - 807
11:30 - 767
12:30 - 777
1:30 - 767
2:30 - 767
3:30 - 767
4:30 - 765
5:30 - 765
6:30 - 765 shut in.

AC_CPUC_0118511

FEB 12, 1973 FLOW TEST ON STANDARD SNOW 29


COEFF 151010


BEAN SIZE	TIME	PLATE SIZE	24 Hr GAS RATE	FLUID GROSS	FLUID NET	
	6:20 AM	OPENED WELL				SI PRESS ON WELL 1180 psi
32/64	7:00 AM	HX 3.000	2591	0.0	0.0	
"	8:00 AM	" "	2375	1.7	1.2	
"	9:00 AM	" "	2412	3.2	2.3	
"	10:00 AM	" "	2573	3.4	2.6	
"	11:00 AM	" "	2732	3.9	3.0	
"	12:00 N	" "	2742	4.3	3.4	
"	1:00 PM	" "	2753	5.1	4.0	
"	2:00 PM	" "	2753	5.7	4.6	
"	3:00 PM	" "	2753	6.3	5.2	
"	4:00 PM	" "	2753	7.2	5.7	
"	5:00 PM	" "	2699	8.1	6.5	
"	6:20 PM	SHUT IN	2720	9.4	7.5	

TOTAL FLUID = 9.4 bbls.
WATER = 1.9 "
OIL = 7.5 "
TOTAL GAS PROD = 13.48 MCF


L. L. Schwab

AC_CPUC_0118512


6 A.M.
7 A.M.
8 A.M.
9 A.M.
10 A.M.
11 A.M.
12 NOON
1 P.M.
2 P.M.
3 P.M.
4 P.M.
5 P.M.
6 P.M.
ARCCO



AC_CPUC_0118514



AC_CPUC_0118515

Open at 10:37 → 10:39 - 330# SS #29 Feb 10 1973

10:41 - 330 #
10:42 - 465
10:43 - 605
10:44 - 222
10:45 - 824
10:46 - 918
10:47 - 980 - Pressure fluctuation
10:48 - 1010
10:49 - 1041
10:50 - 1060 INITIAL FLOW
10:51 - 1078
10:52 - 1082
10:53 - 1090
10:54 - 1100
10:55 - 1039 Pressure broke.
11:00 - 957
11:05 - 937
11:10 - 921 Pressure broke (FTL ready)
11:15 - 710
11:20 - 622
11:30 - 700
11:40 - 640
11:49 - 747
2:37 762 shut in
2:38 - 987
2:39 - 1061
2:40 - 1118
2:41 - 1147 INITIAL SHUT IN
2:42 - 1170
2:43 - 1179
2:44 - 1180
2:45 - 1180
2:46 - 1180
2:47 - 1180
2:48 - 1180
2:49 - 1180
2:50 - 1180

S-4
PERF'D 4 HPF
8456 - 8502
B.P. 8515

AC_CPUC_0118516

55. #24

8:55 - 1180
9:00 - 1180
9:05 - 1180
9:10 - 1180
9:15 - 1180
9:20 - 1180
9:40 - 1180
10:00 - 1180
10:20 - 1180
10:25 - 1180
4:37 1180

AC_CPUC_0118517

FLOW TEST ON STAND SESNON 29 FEB 10, 1973


COEFF

BEAN SIZE	TIME	PLATE SIZE	24 HR GAS RATE	FLUID GROSS	FLUID NET
OPENED TESTER	10:37 AM				
24/64	10:55 AM	HX 3.000	1125	—	—
32/64	11:10 AM	" "			
"	11:20 AM	" "	—	9.2	8.3
"	11:30 AM	" "	2126	10.3	9.3
"	12:30 PM	" "	2283	12.4	11.0
"	1:30 PM	" "	2338	13.4	11.4
"	2:30 PM	" "	2664	14.3	11.8
"	3:45 PM	" "	2718	15.4	12.2
"	3:50 PM	SHUT IN	2718	—	—

TOTAL FLUID = 15.4 bbls
WATER = 3.2 bbls
OIL = 12.2 bbls
TOTAL GAS PROD = 520 MCF


L. J. Schwab

AC_CPUC_0118518



AC_CPUC_0118519

AC_CPUC_0118520


6 A.M.
7 A.M.
8 A.M.
9 A.M.
10 A
4 P.M.
5 P.M.
6 P.M.
7 P.M.
ARCCO
B 0-2000P-12
S-8
SS#29
2-9-73

JAN 16-25, 1973

AC_CPUC_0118522

WELL TEST PRESSURE OBSERVATION CODING FORM

HEADER CARD #1

ALISO CANYON STORAGE FLD
CC 1-24 FIELD NAME

PRESSURE BUILDUP TEST
CC 25-48 TYPE OF TEST

PER CAMCO PRESSURE BOMB

SS 29 FREW ZONE
CC 49-72 WELL IDENTIFICATION

HEADER CARD #2

JAN 16-19, 1973
CC 1-24 TEST DATE

56
CC 25-29 NUMBER OF OBSERVATIONS

24
CC 30-45 DELTA T

0
CC 46-60 DEPTH TO DATUM

500
CC 61-75 STARTING PRESSURE

DATA CARDS

TIME FROM START HOURS CC 7-9	TIME FROM START MIN CC 10-11	PRESSURE CC 16-21
	1.5	6,32
	1.6	6,89
	1.8	7,62
	2.0	7,71
	2.2	7,87
	2.5	7,93
	3.0	7,98
	3.5	8,03
	4.0	8,08
	4.5	8,17
	5.5	8,26
.1	0.5	8,34
.1	1.5	8,42
.1	2.5	8,47
.1	3.5	8,51
.1	4.5	8,54
.1	5.5	8,57
.2	0.5	8,59
.2	1.5	8,62
.3	1.5	8,71
.4	1.5	8,75
.5	1.5	8,77
.6	1.5	8,82
.7	1.5	8,90
.8	1.5	8,98

TIME FROM START HOURS CC 7-9	TIME FROM START MIN CC 10-11	PRESSURE CC 16-21
.9	1.5	9,06
1.0	1.5	9,13
1.1	1.5	9,19
1.2	1.5	9,26
1.3	1.5	9,34
1.4	1.5	9,41
1.5	1.5	9,44
1.6	1.5	9,51
1.7	1.5	9,57
1.8	1.5	9,61
2.0	1.5	9,72
2.2	1.5	9,79
2.4	1.5	9,90
2.6	1.5	9,97
2.8	1.5	10,04
3.0	1.5	10,09
3.2	1.5	10,14
3.4	1.5	10,20
3.6	1.5	10,23
3.8	1.5	10,27
4.0	1.5	10,34
4.2	1.5	10,39
4.4	1.5	10,44
4.6	1.5	10,46
4.8	1.5	10,50

Sys-DP 14 K.P.

Inf-Sys 3 K.P.

Cont. on next page

AC_CPUC_0118523

WELL TEST PRESSURE OBSERVATION CODING FORM

HEADER CARD #1

ALISO CANYON STORAGE FLD
CC 1-24 FIELD NAME

PRESSURE BUILDUP TEST
CC 25-48 TYPE OF TEST

SS 29
CC 49-72 WELL IDENTIFICATION

HEADER CARD #2

JAN 16-19, 1973
CC 1-24 TEST DATE

CC 25-29 NUMBER OF OBSERVATIONS

24
CC 30-45 DELTA T

0
CC 46-60 DEPTH TO DATUM

5000
CC 61-75 STARTING PRESSURE

continued from 1st page
DATA CARDS

TIME FROM START HOURS CC 7-9	TIME FROM START MIN CC 10-11	PRESSURE CC 16-21
50	15	1054
52	15	1058
54	15	1062
71	45	1071
add → 194	00	1089
218	00	1103

TIME FROM START HOURS CC 7-9	TIME FROM START MIN CC 10-11	PRESSURE CC 16-21

Inj-Sta 3 K.P.


Inj-Sta 4 K.P.

AC_CPUC_0118524


ALISO CANYON STORAGE FLD 5829, [illegible] Zone — PRESSURE BUILDUP TEST 9 JAN 16-25, 1973

DELTA T	T + DT / DT	SURFACE PRESSURE	BOTTOM HOLE PRESSURE	PS - PWF
15.0	97.000	632.0	632.0	132.0
16.0	91.000	689.0	689.0	189.0
18.0	81.000	762.0	762.0	262.0
20.0	73.000	771.0	771.0	271.0
22.0	66.455	787.0	787.0	287.0
25.0	58.600	793.0	793.0	293.0
30.0	49.000	798.0	798.0	298.0
35.0	42.143	803.0	803.0	303.0
40.0	37.000	808.0	808.0	308.0
45.0	33.000	817.0	817.0	317.0
55.0	27.182	826.0	826.0	326.0
65.0	23.154	834.0	834.0	334.0
75.0	20.200	842.0	842.0	342.0
85.0	17.941	847.0	847.0	347.0
95.0	16.158	851.0	851.0	351.0
105.0	14.714	854.0	854.0	354.0
115.0	13.522	857.0	857.0	357.0
125.0	12.520	859.0	859.0	359.0
135.0	11.667	862.0	862.0	362.0
185.0	8.385	871.0	871.0	371.0
255.0	6.647	875.0	875.0	375.0
315.0	5.571	877.0	877.0	377.0
375.0	4.840	882.0	882.0	382.0
435.0	4.310	890.0	890.0	390.0
495.0	3.909	896.0	896.0	398.0
555.0	3.595	906.0	906.0	406.0
615.0	3.341	913.0	913.0	413.0
675.0	3.133	919.0	919.0	419.0
735.0	2.959	926.0	926.0	426.0
795.0	2.811	934.0	934.0	434.0
855.0	2.684	941.0	941.0	441.0
915.0	2.574	944.0	944.0	444.0
975.0	2.477	951.0	951.0	451.0
1035.0	2.391	957.0	957.0	457.0
1095.0	2.315	961.0	961.0	461.0
1215.0	2.185	972.0	972.0	472.0
1335.0	2.079	979.0	979.0	479.0
1455.0	1.990	990.0	990.0	490.0
1575.0	1.914	997.0	997.0	497.0
1695.0	1.850	1004.0	1004.0	504.0
1815.0	1.795	1009.0	1009.0	509.0
1935.0	1.744	1014.0	1014.0	514.0
2055.0	1.701	1020.0	1020.0	520.0
2175.0	1.662	1023.0	1023.0	523.0
2295.0	1.627	1027.0	1027.0	527.0
2415.0	1.596	1034.0	1034.0	534.0
2535.0	1.568	1039.0	1039.0	539.0
2655.0	1.542	1044.0	1044.0	544.0
2775.0	1.519	1046.0	1046.0	546.0
2895.0	1.497	1050.0	1050.0	550.0
3015.0	1.478	1054.0	1054.0	554.0
3135.0	1.459	1058.0	1058.0	558.0
3255.0	1.442	1062.0	1062.0	562.0
4305.0	1.334	1071.0	1071.0	571.0
11640.0	1.164	1089.0	1089.0	589.0
13010.0	1.136	1103.0	1103.0	603.0

AC_CPUC_0118525



AC_CPUC_0118526



AC_CPUC_0118527

Mario

① @ (sp) XQT (sp) CUR

② FSTIN (sp) ALITAB/RDH


③ PCH (sp) 1

Fr: Fairbanks to 1108

Ben Barker Harlan
1-19-73
Marion

AC_CPUC_0118528

SEMI-LOGARITHMIC 46 5390
4 CYCLES X 60 DIVISIONS
KEUFFEL & ESSER CO.



AC_CPUC_0118529

ENGINEERING DATA

SOUTHERN CAL. GAS CO.
ALISO CANYON

ΔT.	PRESSURE	Δt(MIN.)
	354#	AT 0' IN LUBRICATOR
15	632#	AT BOTTOM HOLE (8510')
16	689	- 1
18	762	- 3
20	771	- 5
22	787	- 7
25	793	- 10
30	798	- 15
35	803	- 20
40	808	- 25
45	817	- 30
55	826	- 40
65	834	- 50
75	842	- 60
85	847	- 70
95	851	- 80
105	854	- 90
115	857	- 100
125	859	- 110
135	862	- 120
195	871	- 180
255	875	- 240
315	877	- 300
375	882	- 360
435	890	- 420
495	898	- 480
555	906	- 540
615	913	- 600
675	919	- 660
735	926	- 720
795	934	- 780
855	941	- 840
915	944	- 900
975	951	- 960
1035	957	- 1020

PRESSURE	Δt(MIN.)
1095 961#	- 1080 MIN.
1215 972	- 1200
1335 979	- 1320
1455 990	- 1440
1575 997	- 1560
1695 1004	- 1680
1815 1009	- 1800
1935 1014	- 1920
2055 1020	- 2040
2175 1023	- 2160
2295 1027	- 2280
2415 1034	- 2400
2535 1039	- 2520
2655 1044	- 2640
2775 1046	- 2760
2895 1050	- 2880
3015 1054	- 3000
3135 1058	- 3120
3255 1062	- 3240
	CLOCK STOPPED
	MAX. BUILD-UP
4305 1071#	- 4290 MIN.
11520 1089	
13001 1103	


AC_CPUC_0118530

TECHNICAL SERVICE CO
801 West 14th Street
Long Beach, California 90813

Phones: 24 Hours
Long Beach - 436-9901

SUB-SURFACE PRESSURE DATA

Company Southern Calif. Gas Company Field Aliso Canyon Date 1-24-73 Run No. In
Well Standard Sesnon #29 Zone Elev.
Purpose Static Pressure Gradient Survey Status Shut In
Total Depth Effect. Depth
Casing Size Depth Liner Size Top Bottom
Perforations
Tubing 2-1/2" & 2", X-over @ 8028'. G/L mandrels @ 1654', 3049', 4335', 5566', 6212', 7502', 8212', 8631'



OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas-Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	769
Tubinghead Pressure - PSIG	794
Casing Fluid Level - Ft.	

RESULTS

Gross Productivity Index	B/D PSI
Net Productivity Index	B/D PSI
Static M.E.P. - Run No.	PSI
Static M.E.P. - Projected	PSI
Gross Absolute Potential	B/D
Net Absolute Potential	B/D
Datum Pressures:	

Traverse Depth Feet	Pressure PSIG	Gradient PSI/FT
0	794	
4000	877	0.021
5000	897	0.020
6000	918	0.021
7000	939	0.021
8000	962	0.023
8615	1089	0.207
Check	Instr.	
0	794	
4000	879	
5000	903	
6000	924	
7000	944	
8000	966	
8615	1093	

COMMENTS Zero: 10' Above Mat

By Harlan-Worley-Homer

AC_CPUC_0118531

TECHNICAL SERVICE CO.
801 West 14th Street
Long Beach, California 90813

Phones: 24 Hours
Long Beach - 436-9901
Ventura - - - 648-4888

SUB-SURFACE PRESSURE DATA

Company Southern Calif. Gas Company Field Aliso Canyon Date 1-(24-25)-73 Run No.
Well Standard Sesnon #29 Zone Elev.
Purpose Pressure Buildup Survey Status Shut In
Total Depth Effect. Depth
Casing Size Depth Liner Size Top Bottom
Perforations
Tubing 2-1/2" & 2", X-over @ 8028'. G/L mandrels @ 1654', 3049', 4335', 5566', 6212', 7502', 8212', 8631'

DEPTH: 8615'


Time Hrs.	Pressure PSIG	Time Hrs.	Pressure PSIG	Time Hrs.	Pressure PSIG
0:00	1089	23:25	1102	Check	Instr.
1:00	1090			0:00	1093
2:00	1091			5:00	1095
3:00	1091			10:00	1098
4:00	1092			16:00	1100
5:00	1093			20:00	1102
6:00	1093			23:25	1103
8:00	1094				
10:00	1096				
12:00	1098				
14:00	1099				
16:00	1100				
18:00	1100				
20:00	1101				
22:00	1102				

OBSERVATIONS

Stabilization Period - Hrs. 23:25	Shut-in
Run No.	
Time at Depth 2:20 PM	
Time off Depth 1:45 PM	
Csg. PSIG: Start - End 769 - 780	
Tbg. PSIG: Start - End 794 - 805	
Zero: 10' Above Mat	

Comments:
Maximum Temperature 186°F.

By: Harlan-Worley-Homer



T-16—Pfanstiel Printing


AC_CPUC_0118532

TECHNICAL SERVICE CO
801 West 14th Street
Long Beach, California 90813

Phones: 24 Hours
Long Beach - 436-9901

SUB-SURFACE PRESSURE DATA

Company Southern Calif. Gas Company Field Aliso Canyon Date 1-25-73 Run No. Out
Well Standard Sesnon #29 Zone Elev.
Purpose Static Pressure Gradient Survey Status Shut In
Total Depth Effect. Depth
Casing Size Depth Liner Size Top Bottom
Perforations
Tubing 2-1/2" & 2", X-over @ 8028'. G/L mandrels @ 1654', 3049', 4335', 5566', 6212', 7502', 8212', 8631'



OBSERVATIONS

Stabilization Period - Hrs.	
Gross Oil Rate - B/D	
Net Oil Rate - B/D	
Formation Gas MCF/D	
Formation Gas-Oil Ratio CFT/BBL	
Circulated Gas MCF/D	
Oil Dry Gravity - °A.P.I.	
Casinghead Pressure - PSIG	780
Tubinghead Pressure - PSIG	805
Casing Fluid Level - Ft.	

RESULTS

Gross Productivity Index	B/D PSI
Net Productivity Index	B/D PSI
Static M.E.P. - Run No.	PSI
Static M.E.P. - Projected	PSI
Gross Absolute Potential	B/D
Net Absolute Potential	B/D
Datum Pressures:	

Traverse Depth Feet	Pressure PSIG	Gradient PSI/FT
0	805	
4000	889	0.021
5000	912	0.023
6000	935	0.023
7000	955	0.020
8000	977	0.022
8615	1102	0.203
Check	Instr.	
0	803	
4000	887	
5000	909	
6000	931	
7000	955	
8000	978	
8615	1103	

COMMENTS Zero: 10' Above Mat

By Harlan-Worley-Homer

AC_CPUC_0118533

INDIVIDUAL WELL PERFORMANCE TESTS
ALISO CANYON FIELD
STORAGE FIELD

WELL NO. SS 29, FREW ZONE

TEST DATES 1-16-73 THROUGH 1-25-73

BASIC DATA

NET HYDROCARBON THICKNESS	= 313.00	OIL SATURATION	= .400	WELLBORE RADIUS	= .204
NET GAS SAND THICKNESS	= 10.00	GAS SATURATION	= .300	WITHDRAWAL RATE	= .04
POROSITY, PHI	= .100	WATER SATURATION	= .300		

DATA FROM TESTS

PRESSURE BUILDUP

VOLUME FACTOR, BG	.02225
COMPRESSIBILITY, CT	.00060
VISCOSITY, MU	.01329
SLOPE, M	104.000
P(I) = P AT SHUT-IN	500.
P* = EXTRAPOLATED P	977.
P(1 HR)	830.
P-BAR AVERAGE P	1123.
BOUNDARY TIME-LAG	10.20
BOUNDARY SLOPE	457.000

AC_CPUC_0118534

WELL NO. SS 29, FREW ZONE

TEST RESULTS

TEST DATES 1-16-73 THROUGH 1-25-73

PRESSURE BUILDUP

CONDUCTANCE, KH	3.54
PERMEABILITY, K	.35
SKIN EFFECT, S	-.72
PRESSURE LOSS, DELP	-65.
PRODUCTIVITY INDEX ACTUAL	16.1
PRODUCTIVITY INDEX IDEAL	14.1
FLOW EFFICIENCY	1.136
DISTANCE TO NEAREST BOUNDARY	68.732*

* INDICATES MORE THAN ONE BOUNDARY

AC_CPUC_0118535

ALISO CANYON FIELD
STORAGE FIELD

WELL NO, SS 29,FREW ZONE TEST DATES 1-16-73 THROUGH 1-25-73

BASIC DATA

NET HYDROCARBON THICKNESS	= 313,00	OIL SATURATION	= ,400	WELLBORE RADIUS	= ,204
NET GAS SAND THICKNESS	= 10,00	GAS SATURATION	= ,300	WITHDRAWAL RATE	= ,04
POROSITY, PHI	= ,100	WATER SATURATION	= ,300		

DATA FROM TESTS

PRESSURE BUILDUP

VOLUME FACTOR, BG	,02225
COMPRESSIBILITY, CT	,00060
VISCOSITY, MU	,01329
SLOPE, M	104,000
P(I) = P AT SHUT-IN	500,
P* = EXTRAPOLATED P	977,
P(1 HR)	830,
P-BAR AVERAGE P	1123,
BOUNDARY TIME-LAG	10,20
BOUNDARY SLOPE	457,000

AC_CPUC_0118536

ALISO CANYON FIELD
STORAGE FIELD

WELL NO. SS 29,FREW ZONE TEST DATES 1-16-73 THROUGH 1-25-73

TEST RESULTS

PRESSURE BUILDUP

CONDUCTANCE, KH	3,54
PERMEABILITY, K	,35
SKIN EFFECT, S	-,72
PRESSURE LOSS, DELP	-65,
PRODUCTIVITY INDEX ACTUAL	16,1
PRODUCTIVITY INDEX IDEAL	14,1
FLOW EFFICIENCY	1,136
DISTANCE TO NEAREST BOUNDARY	68,732*

* INDICATES MORE THAN ONE BOUNDARY

AC_CPUC_0118537

ALISO CANYON STORAGE FLD SS29, FRew ZONE PRESSURE BUILDUP TEST S JAN 16-25, 1973


DELTA T	T + DT / DT	SURFACE PRESSURE	BOTTOM HOLE PRESSURE	PS - PWF
15.0	97,000	632,0	632,0	132,0
16.0	91,000	689,0	689,0	189,0
18.0	81,000	762,0	762,0	262,0
20.0	73,000	771,0	771,0	271,0
22.0	66,455	787,0	787,0	287,0
25.0	58,600	793,0	793,0	293,0
30.0	49,000	798,0	798,0	298,0
35.0	42,143	803,0	803,0	303,0
40.0	37,000	808,0	808,0	308,0
45.0	33,000	817,0	817,0	317,0
55.0	27,182	826,0	826,0	326,0
65.0	23,154	834,0	834,0	334,0
75.0	20,200	842,0	842,0	342,0
85.0	17,941	847,0	847,0	347,0
95.0	16,158	851,0	851,0	351,0
105.0	14,714	854,0	854,0	354,0
115.0	13,522	857,0	857,0	357,0
125.0	12,520	859,0	859,0	359,0
135.0	11,667	862,0	862,0	362,0
195.0	8,385	871,0	871,0	371,0
255.0	6,647	875,0	875,0	375,0
315.0	5,571	877,0	877,0	377,0
375.0	4,840	882,0	882,0	382,0
435.0	4,310	890,0	890,0	390,0
495.0	3,909	898,0	898,0	398,0
555.0	3,595	906,0	906,0	406,0
615.0	3,341	913,0	913,0	413,0
675.0	3,133	919,0	919,0	419,0
735.0	2,959	926,0	926,0	426,0
795.0	2,811	934,0	934,0	434,0
855.0	2,684	941,0	941,0	441,0
915.0	2,574	944,0	944,0	444,0
975.0	2,477	951,0	951,0	451,0
1035.0	2,391	957,0	957,0	457,0
1095.0	2,315	961,0	961,0	461,0
1215.0	2,185	972,0	972,0	472,0
1335.0	2,079	979,0	979,0	479,0
1455.0	1,990	990,0	990,0	490,0
1575.0	1,914	997,0	997,0	497,0
1695.0	1,850	1004,0	1004,0	504,0
1815.0	1,793	1009,0	1009,0	509,0
1935.0	1,744	1014,0	1014,0	514,0
2055.0	1,701	1020,0	1020,0	520,0
2175.0	1,662	1023,0	1023,0	523,0
2295.0	1,627	1027,0	1027,0	527,0
2415.0	1,596	1034,0	1034,0	534,0
2535.0	1,568	1039,0	1039,0	539,0
2655.0	1,542	1044,0	1044,0	544,0
2775.0	1,519	1046,0	1046,0	546,0
2895.0	1,497	1050,0	1050,0	550,0
3015.0	1,478	1054,0	1054,0	554,0
3135.0	1,459	1058,0	1058,0	558,0
3255.0	1,442	1062,0	1062,0	562,0
4305.0	1,334	1071,0	1071,0	571,0
11640.0	1,164	1089,0	1089,0	589,0
[illegible]	1,110	[illegible]	[illegible]	[illegible]

AC_CPUC_0118538


ALISO CANYON STORAGE FLD SS-29, U SESNON ZONE PRESSURE BUILD-UP TEST 4-6-73 TO 4-9-73

DELTA T	T + DT / DT	SURFACE PRESSURE	BOTTOM HOLE PRESSURE	PS - PWF
1.0	51841,000	1264,0	1264,0	95,0
2.0	25921,001	1315,0	1315,0	146,0
3.0	17281,000	1334,0	1334,0	165,0
4.0	12961,000	1345,0	1345,0	176,0
5.0	10369,000	1348,0	1348,0	179,0
6.0	8641,000	1349,0	1349,0	180,0
7.0	7406,714	1350,0	1350,0	181,0
8.0	6481,000	1350,0	1350,0	181,0
9.0	5761,000	1350,0	1350,0	181,0
10.0	5185,000	1353,0	1353,0	184,0
12.0	4321,000	1353,0	1353,0	184,0
14.0	3703,857	1354,0	1354,0	185,0
16.0	3241,000	1355,0	1355,0	186,0
18.0	2881,000	1355,0	1355,0	186,0
20.0	2593,000	1356,0	1356,0	187,0
22.0	2357,364	1356,0	1356,0	187,0
24.0	2161,000	1356,0	1356,0	187,0
26.0	1994,846	1357,0	1357,0	188,0
28.0	1852,429	1357,0	1357,0	188,0
30.0	1729,000	1360,0	1360,0	191,0
42.0	1235,286	1362,0	1362,0	193,0
50.0	1037,800	1357,0	1357,0	188,0
60.0	865,000	1366,0	1366,0	197,0
70.0	741,571	1363,0	1363,0	194,0
80.0	649,000	1400,0	1400,0	231,0
120.0	433,000	1400,0	1400,0	231,0
300.0	173,800	1400,0	1400,0	231,0
600.0	87,400	1400,0	1400,0	231,0
900.0	58,600	1401,0	1401,0	232,0
1200.0	44,200	1402,0	1402,0	233,0
1320.0	40,273	1402,0	1402,0	233,0
1350.0	39,400	1411,0	1411,0	242,0
1380.0	38,565	1410,0	1410,0	241,0
1500.0	35,560	1410,0	1410,0	241,0
1800.0	29,800	1413,0	1413,0	244,0
2100.0	25,686	1413,0	1413,0	244,0
2400.0	22,600	1415,0	1415,0	246,0
2700.0	20,200	1416,0	1416,0	247,0
3000.0	18,280	1418,0	1418,0	249,0
3300.0	16,709	1419,0	1419,0	250,0
3600.0	15,400	1420,0	1420,0	251,0
3900.0	14,292	1421,0	1421,0	252,0
4200.0	13,343	1418,0	1418,0	249,0
4320.0	13,000	1415,0	1415,0	246,0

AC_CPUC_0118539




AC_CPUC_0118540



AC_CPUC_0118541

Standard Sesnon 29

AC_CPUC_0118542



FLO-LOG INC.

Company So Calif Gas
Type of Survey Noise i Temp
Date of Survey 10-25-91
Lease, Well No. Sesnon 29
Field Aliso

AC_CPUC_0118543

Attachment 4 (2 of 2)

FLO-LOG

PRODUCTION LOGGING SURVEY DATA SHEET

COMPANY So. Cal Gas CO. DATE 10-25-91

WELL NO. Standard Season #29 FIELD Aliso Canyon

COUNTY Los Angeles STATE CA.

REPRESENTATIVE Jim Hemmerly SURVEY CREW Helms, Kiser, Schrader

TYPE OF SURVEY Temp & Noise

PURPOSE OF SURVEY Check Shoe for leaks after Cement Top

CASING AND TUBING RECORD

SIZE	WEIGHT	FROM	TO
11-3/4"	42# & 47#	0	1042
7"	23# & 26#	0	8180
5"	18#	8075	9790

Effective Depth 9094 PBTD
Perforations 8456-8694 @ Intervl.
8727-9094 slotted

W.S.O. _____ C.P. _____

Tubing Size ~~Drillpipe~~ Depth 7544
Packer(s) 7510
~~Mandrel(s)~~

Measurement Datum 16' K.B.
Reference Point R.F.

WELL STATUS Shut-In

Meter Rate 0 BWPD Oil Rate / b/d
Flow Loss / BWPD Oil Gravity / °
Obs. Rate 0 BWPD Gas Rate / Mcf/d
Reported Tbg Press. _____ psi Obs. 2800
Reported Csg Press. _____ psi Obs. 0

Pickup D.D.A @ 8800 Fill N/A
Bottom Temp. 111.9° °F Fluid Level 8532

SPINNER STATS

Depth	Counts	Rate	Depth	Counts	Rate
/	/	/	/	/	/

Reset Depth (from) 8094 (to) 8075
Depth Corrected to Liner Top

Logging Unit 712 Line Size 3/16 Line Length 24,600
Tools Used 2-5' Bars, T.S. Bar, CAP, C.C.L., Temp., Noise
Tool Numbers _____
Tool Diameter 1-7/8"

Time Arrived on Location 6:00 AM Off Location _____ Total Hours _____


Time of Run	Run No.	Type of Survey	Survey Calib.	Line Speed	Direction	Logged Interval (from)	(to)
9:45pm	1	Temp/C.C.L.	5°/In	90	Down	500	8800
	~~2~~	~~Noise~~	~~warm~~		~~up~~		
11:20pm	2	Cap	200#/In	85	up	8800	7400
	3	~~Cap~~ CCL	—	85	up	8200	7900
	4	Noise	warm	—	up	8600	

REMARKS:

☆ Temp in Black Room 10-25-91, Temp in Green Room 10-27-91 ☆

FLO-LOG INC.

WELL NO. Standard Source #39 DATE 10-25-91



AC_CPUC_0118546

7900

20

40

60

80

0 1 2 3 4 5 6 7 8 9 10

9000

20

40

60

80

0 1 2 3 4 5 6 7 8 9 10

8100

20

40

60

80

8200

0 1 2 3 4 5 6 7 8 9 10

Cal for Depth Control

0 1 2 3 4 5 6 7 8 9 10

FLO-LOG

CO. NAME So Cal Gas Co

WELL NO. SS #29 DATE 10-25-91

RUN NO. _____ TYPE LOG _____

CALIB. _____ LINE SPD. _____ DIRECTION _____


METER RATE _____ PRESSURE _____

PRINTED IN U.S.A.


No. BN 6277

PRINTED IN U.S.A.

AC_CPUC_0118547



AC_CPUC_0118548



AC_CPUC_0118549

FLO-LOG INC.


Company So Cal. Gas
Type of Survey Noise & Temp
Date of Survey 10-21-91
Lease, Well No. Standard Sesnon #29
Field Aliso Canyon

AC_CPUC_0118550

3rd log attempt
(Rig)

DF: 7' MV: 6

Standard Sesnon 29



Surface Choke: _____
Casing flow string

--8002' Otis 2-1/2" SSSV
(8002') 2.313"ID

*--8029' Otis "XN" No-Go Nipple
(8029') 2.205"

--8049'

--(8256') (-5400)

--S4 8428'

--S8 8520' (8520')

--HZ 8682'

--Frew 8727'

9077'

(SS - 6941')

4/26/53 Well spud
9/29/53 Well completed
2/2/73-2/28/73 Pressure tested 7" casing, converted to gas stor by perforating in Sesnon Zone, cleaned out to 9074', ran tubing with SSSV
7/31/73-8/7/73 Installed wirel SSSV, cleaned out to 9077'
8/27/77-9/9/77 Cleaned out to 9072', pressure tested casing, reran tubing with SSSV
3/5/79-3/10/79 Replaced safety system, set packer at 8040'

*Note:
USE 2.290 EQUAL. I.D. PRIOR TO 3-79 PACK 2.25" I.D. NIPPLE

Check for Shoe Leak
1) Temp to TD
2) Capacitance to find Fluid Level
3) Noise Log

Interval	Stops
8500-7900'	20'
7800-Surf	200'


WELL VOLUME

	Cu.Ft.	Bbl.
Tubing	262	47
Csg/Lnr.	105	19
Annulus	1405	250

9790
9094
696
9021
9790

6-16-86

AC_CPUC_0118552



OPERATOR Southern California Gas Co.

WELL # S.S. #29

FIELD Aliso Canyon

COUNTY Los Angeles

STATE California

DATE March 13, 1979

☐ NEW COMPLETION ☐ WORKOVER

	CASING	LINER	TUBING 1	TUBING 2	TUBING 3
SIZE					
WEIGHT					
GRADE					
THREAD					
DEPTH					

ITEM NO.	TUBING DETAILS	LENGTH	DEPTH
1.	Kelly Bushing	6.92	-
2.	Tubing Hanger	.30	6.9
3.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	1.18	7.7
4.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	3.15	8.9
5.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	10.25	12.0
6.	16 joints 2 7/8" 6.5# N-80 8rd EUE	500.84	22.3
7.	243 Joints 2 7/8" 6.5# J-55 8rd EUE	7473.19	523.1
8.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	4.09	7996.3
9.	Otis "X" nipple 2.350" I.D.	1.13	8000.4
10.	Otis Annular Flow Safety System 4.88" O.D., 2.313" I.D.	7.66	8001.5
11.	Otis blast joint with 4 centralizers 5.50" O.D., 2.375" I.D.	19.82	8009.2
12.	Otis "XN" No-Go Nipple 2.205" I.D.	1.17	8029.0
13.	Otis Blast Joint 3.668" O.D. 2.375" I.D.	9.80	8030.2
14.	Otis "J" latch locator	1.16	8040.0
15.	Otis "Permatrieve" 7" packer (new) (20-26#) 5.87" O.D. 3.25" I.D.	4.16	8040.0
16.	Otis seal assembly (4) 3.29" O.D., 2.38" I.D.	4.05	8041.1
17.	Otis Production Tube	2.96	8045.2
18	Otis Guide Shoe	.42	8048.1
	End of Tubing		8048.5

NOTES

Side door choke in safety system

Tubing landed with 10,000X compression on packer

Corrected tubing measurments (7,482.13) to meet wireline measurments.

COMMENTS:

AC_CPUC_0118553

FLO-LOG INC.

NOISE LOG DATA SHEET

Page ONE

Company So. Cal Gas Co. Well No. 55 #29

Date 10-21-91 Noise Tool Number 4056 Rev Calibration N

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
10:00	Bkd	55.9	12.1	10.9	3.4	20' STOPS 200 mV
	80	51.8	6.7	5.3	1.1	
	60	49.9	5.3	4.4	.9	Loud gas Sand
	40	58.2	6.5	5.1	1.2	
	20	54.6	6.3	4.7	.9	
	Bkd	58.4	6.4	4.9	1.2	
	80	41.3	6.5	5.0	1.2	
	60	20.7	5.2	4.5	1.1	
	40	20.8	5.5	4.24	1.2	
	20	21.6	5.7	4.5	1.1	
10:25	Bkd	20.2	5.4	4.3	1.1	
	80	18.6	5.4	4.4	1.1	
	60	20.4	4.8	4.0	1.1	
	40	20.1	5.3	4.2	1.1	
	20	20.4	5.0	3.9	1.1	
	Bkd	20.5	5.6	3.6	1.2	
	80	19.8	5.6	3.8	1.1	
	60	20.6	5.2	3.9	1.1	
	40	20.6	5.1	3.6	1.1	
	20	21.2	4.9	3.6	1.1	
	Bkd	19.2	5.6	3.7	1.1	20' STOPS 200mV
10:46	80	17.1	4.9	3.7	1.1	STILL HEAR GAS FLOW JUST
	60	17.8	5.1	3.9	1.1	
	40	19.4	5.1	3.8	1.1	
	20	19.7	5.0	3.9	1.1	
	Bkd	18.8	5.0	3.7	1.1	
	80	17.3	5.2	3.9	1.1	20'
	60	13.2	4.3	3.2	1.1	
	40	13.29	2.56	2.10	.87	
	20	11.16	2.26	1.94	.71	
	Bkd	11.96	2.55	2.07	.68	Tail Bkd'
	80	14.97	3.54	2.59	.68	
	60	12.03	2.69	1.95	.62	
	40	12.15	3.17	1.97	.64	
	20	7.81	2.15	1.67	.62	
	Bkd	6.96	1.78	1.36	.66	

FLO-LOG INC.

NOISE LOG DATA SHEET

Page Two

Company So Cal Gas Well No. SS#29

Date 10-21-91 Noise Tool Number 4056 Calibration N

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
7[illegible]	7880	7.63	1.48	1.02	.63	200mV 20' step
11:02	7860	6.47	1.40	1.05	.60	
	7840	6.80	1.39	.98	.66	
	7820	6.63	1.36	.98	.64	
	7800	6.63	1.35	.97	.67	
	7780	6.57	1.38	.97	.63	
	7760	6.15	1.31	.95	.57	
	7740	6.12	1.25	.87	.59	
	7720	5.99	1.21	.84	.57	
	7700	6.19	1.24	.81	.55	
	7680	5.99	1.23	.78	.55	
	7660	5.87	1.18	.81	.56	
	7640	5.98	1.15	.78	.54	
	7620	6.11	1.14	.80	.56	
	7600	5.79	1.17	.84	.62	
		REPEAT LOG				
11:25	8600	63.7	15.7	13.7	7.2	
	8580	42.2	6.4	4.7	1.3	
	8560	53.0	6.5	4.8	1.1	
	8540	60.4	6.4	4.9	1.3	
	8520	58.0	6.1	4.8	1.2	
	8500	58.2	5.9	4.5	1.1	
	8480	46.5	5.8	4.6	1.1	
	8460	18.3	4.8	4.0	1.0	
	8440	19.2	4.7	4.0	1.1	
	8420	19.2	4.5	3.9	1.1	
	8400	17.2	4.8	4.1	1.1	
	8380	18.8	4.7	4.1	1.1	
	8360	19.0	4.9	4.2	1.0	
	8340	19.1	4.9	4.2	1.0	
	8320	18.0	4.6	4.0	1.1	
	8300	16.7	4.1	3.2	1.0	
	8280	18.7	4.5	3.9	1.2	
	8260	18.6	4.3	3.6	1.2	
	8240	18.8	4.6	3.7	1.1	
		17.8	4.2	3.6	1.1	

FLO-LOG INC.

NOISE LOG DATA SHEET

Page THREE

Company So Cal Gas Co Well No. SS #29

Date 10-21-91 Noise Tool Number 4056 Calibration N

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
	8220	17.0	4.3	3.7	1.1	200mV 20' stops,
12:00	8200	16.9	4.2	3.6	1.1	
	8180	18.0	4.2	3.5	1.1	
	8160	16.4	4.3	3.6	1.1	
	8140	16.6	4.3	3.6	1.1	
	8120	16.9	4.4	3.6	1.1	
	8100	17.1	4.6	3.9	1.1	
	8080	18.7	4.6	4.0	1.0	
	8060	10.5	2.7	2.3	.9	
	8040	11.24	2.48	2.09	.9	20 mV 20' STOPS
	8020	12.19	2.61	2.22	.56	
	8000	12.14	2.32	1.88	.58	TBG TAIL @ 8002
	80	13.79	3.52	2.21	.60	
	60	12.65	2.97	1.83	.57	
	40	13.77	3.33	1.87	.55	
	20	7.89	2.03	1.53	.62	
	7900	7.86	1.86	1.05	.62	
						2' STOPS
	7996	12.17	3.25	2.31	.52	20 mV
	7988	12.90	3.20	2.18	.53	
	7986	12.75	3.11	2.04	.57	
	7984	14.27	2.71	1.94	.59	
	7982	12.30	2.78	1.90	.58	
	7980	12.71	3.11	2.16	.59	
	7978	13.44	2.88	2.12	.57	
	7976	12.40	2.96	2.11	.61	
	7974	12.93	3.07	2.05	.62	
	7972	14.32	3.14	2.06	.58	
	7970	13.96	3.12	2.04	.62	
	7968	13.15	3.05	2.12	.57	
	7966	13.13	3.17	2.11	.57	
	7964	13.09	2.75	1.87	.58	
	7962	11.47	2.35	1.77	.59	
	7960	10.73	2.99	2.06	.59	
	7958	11.64	2.76	1.76	.61	

FLO-LOG INC.

NOISE LOG DATA SHEET

Page FOUR

Company So Cal Gas Well No. SS #29

Date 10-21-91 Noise Tool Number 4056 Calibration N

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
	7956	11.82	2.56	1.67	.57	2' steps 20mV
	7954	13.80	4.53	2.18	.55	
	7952	12.95	3.07	2.32	.56	
	7950	15.56	3.62	2.17	.56	
	7948	14.84	3.24	2.16	.61	
	7946	15.00	3.02	2.04	.57	
	7944	14.89	3.25	2.09	.57	
	7942	14.72	3.16	1.96	.59	
	7940	13.32	3.01	2.03	.64	
	7938	14.10	3.03	1.96	.66	
	7936	9.83	2.54	1.54	.57	
	7934	6.83	1.95	1.44	.57	
	7932	7.29	1.93	1.39	.61	
	7930	7.98	1.82	1.36	.56	
	7928	7.57	1.91	1.47	.64	
	7926	7.56	1.89	1.41	.61	
	7924	7.46	1.89	1.49	.60	
	7922	7.92	1.99	1.53	.65	
	7920	7.42	1.92	1.47	.69	
		REPEAT	LOG	CONTINUED		
	7850	6.58	1.39	.99	.59	250' stops
	7800	6.31	1.39	.96	.63	
13:33	7700	6.64	1.30	.91	.68	
	7600	6.44	1.23	.87	.65	
		END	REPEAT			
	7400	5.46	1.03	.76	.54	
	~~7200~~	~~2.96~~	~~1.44~~	~~1.02~~	.58	
	~~7000~~	2.33	.94	.66	.53	
	7000	~~3.86~~	1.17	.91	.68	
	6800	3.60	.74	.68	.51	
	*					
	6500	4.81	.99	.90	.53	500' stops
	6000	3.89	2.38	1.60	.58	Tools Rooling
	5500	~~4.79~~	2.75	1.43	.68	IN TBG
	5000	~~3.89~~	~~2.97~~	1.52	.62	
Test	5000	47.1	7.0	6.2	3.59	

FLO-LOG INC.

NOISE LOG DATA SHEET

Page Four

Company So Cal Gas Co Well No. SIS #29

Date 10-21-1991 Noise Tool Number 4056 Calibration

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
9:55	2450	3.00	1.24	1.05	.56	
	2400	2.89	.97	.82	.55	
	3500	2.84	.94	.82	.56	Readings Hard To Catch Tool Rasping Around and Tapping
	3000	2.08	.86	75	.62	
	~~3500~~	~~2.89~~	1.~~35~~	1.39	.61	
	2500	2.05	1.78	1.42	.65	
	2000	2.76	1.19	.87	.65	
	1500	2.57	1.62	.92	.63	
	1000	2.98	1.89	1.04	.73	Wind Blowing Hoses and Ropes Around
	500	4.18	.96	.81	.65	

FLO-LOG

SCG_5529

PRODUCTION LOGGING SURVEY DATA SHEET

COMPANY So Cal Gas Co. DATE 10-21-91

WELL NO. Standard Sesnon #29 FIELD Aliso Canyon

COUNTY LA STATE CA

REPRESENTATIVE Jim Hemmerly SURVEY CREW Helms, Sturgess, Vazquez

TYPE OF SURVEY Temp + Noise

PURPOSE OF SURVEY Check Shoe for leaks after Cement Job

CASING AND TUBING RECORD

SIZE	WEIGHT	FROM	TO
7"	23# + 26#	0	8180
5"	18#	8075	9796

Effective Depth 9094 PBTD

Perforations 8456 - 9094 @ Int

W.S.O. _____ C.P. _____

Tubing Size Drillpipe Depth 8007

Packer(s) 7972

Mandrel(s) Tool Assembly 7946 - 7962

Measurement Datum 16' K-B

Reference Point Rig Floor

WELL STATUS Shut in 40 hours

Meter Rate _____ BWPD Oil Rate _____ b/d

Flow Loss _____ BWPD Oil Gravity _____ °

Obs. Rate _____ BWPD Gas Rate _____ Mcf/d

Reported Tbg Press. 2500 psi Obs. 2500

Reported Csg Press. 1900 psi Obs. 1900

Pickup DDA 8800 Fill N/A

Bottom Temp. 178.5 °F Fluid Level @ 8582

SPINNER STATS

Depth	Counts	Rate	Depth	Counts	Rate

Reset Depth (from) 8086 (to) 8075

Depth Corrected to Liner Top

Logging Unit 712 Line Size 3/16" Line Length 24600

Tools Used 60" Bar, 2-30" Bars, T-Bar, CCL, Temp, Cap, Noise, Centralizer


Tool Numbers 1072 4056

Tool Diameter 1 3/8


Time Arrived on Location 0800 Off Location 3/16" Total Hours 24600

Time of Run	Run No.	Type of Survey	Survey Calib.	Line Speed	Direction	Logged Interval (from)	(to)
8:00	1	Temp/CCL	5"/in	80	DN	7000	8800
9:35	2	Cap	200Hz	80	UP	8800	7900
10:10	3	Noise					


REMARKS: Backside full of fluid



AC_CPUC_0118560



AC_CPUC_0118561



AC_CPUC_0118562

FLO-LOG INC.

Company So. Cal Gas. CO.
Type of Survey Temp & Noise & Cap.
Date of Survey 10-18-91
Lease, Well No. Standard Season #29
Field Aliso Canyon

AC_CPUC_0118563

2nd log attempt
(RIG)

NOISE LOG SUMMARY REPORT

Field: Aliso Canyon Date: 10-18-91

Well Name: Standard Season #29 Logging Contractor: FLO-LOG

WELL DATA

Number of ~~Days~~ HRS Shut-in 36 HR Field Inventory _____ Bcf.

Date of Last Noise Log 12-5-90 Field Status Withdraw

Purpose of Survey _____

Surface Pressures

Tubing 2500 psig

Casing 1750 psig

Innerstring N/A psig

Surface Csg N/A psig

Fluid Levels

Tubing NONE ft. (method) _____

Casing 8556 ft. (method) Capacitance

Pickup Depth _____ ft.

Pertinent Marker Beds & Depths _____

Operating Valve Condition (leaking,sweating,icing,etc) OK.

LOGGING RUN DATA

Run No. 1	Run No. _____
Starting time: 11:45 am/~~pm~~	Starting time: _____ am/pm
Pressure:	Pressure:
Casing: 1750 psig	Casing: _____ psig
Tubing: 2500 psig	Tubing: _____ psig
Status: Shutin / ~~Flowing~~	Status: Shutin / Flowing
Noise Anomalies:	Noise Anomalies:
Storage zone: _____	Storage zone: _____
WSO: _____	WSO: _____
Liner: _____	Liner: _____
Packer: _____	Packer: _____
Other: _____	Other: _____

Comments/Recommendations: Wind is Stronger today, than yesterday.

Witness: Jim Hemmerly Resident: _____

AC_CPUC_0118565

FLO-LOG SCG_5529.7

PRODUCTION LOGGING SURVEY DATA SHEET

COMPANY So. Cal Gas Co. DATE 10-18-91

WELL NO. Standard Season #29 FIELD Aliso Canyon

COUNTY L.A. STATE CA.

REPRESENTATIVE Jim Hemmerly SURVEY CREW Schrader, Helms, Kiser

TYPE OF SURVEY Temp & Noise

PURPOSE OF SURVEY Check Shoe for Leaks after Cement Job.

CASING AND TUBING RECORD

SIZE	WEIGHT	FROM	TO
7"	23# & 26#	Ø	8180
5"	18#	8025	9796

Effective Depth 9094 P.B.T.D.
Perforations 8456-9094 @ Intv.

W.S.O. _____ C.P. _____

Tubing Size Drillpipe Depth 8002
Packer(s) 7972
Mandrel(s) Tool Assembly 7946-7962

Measurement Datum 16' KB
Reference Point MAT Rig Floor

WELL STATUS Shut-In

Meter Rate _____ BWPD Oil Rate _____ b/d
Flow Loss _____ BWPD Oil Gravity _____ °
Obs. Rate _____ BWPD Gas Rate _____ Mcf/d
Reported Tbg Press. 2500 psi Obs. 2500
Reported Csg Press. 1700-800 psi Obs. 1750

Pickup D.O.A @ 8620 Fill N/A
Bottom Temp. _____ °F Fluid Level 8556 I

SPINNER STATS

Depth	Counts	Rate	Depth	Counts	Rate

Reset Depth (from) 8089 (to) 8075 14' Deep
Depth Corrected to Liner Top By Cap Tool

Logging Unit 712 Line Size 3/16" Line Length 24,600
Tools Used 2-5 Bars, TS-Bar., C.C.L., Temp., Cap., Noise, Stabilizer
Tool Numbers _____
Tool Diameter 1-7/8"

Time Arrived on Location 6:00 Off Location _____ Total Hours _____

Time of Run	Run No.	Type of Survey	Survey Calib.	Line Speed	Direction	Logged Interval (from)	(to)
10:00 AM	1	Temp/C.C.L.	5°/IN	95	DOWN	200	8620
11:25 AM	2	Cap	2000 PSI	100	UP	8620	7960
11:45 AM	3	Noise	120 KM	—	UP	8600	
1:30 PM	4	Temp/ccl	5°/IN	100	DN	7600	8600
1:50	5	Noise					
3:30	6	TEMP	5°/IN	100	DN	5500	7600

REMARKS: Well shut in 36 HRS prior to Survey

F.C. @ 8510 uncorrected depth.

FLO-LOG INC.

NOISE LOG DATA SHEET

8540

Page ONE

Company So. Calif. Gas CO. Well No. Standard Sesnon #29

Date 10-18-91 Noise Tool Number #4085 Calibration NORM

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
12 00 NOON	8600	46.4	21.7	6.6	2.5	400 MV
	8580	56.3	27.3	7.5	2.5	20 FT
	8560	49.3	16.3	7.3	2.8	
	8540	57.5	13.3	7.0	1.4	
	8520	55.2	13.5	7.0	1.6	
	8500	58.6	14.6	6.8	1.4	
	6480	41.9	13.5	6.9	1.3	
	8460	17.6	10.0	6.0	1.3	
	8440	18.6	9.9	5.9	1.4	
	8420	17.4	8.7	5.7	1.8	
	8400	18.7	7.8	5.3	1.3	
	8380	16.3	7.2	5.1	1.1	
	60	16.4	7.3	5.7	1.0	
	40	16.5	7.7	5.7	1.1	
	20	17.8	7.2	5.4	1.1	
	8300	17.1	6.3	4.8	1.1	
12:20	8280	16.4	6.1	4.6	.8	
	60	16.3	5.7	4.4	.9	
	40	16.7	5.6	4.3	.9	
	20	15.3	5.6	4.2	.9	
	8200	15.1	5.7	4.2	.9	
	80	15.0	5.4	4.0	.9	
12:28	60	14.8	5.5	4.0	.9	
	40	14.7	5.0	3.6	.7	
	20	14.7	5.1	3.7	.7	
	8100	14.7	4.9	3.6	.7	
12:36	80	15.0	4.9	3.6	.7	
	60	10.1	3.53	2.54	.58	80 mV
	40	9.51	3.47	2.60	.63	
	20	9.94	3.32	2.47	.59	
12:43	8000	9.48	3.50	2.59	.77	
	80	14.56	5.21	2.43	.65	
	60	12.99	3.98	2.08	.57	
	40	17.41	4.44	2.37	.57	
	20	11.12	3.40	1.99	.58	
12:51	7900	9.56	2.89	1.51	.59	

FLO-LOG INC.

NOISE LOG DATA SHEET

Page TWO

Company SoCal GAS Co. Well No. SS #29

Date 10-18-91 Noise Tool Number 4085 Calibration Normal

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
						20 mV
		CONT	FIRST LOG			20 FT.
	7880	10.10	3.19	1.69	.61	
	60	9.07	3.18	1.87	.66	
	40	8.08	3.03	1.37	.64	
	20	10.41	6.17	4.54	1.13	TOOL WAS RATTLING
	7800	8.35	2.38	1.18	.55	
	80	7.44	2.38	1.34	.56	
1:13	60	7.20	2.58	1.38	.70	
	40	7.34	2.29	1.16	.58	
	20	7.64	2.28	1.14	.53	
	7700	7.60	2.39	1.27	.59	
	80	7.15	2.40	1.53	.66	
	60	7.30	2.31	1.61	.77	
	40	7.25	2.60	1.41	.63	
1:23	20	7.12	2.31	1.53	.65	
	7600	7.93	2.56	1.53	.64	
	X	REPEAT LOG RUN TWO				
		20' Int.				
1:50pm	8600	58.8	27.3	12.4	4.4	200mV.
	80	36.9	15.7	8.5	3.1	
	60	37.4	13.6	6.9	1.7	
	40	36.7	10.4	4.5	.9	
	20	53.7	7.8	4.2	.8	
	8500	46.8	6.2	2.6	.8	
1:54	80	31.1	5.5	2.6	.8	
	60	13.1	4.2	2.3	.6	
	40	12.3	4.4	2.5	.6	
	20	10.25	3.73	2.33	.51	20mV
	8400	10.16	3.51	2.39	.58	
2:00	80	10.98	3.68	2.19	.63	
	60	10.20	3.15	1.86	.58	
	40	10.18	2.97	1.72	.55	
	20	9.29	2.94	1.85	.57	
	8300	9.49	2.44	1.65	.57	

FLO-LOG INC.

NOISE LOG DATA SHEET

Page THREE

Company SO CAL GAS CO Well No. STANDARD SESNON # 29

Date 10-18-91 Noise Tool Number 4085 Calibration NORMAL

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
		CONT.	REPEAT	LOG	RUN #2	20 mV
2:09	8280	9.81	2.92	1.70	.57	20 FT
	60	9.32	2.66	1.50	.47	
	40	8.60	2.42	1.48	.51	
	20	8.89	2.64	1.57	.52	
2:15	8100	9.38	2.62	1.54	.51	
	80	8.65	2.41	1.38	.55	
	60	8.44	2.35	1.38	.46	
	40	8.58	2.62	1.57	.52	
	20	8.45	2.66	1.46	.57	
	8100	7.31	2.31	1.34	.54	
	80	8.66	2.50	1.42	.61	
	60	5.35	1.88	1.24	.53	
	40	5.63	1.80	1.08	.47	
	20	6.72	1.93	1.07	.49	
	8000	5.03	1.67	1.03	.44	
2:34	80	9.08	2.47	1.21	.54	
	60	7.76	2.54	1.34	.62	
	40	9.23	2.12	1.08	.57	
	20	6.08	1.88	1.03	.62	
	7900	6.05	1.76	1.04	.60	
	7880	5.31	1.49	.90	.58	
	60	5.12	1.58	.78	.50	
	40	5.14	1.46	.75	.49	
	20	4.76	1.35	.75	.53	
	7800	4.77	1.39	.81	.55	
	80	4.65	1.32	.78	.52	
	60	4.70	1.46	.86	.57	
	40	4.46	1.42	.84	.62	
	20	4.31	1.49	.89	.54	
	7700	4.29	1.33	.83	.60	
	80	4.16	1.29	.77	.58	
	60	3.99	1.23	.71	.54	
	40	3.89	1.27	.74	.60	
	20	3.72	1.21	.71	.60	

FLO-LOG INC.

NOISE LOG DATA SHEET

Page 4

Company So Cal Gas Co Well No. 55 #29

Date 10-18-91 Noise Tool Number 408S Calibration Normal

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
3:00 PM	7600	3.87	1.28	.78	.63	
	7550	3.81	1.35	.72	.50	
	7500	3.91	1.26	.71	.56	
		4.01				
	7400	4.01	1.37	.83	.63	
	7300	3.61	1.27	.88	.65	
	7000	3.24	1.22	.79	.61	
	6500	3.01	1.06	.71	.65	
	6000	3.43	.89	.65	.51	
	5500	2.95	.86	.64	.50	
	5000	3.14	.92	.69	.52	
	Tool Test @5000'					
Tool Test	5000	55.2	30.3	21.5	5.2	200 mV
	4500	2.59	.97	.71	.58	
	4000	2.86	1.15	.74	.62	
	3500	3.16	1.07	.78	.62	
4:35	3000	3.79	1.41	.86	.67	
	2500	3.76	1.13	.89	.54	
4:50	2000	4.68	1.29	1.11	.73	
	1500	4.99	1.10	87	.67	
	1000	4.64	1.20	.98	.63	
5:02	500	3.69	1.07	.94	.65	
	300	4.82	1.63	.95	.72	

FLO-LOG INC.

WELL NO. Standard Success #29

DATE 10-18-91

KB 0'
TBG


200
400
600
800
1000
1200
1400
1600
1800
2000
2200
2400
2600
2800
3000
3200
3400
3600
3800
4000
4200
4400
4600
4800
5000
5200
5400
5600
5800
6000
6200
6400
6600
6800
7000
7200
7400
7600
7800
8000
8200
8400
8600
8800
9000
9200


Top of Liner

Top of Liner

Top of Liner

AC_CPUC_0118571



Uncorrected Depth
Corrected Depth
L.T.
L.T.
After Correction
8100
8200
8300
8400
8500
8600
1000
1200




No. BN 6277

PRINTED IN U.S.A.


AC_CPUC_0118573



AC_CPUC_0118574



AC_CPUC_0118575



No. BN 6277
PRINTED IN U.S.A.

AC_CPUC_0118576

FLO-LOG INC.

Company So. Cal. Gas Co.
Type of Survey Temp & Noise
Date of Survey 10-17-91
Lease, Well No. Standard Sesnon #29
Field Aliso Cyn

AC_CPUC_0118578

FLO-LOG INC.

NOISE LOG DATA SHEET

Page THREE

Company SO CAL Well No. SS #29

Date 10-17-91 Noise Tool Number 4085 Calibration NORMAL

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
		CONT REPEAT LOG #2				20 mV
4:54	7940	12.57	9.19	5.39	.75	20 FT STOPS
	20	6.52	5.32	3.09	.75	
	7900	6.90	5.71	3.47	.77	
	80	6.57	5.55	3.32	.71	
	60	6.25	5.04	3.04	.74	
5:00	40	5.64	4.49	2.63	.75	
	20	5.63	4.54	2.63	.72	
5:03	7800	5.68	4.58	2.65	.73	
		END REPEAT				
		CONT FIRST LOG #1				
5:07	7750	5.68	4.69	3.01	.75	50 FT STOPS
	7700	5.26	4.15	2.47	.72	
	50	5.05	4.03	2.47	.75	
5:11	7600	4.96	3.84	2.40	.76	
	7500	4.63	3.54	2.09	.75	100 FT STOPS
5:15	7400	4.05	3.16	1.90	.74	
5:19	7200	3.31	2.44	1.53	.72	200 FT STOPS
	7000	2.37	1.91	1.13	.68	
5:25	6500	3.11	2.12	1.33	.77	500 FT STOPS
	6000	2.56	1.85	1.22	.80	
	5500					
	5000					
	5000	56.3	9.7	5.6	2.2	TOOL TEST

FLO-LOG INC.

NOISE LOG DATA SHEET

Page ONE

Company SO CAL GAS Well No. STANDARD SESNON #29

Date 10-17-91 Noise Tool Number 4085 Calibration NORMAL

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
						200 mV
3:10	60	41.5	12.9	5.2	1.9	20 FT
	8540	35.6	12.2	7.5	2.1	
	20	42.0	12.1	7.3	1.7	
	8500	40.6	12.0	7.0	1.6	
	80	32.2	11.7	7.1	1.9	
3:15	8460	18.2	9.8	6.0	1.8	
	40	12.55	10.15	6.59	1.01	20 mV
	20	11.27	8.91	6.02	.99	
	8400	11.74	9.40	6.26	1.00	
3:22	80	11.78	9.59	6.19	.99	
	60	11.39	9.19	6.57	.99	
	40	11.78	9.20	6.08	.97	
	20	11.77	9.68	6.63	.97	
	8300	11.45	8.94	5.98	.91	
	80	11.09	8.63	5.33	.93	
3:30	60	10.97	8.93	5.44	.90	
	40	10.82	8.26	5.35	.92	
	20	9.98	8.11	5.27	.91	
	8200	10.00	7.91	5.00	.92	
	80	10.85	8.69	5.46	.90	
3:35	60	10.23	7.92	4.97	.87	
	40	10.25	7.89	5.11	.83	
	20	10.25	8.28	5.35	.81	
	8100	10.48	8.15	5.11	.81	
	80	10.22	8.27	5.46	.87	
	60	6.66	5.26	3.32	.90	
3:45	40	7.17	5.79	3.59	.89	
	20	6.93	5.64	3.68	.99	
	8000	6.92	5.26	3.33	.82	
3:50	80	10.92	8.41	5.10	.77	
	60	7.67	5.83	3.26	.76	
	40	12.44	8.83	5.23	.80	
	20	7.01	5.73	3.65	.76	
	7900	7.73	6.71	4.33	.75	

FLO-LOG INC.

NOISE LOG DATA SHEET

Page TWO

Company SO CAL GAS Well No. SS # 29

Date 10-17-91 Noise Tool Number 4085 Calibration NORMAL

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
						20 mV
4:00	7880	6.16	4.94	3.06	.77	20 FT
	60	5.70	4.54	2.86	.72	
	40	5.54	4.43	2.70	.72	
	20	5.47	4.41	2.64	.72	
4:05	7800	5.55	4.44	2.65	.73	
		Repeat Log	Run #	2		200 mV
4:15	8500	39.4	12.8	7.9	2.0	20 FT
	80	32.2	11.2	6.7	1.8	
	60	21.0	11.7	7.4	1.6	
	40	12.1	9.6	6.0	1.4	
	20	12.21	9.77	6.10	1.09	20 mV
	8400	11.47	9.30	5.93	1.04	
	80	11.83	9.45	5.73	1.04	
	60	11.84	9.30	5.60	.97	
	40	11.60	9.39	5.84	1.00	
	20	11.87	9.51	6.19	.99	
	8300	11.98	9.61	6.22	.94	
	80	11.50	8.88	5.71	1.00	
	60	10.77	8.25	5.31	.89	
	40	10.90	8.88	5.67	.92	
	20	10.81	8.57	5.54	.91	
4:35	8200	10.94	8.67	5.93	.96	
	80	10.80	8.71	5.51	.82	
	60	10.91	8.69	5.03	.94	
	40	10.77	8.60	5.45	.90	
	20	10.61	8.33	5.13	.84	
	8100	10.34	8.16	5.10	.90	
	80	10.00	7.65	4.88	.88	
4:45	60	6.62	5.16	3.41	.77	
	40	6.52	5.03	3.20	.75	
	20	6.96	5.42	3.25	.83	
	8000	7.13	5.51	3.36	.81	
	80	11.71	9.39	6.04	.90	
	60	10.65	8.82	5.31	.87	

FLO-LOG

PRODUCTION LOGGING SURVEY DATA SHEET

COMPANY So Cal Gas DATE 10-17-91

WELL NO. Standard Season #29 FIELD Aliso Canyon

COUNTY Los Angeles STATE CA

REPRESENTATIVE Jim Hemmerly SURVEY CREW Helms, Kiser, Schrader

TYPE OF SURVEY Temp Noise

PURPOSE OF SURVEY Check for shoe leak after cmt. job

CASING AND TUBING RECORD

SIZE	WEIGHT	FROM	TO
7"	23 & 26#	0	8180
5"	18#	8075	9790

Effective Depth 9094 BPTD
Perforations 8456 - 9094 2 intervals

W.S.O. ~~Drill Pipe~~ C.P.
Tubing Size ~~2 7/8~~ Depth 8002
Packer(s) 7972
Mandrel(s) Tool Ass 7946 - 7962

Measurement Datum 10' KB
Reference Point ~~MAT~~ Drill floor

WELL STATUS Shut-in

Meter Rate — BWPD Oil Rate — b/d
Flow Loss — BWPD Oil Gravity — °
Obs. Rate — BWPD Gas Rate — Mcf/d
Reported Tbg Press. 2500 psi Obs. —
Reported Csg Press. 1750 psi Obs. —

Pickup 9078 9050 Fill 44'
Bottom Temp. — °F Fluid Level 8555 Cap.

SPINNER STATS

Depth	Counts	Rate	Depth	Counts	Rate

Reset Depth (from) 8102 (to) 8075
Depth Corrected to Liner Top

Logging Unit 712 Line Size 3/16 Line Length 24600
Tools Used 2-5 Bars Tung Bar CCL Temp Cap Noise
Tool Numbers 1024 1031 4085
Tool Diameter 1 3/8

Time Arrived on Location — Off Location — Total Hours —

Time of Run	Run No.	Type of Survey	Survey Calib.	Line Speed	Direction	Logged Interval (from)	(to)
12:45	1	Temp	6"/in	100	Down	200	9078
9:22	2	Cap	200 cap	60	Up	8980	7900
3:15	3	Noise					

REMARKS: 6J Billion Field Inventory
Well on withdrawl 12 hours ~~prior~~ then shut in
13 hours prior to survey
Fluid to surface on the back side

Cap Counts: Gas in lubricator 2964 @ 2500 psi
Water down hole 1154

8605' sow gas

AC_CPUC_0118582

NOISE LOG SUMMARY REPORT

Field: Aliso Canyon Date: 10-17-91

Well Name: Standard Season #29 Logging Contractor: FLO-LOG

WELL DATA

Number of ~~Days~~ HRS Shut-in 13 Field Inventory 62 Bcf.

Date of Last Noise Log 12-05-90 Field Status with draw

Purpose of Survey Check Shoe For Leakage after Cement Job.

Surface Pressures

Tubing 2500 psig

Casing 1750 psig

Innerstring N/A psig

Surface Csg N/A psig

Fluid Levels

Tubing _____ ft. (method) _____

Casing SURF ft. (method) _____

Pickup Depth _____ ft.

Pertinent Marker Beds & Depths _____

Operating Valve Condition (leaking,sweating,icing,etc)


Well was on with draw 12 HRS Prior to Shut-In

LOGGING RUN DATA

Run No. 1	Run No. _____
Starting time: 3:00 ~~am~~/pm	Starting time: _____ am/pm
Pressure:	Pressure:
Casing: 1750 psig	Casing: _____ psig
Tubing: 2500 psig	Tubing: _____ psig
Status: Shutin / ~~Flowing~~	Status: Shutin / Flowing
Noise Anomalies:	Noise Anomalies:
Storage zone: _____	Storage zone: _____
WSO: _____	WSO: _____
Liner: _____	Liner: _____
Packer: _____	Packer: _____
Other: _____	Other: _____

Comments/Recommendations: _____

Witness: _____ Resident: _____



AC_CPUC_0118584

So. Cal. Gas Co. Aliso Canyon Standard Sesnon #29

8-30-90
GAS STORAGE
OIL & WATER

SHUTIN	11-3/4"	42 & 47#	0'	1042'		
9077' PBTD	7	23 & 26	0	8180	2500 PSI	
8992'	5	18	8075	9790		NONE OBS.
85'	2-7/8"	TUBING	0	8049	2500 PSI	

R. MCDONALD
J. KISER
8040
8456-8694' @ INTERVALS 8727-9077-9077 SLOTTED
CHECK SHOE AND CHECK TEMPERATURE ANOMALIES @ 8000'.

SUBSURFACE SAFETY VALVE IS OPEN.
FIELD VOLUME IS 46.524 BCF.

711 23900' 4030

3-60" SINKER BARS, COLLAR LOCATOR, TEMPERATURE,NOISE

7' K.B.
LINER TOP

TEMPERATURE

70° 75° 80° 85° 90° 95° 100°

MILLIVOLTS

2-7/8"
11-3/4" 42&47#
1042'
7" 23&26
5" 18#
110°
115°
120°
125°
130°
135°
140°
150°
155°
160°
165°
170°
175°
180°
[1.0]
[REPEAT]
HEAR SLIGHT GAS FLOW
1.0
10.0

AC_CPUC_0118585

60

80

3660

20

40

60

80

8100


20

40

8160

SS #29

CCC For Path Cont'd



CO. NAME So Cal Gas Co.

WELL NO. SS #29 DATE 10-17-91


RUN NO. ____ TYPE LOG CCL

CALIB. ____ LINE SPD ____ DIRECTION UP

METER RATE ____ PRESSURE 2520

PRINTED IN U.S.A.

AC_CPUC_0118586



AC_CPUC_0118587

PRODUCTION LOGGING SERVICES, INC.

PLS

DATE 12/5/90

COMPANY So. Ca. Gas Co.

TYPE SURVEY Temp + Sound

WELL NUMBER Sesnon 29

FIELD ~~Simi Valley~~ ALISO CANYON

AC_CPUC_0118588

Copies to SO1

PLS PRODUCTION LOGGING SERVICES, INC.

1801 WEST WARDLOW LONG BEACH, CALIF. 90810 (213) 834-3034

PRELIMINARY FIELD REPORT

Date 12/5/90 Start 7:30 Finish 3:00

Customer So. Co. Gas Co.

Attention B. Hazk Crew Lacey

Well Sesnon 29 Field Simi Valley

Type Survey Temp. + Sound

Casing 7" 23#+26# Set ⊖ To 8180'

Liner 5" 18# Set 8075' To 9077 TOC

Tubing 2 7/8" Packer 8040' Tail 8049'

Perforations 8456' - 8694'


	PLS	Meter	Pressure
Rate Upper	____ B/D	____ B/D	2730 PSI
Rate Lower	____ B/D	____ B/D	____ PSI

	O.K.	LEAKING		O.K.	LEAKING
W.S.O.	☐	☐	Packer	☐	☐
Top Eff. Perf.	☐	☐	Shoe	☐	☐

Remarks: P.U. 9000'

F.L. 8760'

AC_CPUC_0118590


Looks like
Shoe leak
Compare to 1989
moving gas
up Soldier pipe

GRAPH PAPER GRAPHIC CONTROLS CORPORATION Buffalo, New York
Printed in U. S. A.

SEMI-LOGARITHMIC 4 CYCLES X 150 DIVISIONS BD-2044 -67

SS-29
12/5/90

6400
6600
6800
7000
7200
7400
7600
7800
8000
8200
8400
8600
8800
9000
9200

1" 23 H
26 H

5" 18 H

PH 9000
9077


12/5/90
Session #7
P&S

1.0 10.0 100.0 1000

AC_CPUC_0118592

GRAPH PAPER GRAPHIC CONTROLS CORPORATION Buffalo, New York
Printed in U. S. A.

SEMI-LOGARITHMIC 4 CYCLES X 150 DIVISIONS BD-2044 -GT



AC_CPUC_0118593

GRAPH PAPER GRAPHIC CONTROLS CORPORATION Buffalo, New York
Printed in U.S.A.

SEMI-LOGARITHMIC 4 CYCLES X 150 DIVISIONS BD-2044-GT

400
600
800
1000
1200
1400
1600
1800
2000
2200
2400
2600
2800
3000
3200


Surface noise

12/5/80
9 x 5
Session 29

AC_CPUC_0118594

AC_CPUC_0118595

SS 29
12/5/90



PLS

Company So Ca Gas Co. Rate

Well # Sesnon 29 Pressure 2730

Date 12/5/90 Run # 1

Hz/in 5° Line Speed 30'

AC_CPUC_0118596

PRODUCTION LOGGING SERVICES, INC.

PLS

Time: Arrive _____

Depart _____

Crew Larry / Arnold

Company So. Ca. Gas Co.

Service Unit 8

Well No. Sesnon 29

Date 12/5/90

API No. _____ Field Simi Valley

WELL DATA

Casing Size & Weight: 7" 23# + 26# Set From 0 to 8180'

Liner Size & Weight: 5" 18# Set From 8075' to 9077' T.O.C.

Tubing Size & Weight: 2 7/8" Set From 0 to 8049', 8040 pkr

Perforations: 8456' - 8694' 2 int.

Surface Datum: 7' Last Pickup _____

Type Survey Temp + Sound Tool Description 1 3/8"

Pickup or Greatest Depth Attempted _____

Depth Correlation and/or Adjustment _____

Meter Coefficient _____ Reading _____ Pressure 2730

Meter Rate _____ B/D. Flow Tube Loss _____ B/D. Net Rate _____ B/D.


SURVEY PROGRAM

Type	Time	Run No.	Line Vel.	Dir.	RPM/in	Off-Set	Time Const.	Remarks
T		1	50'	↓	5"/in			25' ↑ C.C.L.

Remarks: Shoe leak

DF: 7' MV: 6

Standard Sesnon 29



Surface Choke: _____

Casing flow string

--8002' Otis 2-1/2" SSSV
(8002') 2.313"ID

*--8029' Otis "XN" No-Go Nipple
(8029') 2.205"

--8049'

--(8256') (-5400)

--S4 8428'

--S8 8520' (8520')

--HZ 8682'

--Frew 8727'

9077'

(SS - 6941')

4/26/53 Well spud
9/29/53 Well completed
2/2/73-2/28/73 Pressure tested 7" casing, converted to gas stor by perforating in Sesnon Zone, cleaned out to 9074', ran tubing with SSSV
7/31/73-8/7/73 Installed wireli SSSV, cleaned out to 9077'
8/27/77-9/9/77 Cleaned out to 9072', pressure tested casing, reran tubing with SSSV
3/5/79-3/10/79 Replaced safety system, set packer at 8040'

12/5/90
SIWHP
Tbg 2730 psig
Csg 2730 psig

*Note:
USE 2.290 EQUAL. SUB. & RINGS to GET PAST SSSV NIPPLE.


Est FL 8760'

WELL VOLUME	Cu.Ft.	Bbl.
Tubing	262	47
Csg/Lnr.	105	19
Annulus	1405	250

6-16-86

AC_CPUC_0118598

WELL PROFILE



Southern California Gas Co.
OPERATOR

WELL # S.S. #29

FIELD Aliso Canyon

COUNTY Los Angeles

STATE California

DATE March 13, 1979

☐ NEW COMPLETION ☐ WORKOVER

	CASING	LINER	TUBING 1	TUBING 2	TUBING 3
SIZE					
WEIGHT					
GRADE					
THREAD					
DEPTH					

ITEM NO.	TUBING DETAILS	LENGTH	DEPTH
1.	Kelly Bushing	6.92	-
2.	Tubing Hanger	.30	6.92
3.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	1.18	7.72
4.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	3.15	8.90
5.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	10.25	12.05
6.	16 joints 2 7/8" 6.5# N-80 8rd EUE	500.84	22.30
7.	243 Joints 2 7/8" 6.5# J-55 8rd EUE	7473.19	523.14
8.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	4.09	7996.33
9.	Otis "X" nipple 2.350" I.D.	1.13	8000.42
10.	Otis Annular Flow Safety System 4.88" O.D., 2.313" I.D.	7.66	8001.55
11.	Otis blast joint with 4 centralizers 5.50" O.D., 2.375" I.D.	19.82	8009.21
12.	Otis "XN" No-Go Nipple 2.205" I.D.	1.17	8029.03
13.	Otis Blast Joint 3.668" O.D. 2.375" I.D.	9.80	8030.20
14.	Otis "J" latch locator	1.16	8040.00
15.	Otis "Permatrieve" 7" packer (new) (20-26#) 5.87" O.D. 3.25" I.D.	4.16	8040.00
16.	Otis seal assembly (4) 3.29" O.D., 2.38" I.D.	4.05	8041.16
17.	Otis Production Tube	2.96	8045.21
18	Otis Guide Shoe	.42	8048.17
	End of Tubing		8048.59

NOTES


Side door choke in safety system

Tubing landed with 10,000X compression on packer


Corrected tubing measurments (7,482.13) to meet wireline measurments.

COMMENTS:


AC_CPUC_0118599



AC_CPUC_0118600



AC_CPUC_0118601




2½" 18# L. 9077
Pg. 9077'

REVISIONS
Casing - 4-26-61
Geology - 7-12-66

REVISIONS
CASING - 4/26/61
GEOLOGY - 7/12/66

STD. SESNON 1-29

AC_CPUC_0118602


689-5612
5

SHUT IN 5 DAYS PRIOR TO SURVEY.
INJ WD 1.75 HOURS PRIOR TO SHUT IN.

SS-29

SS-29 11-28-90

149 153 157 161 165 169

7500 7700 7900 8100 8300 8500 8700 8900 9100

Shoe appears ok
Disregard gradient
7500' - 7840'
Will run Noise Log

PKR 8040
LNR 8075
SHOE 8180'
PERFS 8456

9077

TBG 3880
CSG 2880
P.U. 9024'

RUN — C.V.
AFAB
PLOT → RM

46 1512
10 X 10 TO THE CENTIMETER
KEUFFEL & ESSER CO. MADE IN U.S.A.
18 X 25 CM.

AC_CPUC_0118604

ALISO CANYON

SS 29

SS-29 10-11-90

TEMP

70 80 90 100 110 120 130 140 150 160 170 180

0 1 2 3 4 5 6 7 8 9 10

0 1000 2000 3000 4000 5000 6000 7000 8000 9000

46 1512

10 X 10 TO THE CENTIMETER 10 X 25 CM
KEUFFEL & ESSER CO. MADE IN U.S.A.

Cooling: 4500'-6000'

No Temp. break @ shoe

11/10/89: RA saw movement to MP & ↑

11/11/89: Noise in zone @ shoe.

CONTINUE TO MONITOR.

Will N.L./n Tracer @ '90 Hi-INV. to Verify S.L.

T-2555

C-2560

TD-9025

Run #6

Read, Plot - MD.

100 FT/INCH

SHUT IN 5 days + PRIOR TO SURVEY.

INJ/WD _____ HOURS PRIOR TO SHUT IN.

4-25-84

AC_CPUC_0118605

PRODUCTION LOGGING SERVICES, INC.

NOISE LOG SURVEY

Company So. Ca. Gas Co.

Well Season 29

Date 12/5/90

Depth	200 HZ	600 HZ	1K	2K	Comments
8700	.568	.546	.523	.071	2 V scale
8600	.761	.698	.652	.092	REPEAT
8500	.767	.611	.551	.104	
8700	583. .583	574. .574	539. .539	79. .079	MV SCALE *
8680	578. .578	569. .569	535. .535	78. .078	
8660	611. .611	598. .598	556. .556	82. .082	
8640	658. .658	642. .642	618. .618	83. .083	
8620	667. .667	643 .643	603. .603	85. .085	
8600	.777 ~~.766~~ 777	.720 ~~.708~~ 720	689 .669	94 .094	
8580	796 .796	730 .730	684 .684	97 .097	
8560	772 .772	709 .709	665 .665	108 .108	
8540	924 .924	799 .799	744 .744	120 .120	
8520	789 .789	640 .640	579 .579	117 .117	
8500	768 .768	612 .612	553 .553	108 .108	
8480	693 .693	578 .578	521 .521	103 .103	
8460	561 .561	539 .539	499 .499	86 .086	
8446	548 .548	529 .529	488 .488	84 .084	
8420	581 .581	565 .565	521 .521	86 .086	
8400	573 .573	555 .555	511 .511	88 .088	
8380	578 .578	560 .560	518 .518	85 .085	
8360	567 .567	550 .550	507 .507	84 .084	
8340	570 .570	554 .554	510 .510	85 .085	
8320	565 .565	546 .546	505 .505	82 .082	
8306	574 .574	555 .555	514 .514	83 .083	

AC_CPUC_0118606

PRODUCTION LOGGING SERVICES, INC.

NOISE LOG SURVEY

Company So Ca. Gas Co.

Well Season 29

Date 12/5/90

Depth	200 HZ	600 HZ	1K	2 K	Comments
8280	.552	.535	.492	.076	
8260	.561	.543	.503	.077	
8240	.559	.544	.500	.076	
8220	.559	.542	.502	.076	
8200	.540	.523	.480	.071	
8180	.528	.510 ~~.468~~	.468	.076	
8160	.533	.514	.476	.072	
8140	.542	.520	.484	.073	
8120	.531	.514	.473 ~~.473~~	.069	
8100	.514	.494	.454	.067	
8080	.525	.509	.470	.072	
8060	.389	.378	.347	.046	
8040	.423	.400	.354	.052	
8020	.427	.395	.341	.048	
8000	.157	.153	.140	.030	
7980	.194	.190	.173	.029	
7960	.208	.208	.192	.029	~~200 mV scale~~
7940	.198	.194	.177	.029	
7920	.195	.192	.175	.027	
7900	.193	.188	.174	.029	
7850	.204	.201	.185	.021	
7800	.197	.193	.177	.017	
7750	.194	.189	.173	.015	
7700	.186	.183	.167	.012	

AC_CPUC_0118607

PRODUCTION LOGGING SERVICES, INC.

NOISE LOG SURVEY

Company So Ca Gas Co

Well Sesnon 29

Date 12/3/90

Depth	200 HZ	600 HZ	1K	2K	Comments
7650	.166	.162	.145	.011	
7600	.148	.145	.128	.010	
7550	.135	.132	.116	.016	
7500	.115	.111	.095	.010	
7450	.101	.097	.081	.010	200 MV scale
7400	90.3	86.3	70.1	10.7	
7350	84.2	79.6	64.8	10.4	
7300	81.7	76.6	62.6	9.4	
7250	78.3	74.2	60.6	7.7	
7200	85.7	82.9	71.7	7.2	
7150	82.9	79.6	68.8	6.3	
7100	83.6	80.9	71	6.6	
7050	84.6	82.4	73.1	6.0	
7000	82.6	79.8	71.9	5.2	
6950	79	76.8	68.1	4.5	
6900	78.1	76	68.3	4.9	
6800	63.3	60.7	52.9	4.1	
6600	54.7	52.5	45	3.2	
6400	42.8	41	34.7	2.3	
6200	35	32.7	27.5	1.8	
6000	125.2	99.1	31.0	8.4	Sound check
6000	23.5	21.8	18.2	4.0	
5800	23.9	22.1	18	1.3	
5600	21.8	19.8	16.6	1.5	

PRODUCTION LOGGING SERVICES, INC.

NOISE LOG SURVEY

Company So. Ca. Gas Co

Well Sesnon 29

Date 12/5/90

Depth	200 HZ	600 HZ	1K	2K	Comments
5400	16.9	15.1	11.9	1.1	
5200	15	13.72	11.34	1.19	20 mv scale
5000	12.49	11.01	9.09	1.12	
4500	8.44	7.05	5.34	1.11	
4000	5.62	4.35	3.17	1.08	
3500	4.22	2.98	2.12	1.09	
3000	4.2	2.3	1.66	1.08	
2500	4.21	2.11	1.77	1.04	
2000	3.59 ~~3.94~~	2.4	2.19	1.04	
1500	3.83	2.88	2.63	1.04	
1000	2.97	4.81	4.47	1.03	Surface noise
500	11.75	9.57	8.92	1.15	

AC_CPUC_0118609

PRODUCTION LOGGING SERVICES, INC.

TEMPERATURE & NOISE LOG
STANDARD SESNON 29

COMPANY SOUTHERN CALIFORNIA GAS COMPANY

WELL SS 29 FIELD ALISO CANYON

COUNTY L. A. STATE CA

WELL DATA


		Casing and Tubing Record			
Date	12-05-90	Size	Wgt.	From	To
Type Log	TEMP.-NOISE	7"	23,26	0'	8180'
Depth-Drill	9094'	5"	18	8075'	9790'
Depth-Log (Pick up)	9000'				
Bottom Logged Interval	9000'				
Top Logged Interval	50'				
Fluid Level					
Recorded By	LARRY CLIFF	Packer @ 8040'			
Witnessed By		Tbg. Tail to 8049', 2-7/8"			
		Perforations: 8456' - 9094' (intervals)			
		Measurement Reference 7"			

EQUIPMENT and TEST DATA


		Truck No.	8
Well Status	SHUT-IN		
Production-Oil, b/d		Tool Size	1-3/8"
Water, b/d			
Gas, mcf			
Injection Rate (meter)		R/A TRACER CHECK RESULTS	
Injection Rate (observ)			
		Packer	
Pressure - TBG. psi	2730	Top Perf.	
CSG. psi		Shoe	
		W.S.O.	
Temp. Sens. °F/inch	TEN	CSG Valve	

SURVEY RESULTS : SHOE LEAKING


REMARKS :



AC_CPUC_D1186101



AC_CPUC_0119611



AC_CPUC_0118612

FLO-LOG INC.

Company So. Calif Gas CO.
Type of Survey Temp & Noise
Date of Survey 8-30-90
Lease, Well No. S.S. #29
Field Aliso Canyon

AC_CPUC_0118613

Copies to | 5.0

FLO-LOG

PRODUCTION LOGGING SURVEY DATA SHEET

COMPANY So. Calif. Gas CO. DATE 8-30-90

WELL NO. Standard Sesson #29 FIELD Aliso Canyon

COUNTY Los Angeles STATE CA.

REPRESENTATIVE Ron McDonald SURVEY CREW Kiser, Schrader, Kergosien

TYPE OF SURVEY Temp. & Noise Log

PURPOSE OF SURVEY Check Shot and Temp. Anomalies @ 8000

CASING AND TUBING RECORD

SIZE	WEIGHT	FROM	TO
7"	23# & 26#	0	8170
		~~8075~~ 8080	~~8080~~
5"	18#	8075	9077

Effective Depth 9077

Perforations 8456-8694 @ Intgl. Perfed 8727 to 9077 Slotted

W.S.O. — 5550 E.P. 8002

Tubing Size 2-7/8" Depth 8049

Packer(s) 8040

~~Mandrel~~(s) NOGO @ 8029

Measurement Datum 7' K.B.

Reference Point D.F.

WELL STATUS GAS STORAGE

Meter Rate 0 BWPD Oil Rate / b/d

Flow Loss / BWPD Oil Gravity / °

Obs. Rate 0 BWPD Gas Rate / Mcf/d

Reported Tbg Press. 2500 psi Obs. 2500 PSI

Reported Csg Press. 2500 psi Obs. 2500 PSI

Pickup 8992 (40#) Fill 85'

Bottom Temp. 189.8 °F Fluid Level None

SPINNER STATS

Depth	Counts	Rate	Depth	Counts	Rate
/	/	/	/	/	/

Reset Depth (from) _____ (to) _____

Depth Corrected to Liner Top

Logging Unit 711 Line Size 3/16" Line Length 23,900

Tools Used 3-5' Bars, C.C.L., Temp., Noise Panel # 1021

Tool Numbers #4030

Tool Diameter 1-3/8"

Time Arrived on Location 7:00 Off Location 1:30 PM Total Hours _____

Time of Run	Run No.	Type of Survey	Survey Calib.	Line Speed	Direction	Logged Interval (from)	(to)
8:10 AM	1	Temp/C.C.L.	5 per In	100-	DOWN	100	8992
9:45 AM	2	NOISE	—	—	UP	8600	500

REMARKS: Peak @ 8000 Looks and sounds like gas cycling Through There, S.S.S.V. is OPEN, Survey Shows almost same as Survey Ran Last year. Pressure For TBG 2510 PSI @ End of Survey CSG 2510 PSI

Field Volume = 46.524 BCF

FLO-LOG INC.

NOISE LOG DATA SHEET

Page # 1

Company So. Cali. Gas. Co. Well No. Standard Session # 29

Date 8-30-90 Noise Tool Number 4030 Calibration

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
10:00	8600	2.19	1.49	1.16	.56	20 mv 50' Intv.
	8550	2.00	1.51	1.21	.60	50 F.T.
	8500	1.87	1.27	1.03	.51	
	8450	1.24	1.08	.92	.48	
	8400	1.23	1.07	.91	.49	
	8350	1.23	1.08	.91	.47	
	8300	1.18	1.03	.86	.46	
10:14	8250	1.15	1.01	.85	.46	
	8200	1.16	1.01	.86	.46	
						20 F.T.
10:17	8180	1.12	.98	.82	.45	
	8160	1.12	.98	.83	.45	
	8140	1.13	.98	.82	.45	
10:21	8120	1.13	.97	.82	.45	
	8100	1.14	.98	.83	.46	
	80	1.13	.99	.83	.46	
	60	.98	83	69	.44	
10:30	40	.91	.80	.67	.44	VERY SLIGHT GAS SOUND Same as in Field
	20	1.89	1.21	.88	.48	SLIGHTLY LOWER GAS FLOW Same as down in zone
	8000	1.35	1.05	.86	.44	
	80	1.35	.79	.61	.41	
	60	1.30	.72	.62	.43	
	40	1.31	.72	.60	.43	
	20	1.22	.74	.62	.42	
	7900	1.0	.9	.6	.2	200 MV Chevron took away line vibration
11:00	80	1.1	.9	.7	.3	
	60	1.0	.8	.5	.2	
	40	1.1	.8	.7	.3	
	20	1.1	.8	.7	.3	
	7800	1.1	.8	.6	.5	
		REPEAT				
11:13	8100	1.23	1.03	.93	.48	20 mV
	8080	1.10	.98	.78	.48	
	8060	1.08	.83	.70	.46	
	8040	.86	.77	.64	.44	

FLO-LOG INC.

NOISE LOG DATA SHEET

Page TWO

Company SO CAL GAS Well No. STANDARD SESSION #29

Date 8-30-90 Noise Tool Number 4030 Calibration

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
		REPEAT CONT				20 mV
11:19	8020	1.14	1.01	.81	.47	Slight Gas Flow, Appears to be Cycling
	8000	1.18	1.03	.89	.54	
	7980	1.18	.77	.61	.43	
	60	.92	.71	.61	.46	
	40	.9	.7	.5	.4	200 mV
11:34	20	.9	.7	.5	.4	
	7900	.9	.7	.5	.4	
		~~	~~~	~~~		50 FT
	7850	.9	.8	.6	.4	
11:38	7800	.9	.8	.6	.4	
		END REPEAT				
		~~	~~~	~~~	~~~	~~~
		CONT RUN ONE				100 FT
	7700	.9	.7	.5	.4	200 mV
11:41	7600	.9	.7	.5	.4	
	7500	.9	.7	.5	.4	
11:44	7400	1.25	.66	.54	.43	20 mV
						200 FT
	7200	.9	.7	.5	.4	200 mV
	7000	.9	.7	.5	.4	
						50 FT
11:51	6950	.9	.7	.5	.4	200 MV
	6900	.8	.7	.5	.4	
	6850	.9	.7	.6	.4	
11:58	6800	.9	.8	.6	.4	
						200 FT.
	6600	.8	.7	.5	.4	200 MV
	6400	.9	.8	.5	.4	
	6200	.9	.8	.5	.4	
12:08	6000	.9	.6	.5	.3	
						500 FT
	5500	1.0	.7	.5	.3	200 M.V.
12:21	5000	1.0	.7	.5	.2	
	5000	23.5	17.3	14.9	3.3	★ TOOL TEST ★
	4500	1.0	.9	.6	.4	

FLO-LOG INC.


NOISE LOG DATA SHEET

Page THREE

Company SO CAL GAS CO Well No. STANDARD SESSION #29

Date 8-30-90 Noise Tool Number 4030 Calibration

Time	DEPTH	200 Hz	600 Hz	1000 Hz	2000 Hz	REMARKS
		CONT FROM ONE				500 FT 900 mV
12:31	4000	1.1	.8	.5	.4	
	3500	1.1	.6	.5	.4	
12:42	3000	1.3	1.0	.7	.4	
	2500	1.5	1.0	.6	.3	
12:53	2000	1.9	.9	.5	.3	
	1500	2.2	.9	.5	.3	
1:04	1000	3.5	1.7	1.0	.2	
	500	6.4	3.0	1.9	.1	


FLO-LOG INC.
WELL NO. Standard Screw #29
DATE 8-30-40
2-7/8" TBG
200
400
600
800
1000
1200
1400
1600
1800
2000
2200
2400
2600
2800
3000
3200
3400
3600
3800
4000
4200
4400
4600
4800
5000
5200
5400
5600
5800
6000
6200
6400
6600
6800
7000
7200
7400
7600
7800
8000
8200
8400
8600
8800
9000
70°
75°
80°
85°
90°
95°
100°
105°
110°
115°
120°
125°
130°
135°
140°
145°
150°
155°
160°
165°
170°
175°
180°
185°
SEAL
PERF
FREW
0
100
200

FLO-LOG INC.

NOISE AND TEMPERATURE SURVEY

COMPANY So. Cal. Gas Co. FIELD Aliso Canyon WELL NAME & NO. Standard Sesnon #29

SURVEY DATA

DATE OF SURVEY	8-30-90
WELL STATUS	GAS STORAGE
TYPE OF FLUID	OIL & WATER
FLUID RATE (S)	SHUTIN
EFFECTIVE DEPTH	9027' PBTD
LOGGER'S DEPTH (PICKUP)	8992'
AMOUNT OF FILL	35'
LOG WITNESSED BY	R. MCDONALD
LOG RECORDED BY	J. KISER
REASON FOR SURVEY	CHECK SHOE AND CHECK TEMPERATURE ANOMALIES @ 8000'.

RESULTS AND REMARKS:

SUBSURFACE SAFETY VALVE IS OPEN.
FIELD VOLUME IS 46.524 MCF.

WELLBORE DATA

CASING AND TUBING RECORD

	SIZE	WEIGHT	FROM	TO	PRESSURE	FLUID LEVEL
	11-3/4"	42 & 47#	0'	1042'		
	7"	23 & 26	0	8180	2500 PSI	
	5"	18	8075	9790		NONE OBS.
	2-7/8"	TUBING	0	8049	2500 PSI	
PACKER (S)		8040	MANDREL (S)			
PERFORATIONS		8456-8696' @ INTERVALS 8727-9077-9077 SLOTTED				

LOGGING UNIT 711 LINE SIZE 3/16" LINE LENGTH 23900' NOISE TOOL NO. 4030

DIAGRAM OF TOOLS USED

DIAMETER OF TOOLS 1-3/8"

3.60" SINKER BARS, COLLAR LOCATOR, TEMPERATURE,NOISE

MEASUREMENT DATUM 7' K.B.

DEPTH REFERENCE LINER TOP


TEMPERATURE

70° 75° 80° 85° 90° 95° 100°

FREQUENCY RESPONCE: (HI FREQUENCY) 2000 HERTZ 1000 HERTZ 600 HERTZ 200 HERTZ (LO FREQUENCY)

MILLIVOLTS

.2 .3 .4 .5 .7 1.0 2 3 4 5 7 10 20 30 40 50 70 100 200 300 400 500 700 1000



AC_CPUC_0118620

FLO-LOG INC.

NOISE AND TEMPERATURE SURVEY

COMPANY So. Cal. Gas Co. FIELD Aliso Canyon WELL NAME & NO. Standard Sesnon #29

SURVEY DATA

DATE OF SURVEY	8-30-90
WELL STATUS	GAS STORAGE
TYPE OF FLUID	OIL & WATER
FLUID RATE (S)	SHUT-IN
EFFECTIVE DEPTH	9027' PBTD
LOGGER'S DEPTH (PICKUP)	8992'
AMOUNT OF FILL	85'
LOG WITNESSED BY	K. MCDONALD
LOG RECORDED BY	J. KISER
REASON FOR SURVEY	CHECK SHOE AND CHECK TEMPERATURE ANOMALIES @ 8000'.

WELLBORE DATA

CASING AND TUBING RECORD

	SIZE	WEIGHT	FROM	TO	PRESSURE	FLUID LEVEL
CASING	11-3/4"	42 & 47#	0'	1042'		
	7	23 & 26	0	8180	2500 PSI	
	5	18	8075	9790		NONE OBS.
TUBING	2-7/8"		0	8049	2500 PSI	

PACKER (S): BAKER 80A40 MANDREL (S):

PERFORATIONS 8456-8694' @ INTERVALS 8727-9077 SLOTTED

RESULTS AND REMARKS:

SUBSURFACE SAFETY VALVE IS OPEN.
FIELD VOLUME IS 46.524 BCF.

LOGGING UNIT 711 LINE SIZE 3/16" LINE LENGTH 23900' NOISE TOOL NO. 4030

DIAGRAM OF TOOLS USED:

DIAMETER OF TOOLS 1-3/8"

3-60° SINKER BARS, COLLAR LOCATOR, TEMPERATURE,NOISE

MEASUREMENT DATUM 7' K.B.

DEPTH REFERENCE LINER TOP


TEMPERATURE

70° 75° 80° 85° 90° 95° 100°

FREQUENCY RESPONCE: (HI FREQUENCY) 2000 HERTZ 1000 HERTZ 600 HERTZ 200 HERTZ (LO FREQUENCY)

MILLIVOLTS

2 3 4 5 7 10 2 3 4 5 7 10 20 30 40 50 70 100 200 300 400 500 700 1000



AC_CPUC_0118621

FLO-LOG INC.

NOISE AND TEMPERATURE SURVEY

COMPANY So. Cal. Gas Co. FIELD Aliso Canyon WELL NAME & NO. Standard Sesnon #29

SURVEY DATA

DATE OF SURVEY	8-30-90
WELL STATUS	GAS STORAGE
TYPE OF FLUID	OIL & WATER
FLUID RATE (S)	SHUTIN
EFFECTIVE DEPTH	9077' PBTD
LOGGER'S DEPTH (PICKUP)	8992'
AMOUNT OF FILL	85'
LOG WITNESSED BY	R. MCDONALD
LOG RECORDED BY	J. KISER
REASON FOR SURVEY	CHECK SHOE AND CHECK TEMPERATURE ANOMALIES @ 8000'.

RESULTS AND REMARKS:

SUBSURFACE SAFETY VALVE IS OPEN.
FIELD VOLUME IS 46.524 BCF.

WELLBORE DATA

CASING AND TUBING RECORD

	SIZE	WEIGHT	FROM	TO	PRESSURE	FLUID LEVEL
	11-3/4"	42 & 47#	0'	1042'		
	7	23 & 26	0	8180	2500 PSI	
	5	18	8075	9790		NONE OBS.
	2-7/8"	TUBING	0	8049	2500 PSI	
	PACKER (S)	8040		MANDREL (S)		
	PERFORATIONS	8456-8695' @ INTERVALS 8727-9077-9077 SLOTTED				

LOGGING UNIT 711 LINE SIZE 3/16" LINE LENGTH 23900' NOISE TOOL NO. 4030

DIAGRAM OF TOOLS USED:

DIAMETER OF TOOLS 1-3/8"

3-60° SINKER BARS, COLLAR LOCATOR, TEMPERATURE,NOISE

MEASUREMENT DATUM 7' K.B.

DEPTH REFERENCE LINER TOP


TEMPERATURE


70° 75° 80° 85° 90° 95° 100°

FREQUENCY RESPONCE: (HI FREQUENCY) 2000 HERTZ 1000 HERTZ 600 HERTZ 200 HERTZ (LO FREQUENCY)

MILLIVOLTS


2 3 4 5 7 10 2 3 4 5 7 10 20 30 40 50 70 100 200 300 400 500 700 1000





PRINTED IN U.S.A.
10. BN 6277
PRINTED IN U.S.A.
BN 6277

AC_CPUC_0118623



AC_CPUC_0118624

FLO-LOG INC.

Company SoCalif Gas CO.
Type of Survey Temp-Noise
Date of Survey 8-9-90
Lease, Well No. S.S. #29
Field Aliso Canyon

AC_CPUC_0118625

Copies to S.O.

FLO-LOG

PRODUCTION LOGGING SURVEY DATA SHEET

COMPANY SO CAL GAS DATE 8-8-90

WELL NO. STANDARD SESNON #29 FIELD ALISO CANYON

COUNTY LA STATE CA

REPRESENTATIVE LARRY SURVEY CREW KISER, SCHRADER, & KARGOSIEN

TYPE OF SURVEY TEMP. NOISE

PURPOSE OF SURVEY CHECK FOR SHOE LEAK

CASING AND TUBING RECORD

SIZE	WEIGHT	FROM	TO
11-3/4	42 + 47 #	Ø	1042
7 "	23 + 26 #	Ø	8180
5 "	18 #	8075	9790

Effective Depth PBTD 9094

Perforations 8456 - 8684 @ INTERVALS
8727 - 9077 SLOTTED

W.S.O. _____ C.P. SSSV 8002

Tubing Size 2-7/8 Depth 8049

Packer(s) 8040

Mandrel(s) -

Measurement Datum 7' DF

Reference Point MAT

WELL STATUS GAS STORAGE SHUT-IN

Meter Rate - BWPD Oil Rate - b/d

Flow Loss - BWPD Oil Gravity - °

Obs. Rate - BWPD Gas Rate - Mcf/d

Reported Tbg Press. 2450 psi Obs. 2425 PSI

Reported Csg Press. 24 psi Obs. _____

Pickup 8993 Fill _____

Bottom Temp. 192.7 °F Fluid Level 8990

SPINNER STATS

Depth	Counts	Rate	Depth	Counts	Rate

Reset Depth (from) _____ (to) _____

Depth Corrected to _____

Logging Unit 711 Line Size 3/16 Line Length 23,950

Tools Used 3-5' BAR CAP, CCL, TEMP, NOISE

Tool Numbers 7107


Tool Diameter 1 3/8

Time Arrived on Location 7:30 Off Location _____ Total Hours _____

Time of Run	Run No.	Type of Survey	Survey Calib.	Line Speed	Direction	Logged Interval (from)	(to)
8:20	1	TEMP	5°/IN	100	DOWN	Ø	8993
10:30	2	CAP	100 CPI	85	UP	9000	7950
11:00	3	NOISE				9000	200

REMARKS:

WELL PROFILE



OPERATOR: Southern California Gas Co.

WELL #: S.S. #29

FIELD: Aliso Canyon

COUNTY: Los Angeles

STATE: California

DATE: March 13, 1979

☐ NEW COMPLETION ☐ WORKOVER

	CASING	LINER	TUBING 1	TUBING 2	TUBING 3
SIZE					
WEIGHT					
GRADE					
THREAD					
DEPTH					

ITEM NO.	TUBING DETAILS	LENGTH	DEPTH
1.	Kelly Bushing	6.92	-
2.	Tubing Hanger	.30	6.92
3.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	1.18	7.72
4.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	3.15	8.90
5.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	10.25	12.05
6.	16 joints 2 7/8" 6.5# N-80 8rd EUE	500.84	22.30
7.	243 Joints 2 7/8" 6.5# J-55 8rd EUE	7473.19	523.14
8.	Pup Jt. 2 7/8" 6.5# N-80 8rd EUE	4.09	7996.33
9.	Otis "X" nipple 2.350" I.D.	1.13	8000.42
10.	Otis Annular Flow Safety System 4.88" O.D., 2.313" I.D.	7.66	8001.55
11.	Otis blast joint with 4 centralizers 5.50" O.D., 2.375" I.D.	19.82	8009.21
12.	Otis "XN" No-Go Nipple 2.205" I.D.	1.17	8029.03
13.	Otis Blast Joint 3.668" O.D. 2.375" I.D.	9.80	8030.20
14.	Otis "J" latch locator	1.16	8040.00
15.	Otis "Permatrieve" 7" packer (new) (20-26#) 5.87" O.D. 3.25" I.D.	4.16	8040.00
16.	Otis seal assembly (4) 3.29" O.D., 2.38" I.D.	4.05	8041.16
17.	Otis Production Tube	2.96	8045.21
18	Otis Guide Shoe	.42	8048.17
	End of Tubing		8048.59

NOTES

Side door choke in safety system

Tubing landed with 10,000X compression on packer


Corrected tubing measurments (7,482.13) to meet wireline measurments.

COMMENTS:

AC_CPUC_0118628

DF: 7' MN: 5½

Standard Sesnon 29



Surface Choke: _____

Casing flow string

--8002' Otis 2-1/2" SSSV
(8002') 2.313"ID

--8029' Otis "XN" No-Go Nipple
(8029') 2.205"

--8049'

--(8256') (-5400)

--S4 8428'

--S8 8520' (8520')

--HZ 8682'

--Frew 8727'

9077'

(SS - 6941')

4/26/53 Well spud
9/29/53 Well completed
2/2/73-2/28/73 Pressure tested 7" casing, converted to gas stor by perforating in Sesnon Zone, cleaned out to 9074', ran tubing with SSSV
7/31/73-8/7/73 Installed wireli SSSV, cleaned out to 9077'
8/27/77-9/9/77 Cleaned out to 9072', pressure tested casing, reran tubing with SSSV
3/5/79-3/10/79 Replaced safety system, set packer at 8040'

WELL VOLUME

	Cu.Ft.	Bbl.
Tubing	262	47
Csg/Lnr.	105	19
Annulus	1405	250

6-16-86

AC_CPUC_0118629

N O I S E L O G

Flo-Log, Inc.

Customer Name _____ Well Number _____

Date _____ Tool Number _____

55 29.3

DEPTH	TIME	200Hz	600Hz	1kHz	2kHz	SCALE	TYPE	REMARKS
6600	14:11	1.47	0.70	0.61	0.47	20mV	3-sec HP	
Interval 200 ft								
6400	14:15	3.23	0.87	0.66	0.48	20mV	3-sec HP	
6200	14:22	1.82	0.80	0.63	0.47	20mV	3-sec HP	
6000	14:27	2.02	0.76	0.64	0.49	20mV	Immed HP	
5800	14:29	4.57	1.24	0.74	0.47	20mV	lo-100 HP	
5600	14:35	1.77	0.80	0.65	0.48	20mV	3-sec HP	
5400	14:39	3.03	0.83	0.64	0.47	20mV	lo-100 HP	
5200	14:44	3.39	0.88	0.64	0.47	20mV	lo-100 HP	
5010	14:49	3.90	0.95	0.66	0.45	20mV	Immed HP	
Interval 10 ft								
5000	14:51	11.11	7.66	3.62	1.11	20mV	Immed HP	Tool test.
4990	14:54	3.10	0.80	0.65	0.44	20mV	3-sec HP	
Interval 200 ft								
4800	15:00	5.76	1.18	0.66	0.40	20mV	Immed HP	
4600	15:02	4.18	1.09	0.68	0.45	20mV	Immed HP	
4400	15:05	2.55	0.77	0.58	0.43	20mV	Immed HP	
4200	15:09	4.36	1.07	0.77	0.46	20mV	Immed HP	
4000	15:12	3.98	0.89	0.61	0.44	20mV	Immed HP	
3600	15:15	3.96	0.89	0.67	0.44	20mV	Immed HP	
3200	15:20	5.79	1.13	0.72	0.46	20mV	Immed HP	
2800	15:25	7.75	1.62	0.83	0.44	20mV	Immed HP	
2400	15:31	8.39	1.51	0.72	0.42	20mV	Immed HP	
2000	15:33	7.55	1.85	1.05	0.54	20mV	Immed HP	
1600	15:39	11.92	1.82	1.00	0.43	20mV	Immed HP	
1200	15:43	12.54	2.94	1.69	0.50	20mV	Immed HP	
800	15:47	13.23	3.70	2.06	0.62	20mV	Immed HP	
400	15:52	14.93	3.24	1.49	0.64	20mV	Immed HP	
200	15:54	13.25	3.61	2.13	0.57	20mV	Immed HP	

N O I S E L O G

Flo-Log, Inc.

Customer Name _____ Well Number _____

Date _____ Tool Number _____

5529.2 (REPEAT)

DEPTH	TIME	200Hz	600Hz	1kHz	2kHz	SCALE	TYPE	REMARKS
7600	13:40	1.28	0.75	0.65	0.50	20mV	3-sec HP	
Interval 50 ft								
7550	13:43	1.38	0.73	0.62	0.48	20mV	3-sec HP	
7500	13:45	1.66	0.81	0.67	0.51	20mV	3-sec HP	
7450	13:47	1.53	0.77	0.68	0.51	20mV	3-sec HP	
7400	13:49	1.55	0.78	0.67	0.51	20mV	3-sec HP	
7350	13:58	1.67	0.77	0.65	0.49	20mV	3-sec HP	
7300	14:01	1.67	0.80	0.67	0.49	20mV	3-sec HP	
7250	14:03	1.52	0.79	0.65	0.49	20mV	3-sec HP	
7200	14:04	1.44	0.76	0.64	0.49	20mV	3-sec HP	

N O I S E L O G

Flo-Log, Inc.

Customer Name _____ Well Number _____


Date _____ Tool Number _____

DEPTH	TIME	200Hz	600Hz	1kHz	2kHz	SCALE	TYPE	REMARKS
8980	10:47	1.04	0.73	0.65	0.50	20mV	3-sec HP	
Interval 20 ft								
8960	10:49	0.96	0.71	0.64	0.50	20mV	3-sec HP	
8940	10:50	0.91	0.71	0.64	0.49	20mV	3-sec HP	
8920	10:51	0.90	0.71	0.64	0.50	20mV	3-sec HP	
8900	10:52	0.96	0.75	0.66	0.51	20mV	3-sec HP	
8880	10:54	1.07	0.73	0.66	0.51	20mV	3-sec HP	
8860	10:55	0.90	0.70	0.63	0.50	20mV	3-sec HP	
8840	10:57	0.96	0.74	0.66	0.51	20mV	3-sec HP	
8820	10:58	0.91	0.73	0.67	0.52	20mV	3-sec HP	
8800	11:02	1.03	0.76	0.67	0.52	20mV	3-sec HP	
8780	11:03	0.93	0.72	0.65	0.51	20mV	3-sec HP	
8760	11:05	1.00	0.74	0.66	0.52	20mV	3-sec HP	
8740	11:06	1.07	0.75	0.67	0.50	20mV	3-sec HP	
8720	11:08	2.17	1.02	0.80	0.52	20mV	3-sec HP	
8700	11:10	2.21	1.02	0.80	0.52	20mV	3-sec HP	
8680	11:11	2.19	1.02	0.80	0.52	20mV	3-sec HP	
8660	11:12	2.14	1.01	0.78	0.51	20mV	3-sec HP	
8640	11:14	2.08	1.00	0.79	0.52	20mV	3-sec HP	
8620	11:15	1.99	1.01	0.79	0.52	20mV	3-sec HP	
8600	11:17	1.51	0.96	0.78	0.52	20mV	3-sec HP	
8580	11:19	1.62	0.97	0.78	0.53	20mV	3-sec HP	
8560	11:20	1.57	0.95	0.77	0.51	20mV	3-sec HP	slight gas noise
8540	11:24	1.55	0.96	0.78	0.51	20mV	3-sec HP	
8520	11:26	2.03	0.95	0.77	0.51	20mV	3-sec HP	
8500	11:28	1.92	0.95	0.75	0.52	20mV	3-sec HP	
8480	11:30	1.64	0.91	0.74	0.50	20mV	3-sec HP	
8460	11:32	1.23	0.90	0.74	0.51	20mV	3-sec HP	

8420	11:35	1.15	0.89	0.74	0.51	20mV	3-sec HP	
8400	11:37	1.18	0.89	0.74	0.51	20mV	3-sec HP	
8380	11:39	1.13	0.86	0.74	0.51	20mV	3-sec HP	
8360	11:41	1.13	0.87	0.74	0.51	20mV	3-sec HP	
8340	11:44	1.14	0.85	0.73	0.51	20mV	3-sec HP	
8320	11:46	1.12	0.89	0.74	0.51	20mV	3-sec HP	
8300	11:50	1.16	0.88	0.74	0.51	20mV	3-sec HP	
8280	11:51	1.12	0.83	0.71	0.50	20mV	3-sec HP	
8260	11:54	1.10	0.86	0.73	0.52	20mV	3-sec HP	
8240	11:55	1.13	0.86	0.73	0.51	20mV	3-sec HP	
8220	11:57	1.10	0.84	0.72	0.51	20mV	3-sec HP	
8200	11:59	1.10	0.86	0.72	0.51	20mV	3-sec HP	
8180	12:01	1.05	0.82	0.70	0.50	20mV	3-sec HP	
8160	12:02	1.07	0.83	0.71	0.51	20mV	Immed HP	
8140	12:04	1.11	0.84	0.72	0.51	20mV	3-sec HP	
8120	12:06	1.10	0.86	0.71	0.51	20mV	3-sec HP	
8100	12:07	1.04	0.81	0.70	0.50	20mV	3-sec HP	
8080	12:10	1.05	0.84	0.72	0.51	20mV	3-sec HP	
8060	12:15	1.03	0.76	0.67	0.50	20mV	3-sec HP	
8040	12:18	1.03	0.78	0.66	0.50	20mV	3-sec HP	
8020	12:20	1.46	0.91	0.72	0.49	20mV	3-sec HP	
8000	12:24	1.41	0.91	0.73	0.51	20mV	3-sec HP	
7980	12:26	1.40	0.78	0.67	0.50	20mV	3-sec HP	
7960	12:29	1.39	0.82	0.68	0.50	20mV	3-sec HP	
7940	12:30	1.42	0.81	0.67	0.50	20mV	3-sec HP	
7920	12:39	1.55	0.82	0.67	0.49	20mV	3-sec HP	
7900	12:40	1.27	0.73	0.63	0.48	20mV	3-sec HP	
7880	12:41	1.29	0.77	0.66	0.50	20mV	3-sec HP	
7860	12:44	1.47	0.81	0.68	0.49	20mV	3-sec HP	
7840	12:46	1.39	0.80	0.67	0.49	20mV	3-sec HP	
7820	12:47	1.31	0.73	0.64	0.48	20mV	3-sec HP	
7800	12:50	1.38	0.76	0.64	0.49	20mV	3-sec HP	

Interval 200 ft

7600	12:54	1.32	0.78	0.68	0.51	20mV	3-sec HP	
7400	13:00	3.38	0.96	0.71	0.48	20mV	3-sec HP	mechanical noise ,maybe adj. well
7200	13:14	1.38	0.70	0.62	0.48	20mV	3-sec HP	
7000	13:22	1.68	0.77	0.65	0.49	20mV	3-sec HP	
6800	13:30	1.69	0.95	0.68	0.51	20mV	3-sec HP	



AC_CPUC_0118637

FLO-LOG INC.

NOISE AND TEMPERATURE SURVEY

COMPANY Southern Cal. Gas FIELD Aliso Canyon WELL NAME & NO. Standard Sesnon #20

SURVEY DATA

DATE OF SURVEY	8-8-90
WELL STATUS	GAS STORAGE SHUT-IN
TYPE OF FLUID	OIL & WATER & GAS
FLUID RATE (S)	NONE
EFFECTIVE DEPTH	9094 PBTD
LOGGER'S DEPTH (PICKUP)	8993'
AMOUNT OF FILL	101'
LOG WITNESSED BY	
LOG RECORDED BY	J. KISER
REASON FOR SURVEY	CHECK FOR CASING SHOE LEAK.

RESULTS AND REMARKS:

WELLBORE DATA

CASING AND TUBING RECORD

	SIZE	WEIGHT	FROM	TO	PRESSURE	FLUID LEVEL
	11-3/4"	42 & 47#	0	1062	2450#	
	7	23 & 26	0	8180		
	5	18	8075	9290		
	2-7/8	TUBING	0	8049	2450PSI	

PACKER (S) 8040 MANDREL (S) NONE

PERFORATIONS 8456-8694 @ INTERVALS 8727-9077 SLOTTED

LOGGING UNIT 711 LINE SIZE 3/16" LINE LENGTH 23,950' NOISE TOOL NO. 7107

DIAGRAM OF TOOLS USED:

DIAMETER OF TOOLS 1-3/8"

3-60" BARS,CAPACITANCE, COLLAR LOCATOR,TEMPERATURE, NOISE

MEASUREMENT DATUM 7' DF

DEPTH REFERENCE TUBING TAIL

TEMPERATURE

75° 80° 85° 90° 95° 100° 105°

FREQUENCY RESPONCE: (HI FREQUENCY) 2000 HERTZ 1000 HERTZ 600 HERTZ 200 HERTZ (LO FREQUENCY)

MILLIVOLTS

.2 .3 .4 .5 .7 1.0 2 3 4 5 7 10 20 30 40 50 70 100 200 300 400 500 700 1000

2-7/8"

200 400 600 800 1000 1200 1400 1600 1800 2000 2200 2400 2600 2800 3000 3200 3400 3600 3800 4000 4200 4400 4600 4800 5000 5200 5400 5600 5800 6000 6200 6400 6600 6800 7000 7200 7400 7600 7800 8000 8200 8400 8600 8800 9000

115°

120°

TOOL TEST

130°

135°

140°

145°

155°

160°

REPEAT

165°

170°

175°

180°

185°

7" 23,26# 8245 8275

5" 18# 9094 PBTD TO 9790'

AC_CPUC_0118638

FLO-LOG INC.

NOISE AND TEMPERATURE SURVEY

COMPANY Southern Cal. Gas FIELD Aliso Canyon WELL NAME & NO. Standard Sesnon #29

SURVEY DATA

DATE OF SURVEY	8-8-90
WELL STATUS	GAS STORAGE SHUT-IN
TYPE OF FLUID	OIL & WATER & GAS
FLUID RATE (S)	NONE
EFFECTIVE DEPTH	9094 PBTD
LOGGER'S DEPTH (PICKUP)	8993'
AMOUNT OF FILL	101'
LOG WITNESSED BY	
LOG RECORDED BY	J. KISER
REASON FOR SURVEY	CHECK FOR CASING SHOE LEAK.

WELLBORE DATA

CASING AND TUBING RECORD

	SIZE	WEIGHT	FROM	TO	PRESSURE	FLUID LEVEL
	11-3/4"	42 & 47#	0	1042	26PSI	
	7	23 & 26	0	8180		
	5	18	8075	9290		
	2-7/8	TUBING	0	8049	2450PSI	

PACKER (S) 8040 MANDREL (S) NONE

PERFORATIONS 8456-8694 @ INTERVALS 8727-9077 SLOTTED

RESULTS AND REMARKS:

LOGGING UNIT 711 LINE SIZE 3/16" LINE LENGTH 23,950' NOISE TOOL NO. 7107

DIAGRAM OF TOOLS USED:

DIAMETER OF TOOLS 1-3/8"

3-60° BARS, CAPACITANCE, COLLAR LOCATOR, TEMPERATURE, NOISE

MEASUREMENT DATUM
7' DF
DEPTH REFERENCE
TUBING TAIL

TEMPERATURE

75° 80° 85° 90° 95° 100° 105°

FREQUENCY RESPONCE: (HI FREQUENCY) 2000 HERTZ 1000 HERTZ 600 HERTZ 200 HERTZ (LO FREQUENCY)

MILLIVOLTS

.2 .3 .4 .5 .7 1.0 2 3 4 5 7 10 20 30 40 50 70 100 200 300 400 500 700 1000

2-7/8"

200 400 600 800 1000 1200 1400 1600 1800 2000 2200 2400 2600 2800 3000 3200 3400 3600 3800 4000 4200 4400 4600 4800 5000 5200 5400 5600 5800 6000 6200 6400 6600 6800 7000 7200 7400 7600 7800 8000 8200 8400 8600 8800 9000

115

120°

TOOL TEST

130°

135°

140°

145°

155°

160°

REPEAT

165°

170°

175°

180°

185°

7" 23,26# @ 8180

5" 18# @ 9290

PBTD TO 9790'

AC_CPUC_0118639

FLO-LOG INC.

NOISE AND TEMPERATURE SURVEY

COMPANY SOUTHERN CAL. GAS FIELD ALISO CANYON WELL NAME & NO. STANDARD SESNON #29

SURVEY DATA

DATE OF SURVEY	8-8-91
WELL STATUS	GAS STORAGE SHUT-IN
TYPE OF FLUID	OIL & WATER & GAS
FLUID RATE (S)	NONE
EFFECTIVE DEPTH	9094 PBTD
LOGGER'S DEPTH (PICKUP)	9997'
AMOUNT OF FILL	101'
LOG WITNESSED BY	
LOG RECORDED BY	J. KISER
REASON FOR SURVEY	CHECK FOR CASING SHOE LEAK.

RESULTS AND REMARKS:

WELLBORE DATA

CASING AND TUBING RECORD

SIZE	WEIGHT	FROM	TO	PRESSURE	FLUID LEVEL
11-3/4"	42 & 47#	0	1042	24PSI	
7	23 & 26	0	8180		
5	18	8075	9790		
2-7/8	TUBING	0	8049	2450PSI	

PACKER (S) 8040 MANDREL (S) NONE

PERFORATIONS 8456-8694 @ INTERVALS 8727-9077 SLOTTED

LOGGING UNIT 711 LINE SIZE 3/16" LINE LENGTH 23,950' NOISE TOOL NO. 7107

DIAGRAM OF TOOLS USED:

DIAMETER OF TOOLS 1-3/8"

3-60" BARS,CAPACITANCE, COLLAR LOCATOR,TEMPERATURE, NOISE

MEASUREMENT DATUM 7' DF

DEPTH INFERENCE TUBING TAIL

TEMPERATURE

75° 80° 85° 90° 95° 100° 105°

FREQUENCY RESPONCE: (HI FREQUENCY) 2000 HERTZ 1000 HERTZ 600 HERTZ 200 HERTZ (LO FREQUENCY)

MILLIVOLTS

2 3 4 5 7 10 2 3 4 5 7 10 20 30 40 50 70 100 200 300 400 500 700 1000

2-7/8"

115°

120°

TOOL TEST

130°

135°

140°

145°

155°

160°

REPEAT

165°

170°

175°


180°


185°

" 23,26#


5" 18# PBTD TO 9790'

AC_CPUC_0118640


DATE
DIRECTION
UNIT NO.
PRESSURE



AC_CPUC_0118642




AC_CPUC_0118643


FLO-LOG INC.

Company So Cal Gas Co
Type of Survey RIA Survey
Date of Survey 11-20-87
Lease, Well No. SS #29
Field ALISO CANYON


AC_CPUC_0118644




AC_CPUC_0118645




AC_CPUC_0118646





AC_CPUC_0118647


7800
7900
8000
8100
8200
8300
8400
1:59
1:51'62
1:11
1:10
1:27
1:38
1:37 pm
1:36
1:35
1:26
1:39
1:28
1:30
1:25
1:27
1:38
1:26
1:36
1:37
1:35
1:36
1:37
1:35
1:36
1:37
1:35



AC_CPUC_0118649


well Connected by Bell Tone



2V @ 9026 UN CONTINUED

AC_CPUC_0118651

FLO-LOG INC.

Company So Cal Gas Co
Type of Survey R/A Survey
Date of Survey 11-30-87
Lease, Well No. SS # 29
Field ALISO CANYON


Incomplete

BKG to High

AC_CPUC_0118652

Elevation: 2849' DF: 7'

Standard Sesnon 29



7/26/53 Well spud
9/29/53 Well completed
2/2/73-2/28/73 Pressure tested 7" casing, converted to gas storag by perforating in Sesnon Zone, cleaned out to 9074', ran tubing with SSSV
7/31/73-8/7/73 Installed wireline SSSV, cleaned out to 9077'
8/27/77-9/9/77 Cleaned out to 9072', pressure tested casing, reran tubing with SSSV
3/5/79-3/10/79 Replaced safety system, set packer at 8040'

WELL VOLUME

	Cu.Ft.	Bbl.
Tubing	262	47
Csg/Lnr.	105	19
Annulus	1405	250

6/12/84

AC_CPUC_0118653

FLO-LOG

PRODUCTION LOGGING SURVEY DATA SHEET

COMPANY So Cal Gas Co DATE 11-30-87

WELL NO. SS #29 FIELD ALISO CANYON

COUNTY L/A STATE Calif.

REPRESENTATIVE Jim MANSDORFER SURVEY CREW Bailey, Tvemello

TYPE OF SURVEY R/A Survey

PURPOSE OF SURVEY Ck Shoe & WSO

CASING AND TUBING RECORD

SIZE	WEIGHT	FROM	TO
7"	23-26	Ø	8180
5"	18	8025	9790

Effective Depth 9077 PBTD

Perforations 8456 - 8727 Cmt

W.S.O. 8/80/8705/10 C.P.

Tubing Size 2 7/8 Depth 8049

Packer(s) 8040

Mandrel(s)

Measurement Datum 9' KB

Reference Point MAT

WELL STATUS gas Storage (S/I)

Meter Rate BWPD Oil Rate b/d

Flow Loss BWPD Oil Gravity °

Obs. Rate BWPD Gas Rate Mcf/d

Reported Tbg Press. psi Obs.

Reported Csg Press. psi Obs.

Pickup 8600 DDA Fill

Bottom Temp. °F Fluid Level

SPINNER STATS

Depth	Counts	Rate	Depth	Counts	Rate

Reset Depth (from) No Reset

Depth Corrected to

Logging Unit 211 Line Size 3/16 Line Length 10,000

Tools Used Head, SB, SR, SB, Gamma, CCL, CAP, INJ

Tool Numbers

Tool Diameter 1 3/8

Time Arrived on Location 7:00AM Off Location 9:00 Total Hours 2.0


Time of Run	Run No.	Type of Survey	Survey Calib.	Line Speed	Direction	Logged Interval (from)	(to)
8:05 AM	One	Temp Log	200 HZ	100	up	9000	5

Unable to Run Survey Due to High BKG from previous try Last week will try again in couple of weeks

REMARKS:

Incomplete log

AC_CPUC_0118654



AC_CPUC_0118655

FLO-LOG INC.

Company So Cal Gas Co
Type of Survey Temp - Noise
Date of Survey 11-17-87
Lease, Well No. SS #29
Field Aliso Canyon

11-17 complete Noise Log
11-18 modified Noise Log (plug in TBG)

AC_CPUC_0118656

PERMANENT DATUM	ELEVATION
LOG MEASURED FROM 1' A.G.	COMPLETED TO 11816 TOP
TOTAL DEPTH 9290'	DRILLING DEPTH (Final) 8393'
TYPE OF FLUID IN HOLE GAS	DRILLING DEPTH (Initial) 8393'
TYPE OF FLUID IN HOLE GAS	FLUID LEVEL 8340' TEMPERATURE
LOG RECORDED BY D. BAILEY	WITNESSED BY JIM MANDSOFER

CASING RECORD			
	Bottom	Top	Cement
13-3/8"	1043'		1000
9-5/8"	8160'		2100
5"	9707'	8008'	

TUBING	2-7/8" TO 8040'
PACKERS	BOWEN
ANOMALIES	
REMARKS/NOTES	8456-8472' W INTERVALS

LOGGING UNIT	331
TOOLS RUN	HEAD,CYSIIRKER BARS,CCL,TEMP,CAPACITANCE,NOISE
TOOL MARKING	

RUN NO.	1
TOP (Driller)	0
TOP (Logger)	0
BOTTOM (Driller)	8393'
BOTTOM (Logger)	8393'
CASING (Driller)	9707'
CASING (Logger)	9707'
BIT SIZE	8-1/2"
TYPE FLUID IN HOLE	GAS
DENSITY	
VISCOSITY	
PH	
FLUID LOSS	
SOURCE OF SAMPLE	
RM @ MEAS TEMP	
RMF @ MEAS TEMP	
RMC @ MEAS TEMP	
SOURCE RMF/RMC	
RM @ BHT	
TIME SINCE CIRC	
MAX REC TEMP	150°F
EQUIP LOCATION	1X/200'
RECORDED BY	
WITNESSED BY	

	Sec. Twp. Rge. or Blk. & Survey
	Other Services
	Permanent Datum
	Elev.: K.B.
	Log Measured From
	Drilling Measured From
	Elev.: K.B.
	D.F.
	G.L.

COMPANY: Flo-Log, Inc.
WELL: Standard #29
FIELD: Acme Gantua Area
COUNTY: Kern
STATE: California
LOCATION: 11-17-87, 11-18-87, 11-19-87

FLO-LOG INC.
TEMPERATURE SURVEY

Permanent Datum
Log Measured From
Drilling Measured From

FLO-LOG INC.

WELL NO. Standard #29
Salmon

DATE 11-17-87
11-18-87

TEMPERATURE

80° 75° 90° 85° 90° 95° 100° 105° 110°

FIRST SURVEY ON 11-17-87 SHOWED MUCH ACTIVITY IN THE STORAGE ZONE.

THE SECOND SURVEY ON 11-18-87 WAS RUN AFTER PUTTING A PLUG IN THE TUBING TAIL. THIS THOUGH TIRED IT STILL SOWS BIRIBRAL NOISE. THE HIGH FREQUENCY ZONE HAS ZEROED NO LOCAL ACTIVITY, HENCE, THE TOOL MUST BE RESPONDING TO DISTANT ZONE ACTIVITY.

LOG #1 (11-17-87)

10.0mv 100.0mv

Log #2 11-17-87 (10.0mv) (100.0mv)

10.0mv 100.0mv

LOG # (11-18-87) 10.0mv 100.0mv


150° 155° 150° 190°

AC_CPUC_31119057

FLO-LOG INC.

WELL NO. SS #29

DATE 11-17-82



AC_CPUC_0118658

Modified Noise Log
SS # 29 11-18-87

6000
6200
6400
6600
6800
7000
7200
7400
7600
7800
8000
8200
8400
8600
8800
9000
9200
9400
9600
9800
10,000

4½ .38 No-go
.75 4½
3½

Clean flo

far away ringing
Howling

Plug in No-go @ 8038'

Heavy ringing flowing

1.0 10.0 100.0
1.0 10.0

Log I = 81K

TBG - 2180
CSN - 2180

Plug @ 9077

N L Mc CULLOUGH
PRODUCTION LOGGING

COMPANY So. Calif Gas
TYPE OF SURVEY Noise Log
DATE OF SURVEY 11-17-81
LEASE, WELL NO. SS-29
FIELD Aliso Canyon

AC_CPUC_0118660

McCullough

PRODUCTION LOGGING

AUDIO ANALYZER SURVEY

OTHER SERVICES

COMPANY So. Calif. Gas Co.

WELL 38-#23 FIELD Aliso Canyon

COUNTY L.A. STATE CA.

SECTION 23 TWP. 2S RGE. 17W

WELL DATA

	Size	Wgt.	From	To
Date				
Run No.	1 1/16"OD			
Log Meas. From	11 3/4	54	0	1182'
Depth—Driller	9760'		1182'	9078'
Depth—Log Tech.	9760'		1182'	9078'
Bottom—Log Tech.	9000'		18	8075'
Last Logged Interval	8600'		2.78	8382'
Top Logged Interval	8600'			
Type Fluid in Hole	Gas		Packer Fluid @	8082'
Fluid Level			Ops. to	8082'
Max. Rec. Temp.	°F		Max. Rec. Temp.	8382'
Recorded By	Bill L & Brian		@ Interval	8382'
Witnessed By	Gupton			


EQUIPMENT and MEASUREMENT DATA

Run No.		Tool No.	
Tool Type		Tool No.	1650
Production—Oil, b/d	3800-1H	Gas, Mcf/d	
Water, b/d		Cond. Gas	1 1/2"
Gas/Oil Ratio		Liner Dia.	3 1/16"
Injection Rate			
Packer Depth			
Tbg. Size and Wgt.			
Tbg. Perforations			
Tbg. Sand Plug			
Tbg. Bridge Plug			
Tbg. Fish			
Tbg. Packer			
Tbg. Anchor			
Tbg. Sand		F/A Sand	
Csg. Perforations		F/A Sand	
F.C. Sand		F/A Sand	

SURVEY RESULTS A/A indicates No Gas Movement

REMARKS:

Form 118


Millivolts
1
1.0
10.0
S.S. 29
SCALE-1"=200'
2000PSI
1500PSI
1000PSI
500PSI
TEST
TEST
TEST

McCullough

PRODUCTION LOGGING

ADDCO ANALYZER SURVEY — OTHER SERVICES:

COMPANY: So. Calif. Gas Co.

WELL: SS-#29 — FIELD: Aliso Canyon — STATE: Ca. — COUNTY: L.A.

WELL DATA		Casing and Tubing Record	Size	Wgt.	Depth	Fluid Level
Date	11-17-51	Casing	11 3/4	47	1812	
Type Log	R/A	Liner	7"	23	8180	
Depth — Log (Fb.vol)	9000'	Tubing	2 7/8	8.7	8070'	
Bottom Logged Interval	9000'		2 1/4	EU	8048	
Top Logged Interval	6000'					
Type Hole Fluid	GAS	Packer/Plug @			8082'	
Max. Rec. Temp. °F		Perforations			8081 - 8684'	
Time Since Circ.					@ intervals	
Max. Rec. Temp.	181	Time Well Ready			1300	
Equip. No. & Loc.		Unit Number				
Recorded By		Witnessed By				

EQUIPMENT and TEST DATA		
Run No.		Tool No. 1550
Wat. Shots	3SHT-IN	Tool Pos.
Production — Oil, Sq.of Water, Gas, and		Tool Size 1 7/8" Hole Dia. 3 7/8"
Tension — Max. psi Cable Size		
Pressure — Max. psi Cable Type		
Log Speed — fpm Cable Length		
Gun Sizes — Type — Shots/Ft.		N/A Sets N/A Spacing

SURVEY RESULTS: A/A indicates No Gas Movement

REMARKS:

Time in

Millivolts

SCALE 1"=100'

TEST

TEST

TEST

TEST

AC_CPUC_0118662

AC_CPUC_0118663

TRIANGLE SERVICE, INC.

AUDIO ANALYZER SURVEY

COMPANY SOUTHERN CALIFORNIA GAS COMPANY

WELL STANDERD 29 FIELD ALISO CANYON

COUNTY L.A. STATE CALIFORNIA

OTHER SERVICES:

ELEVATIONS:
KB
DF
GL

WELL DATA

		Casing and Tubing Record			
Date	10-3-1980	Size	Wgt.	From	To
Run No.		7"		0	8180'
Type Log	A/A	5"		8075'	8727'
Depth — Drill					
Depth — Log (Pick-up)					
Bottom Logged Interval	8600'				
Top Logged Interval	500'				
Type Hole Fluid	Gas	Packer @			
Fluid Level		Tbg. Tail to			
Max. Rec. Temp. °F.		Perforations			
Recorded By	Clark-Olson-Sawyer				
Witnessed By	Bob Hazel	Measurement Reference			


EQUIPMENT and TEST DATA

Run No.		Truck No.	1650
Well Status	Shut in	Tool No.	114
Production — Oil, b/d	0	Tool Size	3/16"
Water, b/d	0		
Gas, mcf	0		
Injection Rate	0		
Pressure — TBG. psi	2900 PSI		
CSG. psi	0		
Log Speed — fpm			
Temp. Sens. °F./inch		R/A Sens.	
Diff. Sens.		R/A Spacing	
T.C.			

SURVEY RESULTS: A/A indicates no gas movement

REMARKS:

Form 128



AC_CPUC_0118664

NL McCullough

PRODUCTION LOGGING

AUDIO ANALYZER SURVEY

Other Services

COMPANY So. Calif. Gas Co.

FIELD Aliso Canyon

WELL SS-#23

COUNTY L.A. STATE Ca.

Sec.	Twp.	Rge.
17	2N	15W

Elevations: KB 7' | DF | GL

WELL DATA

Date	Run No.	Casing and Liners Cemented	Size	Wgt.	From	To
11/12/63	One	Casing	7"	23	0	8180'
		Liner	4½"	11.6	8075'	8804'
		Depth—Driller	9760'			
		Depth—Logger	9760'			
		Bottom Logged Interval	8900'			
		Top Logged Interval	8000'			
		Type Fluid in Hole	Gas			
		Fluid Level				
		Max. Rec. Temp.	°F			
		Recorded By	Bill & Brian			
		Witnessed By	Mr. Gilpin			

Packer/Perfs @ 8091'
Log Tie In 8045'
Perforations 8134 - 8694'
8 intervals
Measure Reference D.F.

EQUIPMENT and TEST DATA

Run No.		Rock No.	1650
Volume Chart		Fold Size	1/2"
Production—Oil B/d		Line Pressure	1475#
Gas M/d			
Injection Rate			
Pressure Gauge Depth			
Log Speed Down			
Log Speed Up			
Tank Gauge			
Oil Tank No.			
I.C. Gauge			

Perforations: CCL pkt
Tubing: 2½" EUE
Tubing Pressure: 1475#
Casing Pressure: 2½" Inch
Tank Gauge: 2½" Inch
Oil Tank No.: 2½" Inch
I.C. Gauge: 2½" Inch

McCullough

PRODUCTION LOGGING

4000 ANALYZER SURVEY

Other Services:

COMPANY So. Calif. Gas Co. | Location:

WELL 35s/23 | FIELD Aliso Canyon | KB | Elev.: | DF | GL 774

COUNTY L.A. | STATE CA.


WELL DATA				Casing and Tubing Record			
Date	11-17-81			Size	Wgt.	From	To
Run No.							
Type Log	Dual Ind			9 5/8"	32	0	1232
Depth—Driller	9700'			11 3/4	47	0	1210
Depth—Log (Pds.op)	9695'			7"	23	0	8027'
Depth—Logger (Pds.op)	9695'			5"	18	8025'	8827'
Top Logged Interval	8000'			2 7/8	EU	0	8838'
Bottom Logged Interval	9695'						
Fluid Level	Full			Perforations: 8067' - 8081'			
Max. Rec. Temp.	165	°F		Hg Sq Ft	8045' - 8067'		
Equip. No.				Perforations: 8161 - 8681'			
Recorded By	Bill & Brian			Hg Sq Ft	8161' - 8681'		
Witnessed By	Guppy			Measurement Reference	D.F.		

EQUIPMENT and MEASUREMENT DATA			
Run No.		Tool No.	1650
Prod. Sonde	Dt. S/d	Tool No.	
	Wave S/d	Tool No.	1 1/2"
Source Type		Centr. Dia.	1 3/4"
Source Size		Lime Dia.	
Injector Rate			
Injection Fluid			
Tool Speed		R/A Spec.	
Log Interval		R/A Spacing	

SURVEY RESULTS A/A indicates No Data Movement

REMARKS:

Tech:


Millivolts
1.0
10.0
SCALE 2"
SCALE 1"=200'
2000'SE
1000'SE
500'SE
SPOOL
TEST
TEST
TEST

McCullough

PRODUCTION LOGGING

ADDIS ANALYZER SURVEY

OTHER SERVICES

COMPANY: So. Calif. Gas Co.

WELL: 35-23 | FIELD: Aliso Canyon | COUNTY: L.A. | STATE: CA.

ELEVATIONS: KB ___ | DF ___ | GL 971

WELL DATA		Casing and Tubing Record	Size	Wt.	From	To
Date	11-17-83					
Run No.	1					
Type Log	Temp Log		11 3/4	47	0	1492
Depth—Driller	9085'		7"	23	0	8027'
Depth—Log (Prtd)	9085'		4½	13	8025'	8093'
Btm. Log Interval	9080'		2 1/8	EU	0	8088'
Top Logged Interval	8800'					
Fluid Used	OAS		Packer/Plug @			8018'
Fluid Level			Packer/Plug @			8088'
Max. Rec. Temp.	°F		Perforations		8838	8698'
Equipment No.	8811 & Jan		Perforations			
Recorded By	Clapp		Measured From			D.F.

EQUIPMENT and TEST DATA			
Rec. No.		Tool No.	1650
Wnd. Size	3HUT-TH	Tool No.	
Thermometer—Ch. No.		Tool No.	1-1/2"
Range	Watch 5/d	Line Dia.	3/16"
	Gen. ref		
Injection Key			
Protocol	DOG gal		
	Gen. ref		
Log Speed — Fpm			
Time Constant — Sec. / inch		F/A Sens.	
Diff. Sens.		F/A Spacing	

SURVEY RESULTS: A/A indicates No Gas Movement

REMARKS:

Time 1Hr



NL McCullough
Production Logging

Company So Cal Gas Co

Type of Survey Noise

Date of Survey 11-17-81

Lease, Well No. SS-29

Field Aliso Canyon

Noise Log Copies
FOR Kern Guppy

AC_CPUC_0118668

TO: Kern

FROM: KERN H. GUPPY

DATE:

Ask for test from Bob Hazel

SOUTHERN CALIFORNIA gas COMPANY

AC_CPUC_0118669

K+E SEMI-LOGARITHMIC 3 CYCLES X 150 DIVISIONS
KEUFFEL & ESSER CO. MADE IN U.S.A.

47 5490

1 2 3 4 5 6 7 8 9 1 2 3 4 5 6 7 8 9 1 2 3 4 5 6 7 8 9 10

200
400
600
800
1000
1200
1400
1600
1800
2000
2200
2400
2600
2800
3000
3200

Surface noise
Can Hear Truck Engine
Reflecting off wall nearby

¼ ⅕ ⅙ ⅐ ⅛ ⅑ 1.0 2.0 3.0 4.0 5.0 10.0

AC_CPUC_0118670

K+E SEMI-LOGARITHMIC 3 CYCLES X 150 DIVISIONS
KEUFFEL & ESSER CO. MADE IN U.S.A.

47 5490

SC-29

11-17-81

3200
3400
3600
3800
4000
4200
4400
4600
4800
5000
5200
5400
5600
5800
6000
6200

1 2 3 4 5 6 7 8 9 1 2 3 4 5 6 7 8 9 10

1.0 2.0 3.0 4.0 5.0 10.0

AC_CPUC_0118671

Date of Survey 10-3-80

Type of Survey Noise Log

Company So. Cal. Gas Co.

Lease, Well No. Standard 22

Field Aliso Canyon

AC_CPUC_0118672

TRIANGLE SERVICE, INC.

AUDIO ANALYZER SURVEY

COMPANY SOUTHERN CALIFORNIA GAS COMPANY

WELL STANDERD 29 FIELD ALISO CANYON

COUNTY L.A. STATE CALIFORNIA

OTHER SERVICES:

ELEVATIONS:
KB.
DF.
GL.

WELL DATA

Date	10-3-1980
Run No.	
Type Log	A/A
Depth — Driller	
Depth — Log (Pick-up)	
Bottom Logged Interval	8600'
Top Logged Interval	500'
Type Hole Fluid	Gas
Fluid level	
Max. Rec. Temp. °F.	
Recorded By	Clark-Olson-Sawyer
Witnessed By	Bob Hazel

Casing and Tubing Record

Size	Wgt.	From	To
7"		0	8180'
5"		8075'	8727'

Packer @
Tbg. Tail to
Perforations
Measurement Reference


EQUIPMENT and TEST DATA

Run No.		Truck No.	1650
Well Status	Shut in	Tool No.	114
Production — Oil, b/d	0	Tool Size	3/16"
Water, b/d	0		
Gas, mcf	0		
Injection Rate	0		
Pressure — TBG. psi	2900 PSI		
CSG. psi	0		
Log Speed — fpm			
Temp. Sens. °F./inch		R/A Sens.	
Diff. Sens.		R/A Spacing	
T.C.			

SURVEY RESULTS: A/A indicates no gas movement

REMARKS:

Form 128



AC_CPUC_0118673

TRIANGLE SERVICE, INC.

AUDIO ANALYZER SURVEY

COMPANY SOUTHERN CALIFORNIA GAS COMPANY

WELL STANDERD 29 FIELD ALISO CANYON

COUNTY L.A. STATE CALIFORNIA

OTHER SERVICES:

ELEVATIONS:
KB
DF
GL

WELL DATA

		Casing and Tubing Record			
Date	10-3-1980	Size	Wgt.	From	To
Run No.		7"		0	8180'
Type Log	A/A	5"		8075'	8727'
Depth — Drill					
Depth — Log (Pick up)					
Bottom Logged Interval	8600'				
Top Logged Interval	500'				
Type Hole Fluid	Gas	Packer @			
Fluid Level		Tbg. Tail to			
Max. Rec. Temp. °F.		Perforations			
Recorded By	Clark-Ollson-Sawyer				
Witnessed By	Bob Hazel	Measurement Reference			


EQUIPMENT and TEST DATA

Run No.		Truck No.	1650
Well Status	Shut in	Tool No.	114
Production — Oil, b/d	0	Tool Size	3/16"
Water, b/d	0		
Gas, mcf	0		
Injection Rate	0		
Pressure — TBG. psi	2900 PSI		
CSG. psi	0		
Log Speed — fpm			
Temp. Sens. °F./inch		R/A Sens.	
Diff. Sens.		R/A Spacing	
T.C.			

SURVEY RESULTS: A/A indicates no gas movement

REMARKS:

Form 129



TRIANGLE SERVICE, INC.

AUDIO ANALYZER SURVEY

COMPANY SOUTHERN CALIFORNIA GAS COMPANY

WELL STANDERD 29 FIELD ALISO CANYON

COUNTY L.A. STATE CALIFORNIA

OTHER SERVICES:

ELEVATIONS:
KB
DF
GL

WELL DATA

		Casing and Tubing Record			
Date	10-3-1980	Size	Wgt.	From	To
Run No.		7"		0	8150'
Type Log	A/A	5"		8075'	8727'
Depth — Drill					
Depth — Log (Pick-up)					
Bottom Logged Interval	8600'				
Top Logged Interval	500'				
Type Hole Fluid	Gas	Packer @			
Fluid Level		Tbg. Tail to			
Max. Rec. Temp. °F.		Perforations			
Recorded By	Clark-Ellison-Sawyer				
Witnessed By	Bob Hazel	Measurement Reference			


EQUIPMENT and TEST DATA

Run No.		Truck No.	1650
Well Status	Shut in	Tool No.	114
Production — Oil, b/d	0	Tool Size	3/16"
Water, b/d	0		
Gas, mcf	0		
Injection Rate	0		
Pressure — TBG. psi	2900 PSI		
CSG. psi	0		
Log Speed — fpm			
Temp. Sens. °F./inch		R/A Sens.	
Diff. Sens.		R/A Spacing	
T.C.			

SURVEY RESULTS: A/A indicates no gas movement

REMARKS:

Form 128



AC_CPUC_0118675

TRIANGLE SERVICE, INC.

AUDIO ANALYZER SURVEY

COMPANY SOUTHERN CALIFORNIA GAS COMPANY

WELL STANDERD 29 FIELD ALISO CANYON

COUNTY L.A. STATE CALIFORNIA

OTHER SERVICES:

ELEVATIONS:
KB
DF
GL

WELL DATA

		Casing and Tubing Record			
Date	10-3-1980				
Run No.		Size	Wgt.	From	To
Type Log	A/A	7"		0	8180'
Depth — Drill		5"		8075'	8727'
Depth — Log (Pick-up)					
Bottom Logged Interval	8600'				
Top Logged Interval	5001'				
Type Hole Fluid	Gas	Packer @			
Fluid Level		Tbg. Tail to			
Max. Rec. Temp. °F.		Perforations			
Recorded By	Clark-Gilson-Sawyer				
Witnessed By	Bob Hazel	Measurement Reference			


EQUIPMENT and TEST DATA

Run No.		Truck No.	1650
Well Status	Shut in	Tool No.	114
Production — Oil, b/d	0	Tool Size	3/16"
Water, b/d	0		
Gas, mcf	0		
Injection Rate	0		
Pressure — TBG. psi	2900 PSI		
CSG. psi	0		
Log Speed — fpm			
Temp. Sens. °F./inch		R/A Sens.	
Diff. Sens.		R/A Spacing	
T.C.			

SURVEY RESULTS: A/A indicates no gas movement

REMARKS:

Form 129



AC_CPUC_0118676

TRIANGLE SERVICE, INC.

AUDIO ANALYZER SURVEY

COMPANY SOUTHERN CALIFORNIA GAS COMPANY

WELL STANDERD 29 FIELD ALISO CANYON

COUNTY L.A. STATE CALIFORNIA

OTHER SERVICES:

ELEVATIONS:
KB.
DF.
GL.

WELL DATA

		Casing and Tubing Record			
		Size	Wgt.	From	To
Date	10-3-1980				
Run No.					
Type Log	A/A	7"		0	8180'
Depth — Drill		5"		8075'	8727'
Depth — Log (Pick up)					
Bottom Logged Interval	8600'				
Top Logged Interval	500'				
Type Hole Fluid	Gas	Packer @			
Fluid Level		Tbg. Tail to			
Max. Rec. Temp. °F.		Perforations			
Recorded By	Clark-Gilson-Sawyer				
Witnessed By	Bob Hazel	Measurement Reference			


EQUIPMENT and TEST DATA

Run No.		Truck No.	1650
Well Status	Shut in	Tool No.	114
Production — Oil, b/d	0	Tool Size	3/16"
Water, b/d	0		
Gas, mcf	0		
Injection Rate	0		
Pressure — TBG. psi	2900 PSI		
CSG. psi	0		
Log Speed — fpm			
Temp. Sens. °F./inch		R/A Sens.	
Diff. Sens.		R/A Spacing	
T.C.			

SURVEY RESULTS: A/A indicates no gas movement

REMARKS:

Form 128



AC_CPUC_0118677

Date of Survey 10-3-80

Type of Survey TEMP & CCL & NOISE

Company So. Cal. Gas

Lease, Well No. SS 29

Field ALISO CANYON

AC_CPUC_0118678

NO. 340D-L310 DIETZGEN GRAPH PAPER
SEMI-LOGARITHMIC
3 CYCLES X 10 DIVISIONS PER INCH

DIETZGEN CORPORATION
MADE IN U.S.A.

SS 29

PAGE 5
10/3/80

5800
6000
6200
6400
6600
6800
7000
7200
7400
7600
7800
8000
8200
8400
8600

1.0
10.0

NO. 340D-L31D DIETZGEN GRAPH PAPER
SEMI-LOGARITHMIC
3 CYCLES X 10 DIVISIONS PER INCH

DIETZGEN CORPORATION
MADE IN U.S.A.

PAGE 2

10/3/80
SS ZG

3000
3200
3400
3600
3800
4000
4200
4400
4600
4800
5000
5200
5400
5600
5800

1.0
10.0

AC_CPUC_0118680

NO. 340D-L310 DIETZGEN GRAPH PAPER
SEMI-LOGARITHMIC
3 CYCLES X 10 DIVISIONS PER INCH

DIETZGEN CORPORATION
MADE IN U.S.A.

SS 29 PAGE 1

10/3/80

100 Ø

500

1000

1500


2000

2500


3000

1500 ft/inch

AC_CPUC_0118681



AC_CPUC_0118682



AC_CPUC_0118883

INTEROFFICE CORRESPONDENCE

CALIFORNIA gas COMPANY

TO McCullough Services FROM Kern H. Guppy DATE

SUBJECT Noise Log Program, Well No. SS-29

1. Notify Shift Supervisor that a noise log will be run in the above well. He will inform you if well is ready to be worked on, or he will provide a field operator to take the well out of service.

2. Run a temperature survey:

from	to	rate
surface	8500'	100'/min.

3. Run noise log:

from	to	survey points
0	5500'	200'
5500'	8500'	20'

If no noise is found, crack valve to create flow, record and report noise both in zone and inside tubing.

The above program is only a guide. Make more frequent stops as necessary to detail any and all significant changes.

4. Before leaving field, clean up walking/working areas, ladders, grates and upper wing valves. Remaining clean-up to be done as time permits.

5. Before leaving field, notify Shift Supervisor of job completion so that well can be returned to service. Do not return well to service yourself. Do not reconnect or change any part of the safety system.

6. Before doing anything that deviates significantly from program, notify this office.

AC_CPUC_0118684

SOUTHERN CALIFORNIA gas COMPANY

INTEROFFICE CORRESPONDENCE

TO Triangle Svcs FROM Mahanand Mishra DATE 9/12/80

SUBJECT Noise Log Program, Well No. SS-29

1. Notify Shift Supervisor that a noise log will be run in the above well. He will inform you if well is ready to be worked on, or he will provide a field operator to take the well out of service.

2. Run a temperature survey:

from	to	rate
0'	8700'	100'/minute

3. Run noise log:

from	to	survey points
T.D.	5500'	50'
5500'	surface at point of noise interference	100'

If no noise is found, crack valve to create flow, record and report noise both in zone and inside tubing.

The above program is only a guide. Make more frequent stops as necessary to detail any and all significant changes.

4. Before leaving field, clean up walking/working areas, ladders, grates and upper wing valves. Remaining clean-up to be done as time permits.

5. Before leaving field, notify Shift Supervisor of job completion so that well can be returned to service. Do not return well to service yourself. Do not reconnect or change any part of the safety system.

6. Before doing anything that deviates significantly from program, notify this office.

64-D

AC_CPUC_0118685

SOUTHERN CALIFORNIA gas COMPANY

INTEROFFICE CORRESPONDENCE

TO Triangle Svcs FROM Mahanand Mishra DATE 9/12/80

SUBJECT Noise Log Program, Well No. SS-29

Done 10-3-80

1. Notify Shift Supervisor that a noise log will be run in the above well. He will inform you if well is ready to be worked on, or he will provide a field operator to take the well out of service.

2. Run a temperature survey:

from	to	rate
0'	8700'	100'/minute

3. Run noise log:

from	to	survey points
T.D.	5500'	50'
5500'	surface at point of noise interference	100'

If no noise is found, crack valve to create flow, record and report noise both in zone and inside tubing.

The above program is only a guide. Make more frequent stops as necessary to detail any and all significant changes.

4. Before leaving field, clean up walking/working areas, ladders, grates and upper wing valves. Remaining clean-up to be done as time permits.

5. Before leaving field, notify Shift Supervisor of job completion so that well can be returned to service. Do not return well to service yourself. Do not reconnect or change any part of the safety system.

6. Before doing anything that deviates significantly from program, notify this office.

AC_CPUC_0118686

ALISO CANYON SAND TEST

WELL: SS-29	INVENTORY: 48.1 m3	DATE: 02/18/10
FLOW STRING: Tubing	ESTIMATED RATE: 10 m2	VERIFIED RATE: 15 m2
TIME ON: 8 10 a	TIME OFF: 2 10 p	TEST HOURS: 6

SHUT IN PRESSURE (SIWHP)	TUBING: 1644 #	CASING: 1683 #
FLOW PRESSURE (FWHP)	UPSTREAM TUBING: 1022 #	DOWNSTREAM TUBING: 478 #
FLOW TEMPERATURE (FWHT)	UPSTREAM TUBING: 91°	DOWNSTREAM TUBING: 62°
FLOW PRESSURE (FWHP)	UPSTREAM CASING: 1743 #	DOWNSTREAM CASING: N #
FLOW TEMPERATURE (FWHT)	UPSTREAM CASING: N	DOWNSTREAM CASING: N

TUBING LATERAL

CHOKE SIZE: 0.9 "	LATERAL SIZE: 6 "	U.S. TAP: ½ "	D.S. TAP: ½ "

PROBE	UPSTREAM #1	DOWNSTREAM #1
NUMBER:	# 3	# 6
WEIGHT BEFORE:	.7085	.7566
WEIGHT AFTER:	.7085	.7566
WEIGHT LOSS:	0	0
EROSION %:	0 %	0 %

CASING LATERAL

CHOKE SIZE: "	LATERAL SIZE: "	U.S. TAP: "	D.S. TAP: "

PROBE	UPSTREAM #1	DOWNSTREAM #1
NUMBER:	#	#
WEIGHT BEFORE:		
WEIGHT AFTER:		
WEIGHT LOSS:		
EROSION %:	%	%

NOTES:

MAXIMUM ALLOWED:3"-28%,4"-28%,6"-12%,8"-7%

NAME: J. Cerulle

SAND TEST INFORMATION

WELL # 35-29	INVENTORY: 62.7 m^3	DATE: 2-9-09
FLOW STRING: 1	ESTIMATED RATE: 15 m^3	VERIFIED RATE: 20 m^3
TIME ON: 855 a	TIME OFF: 9-55 p	TEST HOURS: 5
Time on: 1055 a	Time off: 255 p	
SHUT-IN PRESS (SIWHP)	TUBING: 2160	CASING: 2170
FLOW PRESS (FWHP)	U.S. TUBING: 1810	D.S. TUBING: 510
FLOW TEMP (FWHT)	U.S. TUBING: 84°	D.S. TUBING: 6°
FLOW PRESS (FWHP)	U.S. CASING: 2250	D.S. CASING:
FLOW TEMP (FWHT)	U.S. CASING:	D.S. CASING:

	TUBING LATERAL	
CHOKE SIZE: .900	LATERAL SIZE: 6"	U.S.TAP: 1/2" D.S.TAP: 1/2"

	UPSTREAM #1	DOWNSTREAM #1
PROBE #	5	8
WEIGHT BEFORE	.7056	.7913
WEIGHT AFTER	.7061	.7802
WEIGHT LOSS	.0007	.0001
EROSION %	0.7 %	0.1 %

	CASING LATERAL	
CHOKE SIZE:	LATERAL SIZE:	U.S.TAP: D.S.TAP:

	UPSTREAM #1	DOWNSTREAM #1
PROBE #		
WEIGHT BEFORE		
WEIGHT AFTER		
WEIGHT LOSS		
EROSION %		

NOTES: 5/1 1 hr. due to snow.

MAX. ALLOWED:3"-28%,4"-28%,6"-12%,8"-7% NAME: A. Carrillo

ALISO CANYON SAND TEST

WELL: SS-29	INVENTORY: 53556.84 m3	DATE: 2 / 5 / 15
FLOW STRING: T	ESTIMATED RATE: 35 m2	VERIFIED RATE: 30 m2
TIME ON: 8:35A	TIME OFF: 2:35P	TEST HOURS: 6

SHUT IN PRESSURE (SIWHP)	TUBING: 1917 #	CASING: 472 #
FLOW PRESSURE (FWHP)	UPSTREAM TUBING: 1318 #	DOWNSTREAM TUBING: 500 #
FLOW TEMPERATURE (FWHT)	UPSTREAM TUBING: 92°	DOWNSTREAM TUBING: 50°
FLOW PRESSURE (FWHP)	UPSTREAM CASING: X #	DOWNSTREAM CASING: X #
FLOW TEMPERATURE (FWHT)	UPSTREAM CASING: X	DOWNSTREAM CASING: X

TUBING LATERAL

CHOKE SIZE: 1.0 " ✓	LATERAL SIZE: 6 "	U.S. TAP: .75"	D.S. TAP: .75"

PROBE	UPSTREAM #1	DOWNSTREAM #1
NUMBER:	# 1	# 2
WEIGHT BEFORE:	134.7314	134.7074
WEIGHT AFTER:	.7283	.7057
WEIGHT LOSS:	31	17
EROSION %:	2.7 %	1.5 %

CASING LATERAL

CHOKE SIZE: X "	LATERAL SIZE: X "	U.S. TAP: X "	D.S. TAP: X "

PROBE	UPSTREAM #1	DOWNSTREAM #1
NUMBER:	#	#
WEIGHT BEFORE:		
WEIGHT AFTER:		
WEIGHT LOSS:		
EROSION %:	%	%

NOTES: PROBES REMOVED: #1 COATED WITH OIL. #2 COATED WITH OIL

NO VISIBLE SIGNS OF EROSION ON PROBES

CHEMICAL ~~SAND~~ OFF

MAXIMUM ALLOWED:3"-28%,4"-28%,6"-12%,8"-7%

NAME:

SAND TEST INFORMATION

WELL # 5529	INVENTORY: 78.558	DATE: 9-16-2010
FLOW STRING: T	ESTIMATED RATE: 10	VERIFIED RATE: 15
TIME ON: 9:00 AM	TIME OFF: 3:00 PM	TEST HOURS: 6
SHUT-IN PRESS (SIWHP)	TUBING: 2568	CASING: 2480
FLOW PRESS (FWHP)	U.S. TUBING: 2026	D.S. TUBING: 500
FLOW TEMP (FWHT)	U.S. TUBING: 37	D.S. TUBING: 92
FLOW PRESS (FWHP)	U.S. CASING: 2555	D.S. CASING:
FLOW TEMP (FWHT)	U.S. CASING:	D.S. CASING:

	TUBING LATERAL	
CHOKE SIZE: .9	LATERAL SIZE: 6	U.S.TAP: .5 D.S.TAP: .5

	UPSTREAM #1	DOWNSTREAM #1
PROBE #	1	2
WEIGHT BEFORE	7040	6471
WEIGHT AFTER	7040	6471
WEIGHT LOSS	0	0
EROSION %	0	0

	CASING LATERAL	
CHOKE SIZE:	LATERAL SIZE:	U.S.TAP: D.S.TAP:

	UPSTREAM #1	DOWNSTREAM #1
PROBE #		
WEIGHT BEFORE		
WEIGHT AFTER		
WEIGHT LOSS		
EROSION %		

NOTES:	
MAX. ALLOWED:3"-28%,4"-28%,6"-12%,8"-7%	NAME: Alarcon